



Class GB 1227
Book 5918

OFFICIAL DONATION.

DEPARTMENT OF THE INTERIOR
UNITED STATES GEOLOGICAL SURVEY

CHARLES D. WALCOTT, DIRECTOR

HYDROGRAPHY

OF THE

SUSQUEHANNA RIVER DRAINAGE BASIN

BY

JOHN C. HOYT AND ROBERT H. ANDERSON



WASHINGTON
GOVERNMENT PRINTING OFFICE
1905

PUBLICATIONS OF UNITED STATES GEOLOGICAL SURVEY.

The publications of the United States Geological Survey consist of (1) Annual Reports; (2) Monographs; (3) Professional Papers; (4) Bulletins; (5) Mineral Resources; (6) Water-Supply and Irrigation Papers; (7) Topographic Atlas of the United States, folios and separate sheets thereof; (8) Geologic Atlas of United States, folios thereof. The classes numbered 2, 7, and 8 are sold at cost of publication; the others are distributed free. A circular giving complete lists may be had on application.

The Professional Papers, Bulletins, and Water-Supply Papers treat of a variety of subjects, and the total number issued is large. They have therefore been classified into the following series: A, Economic geology; B, Descriptive geology; C, Systematic geology and paleontology; D, Petrography and mineralogy; E, Chemistry and physics; F, Geography; G, Miscellaneous; H, Forestry; I, Irrigation; J, Water storage; K, Pumping water; L, Quality of water; M, General hydrographic investigations; N, Water power; O, Underground waters; P, Hydrographic progress reports.

The following Water-Supply Papers are out of stock, and can no longer be supplied: Nos. 1-16, 19, 20, 22, 29-34, 36, 39, 40, 43, 46, 57-65, 75. Complete lists of papers relating to water supply and allied subjects follow. (PP=Professional Paper; B=Bulletin; WS=Water-Supply Paper.)

SERIES I—IrrIGATION.

- WS 2. Irrigation near Phoenix, Ariz., by A. P. Davis. 1897. 98 pp., 31 pls. and maps.
- WS 5. Irrigation practice on the Great Plains, by E. B. Cowgill. 1897. 39 pp., 11 pls.
- WS 9. Irrigation near Greeley, Colo., by David Boyd. 1897. 90 pp., 21 pls.
- WS 10. Irrigation in Mesilla Valley, New Mexico, by F. C. Barker. 1898. 51 pp., 11 pls.
- WS 13. Irrigation systems in Texas, by W. F. Hutson. 1898. 68 pp., 10 pls.
- WS 17. Irrigation near Bakersfield, Cal., by C. E. Grunsky. 1898. 96 pp., 16 pls.
- WS 18. Irrigation near Fresno, Cal., by C. E. Grunsky. 1898. 94 pp., 14 pls.
- WS 19. Irrigation near Merced, Cal., by C. E. Grunsky. 1899. 59 pp., 11 pls.
- WS 23. Water-right problems of Bighorn Mountains, by Elwood Mead. 1899. 62 pp., 7 pls.
- WS 32. Water resources of Porto Rico, by H. M. Wilson. 1899. 48 pp., 17 pls. and maps.
- WS 43. Conveyance of water in irrigation canals, flumes, and pipes, by Samuel Fortier. 1901. 86 pp., 15 pls.
- WS 70. Geology and water resources of the Patrick and Goshen Hole quadrangles, Wyoming, by G. I. Adams. 1902. 50 pp., 11 pls.
- WS 71. Irrigation systems of Texas, by T. U. Taylor. 1902. 137 pp., 9 pls.
- WS 74. Water resources of the State of Colorado, by A. L. Fellows. 1902. 151 pp., 14 pls.
- WS 87. Irrigation in India (second edition), by H. M. Wilson. 1903. 238 pp., 27 pls.
- WS 93. Proceedings of first conference of engineers of the reclamation service, with accompanying papers, compiled by F. H. Newell, chief engineer. 1904. 361 pp.

The following papers also relate especially to irrigation: Irrigation in India, by H. M. Wilson, in Twelfth Annual, Pt. II; two papers on irrigation engineering, by H. M. Wilson, in Thirteenth Annual, Pt. III.

SERIES J—WATER STORAGE.

- WS 33. Storage of water on Gila River, Arizona, by J. B. Lippincott. 1900. 98 pp., 33 pls.
- WS 40. The Austin dam, by Thomas U. Taylor. 1900. 51 pp., 16 pls.
- WS 45. Water storage on Cache Creek, California, by A. E. Chandler. 1901. 48 pp., 10 pls.
- WS 46. Physical characteristics of Kern River, California, by F. H. Olmsted, and reconnaissance of Yuba River, California, by Marsden Manson. 1901. 57 pp., 8 pls.
- WS 58. Storage of water on Kings River, California, by J. B. Lippincott. 1902. 100 pp., 32 pls.
- WS 68. Water storage in Truckee basin, California-Nevada, by L. H. Taylor. 1902. 90 pp., 8 pls.
- WS 73. Water storage on Salt River, Arizona, by A. P. Davis. 1902. 54 pp., 25 pls.
- WS 86. Storage reservoirs of Stony Creek, California, by Burt Cole. 1903. 62 pp., 16 pls.
- WS 89. Water resources of Salinas Valley, California, by Homer Hamlin. 1903. 91 pp., 12 pls.
- WS 93. Proceedings of first conference of engineers of the reclamation service, with accompanying papers, compiled by F. H. Newell, chief engineer. 1904. 361 pp.

The following paper also should be noted under this heading: Reservoirs for irrigation, by J. D. Schuyler, in Eighteenth Annual, Pt. IV.

[Continued on third page of cover.]

Water-Supply and Irrigation Paper No. 109

Series { M, General Hydrographic
Investigations, 13
N, Water Power, 9

DEPARTMENT OF THE INTERIOR
UNITED STATES GEOLOGICAL SURVEY

CHARLES D. WALCOTT, DIRECTOR

334


HYDROGRAPHY

OF THE

SUSQUEHANNA RIVER DRAINAGE BASIN

BY

JOHN C. HOYT AND ROBERT H. ANDERSON



WASHINGTON
GOVERNMENT PRINTING OFFICE

1905

Copy 2.

G131227

S9 H 8

MAR 29 1905
D. of D.

RECEIVED BY
RECEIVED TO

CONTENTS.

| | Page. |
|---|-------|
| Letter of transmittal | 7 |
| Introduction | 9 |
| Acknowledgments | 9 |
| Description of drainage area | 10 |
| General features | 10 |
| Susquehanna River below West Branch | 19 |
| Susquehanna River above West Branch | 21 |
| West Branch | 23 |
| Navigation | 24 |
| Measurements of flow | 25 |
| Susquehanna River at Binghamton, N. Y. | 25 |
| Chenango River at Binghamton, N. Y. | 34 |
| Susquehanna River at Wilkesbarre, Pa. | 43 |
| Susquehanna River at Danville, Pa. | 56 |
| West Branch at Williamsport, Pa. | 67 |
| West Branch at Allenwood, Pa. | 84 |
| Juniata River at Newport, Pa. | 93 |
| Susquehanna River at Harrisburg, Pa. | 104 |
| Susquehanna River at McCalls Ferry, Pa. | 130 |
| Chemung River at Chemung, N. Y. | 140 |
| Tioughnioga River at Chenango Forks, N. Y. | 145 |
| Cayuta Creek at Waverly, N. Y. | 146 |
| Chenango River at Oxford, N. Y. | 150 |
| Eaton and Madison brooks, Madison County, N. Y. | 151 |
| Diversions from Chenango River drainage basin | 154 |
| Precipitation | 154 |
| Floods | 172 |
| Flood discharge and values of "n" by Kutter's formula | 178 |
| Low-water conditions | 180 |
| Accuracy of stream measurements | 182 |
| Vertical velocity measurements | 184 |
| Water power | 199 |
| General discussion | 199 |
| Duration of the stages of the lower Susquehanna | 202 |
| Rules for estimating discharge | 203 |
| Tables showing developed horsepower and elevations | 204 |
| Index | 211 |

ILLUSTRATIONS.

| | Page. |
|--|-------|
| ✓ PLATE I. A, Typical view on Susquehanna River near Catawissa, Pa.; | |
| B, Bed of Susquehanna River at McCalls Ferry cable station during low water..... | 18 |
| ✓ II. Rating curve for Susquehanna River at Wilkesbarre, Pa. | 48 |
| ✓ III. Rating curve for Susquehanna River at Danville, Pa. | 60 |
| ✓ IV. Rating curve for West Branch of Susquehanna River at Williamsport, Pa. | 72 |
| ✓ V. Rating curve for West Branch of Susquehanna River at Allenwood, Pa. | 88 |
| ✓ VI. Rating curve for Juniata River at Newport, Pa. | 98 |
| ✓ VII. Rating curve for Susquehanna River at Harrisburg, Pa. | 114 |
| ✓ VIII. View of Susquehanna River, McCalls Ferry gaging stations. | 130 |
| ✓ IX. A, Gaging car in operation at McCalls Ferry cable station; | |
| B, Gaging car at McCalls Ferry cable station | 132 |
| ✓ X. Rating curve for Susquehanna River at McCalls Ferry, Pa. . . | 136 |
| ✓ XI. Curve of mean velocity for Susquehanna River at McCalls Ferry, Pa., cable station..... | 172 |
| ✓ XII. Curve of mean velocity for Susquehanna River at Harrisburg, Pa. | 172 |
| ✓ XIII. Ice flood of 1875 at Wilkesbarre, Pa. | 174 |
| ✓ XIV. Flood of March 8, 1904, at its height, York Haven, Pa. | 174 |
| ✓ XV. A, McCalls Ferry at beginning of flood, March 8, 1904; B, McCalls Ferry after flood of March 8, 1904..... | 176 |
| ✓ XVI. A, Ice left by flood of March 8, 1904, at York Haven, Pa.; | |
| B, Ice left by flood of March 8, 1904, below McCalls Ferry, Pa. | 176 |
| ✓ XVII. Middletown, Pa., during flood of March 8, 1904 | 178 |
| ✓ XVIII. Map showing sections used in Kutter's formula determinations near McCalls Ferry, Pa. | 180 |
| ✓ XIX. Curve of mean velocities of Susquehanna River at Duncans Run, near McCalls Ferry, Pa. | 182 |
| ✓ XX, XXI. Vertical velocity curves of Susquehanna River at Duncans Run, near McCalls Ferry, Pa. | 198 |
| ✓ XXII, XXIII. Vertical velocity curves for Susquehanna River at cable station near McCalls Ferry, Pa. | 198 |
| ✓ XXIV, XXV. Vertical velocity curves for Susquehanna River at cable station near McCalls Ferry, Pa. | 198 |
| ✓ XXVI. Vertical velocity curves of Susquehanna River at Harrisburg, Pa. | 198 |
| ✓ XXVII. Curves showing mean duration of the various stages and discharges of Susquehanna River at Harrisburg for years 1891-1903, inclusive | 202 |
| ✓ XXVIII. Profile of Susquehanna River from mouth to Athens, Pa. | 210 |
| ✓ XXIX. Profiles of some of the tributaries of Susquehanna River | 210 |

| | Page. |
|--|-------|
| FIG. 1. Map showing drainage area and locations of gaging and rainfall stations | 11 |
| 2. Rating curve for Susquehanna River at Binghamton, N. Y..... | 26 |
| 3. Rating curve for Chenango River at Binghamton, N. Y..... | 36 |
| 4. Contour of bottom of Chenango River at Court Street Bridge, Binghamton, N. Y..... | 189 |
| 5. Contours of Susquehanna River bed at Exchange Street Bridge, Binghamton, N. Y..... | 190 |
| 6. Mean vertical velocity curves, Chenango River, Binghamton, N. Y.. | 192 |
| 7. Mean vertical velocity curves, Chenango River, Binghamton, N. Y.. | 192 |
| 8. Mean vertical velocity curves, Susquehanna River, Exchange Street Bridge, Binghamton, N. Y..... | 193 |
| 9. Mean vertical velocity curves, Susquehanna River, upper side of Exchange Street Bridge, Binghamton, N. Y..... | 193 |

LETTER OF TRANSMITTAL.

DEPARTMENT OF THE INTERIOR,
UNITED STATES GEOLOGICAL SURVEY,
HYDROGRAPHIC BRANCH,
Washington, D. C., May 5, 1904.

SIR: I have the honor to transmit herewith a manuscript by John C. Hoyt and Robert H. Anderson, relating to the hydrography of the Susquehanna River drainage basin, and recommend its publication in the series of Water-Supply and Irrigation Papers.

In this paper has been brought together, in such form as to be of use to both the general and the engineering public, all the available hydrographic information in regard to this important area.

It is intended that this paper shall be published in sequence with another (No. 108) entitled "Quality of Water in the Susquehanna River Drainage Basin, by Marshall Ora Leighton, with an Introductory Chapter on Physiographic Features, by George Buell Hollister." The combination of the two papers will make available a large amount of valuable information with reference to the resources of this important river system.

Very respectfully,

F. H. NEWELL, *Chief Engineer.*

Hon. CHARLES D. WALCOTT,

Director United States Geological Survey.

HYDROGRAPHY OF THE SUSQUEHANNA RIVER BASIN.

By JOHN C. HOYT and ROBERT H. ANDERSON.

INTRODUCTION.

A detailed study of the hydrographic features of the Susquehanna River drainage basin has revealed the existence of a large amount of interesting data. These, however, are widely distributed in various publications and manuscripts which are in most cases inaccessible. This paper has been prepared to meet the constant demand for this information from both the general and the engineering public. The general deductions are intended to give the general reader a comprehensive review of the principal conditions which exist in this area, while the base data have been given for the use of the engineer, so that he may make his own deductions and have sufficient data for estimates in hydraulic investigations.

ACKNOWLEDGMENTS.

The records and reports of the United States Geological Survey have been the chief sources from which the data on flow have been obtained. These records have been carefully revised and in many cases recomputed. New rating tables based on all the discharge measurements to date have been prepared and the tables of estimated discharge have been revised to agree with these rating tables. These recomputations will account for the differences between the figures herein presented and many of those in the previous reports, as the latter were prepared from year to year with such information as was available. Special acknowledgment is due to E. G. Paul, resident hydrographer for Pennsylvania, who established the gaging stations and under whose direction the discharge measurements in this State have been made. The stations in New York were established and have been maintained under the direction of R. E. Horton, resident hydrographer for that State.

The base data from which the precipitation tables have been prepared were taken from the published reports of the United States Weather Bureau.

The tables showing the utilized horsepower in 1900 are from manuscript schedules furnished by the manufactures division of the Twelfth Census.

In the preparation of descriptive portions of the paper Vol. XVI of the reports of the Tenth Census (Water Powers, Part I), Rogers's Geology of Pennsylvania, and the Army Engineers' reports have been largely drawn upon.

The annual reports and original records of the Chief of Engineers, United States Army, have furnished valuable information in regard to declivity, and the profiles herewith given are largely based upon them.

The data for McCalls Ferry have been furnished through the kindness of Dr. Cary T. Hutchinson, of New York City, who is interested in the power development at that point and had charge of extensive surveys and studies there in 1902 and 1903. Special mention is due Boyd Ehle and R. H. Anderson, who established and carried on the measurements at the McCalls Ferry gaging station.

Acknowledgment is also due to Frank H. Brundage, H. J. Saunders, L. R. Stockman, and other members of the hydro-computing section of the United States Geological Survey for assistance given in the computations and in other work connected with the preparation of the many tables.

DESCRIPTION OF DRAINAGE AREA.

GENERAL FEATURES.

The Susquehanna River basin is the largest and most important drainage area commercially in the North Atlantic States, although it is not the most important as regards water power. The headwaters of this river system are on the elevated plateau which separates the waters which flow south and east into the Atlantic streams from those flowing north and west into the Mississippi, St. Lawrence, and Great Lakes.

Geologically, this watershed lies in four physiographic divisions: the Allegheny Plateau, the Allegheny Mountains, the Great Allegheny Valley, and the Piedmont Plateau. Its distribution among these provinces is approximately as follows: Allegheny Plateau, 56 per cent; Allegheny Mountains, 31 per cent; Great Allegheny Valley, 6 per cent; Piedmont Plateau, 7 per cent.

As the physical features of the foregoing divisions and the early history of the formation of this basin, as well as the quality of the water, have been fully discussed by Messrs. G. B. Hollister and M. O. Leighton in Water-Supply Paper No. 108, further discussion here is omitted.

The Susquehanna drainage basin, as shown in fig. 1, has a total area of 27,400 square miles. It comprises 21,060 square miles in Pennsylvania, or about 47 per cent of the area of the State; 6,080 square miles in New York, or 13 per cent of the area of the State; 260 square miles in Maryland, or about 2 per cent of the area of the State. It

includes all or a portion of the counties in New York and Pennsylvania listed in the table below:




FIG. 1.—Map showing drainage area and location of gaging and rainfall stations.

Counties in New York and Pennsylvania drained wholly or in part by Susquehanna River and its tributaries.

New York:

Madison.
Cortland.
Otsego.
Chenango.
Delaware.
Broome.
Tioga.
Tompkins.
Schuyler.
Chemung.
Stenben.

Pennsylvania:

Potter.
Tioga.
Bradford.
Susquehanna.
Elk.
Cameron.
Clinton.
Lycoming.
Sullivan.
Wyoming.
Lackawanna.
Luzerne.
Columbia.


Pennsylvania—Continued.

Montour.
Northumberland.
Union.
Center.
Clearfield.
Indiana.
Cambria.
Blair.
Huntingdon.
Mifflin.
Juniata.
Snyder.
Perry.
Cumberland.
York.
Adams.
Franklin.
Fulton.
Bedford.
Somerset.
Dauphin.
Schuylkill.
Lebanon.
Lancaster.

In order to simplify the descriptive matter which follows, the following division has been made of the Susquehanna River system: Susquehanna River and its tributaries below mouth of West Branch; Susquehanna River and its tributaries above mouth of West Branch; West Branch of Susquehanna River and its tributaries. The principal streams in each division are shown by the following diagrams:

Tributaries of Susquehanna River below West Branch.

Shamokin Creek.
Penn Creek.
Middle Creek.
Mahanoy Creek.
Mahantango Creek.
Burgess Creek.
Wiconisco Creek.
Armstrong Creek.



Powell Creek.
Shermans Creek.
Clark Creek.
Stoney Creek.
Fishing Creek No. 1.
Conedoguinet Creek.
Paxton Creek.
Yellows Breeches Creek.
Swatara Creek.
Conewago Creek.
Codus Creek.
Conestoga Creek.
Pequea Creek.
Otter Creek.
Muddy Creek.

Tributaries of Susquehanna River below West Branch—Continued.

Fishing Creek No. 2.
Broad Creek.
Conowingo Creek.
Octoraro Creek.
Deer Creek.

Tributaries of Susquehanna River above West Branch.

Otsego Lake.
Oak Creek, Schnyler Lake.
Cherry Valley Creek.
Schenevus Creek.
Charlotte River.
Otsego Creek.
Onleout Creek.
Carrs Creek.
Unadilla River. {Butternut Creek.
 {Wharton Creek.
Bennetts Creek.
Starucca Creek.
Salt Lick Creek.
Snake Creek.
Chenango River. {Castle Creek.
 {Genegantslet Creek.
 {Canaswacta Creek.
 {Tioughnioga River. {Eastern branch Tioughnioga.
 {Western branch Tioughnioga.
 {Otselic River.
Choconut Creek.
Nanticoke Creek.
Apalachin Creek.
Owego Creek. {Cottalong Creek.
 {East Creek.
Wappasening Creek.
Cayuta Creek.
 {Ten Mile Creek.
 {Twelve Mile Creek.
 {Five Mile Creek.
Chemung River. {Canisteo River. {Carr Valley Creek.
 {Crosby Creek.
 {Purdy Creek.
 {Bennetts Creek.
 {Tuscorora Creek.
 {Tioga River. {Mill Creek.
 {Crooked Creek.
 {Cowanesque Creek.
 {Hammond Creek.
 {Bucks Creek.
Sugar Creek.
Towanda Creek.
Wysox Creek.
Wyalusing Creek.
Tuscarora Creek.
Meshoppen Creek.
Mehoopany Creek.

Tributaries of Susquehanna River above West Branch—Continued.

Tunkhannock Creek.
 Buttermilk Creek.
 Coray Creek.
 Gardner Creek.
 Abraham Creek.
 Mill Creek.
 Toby Creek.
 Buttonwood Creek.
 Warrior Creek.
 Newport Creek.
 Harvey Creek.
 Hunlock Creek.
 Shickshinny Creek.
 Little Wapwallopen Creek.
 Wapwallopen Creek.
 Nescopec Creek.
 Briar Creek.
 Fishing Creek. { Little Fishing Creek.
 { Green Creek.
 { Huntington Creek.
 Catawissa Creek.
 Roaring Creek.
 Mahoning Creek.

Tributaries of West Branch of Susquehanna River.

Anderson Creek.
 Clearfield Creek.
 Moshannon Creek.
 Mosquito Creek.
 Sinnemahoning Creek. { West Creek.
 { Bennetts Brook.
 { East Fork.
 Kettle Creek.
 Youngwomans Creek.
 Bald Eagle Creek. { Spring Creek.
 { Beach Creek.
 { Fishing Creek.
 { Marsh Creek.
 Pine Creek. { Babbs Creek.
 { Little Pine Creek.
 Big Larrys Creek.
 Lycoming Creek.
 Loyalsock Creek.
 Muncy Creek.
 White Deer Hole Creek.
 White Deer Creek.
 Buffalo Creek.
 Chillisquaque Creek.

The following table, compiled from Vol. XVI of the reports of the Tenth Census and from the publications of the United States Geological Survey, shows the drainage area at different points on Susquehanna River and its tributaries.

Drainage areas of Susquehanna River and its tributaries.

| Stream. | Tributary to— | Point of measurement. | Drainage area. <i>Sq. miles.</i> |
|-----------------------|-------------------|--------------------------------------|-------------------------------------|
| Susquehanna River | Chesapeake Bay | Outlet of Otsego Lake. | ^a 81 |
| Do | do | Oak Creek | 97 |
| Do | do | Below and including Oak Creek. | 212 |
| Do | do | Oneonta | ^a 686 |
| Do | do | Below and including Charlotte River. | 713 |
| Do | do | Unadilla River | ^a 914 |
| Do | do | Below and including Unadilla River. | ^a 1,480 |
| Do | do | Nineveh | 1,790 |
| Do | do | Susquehanna | 2,024 |
| Do | do | Binghamton | ^a 2,400 |
| Do | do | Below and including Chenango River. | ^a 3,980 |
| Do | do | Chemung River | 4,940 |
| Do | do | Below and including Chemung River. | ^a 7,460 |
| Do | do | Wilkesbarre | ^a 9,810 |
| Do | do | Danville | ^a 11,070 |
| Do | do | Mouth of west branch | ^a 11,140 |
| Do | do | Sunbury | ^a 18,170 |
| Do | do | Harrisburg | ^a 24,030 |
| Do | do | McCalls Ferry | ^a 26,770 |
| Do | do | Mouth | ^a 27,400 |
| Shamokin Creek | Susquehanna River | do | 165 |
| Penn Creek | do | do | 361 |
| Middle Creek | do | do | 147 |
| Mahanoy Creek | do | do | 133 |
| Mahantango Creek | do | do | 166 |
| Wiconisco Creek | do | do | 83 |
| Clark Creek | do | do | 47 |
| Yellow Breeches Creek | do | do | 247 |
| Conedogwinit Creek | do | do | 450 |
| Swatara Creek | do | do | 536 |
| Conewago Creek | do | do | 560 |
| Shermans Creek | do | do | 232 |
| Pequea Creek | do | do | 148 |

^a Measured by United States Geological Survey.

Drainage areas of Susquehanna River and its tributaries—Continued.

| Stream. | Tributary to— | Point of measurement. | Drainage area. <i>Sq. miles.</i> |
|--------------------------------|-------------------------|---|-------------------------------------|
| Conestoga Creek | Susquehanna River | Lancaster | 332 |
| Do | do | Mouth | 474 |
| Conowingo Creek | do | do | 31 |
| Octorara Creek | do | do | 178 |
| Deer Creek | do | do | 128 |
| Oak Creek | do | do | 115 |
| Cherry Valley Creek | do | do | 121 |
| Scheneyus Creek | do | do | 127 |
| Charlotte River | do | do | 178 |
| Otego Creek | do | do | 106 |
| Oaliout Creek | do | do | 115 |
| Unadilla River | do | do | 561 |
| Butternut Creek | Unadilla River | do | 123 |
| Wharton Creek | do | do | 92 |
| Bennett's Creek | Susquehanna River | do | 47 |
| Chenango River | do | Canasawacta Creek .. | 297 |
| Do | do | Tioughnioga River .. | ^a 730 |
| Do | do | Below and including Tioughnioga River. | ^a 1,490 |
| Do | do | Mouth | ^a 1,580 |
| Canasawacta Creek | Chenango River | do | 63 |
| Genegantslet Creek | do | do | 102 |
| Tioughnioga River | do | Otselic River | ^a 428 |
| Do | do | Mouth | ^a 760 |
| West Branch Tioughnioga River. | Tioughnioga River | do | 103 |
| East Branch Tioughnioga River. | do | do | 164 |
| Otselic River | do | do | 259 |
| Starucca Creek | Susquehanna River | do | 75 |
| Owego Creek | do | do | 391 |
| Cayuta or Shepards Creek. | do | do | 148 |
| Chemung River | do | Elmira | 2,110 |
| Do | do | Mouth | 2,520 |
| Tioga River | Chemung River | do | 1,330 |
| Do | do | Cowanesque Creek .. | 433 |
| Do | do | Canisteo River | 776 |
| Canisteo River | do | Mouth | 545 |
| Tuscarora Creek | do | do | 120 |
| Cowanesque Creek | Tioga River | do | 288 |

^a Measured by United States Geological Survey.

Drainage areas of Susquehanna River and its tributaries—Continued.

| Stream. | Tributary to— | Point of measurement. | Drainage area. <i>Sq. miles.</i> |
|--|--|---------------------------|-------------------------------------|
| Sugar Creek | Susquehanna River | Mouth | 177 |
| Towanda Creek | do | do | 220 |
| Wysox Creek | do | do | 90 |
| Wyalusing Creek | do | do | 204 |
| Tunkhannock Creek | do | do | 409 |
| Lackawanna Creek | do | do | 323 |
| Little Wapwallopen Creek. | do | do | 38 |
| Big Wapwallopen Creek | do | do | 68 |
| Nescopec Creek | do | do | 145 |
| Catawissa Creek | do | do | 131 |
| Fishing Creek | do | do | 353 |
| West Branch Susque- hanna River. | do | Clearfield Creek | 476 |
| Do | do | Sinnemahoning Creek | 1, 440 |
| Do | do | Queens Run | 3, 030 |
| Do | do | Lock Haven | 3, 040 |
| Do | do | Williamsport | ^a 5, 640 |
| Do | do | Allenswood | ^a 6, 540 |
| Do | do | Mouth | ^a 7, 030 |
| Clearfield Creek | West Branch Susque- hanna River. | do | 342 |
| Moshannon Creek | do | do | 233 |
| Mosquito Creek | do | do | 54 |
| Sinnemahoning Creek | do | Benezette | 163 |
| Do | do | Driftwood | 334 |
| Do | do | Mouth | 962 |
| Trout Run | Sinnemahoning Creek | do | 48 |
| Driftwood Branch | do | do | 314 |
| First Fork | do | do | 240 |
| Kettle Creek | West Branch Susque- hanna River. | do | 215 |
| Bald Eagle Creek | do | do | 726 |
| Beach Creek | Bald Eagle Creek | do | 157 |
| Fishing Creek | do | do | 169 |
| Spring Creek | do | do | 148 |
| Pine Creek | West Branch Susque- hanna River. | do | 930 |
| Big Larrys Creek | do | do | 85 |
| Lycoming Creek | do | do | 261 |

^a Measured by United States Geological Survey.

Drainage areas of Susquehanna River and its tributaries—Continued.

| Stream. | Tributary to— | Point of measurement. | Drainage area. <i>Sq. miles.</i> |
|----------------------------|--------------------------------|---|-------------------------------------|
| Loyalsock Creek | West Branch Susquehanna River. | Mouth | 494 |
| Muncy Creek | do | do | 185 |
| White Deer Creek | do | do | 40 |
| Chillisquaque Creek | do | do | 119 |
| Juniata River | Susquehanna River | Junction of and including its two branches. | 1,842 |
| Do | do | Newton Hamilton | 2,270 |
| Do | do | Lewistown dam | 2,550 |
| Do | do | Newport | ^a 3,480 |
| Do | do | Mouth | ^a 3,530 |
| Raystown Branch | Juniata River | Hopewell | 588 |
| Do | do | Mouth | 909 |
| Frankstown Branch | do | Holidaysburg | 129 |
| Do | do | Crooked dam | 249 |
| Do | do | Threemile dam | 273 |
| Do | do | Williamsburg | 279 |
| Do | do | Mud dam | 333 |
| Do | do | Smokers dam | 333 |
| Do | do | Donnellys dam | 342 |
| Do | do | Willow dam | 347 |
| Do | do | Water Street dam | 356 |
| Do | do | Alexandria | 360 |
| Do | do | Little Juniata | 374 |
| Do | do | Pipers dam | 750 |
| Do | do | Huntingdon dam | 759 |
| Do | do | Mouth | 933 |
| Standingstone Creek | Frankstown Branch | do | 129 |
| Shavers Creek | do | do | 45 |
| Little Juniata River | do | Tyrone (including Bald Eagle Creek). | 154 |
| Do | do | Barree | 325 |
| Do | do | Mouth | 327 |
| Spruce Creek | Little Juniata River | do | 94 |
| Bald Eagle Creek | do | do | 54 |
| Great Aughwick | Juniata River | do | 316 |
| Kishacoquillas Creek | do | do | 174 |
| Jacks Creek | do | do | 55 |
| Tuscarora Creek | do | do | 252 |

^a Measured by United States Geological Survey.



A. TYPICAL VIEW ON SUSQUEHANNA RIVER NEAR CATAWISSA, PA.



B. BED OF SUSQUEHANNA RIVER AT McCALLS FERRY CABLE STATION, DURING LOW WATER.

SUSQUEHANNA RIVER BELOW WEST BRANCH.

Susquehanna River is joined by the West Branch at Sunbury, Northumberland County. Below this point the river drains an area of 9,230 square miles. It flows nearly south, between Northumberland, Dauphin, and Lancaster counties on the east and Snyder, Juniata, Perry, Cumberland, and York counties on the west, passing then into Maryland, where it flows between Cecil County on the east and Harford County on the west, and empties into Chesapeake Bay at its northern extremity.

Below the mouth of the West Branch the fall becomes more irregular than above, and there are rapids where the stream flows over a rocky bottom. In the lower part of its course from Marietta to Havre de Grace the river occupies a deep valley, varying in width from a few hundred yards to more than 2 miles, and on either shore it is for the most part bounded by rocky bluffs surmounted by a tableland 100 to 500 feet above the stream. The channel is in many places filled with small rocky islands, some of which are cultivated. Pls. I, B, and VIII show typical views of this part of the river.

The fall of the main river is rapid. Its elevation at the mouth of the West Branch is about 400 feet above mean sea level at Havre de Grace. The distance between this point and Havre de Grace is about 125 miles, hence the mean slope of the main river is nearly $3\frac{1}{2}$ feet per mile. The slope is, however, extremely variable, being over 5 feet per mile in the lower 40 miles and about $2\frac{1}{2}$ feet per mile in the upper 40 miles. The change in slope takes place as the river passes from the Allegheny Mountain and the Allegheny Valley regions to the Piedmont Plateau region.

The tables on pages 207-210 give the elevation of the river and its branches at various points, and Pls. XXVIII and XXIX show their profiles.

This part of the river is described by Prof. H. D. Rogers as follows:^a

Between Northumberland and the Kittatinny Valley the river leads us through many striking scenes. It is studded with many little islands, most of which are covered with trees or bushes to the water's edge, and it is here a wide and majestic river, flowing alternately for long reaches across highly cultivated belts of country and past the ends of steep and rugged mountains. Passing out from the mountains it traverses a beautiful country in the Kittatinny Valley, dividing Dauphin from Cumberland County. Quitting the limestone valley the river next traverses the red-shale belt, between the villages of Highspire and Bainbridge, crossing a rather monotonous country, except at the Conewago Falls, or rapids, where numerous hard trap dikes impede its course and cause it to rush in wild tumult, by deep and dangerous sluices, for a long distance between black and jutting reefs. At Chickies Ridge, 1 mile above Columbia, the river leaves the smoother country and passes between a range of high and picturesque crags. With two or three intermissions, caused by the softer limestone valleys which it next crosses, it runs the whole way thence to the vicinity of Port Deposit, or nearly to the Chesapeake Bay, between steep naked and half naked hillsides, rising

^a Geol. Pennsylvania, p. 49.

from 200 to 400 feet above its channel. In some parts of this long reach, as at Washington Borough, the river is greatly dilated and is filled with rocky islands and projecting reefs. In other localities its rugged banks approach, and the river rushes with tremendous force, especially during freshets, through these deeper gorges. The traveler, who finds only a rough and very toilsome path along its eastern shore from Turkey Hill to Port Deposit, a distance of more than 30 miles, will choose to descend it by its right bank along the towpath of the canal. He will pass an almost unbroken succession of interesting rocky scenes, affording much geological instruction, and he will witness many beautiful bits of river perspective, but he will find himself pent in all the way between the bold river hills.

The principal tributary below the West Branch is the Juniata, which has its source in Bedford, Blair, and Somerset counties, Pa., at an elevation of about 2,000 feet above sea level. The divide between its waters and those of the Ohio attains in places a height of nearly 2,800 feet. The valley of the stream is narrow and the banks are generally high. The stream has a number of both large and small tributaries. Doctor Rogers describes the Juniata as follows:^a

This second great tributary of the Susquehanna has two chief upper divisions, the Frankstown and the Raystown branches, both of which, like the main stream below their junction, traverse much beautiful scenery. We will trace the Frankstown Branch as that which is most accessible. After gathering its headwaters from the eastern slope and the foothills of the Allegheny Mountains it begins to assume the volume of a small river near Frankstown. Below this point it first passes the cove of the Lock Mountain, a curious district of conical hills, in structure like the Muncy Hills of the West Branch. Its course is now by a wild and rocky gorge through the Lock or Canoe Mountain into Canoe Valley. Winding northeastward through this valley it next goes through Tusey Mountain into Hartslog Valley by an interesting curving pass of the form of the letter S. The mountain, which consists of two ridges, is trenched along its center for the passage of the river, and the western ridge is, moreover, breached at Water street by a lateral notch, which gives passage to a small tributary stream and heightens much the picturesqueness of the place, which is further enhanced by a great stone slide covering the ends of the mountain. Crossing Hartslog Valley it next traverses Warrior Ridge, passing by the Pulpit Rocks. Emerging from the Warrior Ridge and deflecting more toward the east it crosses the Huntingdon Valley and passes by the northern end or knob of Terrace Mountain or Slideling Hill, receiving first the Raystown Branch, which nearly doubles the volume of its waters. Here, bending southward, it follows a picturesque gap through Stone Ridge, and turning more eastward it presently enters the deep cleft in Jacks Mountain called "Jacks Narrows," upon the western side of which the mountain is covered with a great stone slide or field of naked angular blocks of sandstone, which imparts a most desolate aspect to the pass, especially when the forest is not in leaf.

On emerging from Jacks Narrows the river crosses a succession of open valleys divided by narrow ridges until it meets the base of Blue Ridge in Sugar Valley. There it makes a great loop, turning in an oxbow backward till it reaches Newton Hamilton, where it flows with many large sinuosities longitudinally through the Juniata or Lewistown Valley to the deep synclinal ravine called the "Long Narrows," formed by the near approach of the Blue and Shade mountains. The Long Narrows of the Juniata is a narrow trough between mountain ridges, deeply trenched on their flanks and thickly clothed with timber on their lower slopes and

^a Geol. Pennsylvania, p. 50.

at their base, and overspread nearer their summits with extensive sloping sheets of dark-gray angular blocks. The pass is 7 miles long and is one of the wildest and most impressive within the mountains. At the eastern end of the Long Narrows the river turns southeastward and winds between hills and valleys across the country to the base of the Tuscarora Mountain, passing Mifflintown, Mexico, and other villages. Below New Mexico it sweeps the base of the Tuscarora Mountain for several miles, until it turns abruptly across its eastern end a mile northwest of Millerstown. Below Millerstown the river crosses the Wildcat and Buffalo valleys, washing the end of the Buffalo Mountain. Pursuing its course, the Juniata, after making two or three bends, flows through a belt of hills called the "Half-Fall Mountain," where, as at nearly all its passes through the larger sandstone ridges, it is impeded by ledges of hard strata and thrown into ripples or rapids. From the Half-Fall Rapids it flows between steep but low cliffs and hills for about 4 miles farther, to its entrance into the main Susquehanna at Duncans Island, having followed a winding course entirely across the central zone of the Appalachian chain through a distance of nearly 200 miles.

SUSQUEHANNA RIVER ABOVE WEST BRANCH.

This portion of the stream and its tributaries drain an area of about 11,140 square miles, of which 6,080 are in New York and 5,060 in Pennsylvania. It rises in Otsego Lake, in Otsego County, N. Y., which is about $7\frac{1}{2}$ miles long and $1\frac{1}{2}$ miles wide, and has an elevation of about 1,193 feet above sea level. It flows in a south-westerly direction through Otsego, Chenango, and Broome counties, N. Y., into Susquehanna County, Pa. It then flows in a westerly-northwesterly direction through this county and again enters New York and takes a westerly course through Broome and Tioga counties to near the western boundary of Tioga County, where it turns south and enters Pennsylvania. Before leaving New York its volume is rapidly swelled by many large tributaries. After entering Pennsylvania the second time it flows through Bradford, Wyoming, Luzerne, Columbia, Montour, and Northumberland counties to its junction with the West Branch, above Sunbury.

This portion of the drainage basin is varied in character. In New York it is a rolling and sometimes rather broken country, forming the plateau bounding the mountain region on the north. The stream has a very uniform declivity in this part of its course and offers comparatively little power. Its bed is gravel or sand, with an occasional rocky ledge. Its banks are moderately high, shelving, and are subject to overflow only in extreme freshets.

After it enters Pennsylvania it flows through the mountain regions, and its course is in many places tortuous as it winds along the parallel ranges of hills. In general, however, its fall is gradual, its bed being composed mostly of drift materials—gravel, sand, and boulders. The banks, as in New York, are generally high and are seldom overflowed, although the river has an extreme rise of as much as 30 feet.

In this portion of the drainage area is located the great Lackawanna and Wyoming coal basin, and J. H. Dager reported upon this, in sub-

stance, as follows:^a This basin extends from Nanticoke on the southwest, where the river emerges from the Coal Measures, to Carbondale on the northeast. It is about 50 miles in length and averages $3\frac{1}{2}$ miles in width. It is surrounded by the Allegheny Mountains, which are composed of the Catskill formation and rocks of the Carboniferous system.

In this vicinity there are several workable seams of coal, ranging from 3 to 14 feet in thickness and at depths varying from nothing to 800 feet. These seams are from 10 to 200 feet apart vertically, and are underlain by sandstone and fire clay.

From the outcrop of the Coal Measures just above Pittston to the New York State line the country is traversed by long, narrow, parallel ranges of mountains whose axes are nearly at right angles to the general direction of the river. At bends on the convex side there rise from the shore abrupt cliffs from 200 to 400 feet in height, opposite which, with one or two exceptions, are gently sloping cultivated lands.

Professor Rogers refers to this portion of the river as follows:^b

That portion of the Susquehanna River which flows near the northern boundary of the State passes from its sharp elbow, called the "Great Bend," to the mouth of its affluent, the Chemung River, through a charming, broad valley, bounded by soft slopes terminating in wide, table-shaped hills. It is a fertile and very beautiful district, and with its westward extension, the plain of the Chemung River, is rapidly becoming one of the most attractive agricultural districts of New York. From the mouth of the Chemung River to Pittston, where the river suddenly turns at a right angle on entering the Wyoming coal field, it flows, with many bendings, along a deep and picturesque valley, almost identical in its features with that of the corresponding stretch of the Delaware, the main difference being that the bed of the valley is wider and the hillsides confining it less mountainous. From the mouth of the Lackawanna, at Pittston, where it enters, to Nanticoke, where it leaves the beautiful Wyoming Valley, the scenery along the river is wholly different. It flows through a broad and almost perfectly level, smooth plain—the Wyoming and Kingston flats—composed of a deep bed of diluvium or drift. On either side of this plain rise the rolling hills of the coal basin, and behind these the long, gentle slopes of the high mountain barriers, which frame in the whole scene. At Nanticoke the river turns abruptly northward out of the coal basin, through its steep barrier, by a highly picturesque pass, and then sweeps again as suddenly westward to run for several miles in a closely confined trench between the outer and the inner ridges of the basin. It does not, however, run round the western end of this, but at the ravine of the Shickshinny turns suddenly southward and cuts across its point, leaving a high, isolated hill of the coal strata on its western or right-hand side. Disengaging itself by a fine pass from the southern barrier of the coal basin, it passes out into an open valley and makes another rectangular bend, to run once more toward the west, parallel with the Nescopeck Mountain, which it follows to the neighborhood of Catawissa. Beyond this point it maintains its general course westward, somewhat south, parallel with the southern base of Montour Ridge, all the way to Northumberland, where it is joined by its great tributary, the West Branch. In some portions of this long reach of the river the scenery adjoining it is uncommonly rich and pleasing. A remarkably fine view up the river is presented from the hills on its west bank, a little below the mouth of Fishing Creek.

^aAnn. Rept. Chief of Engineers, U. S. Army, 1884, pt. 1, p. 873. ^bGeol. Pennsylvania, p. 48.

WEST BRANCH OF SUSQUEHANNA RIVER.

The drainage basin of the West Branch has an area of approximately 7,030 square miles, all of which is in Pennsylvania. The West Branch has its sources in the mountains of Cambria County at an elevation of not less than 2,000 feet above sea level. It flows first in a northward direction, receiving some tributaries from Indiana County on the west, into Clearfield County. Gradually bending to the right, it flows northeast between Center and Clinton counties, east through Clinton and Lycoming counties, and south between Union and Northumberland to join the main stream above Sunbury, Pa.

The watershed of this stream occupies the high table-lands of the north-central part of Pennsylvania. The crest of the watershed has an elevation of from 500 to 1,200 feet above sea level in the vicinity of the junction of the West Branch and the main stream, increasing to about 2,200 feet at its southwestern part; thence along its western side it maintains this latter elevation to its northern line, where, in the northern part of the Pine Creek basin, it attains an elevation of over 2,600 feet. Along the remainder of the northern crest the height quickly falls to about 1,200 feet, but rises again to about 2,000 feet along the eastern crest of the divide. The highest points in the State are along the crest of this watershed.

As far up as Queens Run the fall of this branch is comparatively small, while above that point, in the mountain region, it is much greater. Furthermore, the banks of both the stream and its tributaries above Queens Run are generally high, and there are few low grounds subject to overflow. Below Queens Run the river traverses a wide, fertile valley, without, however, overflowing its banks to any considerable extent. The bed of the river is generally gravel and sand, with a rocky ledge at places. In former years this portion of the drainage was largely used by lumbermen for floating logs. On most of the streams splash dams were built, sometimes flooding considerable areas, and serving to hold the logs which were sent down until a sufficient number were collected. The gates in the dam were then raised, letting the water out suddenly, so that the logs were carried down on the swell or wave to the next dam or to the main river, where the natural current would be sufficient to carry them along. As the forest areas are now largely cut off, but very little logging is done either on this or other portions of the river.

Professor Rogers describes this branch of the river as follows:^a

The upper part of the West Branch of the Susquehanna, and also its tributaries, the Sinnemahoning, Kettle Creek, Pine Creek, etc., draining the high plateau northwest of the Allegheny Mountains, flow through deep trenches in the horizontal strata, very analogous in their features to those which give passage to the Delaware and the Main or North Susquehanna, in the northeastern part of the State. From the mouth of the Sinnemahoning out into the Bald Eagle Valley,

^a Geol. Pennsylvania, p. 49.

the river hills are very high and steep, and admit extremely narrow strips of ground between their feet and the river, except near the openings of the lateral streams. The trough through which the lower half of Pine Creek flows is equally profound. Entering the valley between the Allegheny Mountains and the Bald Eagle ridge, the river pursues a beautiful winding course the whole way from Lockhaven to the neighborhood of Muncy, alternately sweeping toward the middle of the cultivated valley and back again, close in to the base of the steep and wood-covered ridge. Near Muncy it turns with a broad majestic curve round the end of the Bald Eagle Mountains, and in a few miles deflects from a southwest to a west course, through a highly fertile, richly cultivated open country, till it strikes the base of the Blue Hill, or range of red sandstone cliffs above Northumberland. Southwest of Muncy the river crosses a singular belt of deeply eroded country, full of conical hills.

NAVIGATION.

Information in regard to navigation along Susquehanna River and its tributaries is now only of historical interest. The official records of Pennsylvania and other papers published during the early part of the century show that from the first settlement Susquehanna River and its tributaries were regarded as a possible means of navigation.

In this relation the following quotation from Dager's report is of interest:^a

General Sullivan, to punish the Six Nations, late in August, 1779, organized a force of 3,000 men and moved north from Wyoming, the artillery and stores being drawn up the North Branch in 150 boats. At Tioga he was joined by General Clinton with 1,000 New York troops. The latter had marched from Albany to Otsego Lake, where, finding the water too low to float his bateaux, he built a dam across the stream, by which the lake was raised several feet, and when the dam was cut away the discharge wave floated his boats down to Tioga.

The Indians fled in dismay at the sight of a flood in the midst of the summer drought, believing it a signal of the displeasure of the Great Spirit. From this might be inferred that Otsego Lake could be made a reservoir to pay tribute to the river when there was an insufficient flow.

On March 9, 1777, an act was passed declaring Susquehanna River a public highway as far down as Wrights Ferry, and later on, March 31, 1785, the whole river through Pennsylvania was declared a public highway. An appropriation of £6,290 was made as early as April 11, 1791, for the improvement of the navigation of Susquehanna River. Other appropriations were made from time to time and active canals were maintained from Havre de Grace to the New York State line, on the West Branch from Northumberland to Lock Haven, and on the Juniata from Juniata Junction to Holidaysburg.

Between 1800 and 1830 several plans were proposed for connecting Susquehanna River with the Great Lakes and with Mississippi River. Nothing, however, came of any of these projects, and with the coming of the railroads the canals were gradually abandoned, being in most cases bought by the railroad companies. The North Branch extension, from the New York State line to Pittston, was abandoned in 1868 or 1869. The canal from Pittston down was used more or less

^a Ann. Rept. Chief of Engineers, U. S. Army, 1884, pt. 1, p. 876.

until the fall of 1874, but the high floods of the spring of 1875 caused so much damage that no boats were run after that date above Wilkesbarre. The Lackawanna Canal served as a feeder for the Wilkesbarre Branch until the spring of 1882, when it was abandoned to the Nanticoke dam. The canals below Sunbury were abandoned about 1890.

MEASUREMENTS OF FLOW.

The records of the measurements of flow in the Susquehanna drainage have been divided into two classes: First, those at regular stations, where systematic observations have been carried on over a series of years; second, those at miscellaneous stations, which consist of short or broken series of observations. There have been nine regular stations maintained, as given in the following list:

Gaging stations in the Susquehanna drainage basin.

| | Stream. | Location. | Date established. | Established by— |
|----|-------------|--------------------|-------------------|----------------------------------|
| A. | Susquehanna | Binghamton, N. Y. | Aug. 1, 1901 | United States Geological Survey. |
| B. | Chenango | do | do | Do. |
| C. | Susquehanna | Wilkesbarre, Pa. | Mar. 30, 1899 | Do. |
| D. | do | Danville, Pa. | Mar. 25, 1899 | Do. |
| E. | West Branch | Williamsport, Pa. | Mar. 4, 1895 | City engineer. |
| F. | do | Allenwood, Pa. | Mar. 25, 1899 | United States Geological Survey. |
| G. | Juniata | Newport, Pa. | Mar. 21, 1899 | Do. |
| H. | Susquehanna | Harrisburg, Pa. | Mar. 21, 1890 | Water board. |
| I. | do | McCalls Ferry, Pa. | May 17, 1902 | Cary T. Hutchinson. |

The locations of these stations are shown on fig. 1 (p. 11) by the letters in column 1 of the above table.

Miscellaneous records have been collected at the following points:

- Chemung River at Chemung, N. Y.
- Tioughnioga River at Chenango Forks, N. Y.
- Cayuta Creek at Waverly, N. Y.
- Chenango River at Oxford, N. Y.
- Eaton and Madison creeks.
- Diversions from Chenango River drainage.

The following pages give the data which have been collected at both regular and miscellaneous stations, also the results of the computations based upon these data.

SUSQUEHANNA RIVER AT BINGHAMTON, N. Y.

This gaging station was established by R. E. Horton July 31, 1901. The gage is located on the upstream side of the left span of the Washington street bridge. The bench mark is a chiseled draft on the corner of the left abutment on the upstream side. Its elevation

is 23.71 feet above gage datum. This bridge is located about 800 feet upstream from the junction of Chenango and Susquehanna rivers. A rift extends diagonally across the stream underneath the bridge. The gage is above a stretch of smooth water extending from the crest of the rift to the dam 2,800 feet upstream, and the gage readings are not affected by backwater from Chenango River at ordinary stages. On account of unfavorable conditions of Washington Street Bridge discharge measurements are made at Exchange Street Bridge, which is 1,900 feet upstream. At this place the channel is about 300 feet wide at low water and about 450 feet wide at high water, and is straight




FIG. 2.—Rating curve for Susquehanna River at Binghamton, N. Y.

for about 500 feet above and below the bridge. The bed is naturally gravel and small stones. Formerly a wooden footbridge was located at this point, and the channel was divided into three parts by two piers. Large stones were piled around the piers. At present a steel bridge occupies this site, and there is but one pier, above which are two rows of short piles and a quantity of small stones. The upper parts of the old piers have been removed, but the stone filling around them remains, leaving the river bed irregular and rough.

The velocity is good at low water and swift at high water. The lowest observed mean velocity is 0.72 foot per second.

Within the time for which this record has been kept, the gage height has ranged between 1.84 and 19.22 feet, and the estimated discharge between 400 and 60,300 cubic feet per second.

The gage is read twice daily by E. F. Weeks.

Discharge measurements of Susquehanna River at Binghamton, N. Y., 1901-4.

| Date. | Hydrographer. | Area. | Mean velocity. | Gage height. | Discharge. |
|--------------------|---------------|-------------------------|-----------------------------|--------------------|---------------------|
| | | <i>Square feet.</i> | <i>Feet per second.</i> | <i>Feet.</i> | <i>Second-feet.</i> |
| 1901. | | | | | |
| July 3. | E. C. Murphy | 891 | 1.06 | 2.12 | 947 |
| July 10. | do | 1,020 | 1.40 | 2.35 | 1,425 |
| July 30. | do | 847 | .72 | 1.99 | 608 |
| August 20. | do | 909 | 1.04 | 2.05 | 942 |
| August 20. | do | 923 | 1.03 | 2.06 | 952 |
| August 21. | do | 1,989 | 3.65 | 4.60 | 7,244 |
| August 22. | do | 1,439 | 2.61 | 3.19 | 3,752 |
| August 22. | do | 1,324 | 2.25 | 2.90 | 2,983 |
| August 23. | do | 1,189 | 1.83 | 2.60 | 2,176 |
| 1902. | | | | | |
| July 2. | E. C. Murphy | 1,790 | 3.26 | 4.08 | 5,839 |
| July 4. | do | 1,717 | 3.28 | 3.90 | 5,230 |
| July 14. | do | 1,320 | 2.32 | 2.96 | 3,064 |
| August 3. | do | 2,187 | 3.95 | 5.08 | 8,633 |
| August 4. | do | 1,952 | 3.53 | 4.59 | 6,902 |
| August 15. | do | 1,140 | 1.85 | 2.61 | 2,105 |
| August 16. | do | 1,103 | 1.74 | 2.50 | 1,920 |
| 1903. | | | | | |
| April 7. | E. C. Murphy | 1,773 | 3.35 | 4.13 | 5,946 |
| May 15. | do | 794 | .96 | 2.05 | 763 |
| May 19. | do | 746 | .86 | 1.96 | 640 |
| June 13. | C. C. Covert | 2,293 | 3.80 | 5.25 | 8,726 |
| August 22. | do | 1,241 | 2.07 | 2.65 | 2,572 |
| September 3. | do | 544 | 1.81 | 2.00 | 948 |
| October 1. | H. H. Halsey | 889 | 1.08 | 2.14 | 962 |
| October 11. | C. C. Covert | 6,446 | 7.71 | 16.32 | 49,707 |
| October 13. | do | 2,944 | 4.94 | 6.35 | 14,566 |
| 1904. | | | | | |
| March 8. | C. C. Covert | 3,975 | 3.58 | ^a 11.24 | 14,254 |
| March 12. | do | 2,846 | 2.60 | ^a 7.90 | 7,400 |
| April 8. | R. E. Horton | 2,524 | 4.50 | 6.94 | 11,118 |
| July 13. | C. C. Covert | 736 | 1.07 | 2.04 | 786 |
| September 10. | do | 825 | 1.29 | 2.13 | 1,061 |

^a Ice gorge 3 miles below.

Mean daily gage height, in feet, of Susquehanna River at Binghamton, N. Y., 1901-1904.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|------|------|-------|------|------|-------|-------|------|-------|------|------|-------|
| 1901. | | | | | | | | | | | | |
| 1. | | | | | | | | 1.84 | 2.21 | 2.19 | 2.04 | 2.49 |
| 2. | | | | | | | | 1.96 | 2.16 | 2.19 | 2.02 | 2.49 |
| 3. | | | | | | | | 1.91 | 2.16 | 2.16 | 1.94 | 2.64 |
| 4. | | | | | | | | 1.86 | 2.21 | 2.16 | 1.94 | 2.56 |
| 5. | | | | | | | | 1.86 | 2.18 | 2.14 | 1.96 | 2.64 |
| 6. | | | | | | | | 1.86 | 2.16 | 2.06 | 1.94 | 2.44 |
| 7. | | | | | | | | 1.86 | 2.06 | 2.04 | 1.94 | 2.32 |
| 8. | | | | | | | | 1.91 | 2.04 | 1.99 | 1.94 | 2.34 |
| 9. | | | | | | | | 1.91 | 2.04 | 2.04 | 1.92 | 2.44 |
| 10. | | | | | | | | 1.86 | 1.96 | 1.99 | 1.94 | 5.21 |
| 11. | | | | | | | | 1.94 | 1.98 | 2.02 | 1.92 | 6.12 |
| 12. | | | | | | | | 1.84 | 2.06 | 1.96 | 1.96 | 5.32 |
| 13. | | | | | | | | 1.91 | 2.04 | 1.99 | 2.49 | |
| 14. | | | | | | | | 1.96 | 2.01 | 2.06 | 2.96 | 4.62 |
| 15. | | | | | | | | 1.94 | 2.08 | 2.14 | 2.79 | 14.86 |
| 16. | | | | | | | | 1.94 | 2.16 | 2.32 | 2.54 | 13.74 |
| 17. | | | | | | | | 1.96 | 2.21 | 2.39 | 2.44 | 9.24 |
| 18. | | | | | | | | 2.11 | 2.36 | | 2.42 | 5.66 |
| 19. | | | | | | | | 2.16 | 2.36 | 2.26 | 2.36 | 4.29 |
| 20. | | | | | | | | 2.06 | 2.34 | 2.24 | 2.39 | 3.46 |
| 21. | | | | | | | | 3.66 | 2.24 | 2.24 | 2.39 | 2.96 |
| 22. | | | | | | | | 2.98 | 2.16 | 2.26 | 2.32 | 2.76 |
| 23. | | | | | | | | 2.61 | 2.06 | 2.24 | 2.29 | 3.74 |
| 24. | | | | | | | | 4.51 | 2.06 | 2.19 | 2.71 | 4.66 |
| 25. | | | | | | | | 3.86 | 2.06 | 2.14 | 3.42 | 3.96 |
| 26. | | | | | | | | 3.21 | 2.04 | 2.09 | 2.94 | 3.32 |
| 27. | | | | | | | | 2.78 | 2.00 | 2.06 | 2.52 | 3.26 |
| 28. | | | | | | | | 2.46 | | 2.06 | 2.24 | 2.86 |
| 29. | | | | | | | | 2.36 | 2.02 | 2.04 | 2.34 | 2.89 |
| 30. | | | | | | | | 2.26 | 2.04 | 2.04 | 2.39 | 3.69 |
| 31. | | | | | | | 1.91 | 2.31 | | 2.06 | | 4.06 |
| 1902. | | | | | | | | | | | | |
| 1. | 3.22 | 2.56 | 15.59 | 5.20 | 2.85 | 2.35 | 5.10 | 4.90 | 2.13 | 4.57 | 4.60 | 2.75 |
| 2. | 3.39 | 2.54 | 19.22 | 5.10 | 2.85 | 2.37 | 4.23 | 5.94 | 2.13 | 4.25 | 4.07 | 2.70 |
| 3. | 3.22 | 2.56 | 17.69 | 4.87 | 2.75 | 2.30 | 3.60 | 5.27 | 2.13 | 3.67 | 3.70 | 2.85 |
| 4. | 3.56 | 3.24 | 13.79 | 4.55 | 2.65 | 2.63 | 3.87 | 4.51 | 2.15 | 3.35 | 3.47 | 3.10 |
| 5. | 3.22 | 2.96 | 9.19 | 4.20 | 2.65 | 3.07 | 3.43 | 3.77 | 2.13 | 2.90 | 3.27 | 3.33 |
| 6. | 3.14 | 2.66 | 6.36 | | 2.67 | 2.85 | 3.97 | 3.45 | 2.07 | 2.93 | 3.13 | 3.18 |
| 7. | 3.02 | 2.72 | 5.59 | 3.90 | 2.57 | 2.63 | 4.43 | 3.37 | 2.05 | 2.83 | 3.07 | 2.93 |
| 8. | 2.82 | 2.74 | 5.34 | 3.83 | 2.53 | 2.57 | 4.35 | 3.10 | 2.10 | 2.77 | 3.00 | 2.77 |
| 9. | 2.66 | 2.79 | 5.04 | 4.75 | 2.45 | 2.65 | 4.00 | 2.97 | 2.07 | 2.75 | 2.83 | 2.73 |
| 10. | 2.54 | 2.72 | 5.74 | 5.40 | 2.45 | 2.60 | 4.03 | 2.83 | 2.25 | 2.67 | 2.77 | 2.85 |
| 11. | 2.52 | 2.84 | 5.59 | 5.70 | 2.35 | 2.47 | 4.77 | 2.73 | 2.25 | 2.55 | 2.70 | 2.83 |
| 12. | 2.46 | 2.64 | 7.81 | 5.45 | 2.53 | 2.47 | 4.37 | 2.75 | 2.25 | 2.67 | 2.65 | 2.95 |
| 13. | 2.57 | 2.42 | 11.19 | 5.03 | 2.30 | 2.57 | 3.43 | 2.80 | 2.23 | 2.77 | 2.65 | 2.83 |
| 14. | 2.46 | 2.34 | 11.94 | 4.70 | 2.30 | 2.57 | 3.03 | 2.75 | 2.15 | 2.90 | 2.75 | 2.67 |
| 15. | 2.34 | 2.24 | 10.61 | 4.35 | 2.27 | 2.65 | 2.75 | 2.59 | 2.15 | 2.90 | 2.67 | 2.75 |
| 16. | 2.32 | 2.26 | 8.42 | 3.97 | 2.25 | 2.65 | 2.70 | 2.49 | 2.10 | 2.87 | 2.55 | 2.93 |
| 17. | 2.24 | 2.19 | 11.82 | 3.70 | 2.25 | 2.53 | 2.63 | 2.40 | 2.05 | 2.75 | 2.55 | 7.13 |
| 18. | 2.22 | 2.14 | 11.87 | 3.53 | 2.15 | 2.55 | 2.65 | 2.35 | 2.05 | 2.60 | 2.53 | 7.65 |
| 19. | 2.42 | 2.16 | 9.47 | 3.37 | 2.15 | 2.50 | 2.65 | 2.30 | 2.05 | 2.50 | 2.47 | 6.70 |
| 20. | 2.64 | 2.16 | 6.82 | 3.17 | 2.15 | 2.50 | 7.27 | 2.30 | 2.00 | 2.60 | 2.50 | 5.87 |
| 21. | 2.14 | 2.19 | 5.72 | 3.07 | 2.25 | 2.45 | 10.90 | 2.35 | 1.95 | 2.75 | 2.45 | 5.28 |
| 22. | 2.56 | 2.12 | 5.49 | 2.97 | 2.33 | 2.47 | 11.35 | 2.35 | 1.95 | 2.73 | 2.45 | 9.45 |
| 23. | 4.76 | 2.24 | 5.61 | 2.85 | 2.35 | 2.57 | 10.00 | 2.27 | 2.00 | 2.57 | 2.47 | 10.62 |
| 24. | 5.16 | 2.29 | 5.76 | 2.67 | 2.25 | 2.50 | 8.90 | 2.27 | 1.97 | 2.53 | 2.45 | 8.20 |
| 25. | 4.22 | 2.16 | 5.44 | 2.63 | 2.20 | 2.37 | 8.10 | 2.25 | 2.00 | 2.53 | 2.47 | 6.28 |
| 26. | 3.39 | 2.12 | 4.92 | 2.55 | 2.37 | 2.27 | 6.37 | 2.25 | 2.35 | 2.50 | 2.53 | 5.63 |
| 27. | 3.14 | 2.42 | 4.56 | 2.50 | 2.55 | 2.37 | 5.40 | 2.20 | 2.63 | 2.45 | 2.70 | 4.98 |
| 28. | 3.67 | 5.46 | 4.44 | 2.53 | 2.53 | 2.37 | 7.51 | 2.25 | 2.55 | 5.95 | 2.85 | 4.48 |
| 29. | 4.02 | | 5.30 | 2.53 | 2.47 | 2.85 | 6.07 | 2.27 | 5.00 | 8.30 | 2.90 | 3.95 |
| 30. | 3.34 | | 5.70 | 2.60 | 2.40 | 6.98 | 5.00 | 2.30 | 3.80 | 7.15 | 2.83 | 3.81 |
| 31. | 2.86 | | 5.53 | | 2.35 | | 5.55 | 2.17 | | 5.53 | | 3.63 |

Mean daily gage height, in feet, of Susquehanna River at Binghamton, N. Y.,
1901-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|-------|-------|-------|-------|------|-------|-------|-------|-------|-------|-------|------|
| 1903. | | | | | | | | | | | | |
| 1 | 3.40 | 8.60 | 12.92 | 6.65 | 2.33 | 1.85 | 3.35 | 2.55 | 6.55 | 2.07 | 3.25 | 2.62 |
| 2 | 3.30 | 7.20 | 10.82 | 5.85 | 2.27 | 1.87 | 3.00 | 2.43 | 5.17 | 2.13 | 3.07 | 2.69 |
| 3 | 3.70 | 7.23 | 7.75 | 5.15 | 2.25 | 1.85 | 2.73 | 2.30 | 4.30 | 2.15 | 2.95 | 2.65 |
| 4 | 5.15 | 8.27 | 6.17 | 5.05 | 2.25 | 1.80 | 2.57 | 2.25 | 3.70 | 2.10 | 2.85 | 2.65 |
| 5 | 5.33 | 9.60 | 5.63 | 4.80 | 2.23 | 1.83 | 2.45 | 2.50 | ----- | 2.13 | 2.85 | 2.62 |
| 6 | 4.63 | 7.95 | 6.43 | 4.33 | 2.20 | 1.80 | 2.35 | 3.17 | ----- | 2.25 | 3.05 | 2.47 |
| 7 | 3.83 | 6.35 | 6.30 | 4.17 | 2.17 | 1.77 | 2.27 | 3.25 | ----- | 2.35 | 3.17 | 2.52 |
| 8 | 3.75 | 5.00 | 6.35 | 4.95 | 2.15 | 1.85 | 2.25 | 3.03 | 2.70 | 2.70 | 2.97 | 2.52 |
| 9 | 3.45 | 4.65 | 10.75 | 5.63 | 2.15 | 1.80 | 2.20 | 2.80 | 2.67 | 7.97 | 2.85 | 2.57 |
| 10 | 6.05 | 4.33 | 10.55 | 5.05 | 2.10 | 1.80 | 2.17 | 2.63 | 2.55 | 15.49 | 2.75 | 2.29 |
| 11 | 5.55 | 4.20 | 11.55 | 4.70 | 2.05 | 1.80 | 2.13 | 2.73 | 2.65 | 16.35 | 2.72 | 2.45 |
| 12 | 5.95 | 5.47 | 11.47 | 4.40 | 2.05 | 2.77 | 2.10 | 2.83 | 2.67 | 12.12 | 2.67 | 2.55 |
| 13 | 6.00 | 6.95 | 9.57 | 4.03 | 2.05 | 5.35 | 2.10 | 2.70 | 2.60 | 8.17 | 2.62 | 2.65 |
| 14 | 6.07 | 6.07 | 7.75 | 3.73 | 2.05 | 3.45 | 2.07 | 2.60 | 2.50 | 5.99 | 2.59 | 3.17 |
| 15 | 5.85 | 4.97 | 6.65 | 4.05 | 2.05 | 3.03 | 2.13 | 2.55 | 2.37 | 5.09 | 2.52 | 3.22 |
| 16 | 5.80 | 4.40 | 6.03 | 3.97 | 2.00 | 2.63 | 2.07 | 2.43 | 2.30 | 4.49 | 2.52 | 3.12 |
| 17 | 5.53 | 3.65 | 5.55 | 3.73 | 2.00 | 2.50 | 2.05 | 2.33 | 2.37 | 4.22 | 5.70 | 2.97 |
| 18 | 5.10 | 3.13 | 5.45 | 3.47 | 2.00 | 2.45 | 2.10 | 2.30 | 2.50 | 7.85 | 6.89 | 2.85 |
| 19 | 4.60 | 3.27 | 5.13 | 3.23 | 2.00 | 2.35 | 2.17 | 2.27 | 2.45 | 7.59 | 5.45 | 2.79 |
| 20 | 4.15 | 3.57 | 4.75 | 3.07 | 1.95 | 2.30 | 2.15 | 2.27 | 2.45 | 6.55 | 4.25 | 2.62 |
| 21 | 4.30 | 3.75 | 4.50 | 2.90 | 1.95 | 2.53 | 2.23 | 2.45 | 2.35 | 5.47 | 3.67 | 4.37 |
| 22 | 6.53 | 3.53 | 5.60 | 2.77 | 1.95 | 3.77 | 2.25 | 2.65 | 2.27 | 4.82 | 3.35 | 5.39 |
| 23 | 6.63 | 3.55 | 7.57 | 2.70 | 1.95 | 4.45 | 3.50 | 2.40 | 2.20 | 4.25 | 3.29 | 4.97 |
| 24 | 5.63 | 3.25 | 12.11 | 2.65 | 1.87 | 5.03 | 4.65 | 2.30 | 2.23 | 4.02 | 3.39 | 4.25 |
| 25 | 4.80 | 3.20 | 11.48 | 2.60 | 1.85 | 4.43 | 3.43 | 2.25 | 2.20 | 3.92 | 3.32 | 4.05 |
| 26 | 4.53 | 3.15 | 9.20 | 2.57 | 1.85 | 3.97 | 2.80 | 2.70 | 2.15 | 3.67 | 3.05 | 3.79 |
| 27 | 4.23 | 2.95 | 7.15 | 2.50 | 1.87 | 3.40 | 2.60 | 4.13 | 2.10 | 3.52 | 2.87 | 3.72 |
| 28 | 4.20 | 6.80 | 6.07 | 2.45 | 1.90 | 2.95 | 2.45 | 3.57 | 2.10 | 3.45 | 2.79 | 3.45 |
| 29 | 5.35 | ----- | 5.70 | 2.40 | 1.90 | 3.03 | 2.35 | 10.63 | 2.10 | 3.45 | 2.85 | 3.57 |
| 30 | 9.68 | ----- | 5.30 | 2.35 | 1.87 | 3.65 | 2.47 | 10.53 | 2.07 | 3.42 | 2.85 | 3.65 |
| 31 | 10.23 | ----- | 6.20 | ----- | 1.85 | ----- | 2.70 | 8.57 | ----- | 3.35 | ----- | 3.75 |
| 1904. | | | | | | | | | | | | |
| 1 | 3.28 | 3.67 | 3.57 | 7.72 | 5.06 | 2.46 | 2.02 | 2.40 | 2.28 | 4.12 | 3.08 | 2.98 |
| 2 | 3.35 | 3.40 | 3.29 | 9.02 | 4.53 | 2.48 | 1.99 | 2.35 | 2.25 | 3.35 | 3.00 | 2.82 |
| 3 | 3.42 | 3.59 | 3.92 | ----- | 4.08 | 2.38 | 2.14 | 2.98 | 2.28 | 2.90 | 2.92 | 2.80 |
| 4 | 3.88 | 3.67 | 6.65 | 6.95 | 3.68 | 2.36 | 2.14 | 2.95 | 2.28 | 2.80 | 2.88 | 2.75 |
| 5 | 3.52 | 3.55 | 8.48 | 6.20 | 3.51 | 2.38 | 2.06 | 2.60 | 2.20 | 2.68 | 2.82 | 2.85 |
| 6 | 3.58 | 3.15 | 7.68 | 6.15 | 3.33 | 2.41 | 2.09 | 3.52 | 2.22 | 2.62 | 2.80 | 2.68 |
| 7 | 3.30 | 4.42 | 7.52 | 6.35 | 3.13 | 2.46 | 2.04 | 3.40 | 2.28 | 2.62 | 2.92 | 2.68 |
| 8 | 3.28 | 10.49 | 11.40 | 6.98 | 2.98 | 2.57 | 2.04 | 2.72 | 2.22 | 2.52 | 2.90 | 2.60 |
| 9 | 3.15 | 11.92 | 13.62 | 7.14 | 2.86 | 3.67 | 2.04 | 2.50 | 2.22 | 2.45 | 2.80 | 2.60 |
| 10 | 3.20 | 10.85 | 12.25 | 8.74 | 2.80 | 4.23 | 2.04 | 2.38 | 2.20 | 2.42 | 2.75 | 2.68 |
| 11 | 3.10 | 8.62 | 9.80 | 8.24 | 2.69 | 3.43 | 2.04 | 2.50 | 2.18 | 2.40 | 2.75 | 2.58 |
| 12 | 2.98 | 7.15 | 8.02 | 6.94 | 2.65 | 2.93 | 1.99 | 2.45 | 2.18 | 2.88 | 2.75 | 2.98 |
| 13 | 2.78 | 6.09 | 6.88 | 6.09 | 2.65 | 2.65 | 2.04 | 2.30 | 2.20 | 5.60 | 2.70 | 2.50 |
| 14 | 2.72 | 5.27 | 6.08 | 5.51 | 2.49 | 2.50 | 2.03 | 2.22 | 2.15 | 4.68 | 2.70 | 2.58 |
| 15 | 2.85 | 4.77 | 5.30 | 4.97 | 2.59 | 2.43 | 1.95 | 2.20 | 3.00 | 3.65 | 2.68 | 2.58 |
| 16 | 3.05 | 6.12 | 4.75 | 4.61 | 3.22 | 2.45 | 1.92 | 2.28 | 3.10 | 3.45 | 2.70 | 2.58 |
| 17 | 2.85 | 6.85 | 4.28 | 4.49 | 3.45 | 2.33 | 2.05 | 2.22 | 2.82 | 2.95 | 2.78 | 2.60 |
| 18 | 3.00 | 6.07 | 3.85 | 4.39 | 3.17 | 2.33 | 2.28 | 2.18 | 2.55 | 2.80 | 2.75 | 2.48 |
| 19 | 2.98 | 5.67 | 3.55 | 4.49 | 2.92 | 2.23 | 2.10 | 2.18 | 2.42 | 2.70 | 2.65 | 2.60 |
| 20 | 3.08 | 5.22 | 3.92 | 4.37 | 3.22 | 2.17 | 2.05 | 2.22 | 2.35 | 2.62 | 2.65 | 2.40 |
| 21 | 3.80 | 4.72 | 4.45 | 4.17 | 3.05 | 2.20 | 1.98 | 2.90 | 2.30 | 5.95 | 2.82 | 2.45 |
| 22 | 2.78 | 4.52 | 4.30 | 3.97 | 2.75 | 2.13 | 2.00 | 3.18 | 2.30 | 7.43 | 3.58 | 2.58 |
| 23 | 7.02 | 4.92 | 7.42 | 3.97 | 2.67 | 2.24 | 1.98 | 4.55 | 2.28 | 6.95 | 3.72 | 2.40 |
| 24 | 7.82 | 5.72 | 11.40 | 3.77 | 2.59 | 2.09 | 2.00 | 4.20 | 2.18 | 5.32 | 3.55 | 2.55 |
| 25 | 8.27 | 5.52 | 12.12 | 3.79 | 2.62 | 2.06 | 2.02 | 3.38 | 3.52 | 4.40 | 3.38 | 3.08 |
| 26 | 6.85 | 4.67 | 15.92 | 3.96 | 2.52 | 2.02 | 2.02 | 2.92 | 3.25 | 4.40 | 3.32 | 3.15 |
| 27 | 5.95 | 4.19 | 15.70 | 3.93 | 2.49 | 1.99 | 2.05 | 2.78 | 3.22 | 4.35 | 3.18 | 3.40 |
| 28 | 5.25 | 3.75 | 12.62 | 5.83 | 2.45 | 1.99 | 2.52 | ----- | 2.85 | 3.92 | 2.90 | 8.60 |
| 29 | 4.42 | 3.67 | 8.50 | 6.36 | 2.36 | 2.04 | 2.58 | 2.48 | 2.65 | 3.65 | 2.78 | 9.80 |
| 30 | 4.27 | ----- | 6.90 | 5.63 | 2.36 | 1.99 | 3.12 | 2.38 | 2.80 | 3.42 | 2.88 | 7.05 |
| 31 | 3.89 | ----- | 6.72 | ----- | 2.36 | ----- | 2.65 | 2.35 | ----- | 3.18 | ----- | 5.25 |

^a Anchor ice. January 6 river frozen nearly across.

^b Heavy anchor ice. River frozen over 2,000 feet downstream from junction of the two rivers. Ice gorge causes backwater March 4-15.

^c Current of stream very sluggish.

Rating table for Susquehanna River at Binghamton, N. Y., for 1901 to 1904, inclusive.

| Gage height. | Discharge. | Gage height. | Discharge. | Gage height. | Discharge. | Gage height. | Discharge. |
|--------------|---------------------|--------------|---------------------|--------------|---------------------|--------------|---------------------|
| <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> |
| 1.75 | 210 | 3.9 | 5,255 | 7.2 | 15,260 | 11.6 | 30,860 |
| 1.8 | 315 | 4.0 | 5,510 | 7.4 | 15,920 | 11.8 | 31,580 |
| 1.9 | 525 | 4.1 | 5,770 | 7.6 | 16,590 | 12.0 | 32,300 |
| 2.0 | 740 | 4.2 | 6,030 | 7.8 | 17,270 | 12.2 | 33,020 |
| 2.1 | 960 | 4.3 | 6,300 | 8.0 | 17,950 | 12.4 | 33,740 |
| 2.2 | 1,180 | 4.4 | 6,570 | 8.2 | 18,650 | 12.6 | 34,470 |
| 2.3 | 1,400 | 4.5 | 6,845 | 8.4 | 19,350 | 12.8 | 35,210 |
| 2.4 | 1,625 | 4.6 | 7,125 | 8.6 | 20,060 | 13.0 | 35,950 |
| 2.5 | 1,855 | 4.7 | 7,405 | 8.8 | 20,780 | 13.5 | 37,820 |
| 2.6 | 2,085 | 4.8 | 7,690 | 9.0 | 21,500 | 14.0 | 39,720 |
| 2.7 | 2,315 | 4.9 | 7,980 | 9.2 | 22,220 | 14.5 | 41,650 |
| 2.8 | 2,545 | 5.0 | 8,280 | 9.4 | 22,940 | 15.0 | 43,600 |
| 2.9 | 2,785 | 5.2 | 8,880 | 9.6 | 23,660 | 15.5 | 45,550 |
| 3.0 | 3,025 | 5.4 | 9,495 | 9.8 | 24,380 | 16.0 | 47,500 |
| 3.1 | 3,265 | 5.6 | 10,120 | 10.0 | 25,100 | 16.5 | 49,500 |
| 3.2 | 3,505 | 5.8 | 10,760 | 10.2 | 25,820 | 17.0 | 51,500 |
| 3.3 | 3,755 | 6.0 | 11,400 | 10.4 | 26,540 | 17.5 | 53,500 |
| 3.4 | 4,005 | 6.2 | 12,040 | 10.6 | 27,260 | 18.0 | 55,500 |
| 3.5 | 4,255 | 6.4 | 12,680 | 10.8 | 27,980 | 18.5 | 57,500 |
| 3.6 | 4,505 | 6.6 | 13,320 | 11.0 | 28,700 | 19.0 | 59,500 |
| 3.7 | 4,755 | 6.8 | 13,960 | 11.2 | 29,420 | 19.5 | 61,500 |
| 3.8 | 5,005 | 7.0 | 14,600 | 11.4 | 30,140 | 20.0 | 63,500 |

Mean daily discharge, in second-feet, of Susquehanna River at Binghamton, N. Y., 1901-1904.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|------|------|------|------|------|-------|-------|-------|-------|-------|-------|--------|
| 1901. | | | | | | | | | | | | |
| 1 | | | | | | | | 399 | 1,180 | 1,180 | 850 | 1,855 |
| 2 | | | | | | | | 652 | 1,070 | 1,180 | 784 | 1,855 |
| 3 | | | | | | | | 546 | 1,070 | 1,070 | 609 | 2,200 |
| 4 | | | | | | | | 441 | 1,180 | 1,070 | 609 | 1,970 |
| 5 | | | | | | | | 441 | 1,136 | 1,070 | 652 | 2,200 |
| 6 | | | | | | | | 441 | 1,070 | 850 | 609 | 1,740 |
| 7 | | | | | | | | 441 | 850 | 850 | 609 | 1,444 |
| 8 | | | | | | | | 546 | 850 | 718 | 609 | 1,510 |
| 9 | | | | | | | | 546 | 850 | 850 | 567 | 1,740 |
| 10 | | | | | | | | 441 | 652 | 718 | 609 | 8,880 |
| 11 | | | | | | | | 609 | 696 | 784 | 567 | 11,720 |
| 12 | | | | | | | | 609 | 850 | 652 | 652 | 9,185 |
| 13 | | | | | | | | 546 | 850 | 718 | 1,855 | 8,655 |
| 14 | | | | | | | | 652 | 740 | 850 | 2,905 | 7,125 |
| 15 | | | | | | | | 609 | 916 | 1,070 | 2,545 | 43,210 |
| 16 | | | | | | | | 609 | 1,070 | 1,444 | 1,970 | 38,580 |
| 17 | | | | | | | | 652 | 1,180 | 1,625 | 1,740 | 22,220 |
| 18 | | | | | | | | 982 | 1,510 | 1,458 | 1,671 | 10,280 |
| 19 | | | | | | | | 1,092 | 1,510 | 1,290 | 1,510 | 6,300 |
| 20 | | | | | | | | 872 | 1,510 | 1,290 | 1,625 | 4,130 |
| 21 | | | | | | | | 4,630 | 1,290 | 1,290 | 1,625 | 2,905 |
| 22 | | | | | | | | 2,977 | 1,070 | 1,290 | 1,444 | 2,430 |

Mean daily discharge, in second-feet, of Susquehanna River at Binghamton,
N. Y., 1901-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|--------|--------|--------|--------|-------|--------|--------|--------|--------|--------|--------|--------|
| 1901. | | | | | | | | | | | | |
| 23 | | | | | | | | 2,085 | 850 | 1,290 | 1,400 | 4,880 |
| 24 | | | | | | | | 6,845 | 850 | 1,180 | 2,315 | 7,265 |
| 25 | | | | | | | | 5,130 | 850 | 1,070 | 4,055 | 5,380 |
| 26 | | | | | | | | 3,505 | 850 | 960 | 2,905 | 3,805 |
| 27 | | | | | | | | 2,499 | 740 | 850 | 1,901 | 3,630 |
| 28 | | | | | | | | 1,740 | 762 | 850 | 1,290 | 2,665 |
| 29 | | | | | | | | 1,570 | 784 | 850 | 1,510 | 2,785 |
| 30 | | | | | | | | 1,290 | 850 | 850 | 1,625 | 4,755 |
| 31 | | | | | | | | 1,400 | | 850 | | 5,640 |
| 1902. | | | | | | | | | | | | |
| 1 | 3,555 | 1,970 | 45,940 | 8,880 | 2,665 | 1,510 | 8,580 | 7,980 | 1,026 | 6,985 | 7,125 | 2,490 |
| 2 | 4,005 | 1,970 | 60,300 | 8,580 | 2,665 | 1,554 | 6,165 | 11,240 | 1,026 | 6,165 | 5,640 | 2,384 |
| 3 | 3,555 | 1,970 | 54,300 | 7,835 | 2,430 | 1,400 | 4,505 | 9,030 | 1,026 | 4,680 | 4,755 | 2,665 |
| 4 | 4,380 | 3,630 | 38,960 | 6,985 | 2,300 | 2,154 | 5,180 | 6,845 | 1,070 | 3,880 | 4,180 | 3,265 |
| 5 | 3,555 | 2,905 | 22,220 | 6,030 | 2,200 | 3,135 | 4,080 | 4,930 | 1,026 | 2,785 | 3,680 | 3,830 |
| 6 | 3,385 | 2,200 | 12,520 | 5,640 | 2,246 | 2,665 | 5,455 | 4,130 | 894 | 2,857 | 3,337 | 3,460 |
| 7 | 3,075 | 2,361 | 10,120 | 5,255 | 2,016 | 2,154 | 6,705 | 3,930 | 850 | 2,617 | 3,193 | 2,857 |
| 8 | 2,593 | 2,430 | 9,340 | 5,130 | 1,924 | 2,016 | 6,455 | 3,265 | 960 | 2,476 | 3,025 | 2,476 |
| 9 | 2,200 | 2,545 | 8,430 | 7,545 | 1,740 | 2,200 | 5,510 | 2,953 | 894 | 2,430 | 2,617 | 2,384 |
| 10 | 1,970 | 2,361 | 10,600 | 9,495 | 1,740 | 2,085 | 5,640 | 2,617 | 1,290 | 2,246 | 2,476 | 2,665 |
| 11 | 1,901 | 2,665 | 10,120 | 10,440 | 1,510 | 1,786 | 7,545 | 2,384 | 1,290 | 1,970 | 2,315 | 2,617 |
| 12 | 1,740 | 2,200 | 17,270 | 9,650 | 1,466 | 1,786 | 6,455 | 2,430 | 1,290 | 2,246 | 2,200 | 2,905 |
| 13 | 2,016 | 1,671 | 29,420 | 8,430 | 1,400 | 2,016 | 4,080 | 2,545 | 1,246 | 2,476 | 2,200 | 2,617 |
| 14 | 1,740 | 1,510 | 31,940 | 7,405 | 1,400 | 2,016 | 3,100 | 2,430 | 1,070 | 2,785 | 2,430 | 2,246 |
| 15 | 1,510 | 1,290 | 27,260 | 6,435 | 1,334 | 2,200 | 2,430 | 2,085 | 1,070 | 2,785 | 2,246 | 2,430 |
| 16 | 1,444 | 1,290 | 19,350 | 5,880 | 1,290 | 2,200 | 2,315 | 1,855 | 960 | 2,713 | 1,970 | 2,857 |
| 17 | 1,290 | 1,180 | 31,580 | 4,755 | 1,290 | 1,924 | 2,154 | 1,625 | 850 | 2,430 | 1,970 | 14,930 |
| 18 | 1,224 | 1,070 | 31,940 | 4,390 | 1,070 | 1,970 | 2,200 | 1,510 | 850 | 2,085 | 1,924 | 16,760 |
| 19 | 1,671 | 1,070 | 23,300 | 3,930 | 1,070 | 1,855 | 2,200 | 1,400 | 850 | 1,855 | 1,786 | 13,640 |
| 20 | 2,200 | 1,070 | 13,960 | 3,435 | 1,070 | 1,855 | 15,590 | 1,400 | 740 | 2,085 | 1,855 | 10,920 |
| 21 | 1,070 | 1,180 | 10,440 | 3,195 | 1,290 | 1,740 | 28,340 | 1,510 | 630 | 2,430 | 1,740 | 9,185 |
| 22 | 1,970 | 1,004 | 9,805 | 2,953 | 1,466 | 1,786 | 29,960 | 1,510 | 630 | 2,384 | 1,740 | 23,120 |
| 23 | 7,545 | 1,290 | 10,120 | 2,665 | 1,510 | 2,016 | 25,100 | 1,334 | 740 | 2,016 | 1,786 | 27,260 |
| 24 | 8,730 | 1,400 | 10,600 | 2,246 | 1,290 | 1,855 | 21,140 | 1,334 | 674 | 1,924 | 1,740 | 18,650 |
| 25 | 6,030 | 1,070 | 9,650 | 2,154 | 1,180 | 1,554 | 18,300 | 1,290 | 740 | 1,924 | 1,786 | 12,360 |
| 26 | 4,005 | 1,004 | 7,980 | 1,970 | 1,554 | 1,334 | 12,520 | 1,290 | 1,510 | 1,855 | 1,924 | 10,280 |
| 27 | 3,385 | 1,671 | 6,985 | 1,855 | 1,970 | 1,554 | 9,495 | 1,180 | 2,154 | 1,740 | 2,315 | 8,280 |
| 28 | 4,680 | 9,650 | 6,705 | 1,924 | 1,924 | 1,554 | 16,250 | 1,290 | 1,970 | 11,240 | 2,665 | 6,845 |
| 29 | 5,510 | | 9,185 | 1,924 | 1,786 | 2,665 | 11,560 | 1,334 | 8,280 | 19,000 | 2,785 | 5,380 |
| 30 | 3,880 | | 10,440 | 2,085 | 1,625 | 14,600 | 8,280 | 1,400 | 5,005 | 15,085 | 2,617 | 5,005 |
| 31 | 2,665 | | 9,960 | | 1,510 | | 9,960 | 1,114 | | 9,960 | | 4,580 |
| 1903. | | | | | | | | | | | | |
| 1 | 4,005 | 20,060 | 35,580 | 13,480 | 1,466 | 420 | 3,880 | 1,970 | 13,160 | 894 | 3,630 | 2,131 |
| 2 | 3,755 | 15,260 | 27,980 | 10,920 | 1,334 | 462 | 3,025 | 1,694 | 8,730 | 1,026 | 3,193 | 2,315 |
| 3 | 4,755 | 15,260 | 17,100 | 8,730 | 1,290 | 420 | 2,384 | 1,400 | 6,800 | 1,070 | 2,905 | 2,200 |
| 4 | 8,730 | 19,000 | 11,880 | 8,430 | 1,290 | 315 | 2,016 | 1,290 | 4,755 | 960 | 2,665 | 2,200 |
| 5 | 9,340 | 23,660 | 10,280 | 7,690 | 1,246 | 378 | 1,740 | 1,855 | 3,535 | 1,026 | 2,665 | 2,131 |
| 6 | 7,265 | 17,780 | 12,840 | 6,435 | 1,180 | 315 | 1,510 | 3,435 | 3,535 | 1,290 | 3,145 | 1,786 |
| 7 | 5,080 | 12,520 | 12,360 | 5,900 | 1,114 | 252 | 1,334 | 3,630 | 3,535 | 1,510 | 3,435 | 1,901 |
| 8 | 4,880 | 8,280 | 12,520 | 8,130 | 1,070 | 420 | 1,290 | 3,097 | 2,815 | 2,315 | 2,953 | 1,901 |
| 9 | 4,130 | 7,265 | 27,800 | 10,280 | 1,070 | 315 | 1,180 | 2,545 | 2,246 | 17,950 | 2,665 | 2,016 |
| 10 | 11,560 | 6,435 | 27,080 | 8,430 | 960 | 315 | 1,114 | 2,154 | 1,970 | 45,550 | 2,430 | 1,400 |
| 11 | 9,960 | 6,030 | 30,680 | 7,405 | 850 | 315 | 1,026 | 2,384 | 2,200 | 48,900 | 2,361 | 1,740 |
| 12 | 11,240 | 9,650 | 30,500 | 6,570 | 850 | 2,476 | 960 | 2,617 | 2,246 | 32,660 | 2,246 | 1,970 |
| 13 | 11,400 | 14,440 | 23,660 | 5,640 | 850 | 9,340 | 960 | 2,315 | 2,085 | 18,650 | 2,131 | 2,200 |
| 14 | 11,560 | 11,560 | 17,100 | 4,830 | 850 | 4,130 | 894 | 2,085 | 1,855 | 11,400 | 2,085 | 3,435 |
| 15 | 10,920 | 8,130 | 13,480 | 5,640 | 850 | 3,097 | 1,026 | 1,970 | 1,556 | 8,580 | 1,901 | 3,555 |
| 16 | 10,760 | 6,570 | 11,560 | 5,430 | 740 | 2,154 | 894 | 1,697 | 1,400 | 6,845 | 1,901 | 3,313 |
| 17 | 9,960 | 4,630 | 9,960 | 4,830 | 740 | 1,855 | 850 | 1,466 | 1,556 | 6,030 | 10,440 | 2,953 |
| 18 | 8,580 | 3,340 | 9,960 | 4,180 | 740 | 1,740 | 960 | 1,400 | 1,855 | 16,420 | 14,280 | 2,665 |
| 19 | 7,125 | 3,680 | 8,730 | 3,580 | 740 | 1,510 | 1,114 | 1,334 | 1,740 | 17,610 | 9,650 | 2,545 |
| 20 | 5,900 | 4,430 | 7,545 | 3,193 | 630 | 1,400 | 1,070 | 1,334 | 1,740 | 13,160 | 6,165 | 2,131 |
| 21 | 6,300 | 4,880 | 6,845 | 2,785 | 630 | 1,924 | 1,246 | 1,740 | 1,510 | 9,650 | 4,680 | 6,435 |
| 22 | 13,160 | 4,330 | 10,120 | 2,476 | 630 | 4,930 | 1,290 | 2,200 | 1,334 | 7,690 | 3,880 | 9,495 |
| 23 | 13,480 | 4,380 | 16,590 | 2,315 | 630 | 6,705 | 4,255 | 1,625 | 1,180 | 6,165 | 3,755 | 8,130 |
| 24 | 10,280 | 3,630 | 32,660 | 2,200 | 462 | 8,430 | 7,265 | 1,400 | 1,246 | 5,510 | 4,005 | 6,165 |
| 25 | 7,690 | 3,505 | 30,500 | 2,085 | 420 | 6,705 | 4,080 | 1,290 | 1,180 | 5,305 | 3,805 | 5,640 |
| 26 | 6,985 | 3,385 | 22,220 | 2,016 | 420 | 5,430 | 2,545 | 2,315 | 1,070 | 4,680 | 3,145 | 5,005 |
| 27 | 6,165 | 2,905 | 15,095 | 1,855 | 462 | 4,005 | 2,085 | 5,900 | 960 | 4,305 | 2,713 | 4,805 |
| 28 | 6,030 | 13,960 | 11,560 | 1,740 | 525 | 2,905 | 1,740 | 4,430 | 960 | 4,130 | 2,545 | 4,130 |
| 29 | 9,340 | | 10,440 | 1,625 | 525 | 3,097 | 1,510 | 27,260 | 960 | 4,130 | 2,665 | 4,430 |
| 30 | 24,020 | | 9,185 | 1,510 | 462 | 4,630 | 1,786 | 26,900 | 894 | 4,055 | 2,665 | 4,630 |
| 31 | 25,820 | | 12,040 | | 420 | | 2,315 | 20,060 | | 3,880 | | 4,880 |

Mean daily discharge, in second-feet, of Susquehanna River at Binghamton, N. Y., 1901-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|--------|--------|--------|--------|-------|-------|-------|-------|-------|--------|-------|--------|
| 1904. | | | | | | | | | | | | |
| 1 | 3,705 | 4,680 | 4,490 | 16,990 | 8,490 | 1,763 | 784 | 1,625 | 1,356 | 5,770 | 3,217 | 2,977 |
| 2 | 3,880 | 4,005 | 3,790 | 21,500 | 6,985 | 1,809 | 718 | 1,510 | 1,290 | 3,880 | 3,025 | 2,593 |
| 3 | 4,055 | 4,480 | 5,905 | 17,950 | 5,770 | 1,579 | 1,048 | 2,977 | 1,356 | 2,785 | 2,833 | 2,665 |
| 4 | 5,205 | 4,680 | 6,740 | 14,440 | 4,705 | 1,532 | 1,048 | 2,905 | 1,356 | 2,545 | 2,737 | 2,315 |
| 5 | 4,305 | 4,380 | 9,815 | 12,040 | 4,280 | 1,579 | 872 | 2,085 | 1,180 | 2,269 | 2,593 | 2,665 |
| 6 | 4,455 | 3,385 | 8,410 | 11,880 | 3,830 | 1,648 | 938 | 4,905 | 1,224 | 2,131 | 2,545 | 2,269 |
| 7 | 3,755 | 6,624 | 10,100 | 12,520 | 3,337 | 1,763 | 828 | 4,005 | 1,356 | 2,131 | 2,833 | 2,269 |
| 8 | 3,705 | 26,864 | 15,070 | 14,600 | 2,977 | 2,016 | 828 | 2,361 | 1,224 | 1,901 | 2,785 | 2,085 |
| 9 | 3,385 | 32,012 | 19,100 | 15,095 | 2,689 | 4,680 | 828 | 1,855 | 1,224 | 1,740 | 2,545 | 2,085 |
| 10 | 3,505 | 28,160 | 16,600 | 20,600 | 2,545 | 6,165 | 828 | 1,579 | 1,180 | 1,671 | 2,430 | 2,269 |
| 11 | 3,265 | 20,132 | 12,190 | 18,825 | 2,292 | 4,080 | 828 | 1,855 | 1,136 | 1,625 | 2,430 | 2,039 |
| 12 | 2,977 | 15,095 | 8,970 | 14,440 | 2,200 | 2,857 | 718 | 1,740 | 1,136 | 2,737 | 2,430 | 2,977 |
| 13 | 2,499 | 11,688 | 7,140 | 11,720 | 2,200 | 2,200 | 828 | 1,400 | 1,180 | 10,120 | 2,315 | 1,855 |
| 14 | 2,361 | 9,062 | 5,860 | 9,805 | 1,832 | 1,855 | 784 | 1,224 | 1,070 | 7,405 | 2,315 | 2,039 |
| 15 | 2,665 | 7,603 | 5,000 | 8,130 | 2,062 | 1,694 | 630 | 1,180 | 3,025 | 4,630 | 2,269 | 2,039 |
| 16 | 3,145 | 11,784 | 7,545 | 7,125 | 3,555 | 1,740 | 567 | 1,356 | 3,265 | 4,130 | 2,315 | 2,039 |
| 17 | 2,665 | 14,120 | 6,300 | 6,845 | 4,130 | 1,466 | 850 | 1,224 | 2,593 | 2,905 | 2,499 | 2,085 |
| 18 | 3,025 | 11,624 | 5,130 | 6,570 | 3,433 | 1,466 | 1,356 | 1,136 | 1,970 | 2,545 | 2,430 | 1,809 |
| 19 | 2,977 | 10,344 | 4,380 | 6,845 | 2,833 | 1,246 | 960 | 1,136 | 1,671 | 2,315 | 2,200 | 2,085 |
| 20 | 3,217 | 8,940 | 5,305 | 6,435 | 3,555 | 1,114 | 850 | 1,224 | 1,510 | 2,131 | 2,200 | 1,625 |
| 21 | 5,005 | 7,461 | 6,705 | 5,900 | 3,145 | 1,180 | 696 | 2,785 | 1,400 | 11,240 | 2,593 | 1,740 |
| 22 | 2,499 | 6,901 | 6,300 | 5,432 | 2,430 | 1,026 | 740 | 3,457 | 1,400 | 16,250 | 4,455 | 2,039 |
| 23 | 14,666 | 8,040 | 15,920 | 5,432 | 2,246 | 1,048 | 696 | 6,985 | 1,356 | 14,440 | 4,805 | 1,625 |
| 24 | 17,338 | 10,504 | 30,140 | 4,930 | 2,062 | 938 | 740 | 6,030 | 1,136 | 9,185 | 4,380 | 1,970 |
| 25 | 18,895 | 9,867 | 32,660 | 4,980 | 2,131 | 872 | 784 | 3,955 | 4,905 | 6,570 | 3,955 | 3,217 |
| 26 | 14,120 | 7,321 | 47,110 | 5,406 | 1,901 | 784 | 784 | 2,833 | 3,630 | 6,570 | 3,805 | 3,385 |
| 27 | 11,240 | 6,004 | 46,330 | 5,330 | 1,832 | 718 | 850 | 2,499 | 3,355 | 6,435 | 3,457 | 4,005 |
| 28 | 9,630 | 4,890 | 34,470 | 5,080 | 1,740 | 718 | 1,901 | 2,154 | 2,665 | 5,305 | 2,785 | 20,780 |
| 29 | 6,624 | 4,680 | 19,700 | 12,520 | 1,532 | 828 | 2,059 | 1,809 | 2,200 | 4,630 | 2,499 | 23,660 |
| 30 | 6,219 | | 14,280 | 10,280 | 1,532 | 718 | 3,313 | 1,579 | 2,545 | 4,055 | 2,737 | 14,765 |
| 31 | 5,290 | | 13,640 | | 1,532 | | 2,200 | 1,510 | | 3,457 | | 9,034 |

Estimated monthly discharge of Susquehanna River at Binghamton, N. Y., 1901-1904.

[Drainage area, 2,400 square miles.]

| Month. | Discharge in second-feet. | | | Run-off. | |
|-----------|---------------------------|----------|--------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1901. | | | | | |
| August | 6,845 | 399 | 1,475 | 0.61 | 0.70 |
| September | 1,510 | 652 | 988 | .41 | .46 |
| October | 1,625 | 652 | 1,034 | .43 | .50 |
| November | 4,055 | 567 | 1,454 | .61 | .68 |
| December | 43,210 | 1,444 | 7,514 | 3.13 | 3.61 |
| 1902. | | | | | |
| January | 8,730 | 1,070 | 3,177 | 1.32 | 1.52 |
| February | 9,650 | 1,004 | 2,058 | .86 | .89 |
| March | 60,300 | 6,705 | 19,701 | 8.21 | 9.48 |
| April | 10,440 | 1,855 | 5,285 | 2.20 | 2.45 |
| May | 2,665 | 1,070 | 1,672 | .70 | .81 |
| June | 14,600 | 1,334 | 2,373 | .99 | 1.10 |
| July | 29,960 | 2,154 | 9,587 | 4.00 | 4.61 |
| August | 11,240 | 1,114 | 2,941 | 1.23 | 1.42 |
| September | 8,280 | 630 | 1,420 | .59 | .66 |

*Estimated monthly discharge of Susquehanna River at Binghamton, N. Y.,
1901-1904—Continued.*

| Month. | Discharge in second-feet. | | | Run-off. | |
|-----------------|---------------------------|----------|--------|------------------------------------|---------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1902. | | | | | |
| October | 19,000 | 1,740 | 4,197 | 1.75 | 2.02 |
| November | 7,125 | 1,740 | 2,734 | 1.14 | 1.27 |
| December | 27,260 | 2,246 | 7,461 | 3.11 | 3.59 |
| The year | 60,300 | 630 | 5,217 | 2.18 | 29.82 |
| 1903. | | | | | |
| January | 25,820 | 3,755 | 9,360 | 3.90 | 4.50 |
| February | 23,660 | 2,905 | 9,248 | 3.85 | 4.01 |
| March | 35,580 | 6,845 | 17,275 | 7.19 | 8.29 |
| April | 13,480 | 1,510 | 5,344 | 2.23 | 2.49 |
| May | 1,466 | 420 | 821 | .34 | .39 |
| June | 9,340 | 252 | 2,680 | 1.12 | 1.25 |
| July | 7,265 | 850 | 1,914 | .80 | .92 |
| August | 27,260 | 1,290 | 4,413 | 1.84 | 2.12 |
| September | 13,160 | 894 | 2,654 | 1.11 | 1.24 |
| October | 48,900 | 894 | 10,108 | 4.21 | 4.85 |
| November | 14,280 | 1,901 | 3,890 | 1.62 | 1.81 |
| December | 9,495 | 1,400 | 3,556 | 1.48 | 1.71 |
| The year | 48,900 | 252 | 5,930 | 2.47 | 33.58 |
| 1904. | | | | | |
| January | 18,895 | 2,361 | 5,794 | 2.41 | 2.78 |
| February | 32,012 | 3,385 | 10,530 | 4.39 | 4.73 |
| March | 47,110 | 3,730 | 14,010 | 5.84 | 6.73 |
| April | 21,500 | 4,930 | 10,650 | 4.44 | 4.95 |
| May | 8,430 | 1,532 | 3,088 | 1.29 | 1.49 |
| June | 6,165 | 718 | 1,769 | .737 | .822 |
| July | 3,313 | 567 | 1,027 | .428 | .493 |
| August | 6,985 | 1,136 | 2,396 | .998 | 1.151 |
| September | 4,305 | 1,070 | 1,850 | .770 | .859 |
| October | 16,250 | 1,625 | 5,016 | 2.09 | 2.41 |
| November | 4,805 | 2,200 | 2,881 | 1.20 | 1.34 |
| December | 23,660 | 1,625 | 4,226 | 1.76 | 2.03 |
| The year | 47,110 | 567 | 5,270 | 2.20 | 29.78 |

CHENANGO RIVER AT BINGHAMTON, N. Y.

This station was established by R. E. Horton July 31, 1901. The gage is located on the upstream side of the first span from the right bank of Court Street Bridge, Binghamton. It is a boxed wire gage secured to the vertical supports of the hand railing. The bench mark is a circular chisel draft on the upstream corner of the bridge seat on the left abutment. Its elevation is 34.02 feet above gage datum. Court Street Bridge stands squarely across the stream, which has a nearly horizontal bed of gravel and small cobblestones, affording a smooth, uniform current for gaging. The channel is obstructed by three masonry piers supporting the four spans of the bridge, 79 feet clear width each, the bridge having a total length of 337 feet between abutments. The bridge is situated 2,500 feet above the confluence of Chenango and Susquehanna rivers. A small rift below the bridge cuts off backwater from the Susquehanna at ordinary stages of the rivers. For periods during freshets or at times when there is an abnormal rise on one stream, accompanied by a similar rise in the other stream, either the Chenango or Susquehanna River record at Binghamton may be affected by backwater, indicating a too great discharge. For freshets of considerable duration the flow of the two streams will be more nearly equalized. Gage readings on Chenango River, as well as those on Susquehanna River at Binghamton, are taken by E. F. Weeks. In estimating run-off of Chenango River the area directly tributary to storage reservoirs from which diversion is made to supply Erie Canal has been deducted from the total area naturally tributary to Chenango River.

In estimating the run-off of Chenango River the area directly tributary to storage reservoirs, from which diversion is made to supply Erie Canal, has been deducted from the total area naturally tributary to Chenango River, as follows:

| | Square miles. |
|---|---------------|
| Natural tributary area ^a | 1,580 |
| Diversion area, 6 reservoirs at head of Chenango River, whose overflow is turned into Erie Canal through Oriskany Creek..... | 30 |
| Diversion area, De Ruyter reservoir, at head of Tioughnioga River; out-flow turned into Erie Canal through Limestone Creek..... | 18 |
| | 48 |
| Net area used for Chenango basin..... | 1,532 |


Above estimate of diversion area is approximate. No allowance for direct inflow to feeder channels from additional areas nor for waste into original stream. Gross area, from which more or less run-off is diverted, is about 105 square miles.

^a From Bien's Atlas of New York State. Areas tributary to reservoirs are from New York Barge Canal Report, 1900.

Discharge measurements of Chenango River at Binghamton, N. Y., 1901-1904.

| Date. | Hydrographer. | Area. | Mean velocity. | Gage height. | Discharge. |
|---------------------------|---------------|-------------------------|-----------------------------|--------------------|---------------------|
| | | <i>Square feet.</i> | <i>Feet per second.</i> | <i>Feet.</i> | <i>Second-feet.</i> |
| 1901. | | | | | |
| July 2 | E. C. Murphy | 689 | 1.23 | 5.64 | 848 |
| July 8 | do | 764 | 1.46 | 5.78 | 1,119 |
| July 9 | do | 617 | 1.53 | 5.71 | 942 |
| July 29 | do | 602 | .61 | 5.21 | 405 |
| Do | do | 469 | .90 | 5.21 | 425 |
| August 19 | do | 547 | 1.04 | 5.48 | 566 |
| Do | do | 681 | .85 | 5.49 | 577 |
| October 19 | do | 646 | 1.53 | 5.81 | 987 |
| Do | do | 775 | 1.20 | 5.82 | 927 |
| 1902. | | | | | |
| March 27 | E. C. Murphy | 1,384 | 3.04 | 8.15 | 4,201 |
| March 28 | do | 1,489 | 2.94 | 8.21 | 4,377 |
| March 29 | do | 1,590 | 3.27 | 8.75 | 5,205 |
| June 6 ^a | R. E. Horton | 956 | 2.52 | 7.00 | 2,407 |
| July 1 | E. C. Murphy | 1,534 | 3.14 | 8.49 | 4,815 |
| July 3 | do | 1,155 | 2.33 | 7.24 | 2,688 |
| July 15 | do | 995 | 2.13 | 6.64 | 2,098 |
| August 3 | do | 1,775 | 3.12 | 9.16 | 5,543 |
| August 14 | do | 877 | 1.83 | 6.32 | 1,605 |
| August 15 | do | 841 | 1.48 | 6.20 | 1,341 |
| September 3 | C. C. Covert | 675 | .80 | 5.56 | 546 |
| 1903. | | | | | |
| April 6 | E. C. Murphy | 1,359 | 2.71 | 7.72 | 3,695 |
| May 15 | do | 646 | .83 | 5.49 | 538 |
| June 13 | C. C. Covert | 1,490 | 1.93 | 8.06 | 2,877 |
| August 19 | J. C. Hoyt | 621 | .97 | 5.62 | 601 |
| August 21 | C. C. Covert | 1,006 | 2.23 | 6.72 | 2,243 |
| October 1 | H. H. Halsey | 650 | 1.09 | 5.51 | 709 |
| October 10 | C. C. Covert | 5,411 | 5.23 | 19.81 | 28,300 |
| 1904. | | | | | |
| March 8 | C. C. Covert | 3,702 | 3.45 | ^b 14.90 | 9,104 |
| April 8 | R. E. Horton | 2,459 | 5.42 | 10.86 | 11,632 |
| July 12 | C. C. Covert | 595 | .87 | 5.42 | 516 |
| September 10 | do | 467 | 1.15 | 5.55 | 539 |
| November 22 | H. R. Beebe | 1,022 | 2.45 | 6.86 | 2,505 |

^a Rough measurement.^b Backwater, caused by ice jam.



*Mean daily gage height, in feet, of Chenango River at Binghamton, N. Y.,
1901-1904.*

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|------|------|-------|------|------|-------|-------|------|-------|-------|------|-------|
| 1901. | | | | | | | | | | | | |
| 1. | | | | | | | | 5.18 | 5.58 | 5.70 | 5.46 | 6.12 |
| 2. | | | | | | | | 5.12 | 5.75 | 5.50 | 5.30 | 6.33 |
| 3. | | | | | | | | 5.10 | 5.58 | 5.51 | 5.25 | 6.60 |
| 4. | | | | | | | | 5.10 | 5.50 | 5.68 | 5.28 | 6.52 |
| 5. | | | | | | | | 5.05 | 5.42 | 5.54 | 5.26 | 6.19 |
| 6. | | | | | | | | 5.20 | 5.28 | 5.50 | 5.25 | 5.95 |
| 7. | | | | | | | | 5.05 | 5.22 | 5.46 | 5.25 | 5.90 |
| 8. | | | | | | | | 5.10 | 5.20 | 5.47 | 5.22 | 6.02 |
| 9. | | | | | | | | 5.20 | 5.18 | 5.40 | 5.23 | 6.08 |
| 10. | | | | | | | | 5.20 | 5.15 | 5.37 | 5.21 | 8.14 |
| 11. | | | | | | | | 5.22 | 5.15 | 5.34 | 5.13 | 10.00 |
| 12. | | | | | | | | 5.20 | 5.18 | 5.33 | 5.26 | 8.82 |
| 13. | | | | | | | | 5.18 | 5.30 | 5.42 | 6.85 | |
| 14. | | | | | | | | 5.12 | 5.48 | 6.47 | 6.46 | 8.48 |
| 15. | | | | | | | | 5.15 | 5.35 | 6.40 | 6.19 | 19.54 |
| 16. | | | | | | | | 6.35 | 5.42 | 6.08 | 6.11 | 17.67 |
| 17. | | | | | | | | 5.90 | 5.55 | 5.89 | 6.10 | 12.61 |
| 18. | | | | | | | | 5.60 | 5.62 | 5.85 | 6.06 | 9.41 |
| 19. | | | | | | | | 5.48 | 5.55 | 5.80 | 6.06 | 8.11 |
| 20. | | | | | | | | 5.40 | 5.45 | 5.82 | 6.00 | 7.39 |
| 21. | | | | | | | | 5.55 | 5.45 | 5.78 | 5.95 | 6.84 |
| 22. | | | | | | | | 5.58 | 5.30 | 5.75 | 5.95 | 6.66 |
| 23. | | | | | | | | 5.48 | 5.22 | 5.70 | 5.94 | 7.26 |
| 24. | | | | | | | | 6.70 | 5.20 | 5.66 | 6.71 | 8.18 |
| 25. | | | | | | | | 6.20 | 5.25 | 5.57 | 7.78 | 7.41 |
| 26. | | | | | | | | 5.65 | 5.24 | 5.48 | 7.18 | 6.88 |
| 27. | | | | | | | | 5.38 | 5.25 | 5.45 | 6.63 | 6.83 |
| 28. | | | | | | | | 5.30 | | 5.39 | 6.05 | 6.50 |
| 29. | | | | | | | | 5.25 | 5.15 | 5.40 | 6.20 | 6.52 |
| 30. | | | | | | | | 5.20 | 5.88 | 5.35 | 6.32 | 7.20 |
| 31. | | | | | | | | 5.20 | | 5.39 | | 7.36 |
| 1902. | | | | | | | | | | | | |
| 1. | 6.62 | 6.31 | 18.75 | 8.65 | 6.54 | 6.25 | 8.58 | 8.46 | 5.58 | 7.28 | 8.04 | 6.54 |
| 2. | 6.64 | 6.25 | 22.75 | 8.61 | 6.32 | 6.13 | 7.88 | 9.46 | 5.54 | 7.26 | 7.56 | 6.48 |
| 3. | 6.74 | 6.13 | 21.65 | 8.45 | 6.22 | 6.00 | 7.39 | 8.47 | 5.56 | 6.68 | 7.26 | 6.68 |
| 4. | 6.91 | 6.34 | 17.35 | 8.10 | 6.22 | 6.27 | 7.43 | 7.82 | 5.48 | 6.28 | 6.98 | 7.24 |
| 5. | 6.64 | 6.20 | 12.80 | 7.82 | 6.22 | 7.00 | 7.13 | 7.32 | 5.46 | 6.04 | 6.84 | 7.14 |
| 6. | 6.61 | 6.19 | 9.98 | | 6.12 | 6.63 | 7.46 | 7.00 | 5.44 | 6.28 | 6.74 | 6.74 |
| 7. | 6.52 | 6.16 | 9.25 | 7.60 | 6.12 | 6.35 | 8.20 | 7.02 | 5.48 | 6.56 | 6.71 | 6.61 |
| 8. | 6.30 | 6.20 | 9.02 | 7.58 | 6.12 | 6.35 | 8.00 | 6.87 | 5.46 | 6.44 | 7.58 | 6.51 |
| 9. | 6.22 | 6.21 | 8.68 | 8.12 | 6.12 | 6.37 | 7.80 | 6.80 | 5.48 | 6.46 | 6.44 | 6.26 |
| 10. | 6.14 | 6.08 | 9.45 | 8.50 | 6.00 | 6.35 | 7.88 | 6.57 | 5.86 | 6.31 | 6.34 | 6.18 |
| 11. | 6.14 | 6.10 | 9.28 | 8.98 | 5.97 | 6.20 | 9.23 | 6.52 | 6.08 | 6.14 | 6.28 | 6.56 |
| 12. | 6.02 | 5.98 | 11.60 | 8.78 | 5.92 | 6.37 | 8.40 | 6.77 | 5.81 | 6.16 | 6.24 | 6.54 |
| 13. | 5.87 | 5.90 | 15.08 | 8.48 | 5.87 | 6.30 | 7.40 | 6.72 | 5.66 | 6.16 | 6.48 | 6.24 |
| 14. | 5.88 | 5.84 | 15.78 | 8.22 | 5.82 | 6.35 | 6.96 | 6.40 | 5.61 | 6.36 | 6.41 | 6.01 |
| 15. | 5.89 | 5.77 | 14.18 | 7.80 | 5.77 | 6.25 | 6.68 | 6.24 | 5.56 | 6.64 | 6.31 | 6.11 |
| 16. | 5.91 | 5.86 | 11.98 | 7.42 | 5.72 | 6.23 | 6.56 | 6.22 | 5.46 | 6.31 | 6.16 | 6.04 |
| 17. | 5.88 | 5.76 | 15.86 | 7.18 | 5.74 | 6.25 | 6.56 | 6.10 | 5.41 | 6.11 | 6.11 | 10.53 |
| 18. | 5.76 | 5.78 | 15.72 | 7.05 | 5.72 | 6.15 | 6.48 | 6.04 | 5.36 | 6.01 | 6.08 | 10.94 |
| 19. | 5.78 | 5.74 | 13.10 | 6.90 | 5.62 | 6.05 | 6.80 | 6.00 | 5.36 | 5.96 | 6.06 | 9.91 |
| 20. | 5.78 | 5.71 | 10.48 | 6.80 | 5.77 | 6.05 | 11.36 | 6.00 | 5.31 | 6.81 | 6.11 | 9.08 |
| 21. | 5.66 | 5.64 | 9.40 | 6.72 | 6.05 | 6.03 | 15.02 | 5.71 | 5.28 | 6.86 | 6.06 | 8.51 |
| 22. | 6.02 | 5.67 | 9.20 | 6.64 | 5.93 | 6.28 | 15.02 | 6.00 | 5.26 | 6.51 | 6.08 | 12.84 |
| 23. | 8.24 | 5.68 | 9.32 | 6.52 | 5.83 | 6.33 | 13.52 | 5.91 | 5.31 | 6.34 | 6.08 | 14.03 |
| 24. | 8.66 | 5.66 | 9.38 | 6.40 | 5.77 | 6.16 | 12.34 | 5.88 | 5.28 | 6.31 | 6.16 | 11.28 |
| 25. | 7.62 | 5.68 | 8.95 | 6.32 | 6.00 | 6.00 | 11.47 | 5.84 | 5.31 | 6.31 | 6.21 | 9.31 |
| 26. | 6.86 | 5.73 | 8.48 | 6.20 | 6.35 | 6.06 | 9.62 | 5.81 | 5.54 | 6.21 | 6.28 | 8.71 |
| 27. | 6.86 | 6.08 | 8.15 | 6.20 | 6.63 | 6.18 | 8.62 | 5.71 | 5.76 | 6.16 | 6.78 | 8.24 |
| 28. | 7.28 | 8.92 | 8.15 | 6.14 | 6.35 | 6.16 | 11.62 | 5.78 | 5.66 | 9.30 | 7.06 | 7.64 |
| 29. | 7.39 | | 8.95 | 6.14 | 6.25 | 6.73 | 9.70 | 5.74 | 7.64 | 11.71 | 6.78 | 7.24 |
| 30. | 6.85 | | 9.28 | 6.30 | 6.23 | 10.56 | 8.62 | 5.74 | 6.44 | 10.41 | 6.61 | 7.28 |
| 31. | 6.40 | | 8.98 | | 6.20 | | 9.30 | 5.66 | | 8.96 | | 6.98 |

*Mean daily gage height, in feet, of Chenango River at Binghamton, N. Y.,
1901-1904—Continued.*

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|-------|-------|-------|--------------------|------|-------|-------|-------------------|-------|-------|-------|-------|
| 1903. | | | | | | | | | | | | |
| 1 | 6.76 | 12.04 | 16.49 | 10.14 | 5.81 | 5.06 | 6.59 | 5.57 | 10.01 | 5.51 | 6.88 | 6.22 |
| 2 | 6.64 | 10.61 | 14.34 | 9.14 | 5.76 | 5.11 | 6.42 | 5.52 | 8.66 | 5.56 | 6.72 | 6.08 |
| 3 | 7.21 | 10.56 | 11.18 | 8.56 | 5.74 | 5.11 | 6.12 | 5.45 | 7.53 | 5.81 | 6.68 | 6.20 |
| 4 | 8.78 | 11.94 | 9.71 | 8.51 | 5.71 | 5.06 | 5.97 | 5.45 | 7.29 | 5.83 | 6.55 | 6.20 |
| 5 | 8.64 | 13.38 | 9.06 | 8.24 | 5.68 | 5.06 | 5.89 | 6.57 | 6.96 | 5.83 | 6.50 | 6.15 |
| 6 | 7.96 | 11.46 | 10.14 | 7.78 | 5.64 | 5.06 | 5.82 | 6.49 | 6.66 | 7.33 | 6.92 | 6.12 |
| 7 | 7.34 | 9.81 | 10.01 | 7.66 | 5.61 | 4.94 | 5.85 | 6.47 | 6.46 | 6.71 | 6.82 | 6.08 |
| 8 | 7.24 | 8.54 | 10.08 | 8.76 | 5.58 | 5.24 | 5.77 | 6.32 | 6.31 | 6.66 | 6.58 | 6.05 |
| 9 | 6.98 | 8.16 | 14.68 | 9.11 | 5.56 | 5.11 | 5.67 | 5.99 | 6.19 | 11.94 | 6.48 | 6.05 |
| 10 | 9.56 | 7.84 | 14.28 | 8.54 | 5.56 | 5.06 | 5.57 | 6.22 | 6.13 | 19.06 | 6.40 | 5.90 |
| 11 | 9.34 | 7.76 | 15.26 | 8.18 | 5.56 | 5.11 | 5.47 | 6.52 | 6.36 | 19.91 | 6.40 | 5.90 |
| 12 | 9.36 | 9.01 | 15.24 | 7.81 | 5.51 | 5.71 | 5.47 | 6.27 | 6.49 | 15.48 | 6.32 | 6.00 |
| 13 | 9.26 | 10.24 | 13.16 | 7.51 | 5.51 | 7.97 | 5.42 | 6.27 | 6.19 | 11.42 | 6.25 | 6.30 |
| 14 | 9.08 | 9.28 | 11.31 | 7.26 | 5.48 | 6.62 | 5.42 | 6.07 | 6.03 | 9.45 | 6.22 | 6.35 |
| 15 | 9.14 | 8.21 | 10.26 | 7.48 | 5.46 | 6.29 | 5.42 | 5.95 | 5.93 | 8.58 | 6.15 | 6.15 |
| 16 | 9.14 | 7.84 | 9.56 | 7.41 | 5.46 | 6.12 | 5.49 | 5.79 | 5.89 | 7.95 | 6.15 | 6.10 |
| 17 | 8.96 | 7.24 | 9.08 | 7.21 | 5.46 | 5.92 | 5.57 | 5.69 | 5.86 | 7.78 | 9.03 | 6.10 |
| 18 | 8.54 | 6.44 | 9.14 | 6.98 | 5.41 | 5.72 | 5.49 | 5.69 | 6.21 | 11.55 | 10.10 | 6.05 |
| 19 | 7.86 | 6.68 | 8.78 | 6.76 | 5.38 | 5.75 | 5.72 | 5.59 | 6.23 | 11.72 | 8.50 | 5.92 |
| 20 | 7.38 | 6.71 | 8.36 | 6.56 | 5.36 | 5.82 | 5.89 | 7.07 | 5.99 | 10.20 | 7.42 | 5.98 |
| 21 | 7.74 | 6.88 | 8.16 | 6.44 | 5.36 | 6.62 | 5.79 | 6.86 | 5.89 | 9.08 | 6.92 | 7.35 |
| 22 | 9.84 | 6.81 | 9.48 | 6.36 | 5.34 | 8.67 | 5.87 | 6.29 | 5.81 | 8.40 | 6.75 | 8.35 |
| 23 | 9.86 | 6.91 | 11.38 | 6.31 | 5.26 | 8.19 | 6.67 | 5.99 | 5.71 | 7.88 | 6.72 | 8.10 |
| 24 | 8.71 | 6.76 | 15.73 | 6.24 | 5.26 | 8.99 | 7.15 | 5.79 | 5.69 | 7.72 | 6.85 | 7.48 |
| 25 | 7.98 | 6.68 | 14.96 | 6.11 | 5.26 | 8.32 | 6.09 | 5.79 | 5.66 | 7.55 | 6.78 | 7.35 |
| 26 | 7.96 | 6.64 | 12.56 | 6.11 | 5.21 | 7.27 | 5.77 | 7.63 | 5.61 | 7.25 | 6.40 | 7.18 |
| 27 | 7.66 | 6.56 | 10.54 | 6.04 | 5.21 | 7.27 | 5.65 | 7.59 | 5.56 | 7.15 | 6.32 | 6.92 |
| 28 | 7.71 | 9.96 | 9.54 | 5.96 | 5.21 | 6.77 | 5.57 | 6.89 | 5.61 | 7.10 | 6.38 | 6.48 |
| 29 | 8.74 | | 9.16 | 5.88 | 5.24 | 6.69 | 5.57 | 14.61 | 5.59 | 7.20 | 6.18 | 6.48 |
| 30 | 13.31 | | 8.61 | 5.86 | 5.21 | 6.89 | 5.65 | 14.36 | 5.59 | 7.18 | 6.20 | 6.40 |
| 31 | 13.74 | | 9.78 | | 5.16 | | 5.59 | 12.11 | | 7.10 | | 6.50 |
| 1904. | | | | | | | | | | | | |
| 1 | 6.42 | 7.32 | 7.60 | 11.30 | 8.72 | 7.14 | 5.59 | 6.10 | 5.70 | 7.69 | 6.22 | 6.15 |
| 2 | 6.55 | 7.20 | 7.40 | 12.90 | 8.19 | 6.79 | 5.73 | 7.08 | 5.72 | 6.85 | 6.20 | 5.95 |
| 3 | 6.42 | 7.18 | 7.88 | ^a 11.70 | 7.79 | 6.56 | 5.63 | 7.55 | 5.70 | 6.41 | 6.12 | 5.80 |
| 4 | 6.45 | 7.20 | 10.38 | 10.50 | 7.42 | 6.42 | 5.61 | 6.88 | 5.72 | 6.21 | 6.07 | 5.75 |
| 5 | 6.68 | 7.05 | 11.92 | 9.45 | 7.19 | 6.64 | 5.51 | 6.32 | 5.65 | 6.11 | 6.04 | 5.65 |
| 6 | 6.82 | 6.75 | 11.08 | 10.08 | 6.99 | 6.59 | 5.49 | 6.72 | 5.65 | 6.01 | 6.17 | 5.72 |
| 7 | 6.68 | 8.12 | 10.95 | 10.30 | 6.82 | 6.34 | 5.51 | 6.65 | 5.60 | 6.01 | 6.23 | 5.80 |
| 8 | 6.60 | 13.92 | 14.78 | 10.88 | 6.67 | 6.25 | 5.58 | 6.28 | 5.52 | 5.96 | 6.16 | 5.75 |
| 9 | 6.58 | 15.30 | 16.90 | 11.01 | 6.55 | 6.88 | 5.48 | 6.10 | 5.50 | 5.88 | 6.11 | 5.62 |
| 10 | 6.48 | 14.28 | 15.65 | 12.97 | 6.44 | 7.98 | 5.40 | 6.02 | 5.50 | 5.80 | 6.11 | 5.55 |
| 11 | 6.38 | 12.05 | 13.70 | 12.42 | 6.34 | 6.93 | 5.30 | 5.98 | 5.40 | 6.05 | 6.06 | 5.58 |
| 12 | 6.30 | 10.60 | 11.40 | 10.84 | 6.26 | 6.48 | 5.50 | 5.92 | 5.31 | 7.60 | 6.06 | 5.62 |
| 13 | 6.25 | 9.50 | 10.30 | 9.91 | 6.18 | 6.25 | 5.55 | 5.85 | 5.31 | 8.95 | 6.01 | 5.70 |
| 14 | 6.20 | 8.70 | 9.52 | 9.29 | 6.14 | 6.15 | 5.35 | 5.75 | 5.34 | 7.85 | 6.02 | 5.55 |
| 15 | 6.15 | 8.20 | 8.75 | 8.74 | 6.26 | 6.08 | 5.40 | 5.72 | 6.09 | 7.03 | 5.95 | 5.65 |
| 16 | 6.15 | 9.38 | 8.20 | 8.49 | 7.36 | 6.53 | 5.60 | 5.65 | 5.91 | 6.40 | 6.08 | 5.65 |
| 17 | 6.12 | 10.18 | 7.65 | 8.39 | 7.36 | 6.11 | 5.65 | 5.70 | 5.67 | 6.42 | 6.10 | 5.65 |
| 18 | 6.15 | 10.05 | 7.42 | 8.39 | 6.84 | 5.94 | 6.68 | 5.62 | 5.54 | 6.26 | 5.95 | 5.65 |
| 19 | 6.30 | 9.52 | 7.22 | 8.40 | 6.64 | 5.84 | 6.55 | 5.55 | 5.40 | 6.16 | 5.92 | 5.60 |
| 20 | 6.45 | 8.98 | 7.48 | 8.23 | 7.30 | 5.84 | 6.08 | 5.78 | 5.36 | 6.12 | 5.90 | 5.60 |
| 21 | 6.30 | 8.62 | 7.88 | 7.98 | 7.10 | 5.84 | 5.88 | 6.82 | 5.46 | 5.79 | 6.08 | 5.60 |
| 22 | 6.30 | 8.35 | 7.78 | 7.98 | 6.70 | 5.82 | 5.82 | 6.50 | 5.68 | 10.79 | 6.80 | 5.60 |
| 23 | 10.36 | 8.62 | 11.30 | 8.00 | 6.47 | 5.72 | 5.65 | 8.25 | 5.66 | 9.76 | 6.68 | 5.65 |
| 24 | 11.18 | 9.25 | 15.15 | 7.93 | 6.73 | 5.60 | 6.10 | 7.55 | 5.56 | 8.15 | 6.50 | 5.92 |
| 25 | 11.60 | 9.38 | 15.90 | 8.13 | 6.47 | 5.54 | 6.02 | 6.65 | 6.70 | 7.38 | 6.38 | 6.50 |
| 26 | 10.20 | 8.70 | 19.82 | 8.43 | 6.40 | 5.54 | 5.92 | 6.32 | 6.42 | 7.41 | 6.32 | 6.25 |
| 27 | 9.35 | 8.25 | 19.90 | 8.13 | 6.50 | 5.47 | 6.20 | 6.20 | 6.29 | 7.23 | 6.18 | 6.72 |
| 28 | 8.65 | 7.95 | 16.15 | 10.13 | 6.50 | 5.46 | 6.22 | ^a 6.05 | 6.15 | 6.92 | 5.98 | 12.75 |
| 29 | 8.10 | 7.88 | 12.08 | 10.19 | 6.40 | 5.46 | 6.65 | 5.90 | 5.95 | 6.68 | 5.80 | 13.28 |
| 30 | 7.88 | | 10.62 | 9.39 | 6.26 | 5.49 | 6.90 | 5.80 | 6.92 | 6.53 | 6.20 | 10.15 |
| 31 | 7.60 | | 10.58 | | 6.76 | | 6.32 | 5.72 | | 6.32 | | 5.25 |

^aInterpolated.

Rating table for Chenango River at Binghamton, N. Y., for 1901 to 1904, inclusive.

| Gage height. | Discharge. | Gage height. | Discharge. | Gage height. | Discharge. | Gage height. | Discharge. |
|--------------|---------------------|--------------|---------------------|--------------|---------------------|--------------|---------------------|
| <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> |
| 5.0 | 160 | 7.4 | 3,200 | 10.6 | 8,590 | 15.4 | 18,240 |
| 5.1 | 256 | 7.5 | 3,350 | 10.8 | 8,970 | 15.6 | 18,660 |
| 5.2 | 352 | 7.6 | 3,500 | 11.0 | 9,350 | 15.8 | 19,080 |
| 5.3 | 450 | 7.7 | 3,650 | 11.2 | 9,730 | 16.0 | 19,500 |
| 5.4 | 550 | 7.8 | 3,800 | 11.4 | 10,110 | 16.2 | 19,940 |
| 5.5 | 650 | 7.9 | 3,950 | 11.6 | 10,490 | 16.4 | 20,380 |
| 5.6 | 760 | 8.0 | 4,100 | 11.8 | 10,870 | 16.6 | 20,820 |
| 5.7 | 875 | 8.1 | 4,250 | 12.0 | 11,250 | 16.8 | 21,260 |
| 5.8 | 995 | 8.2 | 4,400 | 12.2 | 11,650 | 17.0 | 21,700 |
| 5.9 | 1,115 | 8.3 | 4,550 | 12.4 | 12,050 | 17.2 | 22,140 |
| 6.0 | 1,235 | 8.4 | 4,700 | 12.6 | 12,450 | 17.4 | 22,580 |
| 6.1 | 1,365 | 8.5 | 4,850 | 12.8 | 12,850 | 17.6 | 23,030 |
| 6.2 | 1,495 | 8.6 | 5,020 | 13.0 | 13,250 | 17.8 | 23,490 |
| 6.3 | 1,625 | 8.7 | 5,190 | 13.2 | 13,650 | 18.0 | 23,950 |
| 6.4 | 1,755 | 8.8 | 5,360 | 13.4 | 14,050 | 18.2 | 24,410 |
| 6.5 | 1,885 | 8.9 | 5,530 | 13.6 | 14,460 | 18.4 | 24,870 |
| 6.6 | 2,025 | 9.0 | 5,700 | 13.8 | 14,880 | 18.6 | 25,340 |
| 6.7 | 2,165 | 9.2 | 6,060 | 14.0 | 15,300 | 18.8 | 25,820 |
| 6.8 | 2,305 | 9.4 | 6,420 | 14.2 | 15,720 | 19.0 | 26,300 |
| 6.9 | 2,450 | 9.6 | 6,780 | 14.4 | 16,140 | 19.2 | 26,780 |
| 7.0 | 2,600 | 9.8 | 7,140 | 14.6 | 16,560 | 19.4 | 27,260 |
| 7.1 | 2,750 | 10.0 | 7,500 | 14.8 | 16,980 | 19.6 | 27,760 |
| 7.2 | 2,900 | 10.2 | 7,860 | 15.0 | 17,400 | 19.8 | 28,280 |
| 7.3 | 3,050 | 10.4 | 8,220 | 15.2 | 17,820 | | |

Remarks: Tangent at 19.5 feet. Differences above this point 260 per tenth.

Mean daily discharge, in second-feet, of Chenango River at Binghamton, N. Y., 1901-1904.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|-------|-------|--------|-------|-------|-------|--------|-------|-------|--------|-------|--------|
| 1901. | | | | | | | | | | | | |
| 1 | | | | | | | | 333 | 738 | 875 | 610 | 1,391 |
| 2 | | | | | | | | 275 | 935 | 650 | 450 | 1,664 |
| 3 | | | | | | | | 256 | 738 | 661 | 400 | 2,025 |
| 4 | | | | | | | | 256 | 650 | 851 | 430 | 1,913 |
| 5 | | | | | | | | 208 | 570 | 694 | 410 | 1,482 |
| 6 | | | | | | | | 352 | 430 | 650 | 400 | 1,175 |
| 7 | | | | | | | | 208 | 371 | 610 | 400 | 1,115 |
| 8 | | | | | | | | 256 | 352 | 620 | 371 | 1,261 |
| 9 | | | | | | | | 352 | 333 | 550 | 381 | 1,339 |
| 10 | | | | | | | | 352 | 304 | 520 | 361 | 4,325 |
| 11 | | | | | | | | 371 | 304 | 490 | 285 | 7,500 |
| 12 | | | | | | | | 352 | 333 | 480 | 410 | 5,360 |
| 13 | | | | | | | | 333 | 450 | 570 | 2,375 | 5,105 |
| 14 | | | | | | | | 275 | 630 | 1,846 | 1,833 | 4,850 |
| 15 | | | | | | | | 304 | 500 | 1,755 | 1,482 | 27,630 |
| 16 | | | | | | | | 1,690 | 570 | 1,339 | 1,378 | 23,145 |
| 17 | | | | | | | | 1,115 | 705 | 1,102 | 1,365 | 12,450 |
| 18 | | | | | | | | 760 | 782 | 1,055 | 1,313 | 6,420 |
| 19 | | | | | | | | 630 | 705 | 995 | 1,313 | 4,250 |
| 20 | | | | | | | | 550 | 600 | 1,019 | 1,235 | 3,200 |
| 21 | | | | | | | | 705 | 600 | 971 | 1,175 | 2,361 |
| 22 | | | | | | | | 738 | 450 | 935 | 1,175 | 2,109 |
| 23 | | | | | | | | 630 | 371 | 875 | 1,163 | 2,975 |
| 24 | | | | | | | | 2,165 | 352 | 827 | 2,180 | 4,400 |
| 25 | | | | | | | | 1,495 | 400 | 727 | 3,800 | 3,200 |
| 26 | | | | | | | | 815 | 391 | 630 | 2,900 | 2,420 |
| 27 | | | | | | | | 530 | 400 | 600 | 2,067 | 2,347 |
| 28 | | | | | | | | 450 | 352 | 540 | 1,900 | 1,885 |
| 29 | | | | | | | | 400 | 304 | 550 | 1,495 | 1,913 |
| 30 | | | | | | | | 352 | 1,091 | 500 | 1,651 | 2,900 |
| 31 | | | | | | | | 352 | | 540 | | 3,125 |
| 1902. | | | | | | | | | | | | |
| 1 | 2,053 | 1,638 | 25,700 | 5,105 | 1,941 | 1,560 | 5,020 | 4,775 | 738 | 3,050 | 4,175 | 1,941 |
| 2 | 2,081 | 1,560 | 35,950 | 5,020 | 1,651 | 1,404 | 3,950 | 6,510 | 694 | 2,975 | 3,425 | 1,859 |
| 3 | 2,221 | 1,404 | 33,090 | 4,775 | 1,521 | 1,235 | 3,200 | 4,775 | 716 | 2,137 | 2,975 | 2,137 |
| 4 | 2,465 | 1,677 | 22,470 | 4,250 | 1,521 | 1,586 | 3,275 | 3,800 | 630 | 1,599 | 2,570 | 2,975 |
| 5 | 2,081 | 1,495 | 12,850 | 3,800 | 1,521 | 2,600 | 2,825 | 3,050 | 610 | 1,287 | 2,361 | 2,825 |
| 6 | 2,039 | 1,482 | 7,500 | 3,650 | 1,391 | 2,067 | 3,275 | 2,600 | 590 | 1,599 | 2,221 | 2,221 |
| 7 | 1,913 | 1,443 | 6,150 | 3,500 | 1,391 | 1,690 | 4,400 | 2,630 | 630 | 1,969 | 2,179 | 2,039 |
| 8 | 1,625 | 1,495 | 5,700 | 3,500 | 1,391 | 1,690 | 4,100 | 2,405 | 610 | 1,807 | 3,500 | 1,899 |
| 9 | 1,521 | 1,508 | 5,190 | 4,250 | 1,391 | 1,716 | 3,800 | 2,305 | 630 | 1,833 | 1,807 | 1,573 |
| 10 | 1,391 | 1,339 | 6,510 | 4,850 | 1,235 | 1,690 | 3,950 | 1,983 | 1,067 | 1,638 | 1,677 | 1,469 |
| 11 | 1,417 | 1,365 | 6,240 | 5,700 | 1,199 | 1,495 | 6,150 | 1,913 | 1,339 | 1,417 | 1,599 | 1,969 |
| 12 | 1,261 | 1,211 | 10,490 | 5,360 | 1,139 | 1,716 | 4,700 | 2,263 | 1,007 | 1,443 | 1,547 | 1,941 |
| 13 | 1,079 | 1,115 | 17,610 | 4,850 | 1,079 | 1,625 | 3,200 | 2,193 | 827 | 1,443 | 1,859 | 1,547 |
| 14 | 1,091 | 1,043 | 19,080 | 4,400 | 1,019 | 1,690 | 2,540 | 1,755 | 771 | 1,703 | 1,768 | 1,248 |
| 15 | 1,103 | 959 | 15,720 | 3,800 | 959 | 1,560 | 2,137 | 1,547 | 716 | 2,081 | 1,638 | 1,378 |
| 16 | 1,127 | 1,067 | 11,250 | 3,200 | 899 | 1,534 | 1,969 | 1,521 | 610 | 1,638 | 1,443 | 1,287 |
| 17 | 1,091 | 947 | 19,185 | 2,900 | 923 | 1,560 | 1,969 | 1,365 | 560 | 1,378 | 1,378 | 8,495 |
| 18 | 947 | 971 | 18,870 | 2,675 | 899 | 1,430 | 1,859 | 1,287 | 510 | 1,248 | 1,339 | 9,255 |
| 19 | 971 | 923 | 13,450 | 2,450 | 782 | 1,300 | 2,505 | 1,235 | 510 | 1,187 | 1,313 | 7,320 |
| 20 | 827 | 887 | 8,400 | 2,305 | 959 | 1,300 | 10,015 | 1,235 | 460 | 2,319 | 1,378 | 5,880 |
| 21 | 804 | 804 | 6,420 | 2,193 | 1,300 | 1,274 | 17,400 | 887 | 490 | 2,390 | 1,313 | 4,850 |
| 22 | 1,261 | 839 | 6,060 | 2,081 | 1,151 | 1,599 | 17,400 | 1,235 | 410 | 1,899 | 1,339 | 12,950 |
| 23 | 4,475 | 851 | 6,240 | 1,913 | 1,031 | 1,664 | 14,250 | 1,127 | 460 | 1,677 | 1,339 | 15,405 |
| 24 | 5,105 | 827 | 6,420 | 1,735 | 959 | 1,443 | 11,950 | 1,091 | 430 | 1,638 | 1,443 | 9,920 |
| 25 | 3,500 | 851 | 5,615 | 1,651 | 1,235 | 1,235 | 10,205 | 1,043 | 460 | 1,638 | 1,508 | 6,240 |
| 26 | 2,390 | 911 | 4,850 | 1,495 | 1,690 | 1,313 | 6,780 | 1,007 | 694 | 1,508 | 1,599 | 5,190 |
| 27 | 2,390 | 1,339 | 4,325 | 1,495 | 2,067 | 1,469 | 5,020 | 887 | 947 | 1,443 | 2,277 | 4,475 |
| 28 | 3,050 | 5,530 | 4,325 | 1,417 | 1,690 | 1,443 | 10,490 | 971 | 827 | 6,240 | 2,675 | 3,575 |
| 29 | 3,200 | | 5,615 | 1,417 | 1,560 | 2,207 | 6,960 | 923 | 3,575 | 10,680 | 2,277 | 3,075 |
| 30 | 2,375 | | 6,240 | 1,625 | 1,534 | 8,495 | 5,020 | 923 | 1,807 | 8,220 | 2,039 | 3,950 |
| 31 | 1,755 | | 5,700 | | 1,495 | | 6,240 | 827 | | 5,615 | | 2,570 |

Mean daily discharge, in second-feet, of Chenango River at Binghamton, N. Y., 1901-1904—Continued.

| Days. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|--------|--------|--------|--------|-------|-------|-------|--------|-------|--------|-------|--------|
| 1903. | | | | | | | | | | | | |
| 1 | 2,249 | 11,350 | 20,600 | 7,770 | 1,007 | 217 | 2,011 | 727 | 7,500 | 661 | 2,420 | 1,521 |
| 2 | 2,081 | 8,590 | 18,085 | 5,970 | 947 | 265 | 1,781 | 672 | 5,105 | 716 | 2,193 | 1,339 |
| 3 | 2,900 | 8,495 | 9,730 | 4,935 | 923 | 265 | 1,891 | 600 | 3,875 | 1,007 | 2,137 | 1,495 |
| 4 | 5,360 | 11,155 | 6,960 | 4,850 | 887 | 217 | 1,199 | 600 | 3,050 | 1,031 | 1,955 | 1,495 |
| 5 | 5,105 | 14,050 | 5,790 | 4,475 | 851 | 217 | 1,103 | 1,983 | 2,540 | 1,031 | 1,885 | 1,430 |
| 6 | 4,025 | 10,205 | 7,770 | 3,800 | 804 | 217 | 1,019 | 1,872 | 2,109 | 3,125 | 2,480 | 1,391 |
| 7 | 3,125 | 7,140 | 7,500 | 3,575 | 771 | 103 | 1,055 | 1,846 | 1,833 | 2,179 | 2,333 | 1,339 |
| 8 | 2,975 | 4,935 | 7,680 | 5,275 | 738 | 390 | 959 | 1,651 | 1,638 | 2,109 | 1,997 | 1,300 |
| 9 | 2,570 | 4,325 | 16,770 | 5,880 | 716 | 265 | 839 | 1,223 | 1,482 | 11,155 | 1,859 | 1,300 |
| 10 | 6,690 | 3,875 | 15,930 | 4,935 | 716 | 217 | 727 | 1,521 | 1,404 | 26,420 | 1,755 | 1,115 |
| 11 | 6,330 | 3,725 | 17,925 | 4,400 | 716 | 265 | 620 | 1,913 | 1,703 | 28,540 | 1,755 | 1,115 |
| 12 | 6,330 | 5,700 | 17,925 | 3,800 | 661 | 887 | 620 | 1,586 | 1,872 | 18,450 | 1,651 | 1,235 |
| 13 | 6,150 | 7,950 | 13,550 | 3,350 | 661 | 4,025 | 570 | 1,586 | 1,482 | 10,110 | 1,560 | 1,625 |
| 14 | 5,880 | 6,240 | 9,920 | 2,975 | 630 | 2,053 | 570 | 1,326 | 1,274 | 6,510 | 1,521 | 1,690 |
| 15 | 5,970 | 4,400 | 7,950 | 3,350 | 610 | 1,612 | 570 | 1,175 | 1,151 | 5,020 | 1,430 | 1,430 |
| 16 | 5,970 | 3,875 | 6,690 | 3,200 | 610 | 1,391 | 640 | 983 | 1,103 | 4,025 | 1,430 | 1,365 |
| 17 | 5,615 | 2,975 | 5,880 | 2,900 | 610 | 1,139 | 727 | 863 | 1,067 | 3,800 | 5,790 | 1,365 |
| 18 | 4,935 | 1,807 | 5,970 | 2,570 | 560 | 899 | 640 | 863 | 1,508 | 10,395 | 7,680 | 1,300 |
| 19 | 3,875 | 2,137 | 5,360 | 2,249 | 530 | 935 | 899 | 749 | 1,534 | 10,680 | 4,850 | 1,139 |
| 20 | 3,200 | 2,179 | 4,625 | 1,969 | 510 | 1,019 | 1,103 | 2,675 | 1,223 | 7,860 | 3,200 | 1,211 |
| 21 | 3,725 | 2,420 | 4,325 | 1,807 | 510 | 2,053 | 983 | 2,390 | 1,103 | 5,880 | 2,480 | 3,125 |
| 22 | 7,230 | 2,319 | 6,600 | 1,703 | 490 | 5,105 | 1,079 | 1,612 | 1,007 | 4,700 | 2,235 | 4,625 |
| 23 | 7,230 | 2,465 | 10,110 | 1,638 | 410 | 4,400 | 2,123 | 1,223 | 887 | 3,950 | 2,193 | 4,250 |
| 24 | 5,190 | 2,249 | 18,975 | 1,547 | 410 | 5,700 | 2,825 | 983 | 863 | 3,650 | 2,375 | 3,350 |
| 25 | 4,100 | 2,137 | 17,295 | 1,378 | 410 | 4,550 | 1,352 | 983 | 827 | 3,425 | 2,277 | 3,125 |
| 26 | 4,025 | 2,081 | 12,350 | 1,378 | 362 | 3,875 | 959 | 3,575 | 772 | 2,975 | 1,755 | 2,900 |
| 27 | 3,575 | 1,969 | 8,495 | 1,287 | 362 | 2,975 | 815 | 3,500 | 716 | 2,825 | 1,651 | 2,480 |
| 28 | 3,650 | 7,410 | 6,690 | 1,187 | 362 | 2,263 | 727 | 2,435 | 772 | 2,750 | 1,729 | 1,859 |
| 29 | 5,275 | 5,970 | 5,970 | 1,091 | 390 | 2,151 | 727 | 16,560 | 749 | 2,900 | 1,469 | 1,859 |
| 30 | 13,850 | ----- | 5,020 | 1,067 | 362 | 2,435 | 815 | 16,035 | 749 | 2,900 | 1,495 | 1,885 |
| 31 | 14,775 | ----- | 7,140 | ----- | 314 | ----- | 749 | 11,450 | ----- | 2,750 | ----- | 1,820 |
| 1904. | | | | | | | | | | | | |
| 1 | 1,781 | 3,050 | 3,500 | 9,920 | 5,190 | 2,825 | 749 | 1,365 | 875 | 3,650 | 1,521 | 1,430 |
| 2 | 1,955 | 2,900 | 3,200 | 13,051 | 4,409 | 2,291 | 911 | 2,750 | 899 | 2,375 | 1,495 | 1,175 |
| 3 | 1,781 | 2,900 | 3,950 | 10,680 | 3,800 | 1,969 | 793 | 3,125 | 875 | 1,768 | 1,391 | 995 |
| 4 | 1,820 | 2,900 | 5,750 | 8,400 | 3,200 | 1,781 | 771 | 2,420 | 899 | 1,508 | 1,326 | 935 |
| 5 | 2,137 | 2,675 | 9,000 | 6,510 | 2,900 | 2,081 | 661 | 1,651 | 815 | 1,378 | 1,287 | 818 |
| 6 | 2,333 | 2,235 | 8,500 | 7,680 | 2,585 | 2,011 | 640 | 2,193 | 815 | 1,248 | 1,456 | 899 |
| 7 | 2,137 | 4,250 | 8,300 | 8,040 | 2,333 | 1,677 | 661 | 2,095 | 760 | 1,248 | 1,534 | 995 |
| 8 | 2,028 | 15,090 | 8,985 | 9,160 | 2,123 | 1,560 | 738 | 1,599 | 672 | 1,187 | 1,443 | 935 |
| 9 | 1,997 | 18,030 | 11,400 | 9,350 | 1,955 | 2,420 | 630 | 1,365 | 650 | 1,091 | 1,378 | 783 |
| 10 | 1,859 | 15,930 | 10,700 | 13,150 | 1,807 | 4,100 | 550 | 1,261 | 650 | 995 | 1,378 | 705 |
| 11 | 1,729 | 11,350 | 8,950 | 12,050 | 1,677 | 2,495 | 450 | 1,211 | 550 | 1,300 | 1,313 | 738 |
| 12 | 1,625 | 8,590 | 6,670 | 9,065 | 1,573 | 1,859 | 650 | 1,139 | 460 | 3,500 | 1,313 | 783 |
| 13 | 1,560 | 6,600 | 5,700 | 7,320 | 1,469 | 1,560 | 705 | 1,055 | 460 | 5,615 | 1,248 | 875 |
| 14 | 1,495 | 5,190 | 4,950 | 6,240 | 1,417 | 1,430 | 500 | 935 | 490 | 3,875 | 1,261 | 705 |
| 15 | 1,430 | 4,400 | 4,170 | 5,275 | 1,573 | 1,339 | 550 | 899 | 1,352 | 2,675 | 1,175 | 818 |
| 16 | 1,430 | 6,420 | 3,600 | 4,850 | 3,125 | 1,927 | 760 | 815 | 1,127 | 1,755 | 1,339 | 818 |
| 17 | 1,391 | 7,860 | 3,020 | 4,700 | 3,125 | 1,378 | 815 | 875 | 839 | 1,781 | 1,365 | 818 |
| 18 | 1,430 | 7,590 | 2,800 | 4,700 | 2,361 | 1,163 | 2,137 | 782 | 694 | 1,573 | 1,175 | 818 |
| 19 | 1,625 | 6,600 | 2,680 | 4,700 | 2,081 | 1,043 | 1,955 | 705 | 550 | 1,443 | 1,139 | 760 |
| 20 | 1,820 | 5,700 | 3,015 | 4,475 | 3,050 | 1,043 | 1,339 | 971 | 510 | 1,391 | 1,115 | 760 |
| 21 | 1,625 | 5,100 | 3,555 | 4,100 | 2,750 | 1,043 | 1,091 | 2,333 | 610 | 983 | 1,339 | 760 |
| 22 | 1,625 | 4,625 | 3,350 | 4,100 | 2,165 | 1,019 | 1,019 | 1,885 | 851 | 8,970 | 2,305 | 760 |
| 23 | 8,130 | 5,020 | 9,920 | 4,100 | 1,846 | 899 | 815 | 4,475 | 827 | 7,050 | 2,137 | 818 |
| 24 | 9,730 | 6,330 | 17,715 | 4,025 | 2,207 | 760 | 1,365 | 3,425 | 716 | 4,325 | 1,885 | 1,139 |
| 25 | 10,490 | 6,420 | 19,290 | 4,325 | 1,846 | 694 | 1,261 | 2,095 | 2,165 | 3,200 | 1,729 | 1,885 |
| 26 | 7,860 | 5,190 | 28,280 | 4,775 | 1,755 | 694 | 1,139 | 1,651 | 1,781 | 3,200 | 1,651 | 1,560 |
| 27 | 6,330 | 4,475 | 28,540 | 4,325 | 1,885 | 620 | 1,495 | 1,495 | 1,612 | 2,975 | 1,469 | 2,193 |
| 28 | 5,105 | 4,025 | 19,830 | 7,770 | 1,885 | 610 | 1,521 | 1,300 | 1,430 | 2,480 | 1,211 | 12,750 |
| 29 | 4,250 | 3,950 | 11,450 | 7,860 | 1,775 | 610 | 2,095 | 1,115 | 1,175 | 2,137 | 995 | 13,810 |
| 30 | 3,950 | ----- | 8,590 | 6,420 | 1,573 | 640 | 2,450 | 995 | 2,480 | 1,927 | 1,495 | 7,770 |
| 31 | 3,500 | ----- | 8,590 | ----- | 2,249 | ----- | 1,651 | 899 | ----- | 1,651 | ----- | 401 |

The daily discharge during January, February, and March is only approximate, owing to the ice conditions. From March 4 to 22, 1904, the discharge was estimated from the measurement of March 8, which was approximately 50 per cent of normal conditions. This was due to an ice gorge.

*Estimated monthly discharge of Chenango River at Binghamton, N. Y.,
1901-1904.*

[Drainage area 1,530 square miles.]

| Month. | Discharge in second-feet. | | | Run-off. | | | Rainfall in inches. |
|-----------------|---------------------------|----------|---------|------------------------------------|------------------------|-------------------------------------|---------------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. | Per cent of rain- fall. | |
| 1901. | | | | | | | |
| August | 2, 165 | 208 | 576 | 0.38 | 0.44 | 9 | 4.50 |
| September | 1, 091 | 304 | 524 | .34 | .38 | 12 | 3.12 |
| October | 1, 846 | 480 | 807 | .53 | .61 | 31 | 1.88 |
| November | 3, 800 | 285 | 1, 204 | .78 | .87 | 31 | 2.70 |
| December | 27, 630 | 1, 115 | 4, 750 | 3.10 | 3.57 | 65 | 5.34 |
| 1902. | | | | | | | |
| January | 5, 105 | 827 | 1, 960 | 1.28 | 1.48 | 108 | 1.33 |
| February | 5, 530 | 804 | 1, 339 | .87 | .91 | 29 | 2.99 |
| March | 35, 950 | 4, 325 | 11, 717 | 7.64 | 8.81 | 241 | 3.56 |
| April | 5, 700 | 1, 417 | 3, 246 | 2.12 | 2.37 | 136 | 1.68 |
| May | 2, 067 | 782 | 1, 307 | .85 | .98 | 36 | 2.64 |
| June | 8, 495 | 1, 235 | 1, 820 | 1.19 | 1.33 | 22 | 5.87 |
| July | 17, 400 | 1, 859 | 6, 011 | 3.92 | 4.52 | 54 | 8.07 |
| August | 6, 510 | 827 | 2, 002 | 1.30 | 1.50 | 48 | 3.07 |
| September | 3, 575 | 410 | 809 | .53 | .59 | 17 | 3.28 |
| October | 10, 680 | 1, 187 | 2, 539 | 1.66 | 1.91 | 47 | 3.92 |
| November | 4, 175 | 1, 313 | 1, 999 | 1.30 | 1.43 | 117 | 1.21 |
| December | 15, 405 | 1, 248 | 4, 273 | 2.79 | 3.22 | 71 | 4.36 |
| The year | 35, 950 | 410 | 3, 252 | 2.12 | 29.07 | 67 | 41.97 |
| 1903. | | | | | | | |
| January | 14, 775 | 2, 081 | 5, 389 | 3.44 | 3.99 | 145 | 2.67 |
| February | 14, 050 | 1, 807 | 5, 291 | 3.44 | 3.58 | 142 | 2.45 |
| March | 20, 600 | 4, 325 | 10, 114 | 6.59 | 7.40 | 147 | 5.03 |
| April | 7, 770 | 1, 067 | 3, 210 | 2.09 | 2.33 | 140 | 1.61 |
| May | 1, 007 | 314 | 608 | .40 | .46 | 142 | .31 |
| June | 5, 700 | 103 | 1, 737 | 1.13 | 1.26 | 19 | 6.62 |
| July | 2, 825 | 570 | 1, 039 | .68 | .78 | 20 | 3.79 |
| August | 16, 560 | 600 | 2, 812 | 1.83 | 2.11 | 31 | 6.72 |
| September | 7, 500 | 716 | 1, 763 | 1.15 | 1.28 | 81 | 1.55 |
| October | 28, 540 | 661 | 6, 243 | 4.07 | 4.69 | 60 | 7.64 |
| November | 7, 680 | 1, 430 | 2, 385 | 1.55 | 1.73 | 79 | 2.12 |
| December | 4, 625 | 1, 115 | 1, 886 | 1.23 | 1.42 | 55 | 2.50 |
| The year | 28, 540 | 103 | 3, 532 | 2.30 | 31.21 | 71 | 43.00 |

*Estimated monthly discharge of Chenango River at Binghamton, N. Y.,
1901-1904—Continued.*

| Month. | Discharge in second-feet. | | | Run-off. | |
|-----------------|---------------------------|----------|-------|------------------------------------|------------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1904. | | | | | |
| January | 10,490 | 1,391 | 3,160 | 2.06 | 2.37 |
| February | 18,030 | 2,235 | 6,390 | 4.17 | 4.50 |
| March | 28,540 | 2,680 | 8,966 | 5.84 | 6.73 |
| April | 13,150 | 4,025 | 7,037 | 4.59 | 5.12 |
| May | 5,190 | 1,417 | 2,376 | 1.55 | 1.79 |
| June | 4,100 | 610 | 1,518 | .990 | 1.105 |
| July | 2,450 | 450 | 1,060 | .691 | .807 |
| August | 4,475 | 705 | 1,641 | 1.07 | 1.23 |
| September | 2,480 | 460 | 953 | .621 | .693 |
| October | 8,970 | 983 | 2,587 | 1.69 | 1.95 |
| November | 2,305 | 995 | 1,429 | .932 | 1.04 |
| December | 13,810 | 401 | 1,981 | 1.29 | 1.49 |
| The year | 28,540 | 401 | 3,258 | 2.12 | 28.82 |

SUSQUEHANNA RIVER AT WILKESBARRE, PA.

The Wilkesbarre station was established by E. G. Paul on March 30, 1899.

The standard chain gage is located on the upstream side of the Market Street Bridge. The length of the chain from the end of the weight to the marker is 40.83 feet. The gage is read once each day by W. S. Bennett, the bridge keeper. When this gage was established, there was found to be a gage painted on the bridge pier, being a portion of one established by the Weather Bureau. The lower part of this gage, erected in January, 1898, originally consisted of heavy cast-brass plates graduated to feet and tenths. The gage plates were made in 4-foot sections and bolted to the stone bridge pier. The two lower sections of the brass plates had been torn away by ice, so that there was no graduation below the 8-foot mark, but readings were made by the figures painted on the stone pier. The zero of this old gage is at the base of the dressed-stone portion of the pier and is reported to be 535 feet above sea level. During low stages of the river the water recedes from the pier, rendering it impracticable to read the gage. So far as could be ascertained, this

has not been connected with the city datum. On account of the low water, which in 1897 had gone below the city datum, it was decided to put the zero of the new gage 4 feet below the zero of the old Weather Bureau gage, so as to obviate minus readings. In order, therefore, to compare with former records, it is necessary to add 4 feet to the old figures. The danger mark of this Weather Bureau gage is at 14 feet, or 18 feet of new gage, as at this elevation the west bank of the river is under water in places. River reports from this locality were furnished as early as 1888. During low water measurements were made by wading at a better cross section, at Retreat, 10 miles below Wilkesbarre. The elevation of the Market Street toll bridge above the river bed requires 65 feet of cable to sound across the section.

Observations of fluctuations of Susquehanna River are made by the Weather Bureau above Wilkesbarre, at Towanda, Pa., where the drainage area is estimated to be 8,000 square miles. The river gage, made of iron 1 foot wide and one-half inch thick, is on the east side of the road bridge over Susquehanna River, and is securely bolted to the masonry of the pier. The graduation is from 0 to 25 feet. The highest water was 29 feet in March, 1869, and the lowest, -0.1 foot, in October, 1895. The danger line is at 16 feet. The elevation of the zero is 633.7 feet.

Discharge measurements are made from the downstream side of the bridge, which has a total span of 700 feet between abutments. The initial point for soundings is the end of the iron handrail on the left bank, downstream side. The channel is straight for about one-fourth mile above and below the station. There is a bar across the river about one-half mile above the station, and another at about the same distance below, with deep water between these two points. This makes a sluggish current at low stages. The right bank is low and overflows at a gage height of about 20 feet. The left bank is above ordinary floods. The bed of the stream is composed of sand and gravel and is somewhat shifting. There is but one channel, broken by 3 bridge piers. There are a few willows growing under the right span. The bench mark is the extreme west end of the stone doorsill of the north entrance to the Coal Exchange Building. Its elevation is 32.99 feet above gage datum.

Discharge measurements of Susquehanna River at Wilkesbarre, Pa., 1899-1904.

| Date. | Hydrographer. | Gage height. | Area of section. | Mean velocity. | Dis-charge. |
|-----------------------|----------------------|--------------|------------------|---------------------|-----------------|
| 1899. | | <i>Feet.</i> | <i>Sq. ft.</i> | <i>Ft. per sec.</i> | <i>Sec.-ft.</i> |
| Mar. 30 | E. G. Paul | 9.00 | 6,846 | 3.62 | 24,800 |
| June 6 |do | 4.30 | 3,064 | 1.20 | 3,668 |
| July 26 ^a |do | 2.80 | 1,223 | 1.57 | 1,924 |
| July 27 |do | 2.80 | 1,508 | .90 | 1,357 |
| Sept. 17 |do | 2.30 | 2,193 | .38 | 851 |
| Sept. 18 ^a |do | 2.30 | 1,115 | .98 | 1,096 |
| Oct. 16 |do | 2.35 | 1,054 | 1.06 | 1,114 |
| 1900. | | | | | |
| May 20 | E. G. Paul | 5.60 | 3,599 | 1.88 | 6,772 |
| Sept. 26 ^a |do | 2.20 | 1,023 | .93 | 961 |
| 1901. | | | | | |
| Aug. 20 | E. G. Paul | 3.10 | 3,154 | .69 | 2,170 |
| 1902. | | | | | |
| Sept. 20 | E. G. Paul | 3.10 | 3,154 | .69 | 2,170 |
| 1903. | | | | | |
| Mar. 4 | E. C. Murphy | 13.50 | 9,996 | 4.61 | 46,112 |
| Apr. 8 |do | 8.86 | 6,920 | 3.37 | 23,247 |
| Aug. 4 | John C. Hoyt | 4.00 | 3,489 | 1.35 | 4,718 |
| Oct. 10 | W. C. Sawyer | 19.00 | 13,163 | 6.57 | 86,500 |
| 1904. | | | | | |
| July 20 | N. C. Grover | 4.05 | 3,864 | 1.13 | 4,382 |
| July 21 ^b |do | 4.20 | 4,077 | 1.15 | 4,680 |
| Sept. 15 | John C. Hoyt | 3.70 | 3,670 | .96 | 3,540 |
| Oct. 1 |do | 4.75 | 4,220 | 1.44 | 6,090 |
| Nov. 5 | H. D. Comstock | 4.61 | 4,218 | 1.47 | 6,189 |
| Nov. 7 |do | 4.49 | 4,057 | 1.39 | 5,660 |

^a Measured at Retreat.^b Measured at Pittston.

*Mean daily gage height, in feet, of Susquehanna River at Wilkesbarre, Pa.,
1899-1904.*

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|-------|-------|-------|-------|------|-------|-------|------|-------|------|-------|--------------------|
| 1899. | | | | | | | | | | | | |
| 1 | | | | 8.40 | 6.40 | 4.50 | 3.60 | 2.70 | 3.10 | 2.50 | 2.50 | 3.40 |
| 2 | | | | 8.10 | 6.20 | 5.50 | 3.30 | 2.60 | 2.90 | 2.50 | 3.00 | 3.40 |
| 3 | | | | 7.70 | 6.30 | 5.30 | 3.30 | 2.70 | 2.60 | 2.50 | 8.30 | 3.40 |
| 4 | | | | 7.20 | 6.30 | 5.10 | 3.20 | 2.60 | 2.60 | 2.50 | 6.70 | 3.40 |
| 5 | | | | 6.90 | 6.40 | 4.60 | 3.00 | 3.20 | 2.50 | 2.50 | 7.30 | 3.50 |
| 6 | | | | 6.90 | 6.10 | 4.30 | 3.00 | 3.00 | 2.50 | 2.60 | 6.60 | 3.50 |
| 7 | | | | 7.40 | 5.70 | 3.60 | 2.80 | 2.80 | 2.50 | 2.60 | 6.90 | 3.50 |
| 8 | | | | 10.35 | 5.60 | 3.50 | 2.90 | 2.50 | 2.40 | 2.50 | 5.30 | 3.70 |
| 9 | | | | 14.10 | 5.40 | 3.50 | 2.80 | 2.50 | 2.40 | 2.50 | 5.00 | 3.60 |
| 10 | | | | 14.20 | 5.30 | 3.50 | 2.80 | 2.50 | 2.40 | 2.50 | 4.50 | 3.50 |
| 11 | | | | 12.80 | 5.10 | 3.30 | 2.80 | 2.50 | 2.40 | 2.50 | 4.20 | 3.50 |
| 12 | | | | 11.10 | 5.20 | 3.20 | 2.90 | 2.50 | 2.50 | 2.50 | 4.30 | 3.60 |
| 13 | | | | 11.30 | 5.10 | 3.20 | 2.90 | 2.70 | 2.50 | 2.40 | 4.90 | 7.70 |
| 14 | | | | 14.00 | 5.00 | 3.20 | 3.00 | 2.80 | 2.50 | 2.40 | 4.70 | 9.60 |
| 15 | | | | 14.30 | 5.00 | 3.00 | 3.20 | 2.80 | 2.40 | 2.40 | 4.60 | 9.60 |
| 16 | | | | 13.90 | 4.80 | 3.10 | 3.30 | 2.80 | 2.40 | 2.40 | 4.50 | 8.50 |
| 17 | | | | 13.40 | 4.80 | 3.20 | 3.10 | 2.90 | 2.30 | 2.30 | 5.20 | 7.70 |
| 18 | | | | 12.50 | 4.70 | 3.20 | 3.00 | 2.70 | 2.30 | 2.30 | 5.20 | 7.30 |
| 19 | | | | 11.30 | 4.90 | 3.00 | 3.00 | 2.40 | 2.30 | 2.30 | 5.30 | 6.50 |
| 20 | | | | 10.50 | 4.90 | 3.00 | 3.00 | 2.30 | 2.30 | 2.30 | 5.00 | 6.50 |
| 21 | | | | 9.90 | 5.40 | 3.10 | 3.10 | 2.30 | 2.30 | 2.30 | 4.70 | 8.30 |
| 22 | | | | 9.40 | 5.90 | 3.00 | 3.00 | 2.60 | 2.30 | 2.30 | 4.60 | 8.40 |
| 23 | | | | 9.00 | 5.80 | 3.00 | 3.00 | 2.50 | 2.30 | 2.30 | 4.30 | 7.40 |
| 24 | | | | 8.50 | 5.70 | 2.90 | 2.90 | 2.50 | 2.30 | 2.30 | 4.20 | 6.60 |
| 25 | | | | 8.00 | 5.50 | 2.90 | 2.80 | 2.40 | 2.20 | 2.30 | 4.00 | 8.40 |
| 26 | | | | 7.40 | 5.40 | 3.10 | 2.80 | 2.40 | 2.50 | 2.20 | 3.80 | 8.00 |
| 27 | | | | 7.60 | 5.10 | 3.10 | 2.80 | 2.40 | 2.40 | 2.30 | 3.80 | 7.40 |
| 28 | | | | 7.40 | 4.90 | 3.30 | 2.80 | 2.40 | 2.50 | 2.30 | 3.70 | 6.30 |
| 29 | | | | 7.10 | 4.80 | 3.80 | 2.80 | 4.60 | 2.50 | 2.50 | 3.60 | 9.10 |
| 30 | | | 9.00 | 6.60 | 4.80 | 4.00 | 2.60 | 4.10 | 2.60 | 2.50 | 3.50 | 7.90 |
| 31 | | | 8.70 | | 4.70 | | 2.60 | 3.40 | | 2.50 | | 7.70 |
| 1900. | | | | | | | | | | | | |
| 1 | 6.80 | 7.40 | 10.40 | 6.90 | 6.10 | 3.80 | 3.00 | 3.20 | 3.10 | 2.30 | 2.70 | 10.50 |
| 2 | 6.20 | 6.80 | 17.75 | 7.50 | 5.80 | 3.70 | 2.80 | 3.20 | 3.00 | 2.30 | 2.60 | 9.20 |
| 3 | 6.40 | 6.30 | 14.55 | 9.80 | 5.50 | 4.20 | 2.70 | 3.00 | 3.10 | 2.30 | 2.60 | 8.10 |
| 4 | 6.80 | 6.50 | 11.80 | 11.40 | 5.30 | 3.90 | 2.90 | 2.90 | 3.00 | 2.30 | 2.50 | 7.40 |
| 5 | 7.00 | 8.40 | 9.90 | 11.10 | 5.20 | 3.70 | 2.90 | 2.90 | 2.90 | 2.30 | 2.70 | 9.20 |
| 6 | 7.00 | 8.50 | 8.40 | 9.40 | 5.00 | 3.80 | 3.40 | 2.90 | 2.80 | 2.20 | 2.80 | 11.90 |
| 7 | 6.90 | 7.90 | 8.20 | 9.60 | 4.80 | 3.70 | 3.90 | 2.90 | 2.70 | 2.10 | 3.00 | 11.30 |
| 8 | 6.80 | 7.80 | 8.10 | 11.70 | 4.70 | 3.60 | 3.60 | 2.90 | 2.70 | 2.10 | 2.90 | 9.90 |
| 9 | 6.50 | 14.45 | 7.70 | 12.20 | 4.60 | 3.60 | 3.40 | 2.90 | 2.60 | 2.20 | 2.90 | 8.90 |
| 10 | 6.10 | 9.20 | 8.40 | 10.90 | 4.50 | 3.80 | 3.20 | 2.80 | 2.60 | 2.20 | 2.90 | 8.20 |
| 11 | 5.80 | 9.80 | 9.00 | 9.20 | 4.50 | 3.90 | 3.10 | 2.80 | 2.70 | 2.20 | 3.00 | 7.50 |
| 12 | 5.90 | 9.20 | 7.80 | 7.90 | 4.80 | 4.30 | 2.90 | 2.70 | 2.70 | 2.20 | 3.10 | 6.60 |
| 13 | 5.60 | 9.20 | 6.80 | 7.30 | 4.90 | 4.30 | 3.00 | 2.70 | 2.70 | 2.20 | 3.30 | 6.20 |
| 14 | 5.90 | 12.10 | 6.30 | 7.70 | 4.80 | 4.80 | 3.00 | 2.60 | 2.50 | 2.20 | 3.50 | 6.10 |
| 15 | 5.60 | 13.65 | 5.70 | 8.10 | 4.70 | 4.30 | 3.00 | 2.60 | 2.40 | 2.20 | 3.50 | ^a 10.30 |
| 16 | 5.50 | 11.80 | 5.70 | 7.80 | 4.70 | 4.00 | 3.00 | 2.60 | 2.50 | 2.30 | 3.40 | 9.80 |
| 17 | 5.50 | 9.20 | 9.00 | 7.60 | 4.90 | 3.80 | 2.90 | 2.50 | 2.40 | 2.40 | 3.30 | 9.20 |
| 18 | 5.20 | 7.70 | 8.10 | 10.05 | 5.00 | 3.60 | 2.90 | 2.50 | 2.30 | 2.40 | 3.20 | 8.70 |
| 19 | 5.10 | 8.90 | 8.30 | 12.45 | 5.10 | 3.50 | 2.80 | 2.40 | 2.20 | 2.50 | 3.20 | 9.20 |
| 20 | 5.80 | 10.70 | 8.50 | 12.40 | 5.60 | 3.40 | 3.10 | 2.50 | 2.20 | 2.70 | 3.10 | 9.60 |
| 21 | 14.65 | 9.80 | 10.85 | 11.10 | 5.20 | 3.30 | 3.20 | 2.50 | 2.10 | 2.60 | 3.10 | 9.40 |
| 22 | 16.85 | 11.40 | 9.70 | 10.00 | 5.00 | 3.20 | 3.10 | 2.50 | 2.20 | 2.60 | 3.20 | 9.00 |
| 23 | 13.50 | 16.10 | 9.20 | 9.50 | 4.80 | 3.50 | 3.00 | 2.80 | 2.20 | 2.70 | 3.60 | 8.80 |
| 24 | 10.30 | 14.75 | 8.40 | 11.30 | 4.60 | 3.30 | 2.90 | 3.00 | 2.20 | 2.90 | 4.00 | 9.20 |
| 25 | 8.50 | 11.00 | 9.90 | 10.70 | 4.50 | 3.30 | 2.90 | 2.90 | 2.20 | 2.80 | 4.30 | 8.80 |
| 26 | 7.80 | 8.80 | 8.70 | 9.50 | 4.30 | 3.20 | 4.00 | 2.60 | 2.20 | 2.80 | 4.70 | 12.80 |
| 27 | 7.90 | 7.00 | 8.10 | 8.40 | 4.10 | 3.20 | 3.70 | 2.70 | 2.30 | 2.70 | 16.75 | 14.20 |
| 28 | 6.20 | 8.50 | 7.10 | 7.50 | 4.00 | 3.10 | 3.40 | 2.80 | 2.20 | 2.70 | 20.75 | 12.90 |
| 29 | 9.20 | | 7.00 | 6.90 | 3.90 | 3.10 | 3.20 | 2.80 | 2.20 | 2.70 | 14.65 | 12.40 |
| 30 | 9.00 | | 6.80 | 6.50 | 3.80 | 3.10 | 3.20 | 3.10 | 2.30 | 2.70 | 11.80 | 11.40 |
| 31 | 8.70 | | 6.50 | | 3.70 | | 3.30 | 3.10 | | 2.60 | | 11.40 |

^aIce backed water at gage.

*Mean daily gage height, in feet, of Susquehanna River at Wilkesbarre, Pa.,
1899-1904—Continued.*

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|--------|
| 1901. | | | | | | | | | | | | |
| 1 | 10.60 | 8.60 | 6.20 | 9.70 | 7.80 | 14.55 | 4.50 | 3.40 | 5.80 | 3.90 | 3.20 | 7.30 |
| 2 | 10.60 | 8.40 | 6.10 | 8.80 | 7.20 | 11.70 | 4.00 | 3.20 | 5.60 | 3.70 | 3.20 | 6.70 |
| 3 | 9.50 | 8.30 | 6.10 | 8.30 | 8.70 | 11.00 | 3.50 | 3.00 | 5.70 | 4.00 | 3.10 | 6.80 |
| 4 | 8.70 | 8.40 | 6.10 | 9.30 | 8.90 | 10.60 | 3.60 | 3.00 | 5.30 | 4.30 | 3.10 | a 9.30 |
| 5 | 8.50 | 8.00 | 6.20 | 10.80 | 8.10 | 9.20 | 3.60 | 3.00 | 5.00 | 4.00 | 3.00 | 9.90 |
| 6 | 7.20 | 7.80 | 6.00 | 11.90 | 7.50 | 8.10 | 3.60 | 3.00 | 4.50 | 3.90 | 3.00 | 9.40 |
| 7 | 7.10 | 7.80 | 5.90 | 16.20 | 6.80 | 8.10 | 4.30 | 3.00 | 4.20 | 3.70 | 3.00 | 9.00 |
| 8 | 7.00 | 7.70 | 5.80 | 18.05 | 6.30 | 9.00 | 4.00 | 3.30 | 3.80 | 3.60 | 3.00 | 8.30 |
| 9 | 7.90 | 7.70 | 5.70 | 16.90 | 5.90 | 9.30 | 4.00 | 3.20 | 3.70 | 3.40 | 3.00 | 8.70 |
| 10 | 7.90 | 7.50 | 6.50 | 14.70 | 5.80 | 8.90 | 3.90 | 3.10 | 3.50 | 3.50 | 3.00 | 11.70 |
| 11 | 7.80 | 7.60 | 8.40 | 13.20 | 6.40 | 8.00 | 3.80 | 3.20 | 3.30 | 3.20 | 2.90 | 12.10 |
| 12 | 7.80 | 7.60 | 18.80 | 11.80 | 7.80 | 7.20 | 3.80 | 3.30 | 3.30 | 3.20 | 3.00 | 11.70 |
| 13 | 8.10 | 7.40 | 12.20 | 10.70 | 9.50 | 6.50 | 3.60 | 3.10 | 3.30 | 3.30 | 3.00 | 10.10 |
| 14 | 9.00 | 6.90 | 9.70 | 10.10 | 9.80 | 6.10 | 3.50 | 3.10 | 3.30 | 3.50 | 3.50 | 8.80 |
| 15 | 12.00 | 7.00 | 8.90 | 9.60 | 9.10 | 5.90 | 3.40 | 3.20 | 3.20 | 4.10 | 4.00 | 20.40 |
| 16 | 14.50 | 7.10 | 9.10 | 9.30 | 8.00 | 5.70 | 3.20 | 3.60 | 3.30 | 4.30 | 4.70 | 26.75 |
| 17 | 14.00 | 7.30 | 8.80 | 8.90 | 7.10 | 5.50 | 3.20 | 3.70 | 3.50 | 4.40 | 4.50 | 22.80 |
| 18 | 13.60 | 7.30 | 8.30 | 8.50 | 6.70 | 5.30 | 3.60 | 8.15 | 3.80 | 4.30 | 4.20 | 15.60 |
| 19 | 12.50 | 7.20 | 8.00 | 8.10 | 6.80 | 4.90 | 3.40 | 5.60 | 4.00 | 4.20 | 4.10 | 11.00 |
| 20 | 11.50 | 6.90 | 10.10 | 7.90 | 7.00 | 4.70 | 3.30 | 4.80 | 4.20 | 4.00 | 4.00 | 8.20 |
| 21 | 9.40 | 6.90 | 12.15 | 11.05 | 7.10 | 4.60 | 3.10 | 4.60 | 4.10 | 3.90 | 4.00 | 7.80 |
| 22 | 10.50 | 6.70 | 14.80 | 18.10 | 6.50 | 4.40 | 3.00 | 6.95 | 3.90 | 3.80 | 3.90 | 9.50 |
| 23 | 11.00 | 6.80 | 14.50 | 17.10 | 6.40 | 4.50 | 3.10 | 6.90 | 3.70 | 3.70 | 3.80 | 11.20 |
| 24 | 11.00 | 6.40 | 12.90 | 14.80 | 7.90 | 5.60 | 3.10 | 6.50 | 3.50 | 3.70 | 3.80 | 11.70 |
| 25 | 11.70 | 6.40 | 12.90 | 14.70 | 9.00 | 5.70 | 3.00 | 10.50 | 3.40 | 3.60 | 6.00 | 13.70 |
| 26 | 11.00 | 6.30 | 13.80 | 13.60 | 8.30 | 5.70 | 3.00 | 9.20 | 3.20 | 3.40 | 9.10 | 13.50 |
| 27 | 10.50 | 6.20 | 17.15 | 12.30 | 7.60 | 5.00 | 2.90 | 7.10 | 3.20 | 3.40 | 7.60 | 13.30 |
| 28 | 10.00 | 6.30 | 21.40 | 11.00 | 7.40 | 4.20 | 2.90 | 6.10 | 3.10 | 3.40 | 6.20 | 12.80 |
| 29 | 9.50 | ----- | 19.45 | 9.60 | 10.60 | 4.50 | 3.00 | 5.30 | 3.30 | 3.20 | 5.50 | 13.10 |
| 30 | 9.30 | ----- | 15.50 | 8.60 | 16.85 | 4.20 | 3.30 | 4.80 | 3.80 | 3.10 | 5.70 | 13.10 |
| 31 | 9.10 | ----- | 12.90 | ----- | 17.55 | ----- | 3.60 | 4.90 | ----- | 3.10 | ----- | 13.50 |
| 1902. | | | | | | | | | | | | |
| 1 | 14.00 | 12.70 | 29.57 | 9.70 | 5.00 | 4.10 | 10.60 | 8.80 | 3.60 | 9.60 | 9.50 | 5.10 |
| 2 | 13.00 | 11.40 | 30.75 | 9.20 | 4.90 | 4.00 | 10.50 | 9.50 | 3.50 | 10.80 | 8.20 | 5.00 |
| 3 | 12.10 | 10.80 | 30.05 | 9.00 | 5.10 | 3.90 | 8.30 | 11.10 | 3.40 | 10.60 | 7.40 | 5.00 |
| 4 | 10.90 | 10.70 | 25.25 | 8.50 | 5.10 | 3.90 | 7.80 | 9.60 | 3.40 | 8.50 | 6.80 | 5.20 |
| 5 | 9.60 | 8.50 | 20.20 | 8.10 | 4.80 | 3.80 | 8.50 | 8.80 | 3.20 | 7.30 | 6.40 | 5.50 |
| 6 | 9.90 | 7.00 | 14.65 | 7.90 | 4.80 | 3.80 | 8.26 | 7.50 | 3.20 | 7.10 | 6.00 | 5.90 |
| 7 | 9.80 | 9.10 | 11.65 | 7.60 | 4.70 | 4.80 | 12.70 | 6.80 | 3.20 | 6.90 | 5.80 | 5.80 |
| 8 | 9.60 | 9.80 | 10.70 | 7.70 | 4.70 | 4.50 | 14.20 | 6.50 | 3.20 | 6.70 | 5.50 | 5.50 |
| 9 | 9.70 | 9.60 | 10.30 | 11.85 | 4.50 | 4.40 | 13.15 | 6.20 | 3.20 | 6.20 | 5.60 | 5.20 |
| 10 | 9.40 | 9.40 | 11.00 | 15.80 | 4.40 | 4.20 | 8.75 | 5.80 | 3.20 | 5.80 | 5.70 | 5.90 |
| 11 | 9.20 | 9.00 | 12.50 | 15.45 | 4.30 | 4.20 | 9.00 | 5.60 | 3.60 | 5.50 | 5.00 | 7.20 |
| 12 | 9.00 | 9.00 | 14.80 | 12.80 | 4.20 | 4.20 | 9.70 | 5.50 | 3.50 | 5.80 | 4.70 | 8.00 |
| 13 | 8.20 | 9.00 | 18.00 | 14.40 | 4.10 | 4.10 | 8.50 | 5.40 | 3.60 | 6.50 | 4.70 | 9.85 |
| 14 | 7.20 | 8.30 | 19.60 | 10.30 | 4.00 | 4.20 | 7.40 | 5.40 | 3.50 | 6.00 | 4.70 | 10.20 |
| 15 | 6.40 | 8.00 | 18.20 | 9.40 | 3.90 | 4.20 | 6.30 | 5.20 | 3.50 | 5.80 | 4.70 | 9.20 |
| 16 | 6.80 | 8.20 | 15.80 | 8.60 | 3.80 | 4.20 | 5.80 | 5.00 | 3.40 | 5.90 | 4.60 | 10.70 |
| 17 | 7.20 | 7.80 | 18.50 | 8.00 | 3.80 | 5.00 | 5.40 | 4.60 | 3.30 | 5.90 | 4.50 | 13.45 |
| 18 | 7.00 | 7.70 | 20.20 | 7.40 | 3.70 | 4.70 | 5.20 | 4.40 | 3.30 | 5.60 | 4.40 | 12.70 |
| 19 | 6.70 | 7.20 | 17.45 | 7.00 | 3.70 | 4.40 | 5.10 | 4.20 | 3.20 | 5.30 | 4.30 | 12.40 |
| 20 | 6.10 | 6.60 | 14.30 | 6.70 | 3.60 | 4.60 | 5.40 | 4.10 | 3.10 | 4.90 | 4.20 | 11.30 |
| 21 | 6.20 | 6.60 | 11.60 | 6.40 | 3.50 | 4.30 | 12.10 | 4.00 | 3.10 | 4.80 | 4.20 | 10.00 |
| 22 | 10.60 | 6.50 | 10.20 | 6.20 | 3.50 | 4.30 | 15.90 | 4.00 | 3.00 | 4.90 | 4.20 | 15.60 |
| 23 | 16.70 | 6.40 | 9.70 | 6.00 | 3.50 | 4.20 | 13.90 | 4.00 | 3.00 | 5.20 | 4.10 | 17.65 |
| 24 | 12.20 | 7.20 | 9.60 | 5.70 | 3.70 | 4.20 | 13.45 | 3.90 | 3.00 | 5.00 | 4.10 | 16.35 |
| 25 | 10.70 | 7.20 | 9.50 | 5.50 | 3.70 | 4.20 | 13.85 | 3.90 | 3.00 | 4.70 | 4.10 | 13.70 |
| 26 | 9.70 | 7.70 | 9.00 | 5.20 | 3.70 | 4.20 | 14.90 | 3.80 | 4.20 | 4.70 | 4.10 | 11.00 |
| 27 | 8.90 | 8.80 | 8.50 | 5.00 | 3.80 | 4.10 | 11.70 | 3.70 | 7.10 | 4.60 | 4.50 | 9.70 |
| 28 | 8.20 | 14.03 | 8.00 | 4.80 | 3.90 | 3.90 | 9.70 | 3.60 | 6.00 | 7.62 | 4.70 | 8.50 |
| 29 | 7.70 | ----- | 9.00 | 4.70 | 4.60 | 3.80 | 10.80 | 3.60 | 7.90 | 11.05 | 5.00 | 8.00 |
| 30 | 7.60 | ----- | 10.40 | 4.90 | 4.60 | 5.10 | 10.60 | 3.60 | 10.70 | 12.05 | 5.20 | 7.00 |
| 31 | 13.30 | ----- | 9.80 | ----- | 4.20 | ----- | 9.30 | 3.60 | ----- | 11.10 | ----- | 6.80 |

a River frozen over.

Mean daily gage height, in feet, of Susquehanna River at Wilkesbarre, Pa.,
1899-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|---------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| 1903. | | | | | | | | | | | | |
| 1..... | 8.50 | 15.30 | 20.40 | 11.20 | 4.80 | 3.00 | 6.90 | 4.60 | 13.80 | 3.60 | 5.60 | 7.20 |
| 2..... | 11.00 | 13.10 | 19.94 | 12.00 | 4.60 | 3.00 | 6.80 | 4.60 | 11.90 | 3.60 | 5.60 | 7.30 |
| 3..... | 12.80 | 13.00 | 16.28 | 10.70 | 4.40 | 3.00 | 6.10 | 4.30 | 9.90 | 3.60 | 5.40 | 7.50 |
| 4..... | 13.00 | 14.65 | 13.60 | 9.70 | 4.30 | 2.90 | 5.50 | 4.00 | 8.40 | 3.60 | 5.20 | 6.70 |
| 5..... | 13.50 | 18.78 | 11.30 | 9.80 | 4.20 | 2.90 | 5.40 | 4.80 | 7.40 | 3.60 | 5.00 | 5.20 |
| 6..... | 9.70 | 16.50 | 10.50 | 9.90 | 4.10 | 2.90 | 5.50 | 6.70 | 6.70 | 3.70 | 5.00 | 4.50 |
| 7..... | 8.10 | 13.90 | 12.10 | 8.70 | 4.00 | 2.90 | 7.30 | 7.90 | 6.20 | 3.80 | 5.00 | 4.20 |
| 8..... | 7.90 | 11.30 | 11.60 | 8.80 | 4.00 | 2.90 | 7.30 | 7.60 | 5.80 | 4.70 | 5.20 | 4.20 |
| 9..... | 6.90 | 10.00 | 16.20 | 10.60 | 4.00 | 3.00 | 9.40 | 6.80 | 5.53 | 10.70 | 5.30 | 4.30 |
| 10..... | 6.80 | 8.60 | 18.60 | 10.80 | 3.80 | 3.00 | 4.80 | 6.00 | 5.30 | 19.20 | 5.00 | 4.10 |
| 11..... | 10.70 | 8.00 | 17.94 | 9.80 | 3.70 | 2.90 | 4.40 | 5.70 | 5.20 | 21.25 | 4.90 | 4.00 |
| 12..... | 10.00 | 8.50 | 18.91 | 9.00 | 3.70 | 3.60 | 4.30 | 5.40 | 5.30 | 21.15 | 4.70 | 3.70 |
| 13..... | 9.50 | 9.10 | 17.80 | 8.90 | 3.60 | 6.60 | 4.00 | 5.50 | 6.00 | 18.15 | 4.60 | 3.90 |
| 14..... | 9.10 | 11.00 | 15.70 | 8.30 | 3.50 | 5.00 | 3.80 | 5.20 | 5.60 | 13.70 | 4.50 | 4.70 |
| 15..... | 9.10 | 10.80 | 13.20 | 12.20 | 3.50 | 7.50 | 3.70 | 4.90 | 5.20 | 10.50 | 4.40 | 4.80 |
| 16..... | 10.00 | 9.30 | 11.70 | 14.20 | 3.50 | 6.40 | 3.60 | 4.70 | 4.80 | 9.00 | 4.20 | 5.80 |
| 17..... | 10.50 | 8.40 | 10.60 | 12.30 | 3.40 | 5.80 | 3.60 | 4.50 | 4.60 | 8.00 | 7.90 | 6.60 |
| 18..... | 10.40 | 7.40 | 9.90 | 10.50 | 3.40 | 5.20 | 3.40 | 4.30 | 5.20 | 8.30 | 12.90 | 6.80 |
| 19..... | 9.60 | 10.00 | 9.60 | 9.00 | 3.30 | 5.00 | 4.30 | 3.90 | 4.80 | 12.50 | 13.70 | 6.30 |
| 20..... | 8.70 | 9.20 | 9.20 | 8.00 | 3.30 | 4.80 | 4.60 | 3.70 | 5.00 | 12.40 | 10.80 | 5.80 |
| 21..... | 8.60 | 9.40 | 8.70 | 7.30 | 3.30 | 4.70 | 4.80 | 3.80 | 4.80 | 10.90 | 8.70 | 8.90 |
| 22..... | 9.40 | 10.00 | 8.30 | 6.80 | 3.50 | 6.80 | 5.10 | 5.60 | 4.70 | 9.40 | 7.10 | 9.00 |
| 23..... | 9.80 | 10.50 | 13.32 | 6.40 | 3.30 | 8.00 | 4.70 | 5.30 | 4.40 | 8.30 | 6.70 | 8.40 |
| 24..... | 10.40 | 10.90 | 20.88 | 6.10 | 3.30 | 8.93 | 4.40 | 5.00 | 4.20 | 7.50 | 6.20 | 8.00 |
| 25..... | 10.00 | 11.20 | 21.16 | 5.90 | 3.10 | 9.45 | 4.40 | 4.60 | 4.00 | 7.00 | 6.20 | 7.50 |
| 26..... | 9.60 | 10.40 | 18.00 | 5.70 | 3.10 | 10.40 | 6.10 | 4.40 | 3.90 | 6.80 | 6.10 | 7.10 |
| 27..... | 8.70 | 9.60 | 15.40 | 5.50 | 3.10 | 10.20 | 5.20 | 4.30 | 3.80 | 6.50 | 5.80 | 7.20 |
| 28..... | 8.20 | 10.20 | 12.60 | 5.30 | 3.10 | 8.00 | 4.50 | 5.40 | 3.80 | 6.20 | 5.50 | 10.40 |
| 29..... | 8.20 | ----- | 10.70 | 5.10 | 3.00 | 6.90 | 4.10 | 9.15 | 3.70 | 6.00 | 6.00 | 9.70 |
| 30..... | 14.54 | ----- | 9.90 | 4.90 | 3.00 | 7.60 | 4.20 | 19.40 | 3.60 | 5.80 | 7.70 | 9.20 |
| 31..... | 17.60 | ----- | 9.80 | ----- | 3.00 | ----- | 4.70 | 16.83 | ----- | 5.60 | ----- | 8.40 |
| 1904. | | | | | | | | | | | | |
| 1..... | 9.00 | 14.00 | 10.80 | 12.00 | 11.50 | 5.70 | 3.50 | 4.80 | 3.70 | 4.80 | 5.30 | 4.20 |
| 2..... | 8.90 | 13.00 | 10.90 | 15.10 | 10.50 | 7.40 | 3.50 | 4.40 | 3.60 | 5.40 | 5.10 | 4.10 |
| 3..... | 8.50 | 12.30 | 11.15 | 15.80 | 9.40 | 7.00 | 3.50 | 4.20 | 3.50 | 5.90 | 4.90 | 4.20 |
| 4..... | 7.20 | 11.60 | 16.50 | 14.00 | 8.40 | 6.40 | 3.50 | 4.30 | 3.40 | 5.20 | 4.80 | 4.20 |
| 5..... | 6.50 | 11.00 | 18.20 | 12.00 | 7.60 | 6.00 | 3.50 | 5.30 | 3.40 | 4.70 | 4.60 | 3.60 |
| 6..... | 6.70 | 10.90 | 17.20 | 10.70 | 7.00 | 9.10 | 3.50 | 5.00 | 3.30 | 4.50 | 4.50 | 3.30 |
| 7..... | 7.20 | 11.60 | 17.90 | 10.20 | 6.70 | 7.40 | 3.60 | 4.40 | 3.30 | 4.30 | 4.50 | 3.50 |
| 8..... | 7.20 | 12.70 | 25.20 | 10.50 | 6.30 | 6.40 | 3.70 | 4.60 | 3.30 | 4.00 | 4.50 | 3.60 |
| 9..... | 7.30 | 25.30 | 20.60 | 11.00 | 6.00 | 6.60 | 4.20 | 5.00 | 3.50 | 4.00 | 4.50 | 3.30 |
| 10..... | 7.40 | 24.60 | 26.60 | 11.70 | 5.70 | 11.60 | 3.80 | 4.40 | 3.50 | 3.90 | 4.50 | 3.20 |
| 11..... | 7.30 | 23.80 | 24.00 | 16.20 | 5.50 | 10.90 | 3.70 | 4.60 | 3.30 | 3.80 | 4.40 | 3.10 |
| 12..... | 7.10 | 22.00 | 22.00 | 14.30 | 5.20 | 8.50 | 4.10 | 4.00 | 3.30 | 3.80 | 4.40 | 3.30 |
| 13..... | 7.00 | 20.30 | 19.30 | 12.10 | 5.00 | 7.10 | 4.50 | 3.90 | 3.20 | 3.90 | 4.30 | 3.20 |
| 14..... | 7.00 | 18.00 | 17.40 | 10.80 | 4.80 | 6.20 | 4.20 | 3.80 | 3.10 | 7.00 | 4.20 | 3.50 |
| 15..... | 6.70 | 17.00 | 15.90 | 9.70 | 4.80 | 5.60 | 3.90 | 3.60 | 3.60 | 8.30 | 4.30 | 3.20 |
| 16..... | 6.40 | 15.70 | 14.90 | 8.90 | 6.10 | 5.20 | 3.80 | 3.50 | 5.50 | 6.90 | 4.30 | 3.30 |
| 17..... | 6.20 | 14.70 | 14.00 | 8.30 | 8.00 | 5.10 | 3.60 | 3.40 | 4.30 | 6.00 | 4.30 | 3.30 |
| 18..... | 6.00 | 12.90 | 13.00 | 8.00 | 7.90 | 5.60 | 3.90 | 3.30 | 4.80 | 5.50 | 4.40 | 3.30 |
| 19..... | 5.90 | 12.60 | 12.50 | 7.90 | 7.10 | 4.80 | 3.60 | 3.30 | 4.40 | 5.10 | 4.30 | 3.30 |
| 20..... | 5.60 | 12.90 | 12.80 | 7.90 | 11.20 | 4.50 | 3.70 | 3.20 | 4.10 | 4.80 | 4.30 | 3.40 |
| 21..... | 5.50 | 12.70 | 13.60 | 7.80 | 10.20 | 4.30 | 4.20 | 3.20 | 3.80 | 5.00 | 4.30 | 3.40 |
| 22..... | 6.00 | 12.90 | 10.50 | 7.40 | 8.50 | 4.10 | 3.80 | 3.30 | 3.60 | 8.60 | 4.60 | 3.40 |
| 23..... | 12.70 | 13.70 | 9.70 | 7.10 | 7.30 | 4.30 | 3.50 | 3.70 | 3.40 | 10.20 | 4.60 | 3.30 |
| 24..... | 11.80 | 12.80 | 16.90 | 7.10 | 6.50 | 4.00 | 3.40 | 4.90 | 3.40 | 10.20 | 5.30 | 3.50 |
| 25..... | 13.50 | 12.70 | 16.90 | 7.00 | 6.50 | 3.90 | 3.30 | 6.40 | 3.40 | 8.80 | 5.50 | 3.60 |
| 26..... | 11.60 | 12.60 | 20.40 | 6.90 | 6.70 | 3.80 | 3.40 | 5.80 | 4.00 | 7.40 | 5.20 | 3.30 |
| 27..... | 10.10 | 12.00 | 22.90 | 7.20 | 6.50 | 3.70 | 3.70 | 5.30 | 5.40 | 6.90 | 5.00 | 3.50 |
| 28..... | 19.00 | 12.00 | 22.70 | 7.90 | 5.90 | 3.50 | 3.60 | 4.60 | 5.30 | 6.70 | 4.80 | 10.00 |
| 29..... | 18.20 | 11.50 | 18.40 | 12.40 | 6.00 | 3.50 | 3.60 | 4.30 | 5.20 | 6.40 | 4.20 | 13.85 |
| 30..... | 19.20 | ----- | 14.20 | 12.80 | 5.50 | 3.40 | 3.80 | 4.10 | 4.70 | 6.00 | 4.20 | 13.30 |
| 31..... | 13.90 | ----- | 11.70 | ----- | 5.30 | ----- | 4.10 | 3.90 | ----- | 5.90 | ----- | 10.80 |

^aIce still unbroken.

^bClosed with anchor ice as far up as Ransom.

^cIce started at 5.15 p. m.; moved until February 10, 12. m. Gorged below city.

^dHighest gage reading 30.6.

^eStill gorged.

^fIce blocked as far as Tunkhannock, Pa.


^gIce started at Pittston at 1.30 p. m., at Wilkesbarre, 2 p. m. River closed December 10 to 28, inclusive.

^hIce blocked as far as Laceyville, Pa.

ⁱ12 midnight ice still running; stream nearly full.

^jRiver full of running ice all day; 10 p. m. very little ice running.

^kAnchor ice.



*Rating table for Susquehanna River at Wilkesbarre, Pa., from March 30, 1899,
to December 31, 1904.*

| Gage height. | Discharge. | Gage height. | Discharge. | Gage height. | Discharge. | Gage height. | Discharge. |
|--------------|---------------------|--------------|---------------------|--------------|---------------------|--------------|---------------------|
| <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> |
| 2.0 | 620 | 4.3 | 5,070 | 6.6 | 13,170 | 9.8 | 28,200 |
| 2.1 | 720 | 4.4 | 5,340 | 6.7 | 13,590 | 10.0 | 29,200 |
| 2.2 | 820 | 4.5 | 5,620 | 6.8 | 14,010 | 10.2 | 30,100 |
| 2.3 | 930 | 4.6 | 5,910 | 6.9 | 14,440 | 10.4 | 31,100 |
| 2.4 | 1,050 | 4.7 | 6,210 | 7.0 | 14,870 | 10.6 | 32,100 |
| 2.5 | 1,180 | 4.8 | 6,520 | 7.1 | 15,300 | 10.8 | 33,000 |
| 2.6 | 1,320 | 4.9 | 6,830 | 7.2 | 15,730 | 11.0 | 34,000 |
| 2.7 | 1,470 | 5.0 | 7,150 | 7.3 | 16,160 | 11.2 | 35,000 |
| 2.8 | 1,630 | 5.1 | 7,470 | 7.4 | 16,600 | 11.4 | 36,000 |
| 2.9 | 1,810 | 5.2 | 7,800 | 7.5 | 17,040 | 11.6 | 37,000 |
| 3.0 | 2,000 | 5.3 | 8,140 | 7.6 | 17,490 | 11.8 | 37,900 |
| 3.1 | 2,200 | 5.4 | 8,490 | 7.7 | 17,950 | 12.0 | 38,900 |
| 3.2 | 2,410 | 5.5 | 8,850 | 7.8 | 18,420 | 12.2 | 39,900 |
| 3.3 | 2,620 | 5.6 | 9,210 | 7.9 | 18,900 | 12.4 | 40,800 |
| 3.4 | 2,840 | 5.7 | 9,580 | 8.0 | 19,380 | 12.6 | 41,800 |
| 3.5 | 3,070 | 5.8 | 9,950 | 8.2 | 20,360 | 12.8 | 42,800 |
| 3.6 | 3,300 | 5.9 | 10,330 | 8.4 | 21,340 | 13.0 | 43,700 |
| 3.7 | 3,540 | 6.0 | 10,720 | 8.6 | 22,320 | 13.2 | 44,700 |
| 3.8 | 3,780 | 6.1 | 11,120 | 8.8 | 23,300 | 13.4 | 45,700 |
| 3.9 | 4,030 | 6.2 | 11,520 | 9.0 | 24,300 | 13.8 | 47,600 |
| 4.0 | 4,280 | 6.3 | 11,930 | 9.2 | 25,300 | 14.0 | 48,600 |
| 4.1 | 4,540 | 6.4 | 12,340 | 9.4 | 26,200 | | |
| 4.2 | 4,800 | 6.5 | 12,750 | 9.6 | 27,200 | | |

Table based on discharge measurements of 1899, 1900, 1901, 1902, 1903, and 1904. Well defined between 2 feet gage height and 19 feet gage height. Tangent at 8.80 feet gage height with a difference of 500 per tenth. Table applied to tenths.

Mean daily discharge, in second-feet, of Susquehanna River at Wilkesbarre, Pa., 1899-1904.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|--------|--------|--------|--------|--------|-------|-------|-------|-------|-------|---------|--------|
| 1899. | | | | | | | | | | | | |
| 1 | | | | 21,340 | 12,340 | 5,620 | 3,300 | 1,470 | 2,200 | 1,180 | 1,180 | 2,840 |
| 2 | | | | 19,870 | 11,520 | 8,850 | 2,620 | 1,320 | 1,810 | 1,180 | 2,000 | 2,840 |
| 3 | | | | 17,950 | 11,930 | 8,140 | 2,620 | 1,470 | 1,320 | 1,180 | 20,850 | 2,840 |
| 4 | | | | 15,730 | 11,930 | 7,470 | 2,410 | 1,320 | 1,320 | 1,180 | 13,590 | 2,840 |
| 5 | | | | 14,440 | 12,340 | 5,910 | 2,000 | 2,410 | 1,180 | 1,180 | 16,160 | 3,070 |
| 6 | | | | 14,440 | 11,120 | 5,070 | 2,000 | 2,000 | 1,180 | 1,320 | 13,170 | 3,070 |
| 7 | | | | 16,600 | 9,580 | 3,300 | 1,630 | 1,630 | 1,180 | 1,320 | 14,440 | 3,070 |
| 8 | | | | 49,600 | 9,210 | 3,070 | 1,810 | 1,180 | 1,050 | 1,180 | 8,140 | 3,540 |
| 9 | | | | 49,100 | 8,490 | 3,070 | 1,630 | 1,180 | 1,050 | 1,180 | 7,150 | 3,070 |
| 10 | | | | 49,600 | 8,140 | 3,070 | 1,630 | 1,180 | 1,050 | 1,180 | 5,620 | 3,070 |
| 11 | | | | 42,800 | 7,470 | 2,620 | 1,630 | 1,180 | 1,050 | 1,180 | 4,800 | 3,070 |
| 12 | | | | 34,500 | 7,800 | 2,410 | 1,810 | 1,180 | 1,180 | 1,180 | 5,070 | 3,300 |
| 13 | | | | 33,500 | 7,470 | 2,410 | 1,810 | 1,470 | 1,180 | 1,050 | 6,830 | 17,950 |
| 14 | | | | 48,600 | 7,150 | 2,410 | 2,000 | 1,630 | 1,180 | 1,050 | 6,210 | 27,200 |
| 15 | | | | 50,100 | 7,150 | 2,000 | 2,410 | 1,630 | 1,050 | 1,050 | 5,910 | 27,200 |
| 16 | | | | 48,100 | 6,520 | 2,200 | 2,620 | 1,630 | 1,050 | 1,050 | 5,620 | 21,830 |
| 17 | | | | 45,700 | 6,520 | 2,410 | 2,200 | 1,810 | 930 | 930 | 7,800 | 17,950 |
| 18 | | | | 41,300 | 6,210 | 2,410 | 2,000 | 1,470 | 930 | 930 | 7,800 | 16,160 |
| 19 | | | | 35,500 | 6,830 | 2,000 | 2,000 | 1,050 | 930 | 930 | 8,140 | 12,750 |
| 20 | | | | 31,600 | 6,830 | 2,000 | 2,000 | 930 | 930 | 930 | 7,150 | 12,750 |
| 21 | | | | 28,700 | 8,490 | 2,200 | 2,200 | 930 | 930 | 930 | 6,710 | 20,850 |
| 22 | | | | 26,200 | 10,330 | 2,000 | 2,000 | 1,320 | 930 | 930 | 5,910 | 21,340 |
| 23 | | | | 24,300 | 9,950 | 2,000 | 2,000 | 1,180 | 930 | 930 | 5,070 | 16,600 |
| 24 | | | | 21,830 | 9,580 | 1,810 | 1,810 | 1,180 | 930 | 930 | 4,800 | 13,170 |
| 25 | | | | 19,380 | 8,850 | 1,810 | 1,630 | 1,050 | 820 | 930 | 4,280 | 21,340 |
| 26 | | | | 16,600 | 8,490 | 2,200 | 1,630 | 1,050 | 1,180 | 820 | 3,780 | 19,380 |
| 27 | | | | 17,490 | 7,470 | 2,200 | 1,630 | 1,050 | 1,050 | 930 | 3,780 | 16,600 |
| 28 | | | | 16,600 | 6,830 | 2,620 | 1,630 | 1,050 | 1,180 | 930 | 3,540 | 11,930 |
| 29 | | | | 15,300 | 6,520 | 3,780 | 1,630 | 5,910 | 1,180 | 1,180 | 3,300 | 24,800 |
| 30 | | | | 13,170 | 6,520 | 4,280 | 1,620 | 4,540 | 1,320 | 1,180 | 3,070 | 18,900 |
| 31 | | | | | 6,210 | | 1,620 | 2,840 | | 1,180 | | 17,950 |
| 1900. | | | | | | | | | | | | |
| 1 | 14,010 | 16,600 | 31,100 | 14,440 | 11,120 | 3,780 | 2,000 | 2,410 | 2,200 | 930 | 1,470 | 31,600 |
| 2 | 11,520 | 14,010 | 75,900 | 17,040 | 9,950 | 3,540 | 1,630 | 2,410 | 2,000 | 930 | 1,320 | 25,300 |
| 3 | 12,340 | 11,930 | 52,200 | 28,200 | 8,850 | 4,800 | 1,470 | 2,000 | 2,200 | 930 | 1,320 | 19,870 |
| 4 | 14,010 | 12,750 | 37,900 | 36,000 | 8,140 | 4,030 | 1,810 | 2,000 | 2,000 | 930 | 1,180 | 16,600 |
| 5 | 14,870 | 21,340 | 28,700 | 34,500 | 7,800 | 3,540 | 1,810 | 1,810 | 1,810 | 930 | 1,470 | 25,300 |
| 6 | 14,870 | 21,830 | 21,340 | 26,200 | 7,150 | 3,780 | 2,840 | 1,810 | 1,630 | 820 | 1,630 | 38,400 |
| 7 | 14,440 | 18,900 | 20,360 | 27,200 | 6,520 | 3,540 | 4,030 | 1,810 | 1,470 | 720 | 2,000 | 35,500 |
| 8 | 14,010 | 18,420 | 19,870 | 37,400 | 6,210 | 3,300 | 3,300 | 1,810 | 1,470 | 720 | 1,810 | 28,700 |
| 9 | 11,930 | 51,600 | 17,950 | 39,900 | 5,910 | 3,300 | 2,840 | 1,810 | 1,320 | 820 | 1,810 | 23,800 |
| 10 | 11,120 | 25,300 | 21,340 | 33,500 | 5,620 | 3,780 | 2,410 | 1,630 | 1,320 | 820 | 1,810 | 20,360 |
| 11 | 9,950 | 28,200 | 24,300 | 25,300 | 5,620 | 4,030 | 2,200 | 1,630 | 1,470 | 820 | 2,000 | 17,040 |
| 12 | 10,330 | 25,300 | 18,420 | 18,900 | 6,520 | 5,070 | 1,810 | 1,470 | 1,470 | 820 | 2,200 | 13,170 |
| 13 | 9,210 | 25,300 | 14,010 | 16,160 | 6,830 | 5,070 | 2,000 | 1,470 | 1,470 | 820 | 2,620 | 11,520 |
| 14 | 10,330 | 39,400 | 11,930 | 17,950 | 6,520 | 6,520 | 2,000 | 1,320 | 1,180 | 820 | 3,070 | 11,120 |
| 15 | 9,210 | 46,900 | 9,580 | 19,870 | 6,210 | 5,070 | 2,000 | 1,320 | 1,050 | 820 | 3,070 | 30,600 |
| 16 | 8,850 | 37,900 | 9,580 | 18,420 | 6,210 | 4,280 | 2,000 | 1,320 | 1,180 | 930 | 2,840 | 28,200 |
| 17 | 8,850 | 25,300 | 24,300 | 17,490 | 6,830 | 3,780 | 1,810 | 1,180 | 1,050 | 1,050 | 2,620 | 25,300 |
| 18 | 7,800 | 17,950 | 19,870 | 29,400 | 7,150 | 3,300 | 1,810 | 1,180 | 930 | 1,050 | 2,410 | 22,810 |
| 19 | 7,470 | 23,800 | 20,850 | 41,030 | 7,470 | 3,070 | 1,630 | 1,050 | 820 | 1,180 | 2,410 | 25,300 |
| 20 | 9,950 | 32,600 | 21,830 | 40,800 | 9,210 | 2,840 | 2,200 | 1,180 | 820 | 1,470 | 2,200 | 27,200 |
| 21 | 52,900 | 28,200 | 33,200 | 34,500 | 7,800 | 2,620 | 2,410 | 1,180 | 720 | 1,320 | 2,200 | 26,200 |
| 22 | 68,800 | 36,000 | 27,700 | 29,200 | 7,150 | 2,410 | 2,200 | 1,180 | 820 | 1,320 | 2,410 | 24,300 |
| 23 | 46,200 | 63,200 | 25,300 | 26,700 | 6,520 | 3,070 | 2,000 | 1,630 | 820 | 1,470 | 3,300 | 23,300 |
| 24 | 30,600 | 53,600 | 21,340 | 35,500 | 5,910 | 2,620 | 1,810 | 2,000 | 820 | 1,810 | 4,280 | 25,300 |
| 25 | 21,830 | 34,000 | 28,700 | 32,600 | 5,620 | 2,620 | 1,810 | 1,810 | 820 | 1,630 | 5,070 | 23,300 |
| 26 | 18,420 | 23,300 | 22,810 | 26,700 | 5,070 | 2,410 | 4,280 | 1,320 | 820 | 1,630 | 6,210 | 42,800 |
| 27 | 18,900 | 14,870 | 19,870 | 21,340 | 4,540 | 2,410 | 3,540 | 1,470 | 930 | 1,470 | 68,000 | 49,600 |
| 28 | 11,520 | 21,830 | 15,300 | 17,040 | 4,280 | 2,200 | 2,840 | 1,630 | 820 | 1,470 | 102,200 | 43,300 |
| 29 | 25,300 | | 14,870 | 14,440 | 4,030 | 2,200 | 2,410 | 1,630 | 820 | 1,470 | 52,900 | 40,800 |
| 30 | 24,300 | | 14,010 | 12,750 | 3,780 | 2,200 | 2,410 | 2,200 | 930 | 1,470 | 37,900 | 36,000 |
| 31 | 22,810 | | 12,750 | | 3,540 | | 2,620 | 2,200 | | 1,470 | | 36,000 |

Mean daily discharge, in second-feet, of Susquehanna River at Wilkesbarre, Pa.,
1899-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|--------|--------|---------|--------|--------|--------|--------|--------|--------|--------|--------|---------|
| 1901. | | | | | | | | | | | | |
| 1. | 32,100 | 22,320 | 11,520 | 27,700 | 18,420 | 51,300 | 5,620 | 2,840 | 9,950 | 4,030 | 2,410 | 16,160 |
| 2. | 32,100 | 21,340 | 11,120 | 23,300 | 15,730 | 37,400 | 4,280 | 2,410 | 9,210 | 3,540 | 2,410 | 13,590 |
| 3. | 22,700 | 20,850 | 11,120 | 20,850 | 22,810 | 34,000 | 3,070 | 2,000 | 9,580 | 4,280 | 2,200 | 14,010 |
| 4. | 22,810 | 21,340 | 11,120 | 25,800 | 23,800 | 32,100 | 3,300 | 2,000 | 8,140 | 5,070 | 2,200 | 25,800 |
| 5. | 21,830 | 19,380 | 11,520 | 33,000 | 19,870 | 25,300 | 3,300 | 2,000 | 7,150 | 4,280 | 2,000 | 28,700 |
| 6. | 15,730 | 18,420 | 10,720 | 38,400 | 17,040 | 19,870 | 3,300 | 2,000 | 5,620 | 4,030 | 2,000 | 26,200 |
| 7. | 15,300 | 18,420 | 10,330 | 63,900 | 14,010 | 19,870 | 5,070 | 2,000 | 4,800 | 3,540 | 2,000 | 24,300 |
| 8. | 14,870 | 17,950 | 9,950 | 78,400 | 11,930 | 24,300 | 4,280 | 2,620 | 3,780 | 3,300 | 2,000 | 20,850 |
| 9. | 18,900 | 17,950 | 9,580 | 69,200 | 10,330 | 25,800 | 4,280 | 2,410 | 3,540 | 2,840 | 2,000 | 22,810 |
| 10. | 18,900 | 17,040 | 12,750 | 53,300 | 9,950 | 23,800 | 4,030 | 2,200 | 3,070 | 2,620 | 2,000 | 37,400 |
| 11. | 18,420 | 17,490 | 21,340 | 44,700 | 12,340 | 19,380 | 3,780 | 2,410 | 2,620 | 2,410 | 1,810 | 39,400 |
| 12. | 18,420 | 17,490 | 84,700 | 37,900 | 18,420 | 15,730 | 3,780 | 2,620 | 2,620 | 2,410 | 2,000 | 37,400 |
| 13. | 19,870 | 16,600 | 39,900 | 32,600 | 26,700 | 12,750 | 3,300 | 2,200 | 2,620 | 2,620 | 2,000 | 29,600 |
| 14. | 24,300 | 14,440 | 27,700 | 29,600 | 28,200 | 11,120 | 3,070 | 2,200 | 2,620 | 3,070 | 3,070 | 23,300 |
| 15. | 38,900 | 14,870 | 23,800 | 27,200 | 24,800 | 10,330 | 2,840 | 2,410 | 2,410 | 4,540 | 4,280 | 98,900 |
| 16. | 52,000 | 15,300 | 24,800 | 25,800 | 19,380 | 9,580 | 2,410 | 3,300 | 2,620 | 5,070 | 6,210 | 166,300 |
| 17. | 48,600 | 16,160 | 23,300 | 23,800 | 15,300 | 8,850 | 2,410 | 3,540 | 3,070 | 5,340 | 5,620 | 122,300 |
| 18. | 43,700 | 16,160 | 20,850 | 21,830 | 13,590 | 8,140 | 3,300 | 20,110 | 3,780 | 5,070 | 4,800 | 59,500 |
| 19. | 41,300 | 15,730 | 19,380 | 19,870 | 14,010 | 6,890 | 2,840 | 9,210 | 4,280 | 4,800 | 4,540 | 34,000 |
| 20. | 36,500 | 14,440 | 29,600 | 18,890 | 14,870 | 6,210 | 2,620 | 6,520 | 4,800 | 4,280 | 2,800 | 20,360 |
| 21. | 26,200 | 14,440 | 39,600 | 34,200 | 15,300 | 5,910 | 2,200 | 5,910 | 4,540 | 4,030 | 4,280 | 18,420 |
| 22. | 31,600 | 13,590 | 54,000 | 78,800 | 12,750 | 5,340 | 2,000 | 14,655 | 4,030 | 3,780 | 4,030 | 26,700 |
| 23. | 34,000 | 14,010 | 52,000 | 70,800 | 12,340 | 5,620 | 2,200 | 14,440 | 3,540 | 3,540 | 3,780 | 35,000 |
| 24. | 34,000 | 12,340 | 43,300 | 54,000 | 18,900 | 9,210 | 2,200 | 12,750 | 3,070 | 3,540 | 3,780 | 37,400 |
| 25. | 37,400 | 12,340 | 43,300 | 53,300 | 24,300 | 9,580 | 2,000 | 31,600 | 2,840 | 3,300 | 10,720 | 47,100 |
| 26. | 34,000 | 11,930 | 47,600 | 46,700 | 20,850 | 9,580 | 2,000 | 25,300 | 2,410 | 2,840 | 2,800 | 46,200 |
| 27. | 31,600 | 11,520 | 71,100 | 40,300 | 17,490 | 7,150 | 1,810 | 15,300 | 2,410 | 2,840 | 17,490 | 45,200 |
| 28. | 29,200 | 11,930 | 108,400 | 34,000 | 16,600 | 4,800 | 1,810 | 11,120 | 2,200 | 2,840 | 11,520 | 42,800 |
| 29. | 26,700 | | 90,300 | 27,200 | 32,100 | 5,620 | 2,000 | 8,140 | 2,620 | 2,410 | 8,850 | 44,200 |
| 30. | 25,800 | | 58,800 | 22,320 | 68,900 | 4,800 | 2,620 | 6,520 | 3,780 | 2,200 | 9,580 | 46,200 |
| 31. | 24,800 | | 43,300 | | 74,300 | | 3,300 | 6,830 | | 2,200 | | |
| 1902. | | | | | | | | | | | | |
| 1. | 48,600 | 42,300 | 201,800 | 27,700 | 7,150 | 4,540 | 32,100 | 23,300 | 3,300 | 27,200 | 26,700 | 7,470 |
| 2. | 43,700 | 36,000 | 217,700 | 25,300 | 6,830 | 4,280 | 31,600 | 26,700 | 3,070 | 33,000 | 20,360 | 7,150 |
| 3. | 39,400 | 33,000 | 208,200 | 24,300 | 7,470 | 4,030 | 20,850 | 34,500 | 2,840 | 32,100 | 16,600 | 7,150 |
| 4. | 33,500 | 32,600 | 148,800 | 21,830 | 7,470 | 4,030 | 18,420 | 27,200 | 2,840 | 21,830 | 14,010 | 7,800 |
| 5. | 27,200 | 21,830 | 97,100 | 19,870 | 6,520 | 3,780 | 21,830 | 23,300 | 2,410 | 16,160 | 12,340 | 8,850 |
| 6. | 28,700 | 14,870 | 52,900 | 18,900 | 6,520 | 3,780 | 20,600 | 17,040 | 2,410 | 15,300 | 10,720 | 10,330 |
| 7. | 28,200 | 24,800 | 37,200 | 17,490 | 6,210 | 6,520 | 42,300 | 14,010 | 2,410 | 14,440 | 9,950 | 9,950 |
| 8. | 27,200 | 28,200 | 32,600 | 17,950 | 6,210 | 5,620 | 49,900 | 12,750 | 2,410 | 13,590 | 8,850 | 8,850 |
| 9. | 27,700 | 27,200 | 30,600 | 38,100 | 5,620 | 5,340 | 44,400 | 11,520 | 2,410 | 11,520 | 9,210 | 7,800 |
| 10. | 26,200 | 26,200 | 34,000 | 61,000 | 5,340 | 4,800 | 23,050 | 9,950 | 2,410 | 9,950 | 9,580 | 10,330 |
| 11. | 25,300 | 24,300 | 41,300 | 58,400 | 5,070 | 4,800 | 24,300 | 9,210 | 3,300 | 8,850 | 7,150 | 15,730 |
| 12. | 24,300 | 24,300 | 54,000 | 42,800 | 4,800 | 4,800 | 27,700 | 8,850 | 3,070 | 9,950 | 6,210 | 19,380 |
| 13. | 20,360 | 24,300 | 78,000 | 51,300 | 4,540 | 4,540 | 21,830 | 8,490 | 3,300 | 12,750 | 6,210 | 28,400 |
| 14. | 15,730 | 20,850 | 91,700 | 30,600 | 4,280 | 4,800 | 16,600 | 8,490 | 3,070 | 10,720 | 6,210 | 30,100 |
| 15. | 12,340 | 19,380 | 79,600 | 26,200 | 4,030 | 4,800 | 11,930 | 7,800 | 3,070 | 9,950 | 6,210 | 25,300 |
| 16. | 14,010 | 20,360 | 61,000 | 22,320 | 3,780 | 4,800 | 9,950 | 7,150 | 2,840 | 10,330 | 5,910 | 32,600 |
| 17. | 15,730 | 18,420 | 82,100 | 19,380 | 3,780 | 7,150 | 8,490 | 5,910 | 2,620 | 10,330 | 5,620 | 46,000 |
| 18. | 14,870 | 17,950 | 97,100 | 16,600 | 3,540 | 6,210 | 7,800 | 5,340 | 2,620 | 9,210 | 5,340 | 42,300 |
| 19. | 13,590 | 15,730 | 73,500 | 14,870 | 3,540 | 5,340 | 7,470 | 4,800 | 2,410 | 8,140 | 5,070 | 40,800 |
| 20. | 11,120 | 13,170 | 50,600 | 13,590 | 3,300 | 5,910 | 8,490 | 4,540 | 2,200 | 6,830 | 4,800 | 35,500 |
| 21. | 11,520 | 13,170 | 37,000 | 12,340 | 3,070 | 5,070 | 39,400 | 4,280 | 2,200 | 6,520 | 5,070 | 29,200 |
| 22. | 32,100 | 12,750 | 30,100 | 11,520 | 3,070 | 5,070 | 57,800 | 4,280 | 2,000 | 6,830 | 4,800 | 59,500 |
| 23. | 67,700 | 12,340 | 27,700 | 10,720 | 3,070 | 4,800 | 48,100 | 4,280 | 2,000 | 7,800 | 4,540 | 75,100 |
| 24. | 39,900 | 15,730 | 27,200 | 9,580 | 3,540 | 4,800 | 45,900 | 4,030 | 2,000 | 7,150 | 4,540 | 65,000 |
| 25. | 32,600 | 15,730 | 26,700 | 8,850 | 3,540 | 4,800 | 47,900 | 4,030 | 2,000 | 6,210 | 4,540 | 47,100 |
| 26. | 27,700 | 17,950 | 24,300 | 7,800 | 3,540 | 4,800 | 54,700 | 3,780 | 4,800 | 6,210 | 4,540 | 34,000 |
| 27. | 23,800 | 23,300 | 21,830 | 7,150 | 3,780 | 4,540 | 37,400 | 3,540 | 15,300 | 5,910 | 6,620 | 27,700 |
| 28. | 20,360 | 48,800 | 19,380 | 6,520 | 4,030 | 4,030 | 27,700 | 3,300 | 10,720 | 17,580 | 6,210 | 21,830 |
| 29. | 17,950 | | 24,300 | 6,210 | 5,910 | 3,780 | 33,000 | 3,300 | 18,900 | 34,200 | 7,150 | 19,380 |
| 30. | 17,490 | | 31,100 | 6,830 | 5,910 | 7,470 | 32,100 | 3,300 | 32,600 | 39,200 | 7,800 | 14,870 |
| 31. | 45,200 | | 28,200 | | 4,800 | | 25,800 | 3,300 | | 34,500 | | 14,010 |

Mean daily discharge, in second-feet, of Susquehanna River at Wilkesbarre, Pa., 1899-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|---------|--------|--------|---------|--------|--------|--------|--------|--------|--------|---------|--------|--------|
| 1903. | | | | | | | | | | | | |
| 1..... | 21,830 | 57,400 | 98,900 | 35,000 | 6,520 | 2,000 | 14,440 | 5,910 | 47,600 | 3,300 | 9,210 | 15,730 |
| 2..... | 34,000 | 44,200 | 94,700 | 38,900 | 5,910 | 2,000 | 14,010 | 5,916 | 38,400 | 3,300 | 9,210 | 16,160 |
| 3..... | 42,800 | 43,700 | 64,500 | 32,600 | 5,340 | 2,000 | 11,120 | 5,070 | 28,700 | 3,300 | 8,490 | 17,040 |
| 4..... | 43,700 | 53,000 | 46,700 | 27,700 | 5,070 | 1,810 | 8,850 | 4,280 | 21,340 | 3,300 | 7,800 | 13,590 |
| 5..... | 46,200 | 84,500 | 35,500 | 28,200 | 4,800 | 1,810 | 8,490 | 6,520 | 16,600 | 3,300 | 7,150 | 7,800 |
| 6..... | 27,700 | 66,100 | 31,600 | 28,700 | 4,540 | 1,810 | 8,850 | 13,590 | 13,590 | 3,540 | 7,150 | 5,620 |
| 7..... | 19,870 | 48,100 | 39,400 | 22,810 | 4,280 | 1,810 | 16,160 | 18,900 | 11,520 | 3,780 | 7,150 | 4,800 |
| 8..... | 18,900 | 33,500 | 37,000 | 23,300 | 4,280 | 1,810 | 16,160 | 17,490 | 9,950 | 6,210 | 7,800 | 4,800 |
| 9..... | 14,440 | 29,200 | 63,900 | 32,100 | 4,280 | 2,000 | 26,200 | 14,010 | 8,960 | 32,600 | 8,140 | 5,070 |
| 10..... | 14,010 | 22,320 | 85,000 | 33,000 | 3,780 | 2,000 | 6,520 | 10,720 | 8,140 | 88,100 | 7,150 | 4,540 |
| 11..... | 32,600 | 19,380 | 77,300 | 28,200 | 3,540 | 1,810 | 5,340 | 9,580 | 7,800 | 106,900 | 6,830 | 4,280 |
| 12..... | 29,200 | 21,830 | 85,600 | 24,300 | 3,540 | 3,300 | 5,070 | 8,490 | 8,140 | 106,000 | 6,210 | 3,540 |
| 13..... | 26,700 | 24,800 | 76,300 | 23,800 | 3,300 | 3,300 | 13,170 | 4,280 | 8,850 | 10,720 | 79,200 | 5,910 |
| 14..... | 24,800 | 34,000 | 60,300 | 20,850 | 3,070 | 7,150 | 3,780 | 7,800 | 9,210 | 47,100 | 5,620 | 6,210 |
| 15..... | 24,800 | 33,000 | 44,700 | 39,900 | 3,070 | 17,040 | 3,540 | 6,830 | 7,900 | 31,600 | 5,340 | 6,520 |
| 16..... | 29,200 | 25,800 | 37,400 | 49,900 | 3,070 | 12,340 | 3,300 | 6,210 | 6,520 | 24,300 | 4,800 | 9,950 |
| 17..... | 31,600 | 21,340 | 32,100 | 40,300 | 2,840 | 9,950 | 3,300 | 5,620 | 5,910 | 19,380 | 18,900 | 13,170 |
| 18..... | 31,100 | 16,600 | 28,700 | 31,600 | 2,840 | 7,800 | 2,840 | 5,070 | 7,800 | 20,850 | 43,300 | 14,010 |
| 19..... | 27,200 | 29,200 | 27,200 | 24,300 | 2,620 | 7,150 | 5,070 | 4,030 | 6,520 | 41,300 | 47,100 | 11,930 |
| 20..... | 22,810 | 25,300 | 25,300 | 19,380 | 2,620 | 6,520 | 5,910 | 3,540 | 7,150 | 40,800 | 33,000 | 9,950 |
| 21..... | 22,320 | 26,200 | 22,810 | 16,160 | 2,620 | 6,210 | 6,520 | 3,780 | 6,520 | 53,500 | 22,810 | 23,800 |
| 22..... | 26,200 | 29,200 | 20,850 | 14,010 | 3,070 | 14,010 | 7,470 | 9,210 | 6,210 | 26,200 | 15,300 | 24,300 |
| 23..... | 28,200 | 31,600 | 48,100 | 12,340 | 2,620 | 19,380 | 6,210 | 8,140 | 5,340 | 20,850 | 13,590 | 21,340 |
| 24..... | 31,100 | 33,500 | 103,400 | 11,120 | 2,620 | 24,050 | 5,340 | 7,150 | 4,800 | 17,040 | 11,520 | 19,380 |
| 25..... | 29,200 | 35,000 | 106,100 | 10,330 | 2,220 | 26,500 | 5,340 | 5,910 | 4,030 | 14,780 | 11,520 | 17,040 |
| 26..... | 27,200 | 31,100 | 78,100 | 9,580 | 2,200 | 31,100 | 11,120 | 5,340 | 4,280 | 14,010 | 11,120 | 15,300 |
| 27..... | 22,810 | 27,200 | 58,100 | 8,850 | 2,200 | 30,100 | 7,800 | 5,070 | 3,780 | 12,750 | 9,950 | 15,730 |
| 28..... | 20,360 | 30,100 | 41,800 | 8,140 | 2,200 | 19,380 | 5,620 | 8,490 | 3,780 | 11,520 | 8,850 | 31,100 |
| 29..... | 20,360 | ----- | 32,600 | 7,470 | 2,000 | 14,440 | 4,540 | 25,000 | 3,540 | 10,720 | 10,720 | 27,700 |
| 30..... | 51,300 | ----- | 28,700 | 6,830 | 2,000 | 17,490 | 4,800 | 90,000 | 3,300 | 9,950 | 17,950 | 25,300 |
| 31..... | 66,100 | ----- | 28,200 | ----- | 2,000 | ----- | 6,210 | 68,700 | ----- | 9,210 | ----- | 21,340 |
| 1904. | | | | | | | | | | | | |
| 1..... | 24,300 | 48,600 | 16,600 | 38,900 | 36,500 | 9,580 | 3,070 | 6,520 | 3,540 | 6,520 | 8,140 | 4,800 |
| 2..... | 23,800 | 43,700 | 16,900 | 56,000 | 31,600 | 16,600 | 3,070 | 5,340 | 3,300 | 8,490 | 7,470 | 4,540 |
| 3..... | 21,830 | 40,300 | 18,350 | 61,000 | 26,200 | 14,870 | 3,070 | 4,800 | 3,070 | 10,330 | 6,830 | 4,800 |
| 4..... | 15,730 | 37,000 | 33,300 | 48,600 | 21,340 | 12,340 | 3,070 | 5,070 | 2,840 | 7,800 | 6,520 | 4,800 |
| 5..... | 12,750 | 34,000 | 40,100 | 38,900 | 17,490 | 10,720 | 3,070 | 8,140 | 2,840 | 6,210 | 5,910 | 3,300 |
| 6..... | 13,590 | 33,500 | 36,100 | 32,600 | 14,870 | 24,800 | 3,070 | 7,150 | 2,620 | 5,620 | 5,620 | 2,620 |
| 7..... | 15,730 | 37,000 | 38,900 | 30,100 | 13,590 | 16,600 | 3,300 | 5,340 | 2,620 | 5,070 | 5,620 | 3,070 |
| 8..... | 15,730 | 55,900 | 74,760 | 31,600 | 11,930 | 12,340 | 3,540 | 5,910 | 2,620 | 4,280 | 5,620 | 3,300 |
| 9..... | 16,160 | 75,100 | 108,700 | 34,000 | 10,720 | 13,170 | 4,800 | 7,150 | 3,070 | 4,280 | 5,620 | 2,620 |
| 10..... | 16,600 | 71,800 | 82,900 | 37,400 | 9,580 | 37,000 | 3,780 | 5,340 | 3,070 | 4,030 | 5,620 | 2,410 |
| 11..... | 16,160 | 67,000 | 68,000 | 63,900 | 8,850 | 33,500 | 3,540 | 5,910 | 2,620 | 3,780 | 5,340 | 2,200 |
| 12..... | 15,300 | 57,600 | 57,600 | 50,600 | 7,800 | 21,830 | 4,540 | 4,280 | 2,620 | 3,780 | 5,340 | 2,620 |
| 13..... | 14,870 | 49,400 | 44,900 | 39,400 | 7,150 | 15,300 | 5,620 | 4,030 | 2,410 | 4,030 | 5,070 | 2,410 |
| 14..... | 14,870 | 39,300 | 36,800 | 33,000 | 6,520 | 11,520 | 4,800 | 3,780 | 2,200 | 14,870 | 4,800 | 2,620 |
| 15..... | 13,590 | 35,300 | 31,100 | 27,700 | 6,520 | 9,210 | 4,030 | 3,300 | 3,300 | 20,850 | 5,070 | 2,410 |
| 16..... | 12,340 | 30,350 | 27,500 | 23,800 | 11,120 | 7,800 | 3,780 | 3,070 | 8,850 | 14,440 | 5,070 | 2,620 |
| 17..... | 11,520 | 26,800 | 31,000 | 20,850 | 19,380 | 7,470 | 3,300 | 2,840 | 5,070 | 10,720 | 5,070 | 2,620 |
| 18..... | 10,720 | 21,850 | 30,000 | 19,380 | 18,900 | 9,210 | 4,030 | 2,620 | 6,520 | 8,850 | 5,340 | 2,620 |
| 19..... | 10,530 | 21,050 | 35,500 | 18,900 | 15,300 | 6,520 | 3,300 | 2,620 | 5,340 | 7,470 | 5,070 | 2,620 |
| 20..... | 9,210 | 21,850 | 42,800 | 18,900 | 35,000 | 5,620 | 3,540 | 2,410 | 4,540 | 6,520 | 5,070 | 2,840 |
| 21..... | 9,210 | 21,350 | 46,700 | 18,420 | 30,100 | 5,070 | 4,800 | 2,410 | 3,780 | 7,150 | 5,070 | 2,840 |
| 22..... | 10,720 | 21,850 | 31,600 | 16,600 | 21,830 | 4,540 | 3,780 | 2,620 | 3,300 | 22,320 | 5,910 | 2,840 |
| 23..... | 42,300 | 23,700 | 27,700 | 15,300 | 16,160 | 5,070 | 3,070 | 3,540 | 2,840 | 30,100 | 5,910 | 2,620 |
| 24..... | 79,600 | 21,550 | 69,200 | 15,300 | 12,750 | 4,280 | 2,840 | 6,830 | 2,840 | 30,100 | 8,140 | 3,070 |
| 25..... | 46,200 | 21,350 | 69,200 | 14,870 | 12,750 | 4,030 | 2,620 | 12,340 | 2,840 | 23,300 | 8,850 | 3,300 |
| 26..... | 37,000 | 21,500 | 98,900 | 14,440 | 13,590 | 3,780 | 2,840 | 9,950 | 4,280 | 16,600 | 7,800 | 2,620 |
| 27..... | 29,600 | 19,600 | 123,400 | 15,730 | 12,750 | 3,540 | 3,540 | 8,140 | 8,490 | 14,440 | 7,150 | 3,070 |
| 28..... | 24,300 | 19,600 | 121,300 | 18,900 | 10,330 | 3,070 | 3,300 | 5,910 | 8,140 | 13,590 | 6,520 | 29,200 |
| 29..... | 20,360 | 18,350 | 81,300 | 40,800 | 10,720 | 3,070 | 3,300 | 5,070 | 7,800 | 12,340 | 4,800 | 47,850 |
| 30..... | 25,800 | ----- | 49,900 | 42,800 | 8,850 | 2,840 | 3,780 | 4,540 | 6,210 | 10,720 | 4,800 | 45,200 |
| 31..... | 48,100 | ----- | 37,400 | ----- | 8,140 | ----- | 4,540 | 4,030 | ----- | 10,330 | ----- | 33,000 |

From February 8 to March 19, 1904, discharges reduced 50 per cent on account of ice gorge.

*Estimated monthly discharge of Susquehanna River at Wilkesbarre, Pa.,
1899-1904.*

[Drainage area, 9,810 square miles.]

| Month. | Discharge in second-feet. | | | Run-off. | |
|-----------------|---------------------------|----------|--------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1899. | | | | | |
| April | 50,100 | 13,170 | 28,773 | 2.93 | 3.27 |
| May | 12,340 | 6,210 | 8,574 | .87 | 1.00 |
| June | 8,850 | 1,810 | 3,378 | .34 | .38 |
| July | 3,300 | 1,320 | 1,965 | .20 | .23 |
| August | 5,910 | 930 | 1,653 | .17 | .20 |
| September | 2,200 | 820 | 1,140 | .12 | .13 |
| October | 1,320 | 820 | 1,072 | .11 | .13 |
| November | 20,850 | 1,180 | 7,046 | .72 | .80 |
| December | 27,200 | 2,840 | 12,694 | 1.29 | 1.49 |
| 1900. | | | | | |
| January | 68,800 | 7,470 | 18,279 | 1.86 | 2.14 |
| February | 63,200 | 11,930 | 28,226 | 2.88 | 3.00 |
| March | 75,900 | 9,580 | 23,780 | 2.42 | 2.79 |
| April | 41,000 | 12,750 | 26,348 | 2.69 | 3.00 |
| May | 11,120 | 3,540 | 6,583 | .67 | .77 |
| June | 6,520 | 2,200 | 3,506 | .36 | .40 |
| July | 4,280 | 1,470 | 2,320 | .24 | .28 |
| August | 2,410 | 1,050 | 1,635 | .17 | .20 |
| September | 2,200 | 720 | 1,239 | .13 | .15 |
| October | 1,810 | 720 | 1,120 | .11 | .13 |
| November | 102,200 | 1,180 | 10,858 | 1.11 | 1.24 |
| December | 49,600 | 11,120 | 27,374 | 2.79 | 3.22 |
| The year | 102,200 | 720 | 12,606 | 1.29 | 17.32 |

*Estimated monthly discharge of Susquehanna River at Wilkesbarre, Pa.,
1899-1904—Continued.*

| Month. | Discharge in second-feet. | | | Run-off. | |
|-----------------------------|---------------------------|----------|--------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1901. | | | | | |
| January | 52,000 | 14,870 | 29,018 | 2.96 | 3.41 |
| February | 22,320 | 11,520 | 16,278 | 1.66 | 1.73 |
| March | 108,400 | 9,580 | 34,736 | 3.54 | 4.08 |
| April | 78,800 | 18,890 | 39,255 | 4.00 | 4.46 |
| May | 74,300 | 9,950 | 21,462 | 2.19 | 2.52 |
| June | 51,300 | 4,800 | 15,676 | 1.60 | 1.79 |
| July | 5,620 | 1,810 | 3,065 | .31 | .36 |
| August | 31,600 | 2,000 | 7,405 | .75 | .86 |
| September | 9,950 | 2,200 | 4,257 | .43 | .48 |
| October | 5,340 | 2,200 | 3,570 | .36 | .42 |
| November | 24,800 | 1,810 | 5,289 | .54 | .60 |
| December ^a | 166,300 | 13,590 | 41,752 | 4.26 | 4.91 |
| The year | 166,300 | 1,810 | 18,480 | 1.88 | 25.62 |
| 1902. | | | | | |
| January | 67,700 | 11,120 | 26,905 | 2.74 | 3.16 |
| February | 48,800 | 12,340 | 23,055 | 2.35 | 2.45 |
| March | 217,700 | 19,380 | 66,697 | 6.80 | 7.84 |
| April | 61,000 | 6,210 | 21,867 | 2.23 | 2.49 |
| May | 7,470 | 3,070 | 4,847 | .49 | .56 |
| June | 7,470 | 3,780 | 4,968 | .51 | .57 |
| July | 57,800 | 7,470 | 29,013 | 2.96 | 3.41 |
| August | 34,500 | 3,300 | 10,073 | .10 | .12 |
| September | 32,600 | 2,000 | 4,918 | .50 | .56 |
| October | 39,200 | 5,910 | 14,976 | 1.53 | 1.76 |
| November | 26,700 | 4,540 | 8,395 | .86 | .96 |
| December | 75,100 | 7,150 | 26,112 | 2.66 | 3.07 |
| The year | 217,700 | 2,000 | 20,152 | 1.98 | 26.95 |

^aFrozen December 4 to 31. Rating table assumed to apply correctly.

*Estimated monthly discharge of Susquehanna River at Wilkesbarre, Pa.,
1899-1904—Continued.*

| Month. | Discharge in second-feet. | | | Run-off. | |
|-----------------|---------------------------|----------|--------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second feet per square mile. | Depth in inches. |
| 1903. | | | | | |
| January | 66,100 | 14,010 | 29,310 | 2.99 | 3.45 |
| February | 84,500 | 16,600 | 34,970 | 3.56 | 3.71 |
| March | 106,100 | 20,850 | 53,502 | 5.45 | 6.28 |
| April | 49,900 | 6,830 | 23,656 | 2.41 | 2.69 |
| May | 6,520 | 2,000 | 3,388 | .35 | .40 |
| June | 31,100 | 1,810 | 10,265 | 1.05 | 1.17 |
| July | 26,200 | 2,840 | 7,877 | .80 | .92 |
| August | 90,000 | 3,540 | 13,071 | 1.33 | 1.53 |
| September | 47,600 | 3,300 | 10,932 | 1.11 | 1.24 |
| October | 106,900 | 3,300 | 27,377 | 2.79 | 3.22 |
| November | 47,100 | 4,800 | 12,986 | 1.32 | 1.47 |
| December | 31,100 | 3,540 | 13,583 | 1.38 | 1.59 |
| The year | 106,900 | 1,810 | 20,076 | 2.04 | 27.67 |
| 1904. | | | | | |
| January | 79,600 | 9,210 | 21,860 | 2.23 | 2.57 |
| February | 75,100 | 18,350 | 35,720 | 3.64 | 3.92 |
| March | 123,400 | 16,600 | 52,530 | 5.34 | 6.16 |
| April | 63,900 | 14,440 | 31,290 | 3.19 | 3.56 |
| May | 36,500 | 6,520 | 15,750 | 1.61 | 1.86 |
| June | 37,000 | 2,840 | 11,180 | 1.14 | 1.27 |
| July | 5,620 | 2,620 | 3,636 | .371 | .428 |
| August | 12,340 | 2,410 | 5,194 | .529 | .610 |
| September | 8,850 | 2,200 | 4,119 | .420 | .469 |
| October | 30,100 | 3,780 | 11,260 | 1.15 | 1.33 |
| November | 8,850 | 4,800 | 5,972 | .609 | .679 |
| December | 47,850 | 2,200 | 7,660 | .781 | .900 |
| The year | 123,400 | 2,200 | 17,180 | 1.75 | 23.76 |

SUSQUEHANNA RIVER AT DANVILLE, PA.

This station, 52 miles below Wilkesbarre and 11 miles above the mouth of the West Branch, was established on March 25, 1899, by E. G. Paul. It is located at the Mill Street Bridge, 600 feet south of the public square, Danville, Pa., near the Pennsylvania Railroad station at South Danville. The box of the standard chain gage is bolted to the hand rail on the lower side of the bridge 200 feet from the right bank. The length from the end of the weight to the marker is 42.85 feet. The gage is read once each day by E. F. Bell. Discharge measurements were made from the lower side of the Mill street covered wooden highway bridge. This bridge was carried away by the ice on March 9, 1904. From that time until the water dropped below gage height, 5 feet, its stage was observed on the Weather Bureau gage. After the water fell below 5 feet its stage was measured approximately, until September 30, 1904, by means of temporary gages set by the gage reader. This bridge had a total span of about 1,300 feet. The initial point for soundings was at the end of the wooden hand rail on the left bank, downstream side. The channel is straight for about one-half mile above and below the station. The right bank is low and liable to overflow. The left bank is high and is not subject to overflow. The bed of the stream is rocky, with some gravel, and is permanent. There is but one channel, broken by the six bridge piers, which do not obstruct the flow to any considerable extent. The current is moderately rapid, except at very low stages, when it becomes sluggish. The bench mark is the extreme south end of the stone doorsill at the east entrance to the city filter plant. Its elevation is 31.7 feet above gage datum.

Discharge measurements of Susquehanna River at Danville, Pa., 1899-1903.

| Date. | Hydrographer. | Gage height. | Area of section. | Mean velocity. | Dis-charge. |
|----------|---------------|--------------|------------------|-------------------------|---------------------|
| 1899. | | <i>Feet.</i> | <i>Sq. feet.</i> | <i>Feet per second.</i> | <i>Second-feet.</i> |
| Mar. 25 | E. G. Paul | 10.00 | 10,971 | 4.34 | 47,646 |
| June 8 | do | 3.00 | 2,235 | 1.76 | 3,927 |
| July 27 | do | 2.40 | 1,607 | 1.41 | 2,272 |
| Sept. 16 | do | 2.00 | 1,265 | 1.13 | 1,427 |
| Oct. 17 | do | 1.90 | 1,123 | 1.03 | 1,163 |
| 1900. | | | | | |
| May 20 | E. G. Paul | 4.60 | 3,799 | 2.76 | 10,515 |
| Sept. 25 | do | 1.60 | 798 | 1.03 | 822 |
| 1901. | | | | | |
| Aug. 19 | E. G. Paul | 7.50 | 7,631 | 3.63 | 27,714 |
| Oct. 27 | do | 3.10 | 2,051 | 2.20 | 4,510 |
| 1902. | | | | | |
| Apr. 22 | E. G. Paul | 5.20 | 4,541 | 3.17 | 14,393 |
| Sept. 19 | do | 2.75 | 1,993 | 1.56 | 3,115 |
| 1903. | | | | | |
| Mar. 5 | E. C. Murphy | 9.82 | 10,413 | 3.72 | 39,600 |
| Apr. 9 | do | 8.60 | 8,848 | 3.66 | 33,000 |
| May 9 | do | 3.44 | 2,688 | 1.85 | 4,963 |
| Oct. 8 | W. C. Sawyer | 3.46 | 2,845 | 2.01 | 5,728 |

Mean daily gage height, in feet, of Susquehanna River at Danville, Pa., 1899-1904.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|-------|-------|-------|-------|------|-------|-------|------|-------|------|-------|------|
| 1899. | | | | | | | | | | | | |
| 1 | | | | 6.95 | 4.80 | 3.30 | 3.20 | 2.20 | 2.80 | 2.10 | 2.10 | 3.10 |
| 2 | | | | 6.80 | 4.65 | 3.40 | 3.00 | 2.20 | 2.60 | 2.10 | 2.60 | 3.00 |
| 3 | | | | 6.35 | 4.60 | 3.70 | 2.80 | 2.60 | 2.50 | 2.10 | 2.60 | 3.00 |
| 4 | | | | 6.00 | 4.60 | 3.60 | 2.70 | 2.50 | 2.50 | 2.10 | 6.10 | 3.00 |
| 5 | | | | 5.65 | 4.60 | 3.50 | 2.60 | 2.20 | 2.30 | 2.00 | 5.40 | 3.00 |
| 6 | | | | 5.50 | 4.55 | 3.30 | 2.60 | 2.20 | 2.20 | 2.00 | 5.70 | 2.90 |
| 7 | | | | 5.65 | 4.35 | 3.20 | 2.60 | 2.50 | 2.20 | 2.00 | 5.20 | 3.10 |
| 8 | | | | 6.90 | 4.15 | 3.00 | 2.50 | 2.30 | 2.10 | 2.00 | 4.70 | 3.10 |
| 9 | | | | 10.50 | 3.80 | 3.00 | 2.50 | 2.20 | 2.40 | 2.10 | 4.30 | 3.10 |
| 10 | | | | 11.60 | 3.70 | 2.90 | 2.50 | 2.20 | 2.20 | 2.10 | 3.90 | 3.00 |
| 11 | | | | 10.45 | 3.70 | 2.90 | 2.50 | 2.60 | 2.10 | 2.00 | 7.30 | 3.00 |
| 12 | | | | 9.15 | 3.75 | 2.90 | 2.40 | 2.30 | 2.20 | 2.00 | 3.90 | 3.10 |
| 13 | | | | 8.95 | 3.80 | 2.70 | 2.60 | 2.40 | 2.10 | 2.00 | 3.70 | 4.20 |
| 14 | | | | 10.75 | 3.70 | 2.70 | 2.70 | 2.30 | 2.10 | 1.90 | 4.00 | 6.80 |
| 15 | | | | 11.55 | 3.70 | 2.60 | 2.60 | 2.30 | 2.10 | 1.90 | 3.90 | 7.80 |
| 16 | | | | 11.40 | 3.60 | 2.60 | 2.80 | 2.30 | 2.00 | 1.90 | 3.80 | 7.60 |
| 17 | | | | 10.85 | 3.60 | 2.60 | 2.80 | 2.30 | 1.90 | 1.90 | 3.90 | 6.70 |
| 18 | | | | 10.05 | 3.70 | 2.60 | 2.70 | 2.30 | 1.90 | 1.90 | 4.30 | 6.10 |
| 19 | | | | 9.05 | 3.60 | 2.60 | 2.70 | 2.30 | 1.80 | 1.90 | 4.40 | 5.70 |
| 20 | | | | 8.25 | 3.60 | 2.50 | 2.50 | 2.20 | 1.80 | 1.90 | 4.30 | 5.40 |
| 21 | | | | 7.75 | 3.60 | 2.50 | 2.50 | 2.10 | 1.90 | 1.90 | 4.10 | 5.60 |
| 22 | | | | 7.35 | 3.80 | 2.50 | 2.50 | 2.10 | 1.90 | 1.90 | 3.80 | 6.90 |
| 23 | | | | 7.05 | 3.80 | 2.50 | 2.50 | 2.10 | 1.80 | 1.90 | 3.90 | 6.30 |
| 24 | | | | 6.65 | 3.80 | 2.50 | 2.50 | 2.10 | 1.80 | 1.90 | 3.60 | 6.30 |
| 25 | | | 10.00 | 6.20 | 3.80 | 2.50 | 2.50 | 2.00 | 1.80 | 1.90 | 3.40 | 6.50 |
| 26 | | | 9.25 | 5.85 | 3.70 | 2.70 | 2.40 | 2.00 | 1.90 | 1.90 | 3.40 | 7.10 |
| 27 | | | 8.10 | 5.70 | 3.60 | 2.60 | 2.40 | 2.00 | 1.90 | 1.90 | 3.30 | 6.90 |
| 28 | | | 7.35 | 5.65 | 3.50 | 2.60 | 2.40 | 2.30 | 1.80 | 1.80 | 3.20 | 6.40 |
| 29 | | | 7.30 | 5.35 | 3.30 | 2.90 | 2.40 | 2.20 | 1.90 | 1.90 | 3.10 | 5.80 |
| 30 | | | 7.55 | 5.10 | 3.20 | 3.20 | 2.40 | 3.50 | 2.10 | 1.90 | 3.10 | 5.00 |
| 31 | | | 7.45 | | 3.30 | | 2.30 | 3.20 | | 1.90 | | |
| 1900. | | | | | | | | | | | | |
| 1 | (a) | (a) | 7.55 | 5.60 | 5.35 | 3.00 | 2.30 | 2.40 | 2.20 | 1.70 | 2.00 | 8.75 |
| 2 | (a) | (a) | 15.25 | 5.80 | 5.05 | 2.90 | 2.30 | 2.40 | 2.20 | 1.70 | 2.00 | 7.15 |
| 3 | (a) | (a) | 13.10 | 6.75 | 4.80 | 2.90 | 2.30 | 2.30 | 2.20 | 1.70 | 2.00 | 5.90 |
| 4 | (a) | (a) | 10.65 | 8.40 | 4.55 | 3.50 | 2.20 | 2.20 | 2.20 | 1.70 | 2.00 | 5.50 |
| 5 | (a) | (a) | 9.25 | 9.30 | 4.40 | 3.30 | 2.20 | 2.20 | 2.20 | 1.70 | 2.00 | 7.10 |
| 6 | (a) | (a) | 7.10 | 8.45 | 4.25 | 3.10 | 2.30 | 2.10 | 2.10 | 1.70 | 2.00 | 8.80 |
| 7 | (a) | (a) | 7.10 | 7.40 | 4.15 | 3.00 | 2.70 | 2.50 | 2.10 | 1.70 | 2.00 | 9.65 |
| 8 | (a) | (a) | 7.30 | 8.70 | 4.05 | 2.90 | 2.90 | 2.20 | 2.00 | 1.70 | 2.00 | 8.55 |
| 9 | (a) | 9.70 | 6.85 | 9.75 | 4.00 | 2.90 | 2.90 | 2.10 | 1.80 | 1.70 | 2.00 | 7.50 |
| 10 | (a) | 9.90 | 6.75 | 9.45 | 3.95 | 2.90 | 2.70 | 2.10 | 1.90 | 1.70 | 2.00 | 6.85 |
| 11 | (a) | 7.60 | 7.50 | 8.25 | 3.85 | 3.10 | 2.50 | 2.00 | 1.80 | 1.70 | 2.10 | 6.30 |
| 12 | (a) | 7.80 | 7.20 | 7.10 | 3.90 | 3.10 | 2.50 | 2.00 | 1.80 | 1.70 | 2.10 | 5.55 |
| 13 | (a) | 9.40 | 6.40 | 6.30 | 4.10 | 3.30 | 2.40 | 1.90 | 1.80 | 1.70 | 2.20 | 5.20 |
| 14 | (a) | 9.60 | 5.65 | 6.10 | 4.20 | 3.30 | 2.30 | 2.00 | 1.80 | 1.70 | 2.40 | 5.00 |
| 15 | (a) | 11.20 | 5.20 | 6.30 | 4.00 | 3.90 | 2.30 | 2.00 | 1.80 | 1.80 | 2.40 | 5.00 |
| 16 | (a) | 10.40 | 4.90 | 6.65 | 4.00 | 3.50 | 2.30 | 1.90 | 1.80 | 1.80 | 2.60 | 6.80 |
| 17 | (a) | 8.30 | 4.70 | 6.35 | 3.80 | 3.20 | 2.30 | 1.90 | 1.70 | 1.80 | 2.50 | (a) |
| 18 | (a) | 7.30 | 4.90 | 7.00 | 3.90 | 3.00 | 2.30 | 1.90 | 1.70 | 1.80 | 2.50 | (a) |
| 19 | (a) | 5.70 | 5.05 | 9.75 | 3.90 | 3.00 | 2.30 | 1.80 | 1.70 | 1.80 | 2.50 | (a) |
| 20 | (a) | 5.00 | 5.10 | 10.55 | 4.40 | 2.90 | 2.30 | 1.80 | 1.70 | 1.80 | 2.50 | (a) |
| 21 | 9.40 | 4.70 | 7.95 | 9.85 | 4.40 | 2.80 | 2.20 | 1.90 | 1.70 | 1.70 | 2.50 | (a) |
| 22 | 12.70 | 5.95 | 8.80 | 8.95 | 4.10 | 2.70 | 2.40 | 1.90 | 1.70 | 1.70 | 2.50 | (a) |
| 23 | 11.95 | 12.15 | 7.95 | 8.10 | 3.90 | 2.60 | 2.30 | 1.80 | 1.60 | 1.90 | 2.60 | (a) |
| 24 | 9.70 | 13.50 | 7.40 | 8.35 | 3.70 | 2.60 | 2.20 | 1.80 | 1.60 | 2.10 | 2.70 | (a) |
| 25 | 7.80 | 11.05 | 7.40 | 9.30 | 3.60 | 2.70 | 2.10 | 2.30 | 1.60 | 2.30 | 2.90 | (a) |
| 26 | 6.80 | 8.95 | 7.65 | 8.40 | 3.60 | 2.60 | 2.30 | 2.10 | 1.70 | 2.20 | 3.90 | 7.05 |
| 27 | 6.45 | 6.85 | 6.95 | 7.40 | 3.40 | 2.50 | 3.00 | 2.20 | 1.70 | 2.10 | 8.45 | 8.60 |
| 28 | 6.30 | 5.45 | 6.50 | 6.65 | 3.20 | 2.50 | 2.30 | 2.10 | 1.70 | 2.10 | 16.60 | 7.55 |
| 29 | 5.80 | | 5.85 | 6.10 | 3.20 | 2.40 | 2.60 | 2.00 | 1.70 | 2.10 | 12.65 | 6.95 |
| 30 | 5.80 | | 5.90 | 5.65 | 3.10 | 2.40 | 2.40 | 2.00 | 1.70 | 2.00 | 10.20 | 6.55 |
| 31 | (a) | | 5.65 | | 3.00 | | 2.40 | 2.00 | | 2.00 | | 6.30 |

*a*River frozen.

*Mean daily gage height, in feet, of Susquehanna River at Danville, Pa.,
1899-1904—Continued.*

| Days. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|------|------|-------------------|
| 1901. | | | | | | | | | | | | |
| 1 | 5.70 | (a) | (a) | 8.50 | 6.65 | 13.60 | 3.70 | 3.30 | 4.60 | 3.50 | 2.90 | 4.10 |
| 2 | 8.60 | (a) | (a) | 7.65 | 6.10 | 9.65 | 3.70 | 3.00 | 5.10 | 3.50 | 2.90 | 3.90 |
| 3 | (a) | (a) | (a) | 7.20 | 6.50 | 9.65 | 3.40 | 2.70 | 4.90 | 3.85 | 2.80 | 3.90 |
| 4 | (a) | (a) | (a) | 7.60 | 7.60 | 9.15 | 3.20 | 2.60 | 4.90 | 4.05 | 2.80 | 4.55 |
| 5 | (a) | (a) | (a) | 8.65 | 7.35 | 8.30 | 3.10 | 2.60 | 4.30 | 3.85 | 2.80 | 5.95 |
| 6 | (a) | (a) | (a) | 9.40 | 6.65 | 7.30 | 3.10 | 2.60 | 4.25 | 3.70 | 2.70 | 7.90 |
| 7 | (a) | (a) | (a) | 8.60 | 6.05 | 6.80 | 3.10 | 2.70 | 3.95 | 3.50 | 2.70 | ^b 8.30 |
| 8 | (a) | (a) | (a) | 8.55 | 5.35 | 7.30 | 3.60 | 2.90 | 3.70 | 3.30 | 2.60 | ^b 8.70 |
| 9 | (a) | (a) | (a) | 7.80 | 5.30 | 7.60 | 3.50 | 3.10 | 3.50 | 3.20 | 2.60 | ^b 9.10 |
| 10 | (a) | (a) | (a) | 7.45 | 6.50 | 7.55 | 3.40 | 2.90 | 3.35 | 3.20 | 2.60 | 9.55 |
| 11 | (a) | (a) | (a) | 7.10 | 5.00 | 7.00 | 3.30 | 3.50 | 3.25 | 3.10 | 2.60 | 9.80 |
| 12 | (a) | (a) | 12.00 | 6.75 | 5.70 | 6.40 | 3.30 | 3.30 | 3.10 | 3.00 | 2.60 | 10.05 |
| 13 | (a) | (a) | 11.15 | 6.50 | 6.60 | 5.60 | 3.20 | 3.00 | 3.00 | 2.90 | 2.80 | 8.90 |
| 14 | (a) | (a) | 8.50 | 8.60 | 7.95 | 5.20 | 3.10 | 2.90 | 3.05 | 3.90 | 2.90 | 7.90 |
| 15 | (a) | (a) | 7.60 | 8.15 | 7.85 | 5.00 | 3.00 | 2.80 | 3.00 | 3.85 | 3.00 | 14.65 |
| 16 | (a) | (a) | 7.30 | 7.80 | 7.05 | 4.95 | 2.90 | 2.80 | 3.10 | 3.90 | 3.45 | 22.57 |
| 17 | (a) | (a) | 7.40 | 7.45 | 6.30 | 4.60 | 2.90 | 2.80 | 3.10 | 3.90 | 3.90 | 20.05 |
| 18 | (a) | (a) | 6.90 | 7.10 | 5.80 | 4.60 | 3.00 | 6.60 | 3.40 | 3.90 | 3.90 | 13.85 |
| 19 | (a) | (a) | 6.60 | 6.75 | 5.80 | 4.45 | 3.10 | 7.85 | 3.50 | 3.80 | 3.60 | 10.25 |
| 20 | (a) | (a) | 6.60 | 6.50 | 5.70 | 4.10 | 3.00 | 5.60 | 3.50 | 3.90 | 3.50 | 8.80 |
| 21 | (a) | (a) | 9.25 | 6.90 | 5.95 | 4.00 | 2.90 | 4.55 | 3.60 | 3.60 | 3.50 | 7.10 |
| 22 | (a) | (a) | 11.85 | 12.60 | 5.75 | 3.90 | 2.80 | 4.75 | 3.60 | 3.50 | 3.50 | 5.90 |
| 23 | (a) | (a) | 12.70 | 15.25 | 5.35 | 3.90 | 2.70 | 6.30 | 3.40 | 3.40 | 3.40 | 5.10 |
| 24 | (a) | (a) | 11.35 | 12.75 | 5.40 | 4.25 | 2.60 | 8.10 | 3.40 | 3.30 | 3.40 | 4.90 |
| 25 | (a) | (a) | 11.25 | 12.05 | 6.55 | 6.35 | 2.60 | 11.02 | 3.10 | 3.30 | 3.70 | 4.75 |
| 26 | (a) | (a) | 11.15 | 11.70 | 7.40 | 4.70 | 2.60 | 9.25 | 3.00 | 3.20 | 6.17 | 4.95 |
| 27 | (a) | (a) | 13.35 | 10.65 | 6.90 | 4.45 | 2.60 | 7.55 | 2.90 | 3.10 | 7.00 | 5.10 |
| 28 | (a) | (a) | 17.00 | 8.90 | 6.40 | 4.10 | 2.60 | 6.15 | 2.80 | 3.10 | 5.85 | 5.00 |
| 29 | (a) | | 16.85 | 8.25 | 8.00 | 3.85 | 2.50 | 5.55 | 2.90 | 3.00 | 4.95 | 5.20 |
| 30 | (a) | | 13.35 | 7.55 | 12.70 | 3.80 | 2.70 | 4.70 | 3.20 | 3.00 | 4.35 | 7.15 |
| 31 | (a) | | 10.45 | | 14.95 | | 2.90 | 4.40 | | 2.90 | | 6.80 |
| 1902. | | | | | | | | | | | | |
| 1 | 6.60 | 4.85 | 20.67 | 7.85 | 4.40 | 3.50 | 6.10 | 7.70 | 3.10 | 8.95 | 7.05 | 4.30 |
| 2 | 6.20 | 5.05 | 24.43 | 7.60 | 4.30 | 3.40 | 8.95 | 7.75 | 3.00 | 9.15 | 6.30 | 4.20 |
| 3 | 5.40 | (c) | 26.07 | 7.40 | 4.20 | 3.30 | 7.40 | 8.70 | 3.00 | 9.05 | 5.80 | 4.20 |
| 4 | 5.50 | | 22.25 | 7.10 | 4.20 | 3.30 | 6.90 | 8.20 | 2.90 | 7.65 | 5.45 | 4.60 |
| 5 | 6.70 | | 18.20 | 6.65 | 4.20 | 3.30 | 6.90 | 7.20 | 2.90 | 6.75 | 5.20 | 4.70 |
| 6 | (c) | | 14.50 | 6.45 | 4.10 | 3.20 | 6.90 | 6.75 | 2.80 | 6.80 | 5.00 | 4.90 |
| 7 | | | 10.75 | 6.30 | 4.00 | 3.20 | 8.50 | 5.85 | 2.80 | 6.50 | 4.85 | 4.90 |
| 8 | | | 8.55 | 6.50 | 4.00 | 3.90 | 11.90 | 5.45 | 2.80 | 6.10 | 4.70 | 4.80 |
| 9 | 10.60 | | 8.35 | 7.30 | 3.90 | 3.70 | 10.45 | 5.20 | 2.70 | 5.60 | 4.70 | 4.70 |
| 10 | 9.45 | | 9.10 | 11.90 | 3.80 | 3.50 | 7.85 | 5.00 | 2.60 | 5.20 | 4.50 | 4.30 |
| 11 | 9.10 | | 10.25 | 13.10 | 3.80 | 3.50 | 7.25 | 4.70 | 3.00 | 4.90 | 4.30 | 4.20 |
| 12 | 9.30 | | 11.55 | 11.20 | 3.70 | 3.60 | 7.80 | 4.60 | 3.10 | 5.40 | 4.20 | 4.30 |
| 13 | (c) | | 14.15 | 9.75 | 3.60 | 3.50 | 7.90 | 4.50 | 3.00 | 6.00 | 4.10 | 4.40 |
| 14 | | | 16.15 | 8.65 | 3.50 | 3.50 | 7.20 | 4.50 | 3.10 | 5.60 | 4.00 | 5.00 |
| 15 | | | 15.55 | 7.70 | 3.50 | 3.60 | 5.55 | 4.40 | 3.10 | 5.25 | 3.90 | 6.50 |
| 16 | | | 13.95 | 7.05 | 3.40 | 3.60 | 5.15 | 4.30 | 3.00 | 5.10 | 3.90 | 7.80 |
| 17 | | | 14.25 | 6.60 | 3.30 | 3.70 | 4.85 | 4.10 | 2.90 | 5.10 | 3.90 | 9.40 |
| 18 | | | 16.60 | 6.35 | 3.30 | 4.10 | 4.60 | 3.80 | 2.80 | 5.00 | 3.80 | 10.30 |
| 19 | | | 15.60 | 6.15 | 3.20 | 4.00 | 4.40 | 3.70 | 2.70 | 4.70 | 3.70 | 10.60 |
| 20 | | | 12.80 | 5.90 | 3.10 | 3.80 | 4.40 | 3.60 | 2.60 | 4.50 | 3.60 | 9.40 |
| 21 | | | 10.95 | 5.45 | 3.10 | 3.80 | 5.30 | 3.50 | 2.60 | 4.20 | 3.60 | 8.80 |
| 22 | | | 8.90 | 5.30 | 3.10 | 3.70 | 11.90 | 3.50 | 2.60 | 4.10 | 3.60 | 12.70 |
| 23 | | | 8.00 | 5.10 | 3.00 | 3.60 | 12.00 | 3.40 | 2.60 | 4.20 | 3.50 | 14.80 |
| 24 | 8.10 | | 6.40 | 4.90 | 3.00 | 3.50 | 11.30 | 3.40 | 2.50 | 4.30 | 3.50 | 14.40 |
| 25 | 8.50 | | 7.20 | 4.70 | 3.20 | 3.50 | 10.90 | 3.40 | 2.60 | 4.20 | 3.50 | 11.80 |
| 26 | 7.40 | | 7.10 | 4.50 | 3.30 | 3.60 | 11.90 | 3.30 | 4.75 | 4.00 | 3.60 | 9.75 |
| 27 | 6.90 | | 7.05 | 4.30 | 3.20 | 3.70 | 10.20 | 3.20 | 6.85 | 5.60 | 3.80 | 8.40 |
| 28 | 6.75 | 13.75 | 6.65 | 4.10 | 3.30 | 3.70 | 8.50 | 3.20 | 6.20 | 8.90 | 3.90 | 7.60 |
| 29 | 6.40 | | 6.75 | 4.00 | 3.50 | 3.50 | 8.00 | 3.20 | 6.05 | 9.70 | 4.00 | 6.80 |
| 30 | 6.20 | | 8.15 | 4.30 | 3.80 | 4.20 | 9.30 | 3.10 | 7.95 | 9.35 | 4.20 | 6.30 |
| 31 | 5.55 | | 8.30 | | 3.70 | | 8.20 | 3.10 | | 8.20 | | 5.70 |

^aIce.^bEstimated.^cFrozen from January 6 to 8, 13 to 21, February 3 to 27.

Mean daily gage height, in feet, of Susquehanna River at Danville, Pa., 1899-1904—Cont'd.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|--------------------|--------|--------|--------|-------|------|-------|-------|-------|-------|-------|-------|-------|
| 1903. | | | | | | | | | | | | |
| 1. | 5.20 | a13.80 | 16.40 | 8.50 | 4.10 | 2.70 | 6.50 | 4.10 | 11.60 | 3.00 | 4.80 | 4.00 |
| 2. | 5.20 | a12.40 | 17.60 | 9.80 | 4.00 | 2.60 | 6.00 | 3.90 | 9.85 | 2.90 | 4.60 | 4.60 |
| 3. | 6.10 | a10.20 | 14.40 | 8.90 | 3.80 | 2.60 | 5.55 | 3.90 | 8.00 | 2.90 | 4.50 | 5.10 |
| 4. | 6.60 | a11.20 | 11.60 | 7.80 | 3.70 | 2.60 | 5.30 | 3.70 | 6.90 | 2.90 | 4.40 | 4.60 |
| 5. | 7.30 | a14.00 | 9.60 | 7.60 | 3.70 | 2.50 | 5.00 | 4.15 | 6.05 | 2.90 | 4.30 | 4.00 |
| 6. | 8.20 | a15.20 | 8.70 | 8.30 | 3.60 | 2.50 | 4.70 | 4.85 | 5.60 | 3.00 | 4.10 | 3.90 |
| 7. | 7.40 | a11.80 | 9.20 | 7.60 | 3.50 | 2.50 | 4.70 | 6.70 | 5.10 | 3.00 | 4.10 | 4.40 |
| 8. | 6.60 | a9.70 | 9.60 | 7.20 | 3.50 | 2.80 | 6.50 | 6.45 | 4.90 | 3.40 | 4.20 | 4.50 |
| 9. | 6.00 | a7.80 | 10.40 | 8.80 | 3.40 | 2.90 | 5.30 | 6.00 | 4.50 | 4.70 | 4.30 | 4.00 |
| 10. | 5.70 | a7.00 | 15.00 | 9.30 | 3.30 | 2.80 | 4.60 | 5.60 | 4.30 | 12.50 | 4.30 | 4.40 |
| 11. | a9.40 | a7.20 | 14.50 | 8.60 | 3.30 | 2.70 | 4.00 | 5.00 | 4.20 | 16.60 | 4.10 | 5.10 |
| 12. | (b) | a7.10 | 15.00 | 7.90 | 3.20 | 3.40 | 4.00 | 4.90 | 4.30 | 17.00 | 4.00 | (c) |
| 13. | (b) | a7.40 | 14.80 | 7.70 | 3.10 | 3.10 | 3.90 | 4.60 | 4.30 | 15.40 | 3.80 | (c) |
| 14. | (b) | a8.50 | 12.80 | 7.30 | 3.10 | 5.00 | 3.60 | 4.70 | 4.70 | 11.60 | 3.80 | (c) |
| 15. | (b) | a8.80 | 11.40 | 8.10 | 3.10 | 5.90 | 3.50 | 4.30 | 4.30 | 8.95 | 3.70 | (c) |
| 16. | (b) | a8.10 | 9.60 | 11.35 | 3.10 | 5.65 | 3.40 | 4.30 | 4.00 | 7.60 | 3.90 | (c) |
| 17. | (b) | a7.00 | 8.70 | 11.05 | 3.00 | 5.00 | 3.30 | 4.10 | 3.80 | 6.80 | 3.90 | (c) |
| 18. | (b) | a6.60 | 7.60 | 9.05 | 3.00 | 4.60 | 3.20 | 3.90 | 4.30 | 7.50 | 7.75 | (c) |
| 19. | (b) | a5.70 | 7.60 | 7.30 | 3.00 | 4.25 | 3.90 | 3.70 | 4.30 | 9.00 | 10.10 | (c) |
| 20. | (b) | a6.00 | 7.40 | 7.10 | 2.90 | 4.15 | 4.50 | 3.50 | 3.90 | 10.20 | 7.80 | (c) |
| 21. | (b) | (b) | 7.00 | 6.40 | 2.90 | 4.00 | 4.40 | 3.50 | 4.10 | 9.40 | 7.50 | (c) |
| 22. | (b) | (b) | 6.80 | 5.90 | 2.90 | 4.30 | 4.50 | 3.85 | 3.90 | 8.20 | 6.80 | (c) |
| 23. | (b) | (b) | 8.00 | 5.50 | 3.00 | 6.40 | 4.40 | 4.50 | 3.80 | 7.20 | 5.80 | (c) |
| 24. | (b) | (b) | 15.85 | 5.30 | 3.00 | 6.95 | 4.10 | 4.20 | 3.70 | 6.50 | 5.50 | (c) |
| 25. | (b) | (b) | 18.05 | 5.00 | 2.90 | 7.75 | 3.80 | 3.90 | 3.40 | 6.00 | 5.20 | (c) |
| 26. | (b) | (b) | 15.25 | 4.80 | 2.90 | 7.80 | 5.30 | 3.70 | 3.30 | 5.60 | 5.00 | (c) |
| 27. | (b) | (b) | 12.80 | 4.70 | 2.80 | 8.55 | 4.90 | 3.50 | 3.20 | 5.40 | 4.80 | (c) |
| 28. | (b) | 10.85 | 10.70 | 4.50 | 2.70 | 6.90 | 4.10 | 3.70 | 3.20 | 5.20 | 4.70 | (c) |
| 29. | (b) | ----- | 9.30 | 4.40 | 2.80 | 6.80 | 3.80 | 5.15 | 3.20 | 5.00 | 4.30 | (c) |
| 30. | (b) | ----- | 8.80 | 4.20 | 2.80 | 7.30 | 3.80 | 10.73 | 3.00 | 4.80 | 4.20 | (c) |
| 31. | a14.80 | ----- | 7.80 | ----- | 2.70 | ----- | 3.80 | 14.65 | ----- | 4.80 | ----- | (c) |
| 1904. ^k | | | | | | | | | | | | |
| 1. | (c) | 14.70 | 11.40 | 11.05 | 8.10 | 4.00 | 2.00 | 2.40 | 1.90 | ----- | ----- | ----- |
| 2. | (c) | 14.10 | 11.30 | 10.85 | 8.00 | 4.20 | 2.00 | 2.50 | 1.90 | ----- | ----- | ----- |
| 3. | (c) | 13.30 | 11.80 | 10.60 | 7.50 | 4.70 | 1.90 | 2.50 | 1.80 | ----- | ----- | ----- |
| 4. | (c) | 12.70 | a12.90 | 10.40 | 6.40 | 4.20 | 1.90 | 2.70 | 1.70 | ----- | ----- | ----- |
| 5. | (c) | 12.10 | 13.80 | 10.40 | 5.30 | 4.70 | 1.80 | 2.90 | 1.70 | ----- | ----- | ----- |
| 6. | (c) | 11.70 | 16.00 | 9.70 | 4.20 | 5.10 | 2.40 | 2.50 | 1.60 | ----- | ----- | ----- |
| 7. | (c) | 11.50 | 17.25 | 9.30 | 3.70 | 5.50 | 2.30 | 2.40 | 1.50 | ----- | ----- | ----- |
| 8. | (c) | 13.10 | 19.95 | 8.80 | 3.60 | 4.70 | 2.10 | 2.70 | 1.50 | ----- | ----- | ----- |
| 9. | (c) | f20.00 | f24.00 | 8.20 | 3.60 | 4.30 | 2.10 | 2.90 | 1.40 | ----- | ----- | ----- |
| 10. | (c) | g23.86 | ----- | 7.90 | 3.40 | 4.90 | 2.00 | 2.40 | 1.40 | ----- | ----- | ----- |
| 11. | (c) | 21.25 | ----- | 7.40 | 3.30 | 7.10 | 1.90 | 1.90 | 1.40 | ----- | ----- | ----- |
| 12. | (c) | 19.50 | ----- | 6.80 | 3.30 | 6.20 | 1.90 | 1.70 | 1.30 | ----- | ----- | ----- |
| 13. | (c) | 18.05 | ----- | 6.30 | 3.20 | 4.80 | 2.00 | 1.70 | 1.30 | ----- | ----- | ----- |
| 14. | (c) | 16.90 | ----- | 6.10 | 3.10 | 4.70 | 2.40 | 1.60 | 1.60 | ----- | ----- | ----- |
| 15. | (c) | 15.40 | ----- | 5.80 | 2.90 | 4.50 | 2.60 | 1.60 | 1.90 | ----- | ----- | ----- |
| 16. | (c) | h13.90 | ----- | 5.40 | 2.70 | 4.30 | 2.20 | 1.50 | 2.20 | ----- | ----- | ----- |
| 17. | (c) | 13.00 | ----- | 5.00 | 3.90 | 4.00 | 1.90 | 1.40 | 1.90 | ----- | ----- | ----- |
| 18. | (c) | 12.40 | ----- | 4.70 | 4.50 | 3.70 | 1.80 | 1.70 | 1.70 | ----- | ----- | ----- |
| 19. | (c) | 11.00 | ----- | 4.30 | 6.30 | 3.30 | 1.80 | 1.60 | 1.60 | ----- | ----- | ----- |
| 20. | (c) | 10.60 | ----- | 4.10 | 6.90 | 3.00 | 1.70 | 1.50 | 1.50 | ----- | ----- | ----- |
| 21. | (c) | 11.20 | ----- | 4.00 | 7.20 | 2.80 | 1.70 | 1.50 | 1.50 | ----- | ----- | ----- |
| 22. | (c) | 12.30 | ----- | 3.70 | 6.30 | 2.60 | 1.60 | 1.40 | 1.90 | ----- | ----- | ----- |
| 23. | (c) | 12.30 | ----- | 3.50 | 4.90 | 2.60 | 1.90 | 1.40 | 2.40 | ----- | ----- | ----- |
| 24. | a19.85 | 12.40 | ----- | 3.30 | 4.40 | 2.50 | 2.00 | 1.80 | 2.90 | ----- | ----- | ----- |
| 25. | c24.00 | 12.00 | ----- | 3.30 | 4.10 | 2.50 | 1.80 | 2.40 | 2.30 | ----- | ----- | ----- |
| 26. | 23.25 | 11.70 | ----- | 3.20 | 4.70 | 2.30 | 1.70 | 2.90 | 2.00 | ----- | ----- | ----- |
| 27. | 19.85 | 11.70 | 14.25 | 3.00 | 4.40 | 2.20 | 1.50 | 2.60 | 2.20 | ----- | ----- | ----- |
| 28. | 17.90 | 11.40 | 13.80 | 4.20 | 3.90 | 2.20 | 1.80 | 2.50 | 2.70 | ----- | ----- | ----- |
| 29. | 16.00 | 11.10 | 13.35 | 5.30 | 3.70 | 2.10 | 1.80 | 2.30 | 2.10 | ----- | ----- | ----- |
| 30. | 15.55 | ----- | 12.55 | 6.90 | 3.70 | 2.10 | 2.00 | 2.00 | 2.40 | ----- | ----- | ----- |
| 31. | 15.05 | ----- | 11.75 | ----- | 3.90 | ----- | 2.20 | 1.90 | ----- | ----- | ----- | ----- |

a Water backed up by ice.

b River frozen.

c River frozen.

d The ice started at 11.30 a. m.

e The ice gorged 1 p. m.

f The river is still frozen over.


g The ice broke and gorged and left an open place by the bridge.

h The ice is still gorged in the river.

i The ice gorge is still in the river above and below town.

j The ice started at 4 o'clock and the water backed up to 29 feet.

k The gage heights for 1904 are somewhat uncertain, therefore no estimates of flow have been made.



RATING CURVE FOR SUSQUEHANNA RIVER AT DANVILLE, PA.

Rating table for Susquehanna River at Danville, Pa., for 1899 to 1904.

| Gage height. | Discharge. | Gage height. | Discharge. | Gage height. | Discharge. | Gage height. | Discharge. |
|--------------|---------------------|--------------|---------------------|--------------|---------------------|--------------|---------------------|
| <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> |
| 1.5 | 700 | 3.8 | 6,880 | 6.1 | 19,230 | 9.8 | 42,900 |
| 1.6 | 830 | 3.9 | 7,330 | 6.2 | 19,800 | 10.0 | 44,800 |
| 1.7 | 970 | 4.0 | 7,780 | 6.3 | 20,370 | 10.2 | 46,700 |
| 1.8 | 1,120 | 4.1 | 8,230 | 6.4 | 20,940 | 10.4 | 48,600 |
| 1.9 | 1,270 | 4.2 | 8,690 | 6.5 | 21,510 | 10.6 | 50,400 |
| 2.0 | 1,440 | 4.3 | 9,160 | 6.6 | 22,080 | 10.8 | 52,300 |
| 2.1 | 1,620 | 4.4 | 9,660 | 6.7 | 22,660 | 11.0 | 54,300 |
| 2.2 | 1,810 | 4.5 | 10,170 | 6.8 | 23,240 | 11.2 | 56,300 |
| 2.3 | 2,010 | 4.6 | 10,700 | 6.9 | 23,820 | 11.4 | 58,300 |
| 2.4 | 2,230 | 4.7 | 11,250 | 7.0 | 24,400 | 11.6 | 60,400 |
| 2.5 | 2,470 | 4.8 | 11,820 | 7.2 | 25,600 | 11.8 | 62,500 |
| 2.6 | 2,720 | 4.9 | 12,390 | 7.4 | 26,800 | 12.0 | 64,600 |
| 2.7 | 3,000 | 5.0 | 12,960 | 7.6 | 28,000 | 12.2 | 66,700 |
| 2.8 | 3,280 | 5.1 | 13,530 | 7.8 | 29,100 | 12.4 | 68,900 |
| 2.9 | 3,580 | 5.2 | 14,100 | 8.0 | 30,300 | 12.6 | 71,200 |
| 3.0 | 3,900 | 5.3 | 14,670 | 8.2 | 31,600 | 12.8 | 73,500 |
| 3.1 | 4,230 | 5.4 | 15,240 | 8.4 | 32,800 | 13.0 | 75,800 |
| 3.2 | 4,570 | 5.5 | 15,810 | 8.6 | 34,100 | 13.5 | 81,800 |
| 3.3 | 4,920 | 5.6 | 16,380 | 8.8 | 35,400 | 14.0 | 87,800 |
| 3.4 | 5,280 | 5.7 | 16,950 | 9.0 | 36,700 | 14.5 | 94,300 |
| 3.5 | 5,650 | 5.8 | 17,520 | 9.2 | 38,000 | 15.0 | 101,000 |
| 3.6 | 6,040 | 5.9 | 18,090 | 9.4 | 39,500 | | |
| 3.7 | 6,450 | 6.0 | 18,660 | 9.6 | 41,100 | | |

Mean daily discharge, in second-feet, of Susquehanna River at Danville, Pa., 1899-1903.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|------|---------|---------|----------|---------|---------|--------|--------|--------|--------|---------|---------|
| 1899. | | | | | | | | | | | | |
| 1 | | | | 24, 110 | 11, 820 | 4, 920 | 4, 570 | 1, 810 | 3, 280 | 1, 620 | 1, 620 | 4, 230 |
| 2 | | | | 23, 240 | 10, 920 | 5, 280 | 3, 900 | 1, 810 | 2, 720 | 1, 620 | 2, 720 | 3, 900 |
| 3 | | | | 20, 660 | 10, 700 | 6, 450 | 3, 280 | 2, 720 | 2, 470 | 1, 620 | 2, 720 | 3, 900 |
| 4 | | | | 18, 660 | 10, 700 | 6, 040 | 3, 000 | 2, 010 | 2, 470 | 1, 620 | 19, 230 | 3, 900 |
| 5 | | | | 16, 660 | 10, 700 | 5, 650 | 2, 720 | 1, 810 | 2, 010 | 1, 440 | 15, 240 | 3, 900 |
| 6 | | | | 15, 810 | 10, 440 | 4, 920 | 2, 720 | 1, 810 | 1, 810 | 1, 440 | 16, 950 | 3, 580 |
| 7 | | | | 16, 660 | 9, 410 | 4, 570 | 2, 720 | 2, 470 | 1, 810 | 1, 440 | 14, 100 | 4, 230 |
| 8 | | | | 23, 820 | 8, 460 | 3, 900 | 2, 470 | 2, 010 | 1, 620 | 1, 440 | 11, 250 | 4, 230 |
| 9 | | | | 49, 500 | 6, 880 | 3, 900 | 2, 470 | 1, 810 | 2, 230 | 1, 620 | 9, 160 | 4, 230 |
| 10 | | | | 60, 400 | 6, 450 | 3, 580 | 2, 470 | 1, 810 | 1, 810 | 1, 620 | 7, 330 | 3, 900 |
| 11 | | | | 49, 000 | 6, 450 | 3, 580 | 2, 470 | 2, 720 | 1, 620 | 1, 440 | 6, 450 | 3, 900 |
| 12 | | | | 37, 600 | 6, 660 | 3, 580 | 2, 230 | 2, 010 | 1, 810 | 1, 440 | 7, 330 | 4, 230 |
| 13 | | | | 36, 400 | 6, 880 | 3, 000 | 2, 720 | 2, 230 | 1, 620 | 1, 440 | 6, 450 | 8, 690 |
| 14 | | | | 51, 800 | 6, 450 | 3, 000 | 3, 000 | 2, 010 | 1, 620 | 1, 270 | 7, 780 | 23, 240 |
| 15 | | | | 59, 800 | 6, 450 | 2, 720 | 2, 720 | 2, 010 | 1, 620 | 1, 270 | 7, 330 | 29, 100 |
| 16 | | | | 58, 300 | 6, 040 | 2, 720 | 3, 280 | 2, 010 | 1, 440 | 1, 270 | 6, 880 | 28, 000 |
| 17 | | | | 52, 800 | 6, 040 | 2, 720 | 3, 280 | 2, 010 | 1, 270 | 1, 270 | 7, 330 | 22, 660 |
| 18 | | | | 45, 250 | 6, 450 | 2, 720 | 3, 000 | 2, 010 | 1, 270 | 1, 270 | 9, 160 | 19, 230 |
| 19 | | | | 37, 000 | 6, 040 | 2, 720 | 3, 000 | 2, 010 | 1, 120 | 1, 270 | 9, 660 | 16, 950 |
| 20 | | | | 31, 900 | 6, 040 | 2, 470 | 2, 470 | 1, 810 | 1, 120 | 1, 270 | 9, 160 | 15, 240 |
| 21 | | | | 28, 800 | 6, 040 | 2, 470 | 2, 470 | 1, 620 | 1, 270 | 1, 270 | 8, 230 | 16, 380 |
| 22 | | | | 26, 500 | 6, 880 | 2, 470 | 2, 470 | 1, 620 | 1, 270 | 1, 270 | 6, 880 | 23, 820 |
| 23 | | | | 24, 700 | 6, 880 | 2, 470 | 2, 470 | 1, 620 | 1, 120 | 1, 270 | 7, 330 | 20, 370 |
| 24 | | | | 22, 370 | 6, 880 | 2, 470 | 2, 470 | 1, 620 | 1, 120 | 1, 270 | 6, 040 | 20, 370 |
| 25 | | | 44, 800 | 19, 800 | 6, 880 | 2, 470 | 2, 470 | 1, 440 | 1, 120 | 1, 270 | 5, 280 | 21, 510 |
| 26 | | | 38, 350 | 17, 800 | 6, 450 | 3, 000 | 2, 230 | 1, 440 | 1, 270 | 1, 270 | 5, 280 | 25, 000 |
| 27 | | | 31, 000 | 16, 950 | 6, 040 | 2, 720 | 2, 230 | 1, 440 | 1, 270 | 1, 270 | 4, 920 | 23, 820 |
| 28 | | | 26, 500 | 16, 660 | 5, 650 | 2, 720 | 2, 230 | 2, 010 | 1, 120 | 1, 120 | 4, 570 | 20, 940 |
| 29 | | | 26, 200 | 14, 950 | 4, 920 | 3, 580 | 2, 230 | 1, 810 | 1, 270 | 1, 270 | 4, 230 | 17, 520 |
| 30 | | | 27, 700 | 13, 530 | 4, 570 | 4, 570 | 2, 230 | 5, 650 | 1, 620 | 1, 270 | 4, 230 | 12, 960 |
| 31 | | | 27, 100 | | 4, 920 | | 2, 010 | 4, 570 | | 1, 270 | | |
| 1900. | | | | | | | | | | | | |
| 1 | | | | 27, 700 | 16, 380 | 14, 950 | 3, 900 | 2, 010 | 2, 230 | 1, 810 | 970 | 35, 000 |
| 2 | | | | 104, 300 | 17, 520 | 13, 240 | 3, 580 | 2, 010 | 2, 230 | 1, 810 | 970 | 25, 300 |
| 3 | | | | 77, 000 | 22, 940 | 11, 820 | 3, 580 | 2, 010 | 2, 010 | 1, 810 | 970 | 1, 440 |
| 4 | | | | 50, 800 | 32, 800 | 10, 440 | 5, 650 | 1, 810 | 1, 810 | 1, 810 | 970 | 1, 440 |
| 5 | | | | 38, 350 | 38, 700 | 9, 660 | 4, 920 | 1, 810 | 1, 810 | 1, 810 | 970 | 1, 440 |
| 6 | | | | 25, 000 | 33, 100 | 8, 920 | 4, 230 | 2, 010 | 1, 620 | 1, 620 | 970 | 1, 440 |
| 7 | | | | 25, 000 | 26, 800 | 8, 460 | 3, 900 | 3, 000 | 2, 470 | 1, 620 | 970 | 1, 440 |
| 8 | | | | 26, 200 | 34, 700 | 8, 000 | 3, 580 | 3, 580 | 1, 810 | 1, 440 | 970 | 1, 440 |
| 9 | | 42, 000 | | 23, 530 | 42, 400 | 7, 780 | 3, 580 | 3, 580 | 1, 620 | 1, 120 | 970 | 1, 440 |
| 10 | | 43, 800 | | 22, 940 | 39, 900 | 7, 550 | 3, 580 | 3, 000 | 1, 620 | 1, 270 | 970 | 1, 440 |
| 11 | | 28, 000 | | 27, 400 | 31, 900 | 7, 100 | 4, 230 | 2, 470 | 1, 440 | 1, 120 | 970 | 1, 620 |
| 12 | | 29, 100 | | 25, 600 | 25, 000 | 7, 530 | 4, 230 | 2, 470 | 1, 440 | 1, 120 | 970 | 1, 620 |
| 13 | | 39, 500 | | 20, 940 | 20, 370 | 8, 230 | 4, 920 | 2, 230 | 1, 270 | 1, 120 | 970 | 1, 810 |
| 14 | | 41, 100 | | 16, 660 | 19, 230 | 8, 690 | 4, 920 | 2, 010 | 1, 440 | 1, 120 | 970 | 2, 230 |
| 15 | | 56, 300 | | 14, 100 | 20, 370 | 7, 780 | 7, 330 | 2, 010 | 1, 440 | 1, 120 | 1, 120 | 2, 230 |
| 16 | | 48, 600 | | 12, 390 | 22, 370 | 7, 780 | 5, 650 | 2, 010 | 1, 270 | 1, 120 | 1, 120 | 2, 230 |
| 17 | | 32, 200 | | 11, 250 | 20, 660 | 6, 880 | 4, 570 | 2, 010 | 1, 270 | 970 | 1, 120 | 2, 470 |
| 18 | | 26, 200 | | 12, 390 | 24, 400 | 7, 330 | 3, 900 | 2, 010 | 1, 270 | 970 | 1, 120 | 2, 470 |
| 19 | | 16, 950 | | 13, 240 | 42, 400 | 7, 330 | 3, 900 | 2, 010 | 1, 120 | 970 | 1, 120 | 2, 470 |
| 20 | | | 12, 960 | 13, 530 | 50, 000 | 9, 660 | 3, 580 | 2, 010 | 1, 120 | 970 | 1, 120 | 2, 470 |
| 21 | | 39, 500 | | 11, 250 | 30, 000 | 43, 400 | 9, 660 | 3, 280 | 1, 810 | 1, 270 | 970 | 2, 470 |
| 22 | | 72, 300 | | 18, 370 | 35, 400 | 36, 400 | 8, 230 | 3, 000 | 2, 230 | 1, 270 | 970 | 2, 470 |
| 23 | | 64, 000 | | 66, 200 | 30, 000 | 31, 000 | 7, 330 | 2, 720 | 2, 010 | 1, 120 | 830 | 1, 270 |
| 24 | | 42, 000 | | 81, 800 | 26, 800 | 32, 500 | 6, 450 | 2, 720 | 1, 810 | 1, 120 | 830 | 1, 620 |
| 25 | | 29, 100 | | 54, 800 | 26, 800 | 38, 700 | 6, 040 | 3, 000 | 1, 620 | 2, 010 | 830 | 2, 010 |
| 26 | | 23, 240 | | 36, 400 | 28, 200 | 32, 800 | 6, 040 | 2, 720 | 2, 010 | 1, 620 | 970 | 1, 810 |
| 27 | | 21, 220 | | 23, 530 | 24, 110 | 26, 800 | 5, 280 | 2, 470 | 3, 900 | 1, 810 | 970 | 1, 620 |
| 28 | | 20, 370 | | 15, 520 | 21, 510 | 22, 370 | 4, 570 | 2, 470 | 3, 280 | 1, 620 | 970 | 1, 620 |
| 29 | | 17, 520 | | | 17, 800 | 19, 230 | 4, 570 | 2, 230 | 2, 720 | 1, 440 | 970 | 1, 620 |
| 30 | | 17, 520 | | | 18, 090 | 16, 660 | 4, 230 | 2, 230 | 2, 230 | 1, 440 | 970 | 1, 440 |
| 31 | | | | 16, 660 | | 3, 900 | | 2, 230 | 1, 440 | | 1, 440 | 20, 370 |

Mean daily discharge, in second-feet, of Susquehanna River at Danville, Pa., 1899-1903—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|--------|--------|---------|---------|---------|--------|--------|--------|--------|--------|--------|---------|
| 1901. | | | | | | | | | | | | |
| 1 | 16,950 | | | 33,400 | 22,370 | 83,000 | 6,450 | 4,920 | 10,700 | 5,650 | 3,580 | 8,230 |
| 2 | 34,100 | | | 28,200 | 19,230 | 37,000 | 6,450 | 3,900 | 13,530 | 5,650 | 3,580 | 7,330 |
| 3 | | | | 25,600 | 21,510 | 41,600 | 5,280 | 3,000 | 12,390 | 7,100 | 3,280 | 7,330 |
| 4 | | | | 28,000 | 28,000 | 37,600 | 4,570 | 2,720 | 12,390 | 8,000 | 3,280 | 10,440 |
| 5 | | | | 34,400 | 26,500 | 32,200 | 4,230 | 2,720 | 9,160 | 7,100 | 3,280 | 18,370 |
| 6 | | | | 39,500 | 22,370 | 26,200 | 4,230 | 2,720 | 8,920 | 6,450 | 3,000 | 29,700 |
| 7 | | | | 34,100 | 18,940 | 23,240 | 4,230 | 3,000 | 7,550 | 5,650 | 3,000 | 32,200 |
| 8 | | | | 33,800 | 14,950 | 26,200 | 6,040 | 3,580 | 6,450 | 4,920 | 2,720 | 34,700 |
| 9 | | | | 29,100 | 14,670 | 28,000 | 5,650 | 4,230 | 5,650 | 4,570 | 2,720 | 37,300 |
| 10 | | | | 27,100 | 21,510 | 27,700 | 5,280 | 3,580 | 5,100 | 4,570 | 2,720 | 40,700 |
| 11 | | | | 25,000 | 12,960 | 24,400 | 4,920 | 5,650 | 4,790 | 4,230 | 2,720 | 42,900 |
| 12 | | | | 22,940 | 16,950 | 20,940 | 4,920 | 4,920 | 4,230 | 3,900 | 2,720 | 45,200 |
| 13 | | | 64,600 | 22,510 | 22,080 | 16,380 | 4,570 | 3,900 | 3,900 | 3,580 | 3,280 | 36,000 |
| 14 | | | 33,400 | 34,100 | 30,000 | 14,100 | 4,230 | 3,580 | 4,060 | 7,330 | 3,580 | 29,700 |
| 15 | | | 28,000 | 31,300 | 29,400 | 12,960 | 3,900 | 3,280 | 3,900 | 7,100 | 3,900 | 96,300 |
| 16 | | | 26,200 | 29,100 | 24,700 | 12,670 | 3,580 | 3,280 | 4,230 | 7,330 | 5,460 | 228,400 |
| 17 | | | 26,800 | 27,100 | 20,370 | 10,700 | 3,580 | 3,280 | 4,230 | 7,330 | 7,330 | 180,300 |
| 18 | | | 23,820 | 25,000 | 17,520 | 10,700 | 3,900 | 22,080 | 5,280 | 7,330 | 7,330 | 86,000 |
| 19 | | | 22,080 | 22,940 | 17,520 | 9,920 | 4,230 | 29,400 | 5,650 | 6,880 | 6,040 | 47,200 |
| 20 | | | 22,080 | 21,510 | 16,950 | 8,230 | 3,900 | 16,380 | 5,650 | 7,330 | 5,650 | 32,200 |
| 21 | | | 38,350 | 23,820 | 18,370 | 7,780 | 3,580 | 10,440 | 6,040 | 6,040 | 5,650 | 25,000 |
| 22 | | | 63,000 | 71,200 | 17,230 | 7,330 | 3,280 | 11,540 | 6,040 | 5,650 | 5,650 | 18,090 |
| 23 | | | 72,300 | 104,300 | 14,950 | 7,330 | 3,000 | 20,370 | 5,280 | 5,280 | 5,280 | 15,530 |
| 24 | | | 57,800 | 72,000 | 15,240 | 8,920 | 2,720 | 31,000 | 5,280 | 4,920 | 5,280 | 11,540 |
| 25 | | | 56,800 | 65,100 | 21,800 | 14,950 | 2,720 | 54,300 | 4,230 | 4,920 | 6,450 | 11,540 |
| 26 | | | 55,800 | 61,400 | 26,800 | 11,250 | 2,720 | 38,350 | 3,900 | 4,570 | 19,520 | 12,670 |
| 27 | | | 80,000 | 50,800 | 23,820 | 9,920 | 2,720 | 27,700 | 3,580 | 4,230 | 24,400 | 13,530 |
| 28 | | | 129,600 | 36,000 | 20,940 | 8,230 | 2,720 | 19,520 | 3,280 | 4,230 | 17,800 | 12,960 |
| 29 | | | 127,300 | 31,900 | 30,300 | 7,100 | 2,470 | 14,950 | 3,580 | 3,900 | 12,670 | 14,100 |
| 30 | | | 80,000 | 26,500 | 72,300 | 6,880 | 3,000 | 11,250 | 4,570 | 3,900 | 9,410 | 25,300 |
| 31 | | | 49,000 | | 100,300 | | 3,580 | 9,660 | | 3,580 | | 23,240 |
| 1902 | | | | | | | | | | | | |
| 1 | 22,080 | 12,100 | 191,600 | 29,400 | 9,660 | 5,650 | 19,230 | 28,500 | 4,230 | 36,400 | 24,700 | 9,160 |
| 2 | 19,800 | 13,240 | 267,600 | 28,000 | 9,160 | 5,280 | 36,400 | 28,800 | 3,900 | 37,600 | 20,370 | 8,690 |
| 3 | 15,240 | | 304,800 | 26,800 | 8,690 | 4,920 | 26,800 | 34,700 | 3,900 | 37,000 | 17,520 | 8,690 |
| 4 | 15,810 | | 222,000 | 25,000 | 8,690 | 4,920 | 23,820 | 31,600 | 3,580 | 28,200 | 15,520 | 10,700 |
| 5 | 22,660 | | 148,500 | 22,370 | 8,690 | 4,920 | 23,820 | 25,600 | 3,580 | 22,940 | 14,100 | 11,250 |
| 6 | | | 94,300 | 21,220 | 8,230 | 4,570 | 23,820 | 22,940 | 3,280 | 23,240 | 12,960 | 12,390 |
| 7 | | | 51,800 | 20,370 | 7,780 | 4,570 | 33,400 | 17,800 | 3,280 | 21,510 | 12,100 | 12,390 |
| 8 | | | 33,800 | 21,510 | 7,780 | 7,330 | 63,500 | 15,520 | 3,280 | 19,230 | 11,250 | 11,820 |
| 9 | 50,400 | | 32,500 | 26,200 | 7,330 | 6,450 | 49,000 | 14,100 | 3,000 | 16,380 | 11,250 | 11,250 |
| 10 | 39,900 | | 37,300 | 63,500 | 6,880 | 5,650 | 29,400 | 12,960 | 3,580 | 14,100 | 10,170 | 9,160 |
| 11 | 37,300 | | 47,200 | 77,000 | 6,880 | 5,650 | 25,900 | 11,250 | 3,900 | 12,390 | 9,160 | 8,690 |
| 12 | 38,700 | | 59,800 | 56,300 | 6,450 | 6,040 | 29,100 | 10,700 | 4,230 | 15,240 | 8,690 | 9,160 |
| 13 | | | 89,600 | 42,400 | 6,040 | 5,650 | 29,700 | 10,170 | 3,900 | 18,660 | 8,230 | 9,660 |
| 14 | | | 117,000 | 34,400 | 5,650 | 5,650 | 25,600 | 10,170 | 4,230 | 16,380 | 7,780 | 12,960 |
| 15 | | | 108,400 | 28,500 | 5,650 | 6,040 | 16,200 | 9,660 | 4,230 | 14,380 | 7,330 | 21,510 |
| 16 | | | 87,200 | 24,700 | 5,280 | 6,040 | 13,810 | 9,160 | 3,900 | 13,530 | 7,330 | 29,100 |
| 17 | | | 91,000 | 22,080 | 4,920 | 6,450 | 12,100 | 8,230 | 3,580 | 13,530 | 7,330 | 39,500 |
| 18 | | | 123,600 | 20,660 | 4,920 | 8,230 | 10,700 | 6,880 | 3,280 | 12,960 | 6,880 | 47,600 |
| 19 | | | 109,100 | 19,520 | 4,570 | 7,780 | 9,660 | 6,450 | 3,000 | 11,250 | 6,450 | 50,400 |
| 20 | | | 73,500 | 18,090 | 4,230 | 6,880 | 9,660 | 6,040 | 2,720 | 10,170 | 6,040 | 39,500 |
| 21 | | | 53,800 | 15,520 | 4,230 | 6,880 | 14,670 | 5,650 | 2,720 | 8,690 | 6,040 | 35,400 |
| 22 | | | 36,000 | 14,670 | 4,230 | 6,450 | 63,500 | 5,650 | 2,720 | 8,230 | 6,040 | 72,300 |
| 23 | | | 30,300 | 13,530 | 3,900 | 6,040 | 64,600 | 5,280 | 2,720 | 8,690 | 5,650 | 98,300 |
| 24 | 39,900 | | 20,940 | 12,390 | 3,900 | 5,650 | 57,300 | 5,280 | 2,470 | 9,160 | 5,650 | 93,000 |
| 25 | 33,400 | | 25,600 | 11,250 | 4,570 | 5,650 | 53,300 | 5,280 | 2,720 | 8,690 | 5,650 | 62,500 |
| 26 | 26,800 | | 25,000 | 10,170 | 4,920 | 6,040 | 63,500 | 4,920 | 11,540 | 7,780 | 6,040 | 42,400 |
| 27 | 23,820 | | 24,700 | 9,160 | 4,570 | 6,450 | 46,700 | 4,570 | 23,530 | 16,380 | 6,880 | 32,800 |
| 28 | 22,940 | 84,800 | 22,370 | 8,230 | 4,920 | 6,450 | 32,200 | 4,570 | 19,800 | 36,000 | 7,330 | 28,000 |
| 29 | 20,940 | | 22,940 | 7,780 | 5,650 | 5,650 | 30,300 | 4,570 | 18,940 | 42,000 | 7,780 | 23,240 |
| 30 | 19,800 | | 31,300 | 9,160 | 6,880 | 8,690 | 38,700 | 4,230 | 30,000 | 39,100 | 8,690 | 20,370 |
| 31 | 16,200 | | 32,200 | | 6,450 | | 31,600 | 4,230 | | 31,600 | | 16,950 |

Mean daily discharge, in second-feet, of Susquehanna River at Danville, Pa., 1899—1903—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|-------|--------|---------|---------|--------|-------|--------|--------|--------|--------|---------|--------|
| 1903. | | | | | | | | | | | | |
| 1. | ----- | 85,400 | 120,600 | 33,400 | 8,230 | 3,000 | 21,510 | 8,230 | 60,400 | 3,900 | 11,820 | 7,780 |
| 2. | ----- | 68,900 | 138,900 | 42,900 | 7,780 | 2,720 | 18,660 | 7,330 | 43,400 | 3,580 | 10,700 | 10,700 |
| 3. | ----- | 46,700 | 93,000 | 36,000 | 6,880 | 2,720 | 16,200 | 7,330 | 30,300 | 3,580 | 10,170 | 13,530 |
| 4. | ----- | 56,300 | 60,400 | 29,100 | 6,450 | 2,720 | 14,670 | 6,450 | 23,820 | 3,580 | 9,660 | 10,700 |
| 5. | ----- | 26,200 | 87,800 | 41,100 | 28,000 | 6,450 | 2,470 | 12,960 | 8,460 | 18,940 | 3,580 | 9,160 |
| 6. | ----- | 31,600 | 103,600 | 34,700 | 32,200 | 6,040 | 2,470 | 11,250 | 12,100 | 16,380 | 3,900 | 8,230 |
| 7. | ----- | 26,800 | 62,500 | 38,000 | 28,000 | 5,650 | 2,470 | 11,250 | 22,660 | 13,530 | 3,900 | 8,230 |
| 8. | ----- | 22,080 | 42,000 | 41,100 | 25,600 | 5,650 | 3,280 | 21,510 | 21,220 | 12,390 | 5,280 | 8,690 |
| 9. | ----- | 18,660 | 29,100 | 48,600 | 55,400 | 5,280 | 3,580 | 14,670 | 18,660 | 10,170 | 11,250 | 9,160 |
| 10. | ----- | 16,950 | 24,400 | 101,000 | 38,700 | 4,920 | 3,280 | 10,700 | 16,380 | 9,160 | 70,000 | 9,160 |
| 11. | ----- | 39,500 | 25,600 | 94,300 | 55,400 | 4,920 | 3,000 | 7,780 | 12,960 | 8,690 | 123,600 | 8,230 |
| 12. | ----- | ----- | 25,000 | 101,000 | 29,700 | 4,570 | 5,280 | 7,780 | 12,390 | 9,160 | 129,600 | 7,780 |
| 13. | ----- | ----- | 26,800 | 98,300 | 28,500 | 4,230 | 8,230 | 7,330 | 10,700 | 9,160 | 106,300 | 6,880 |
| 14. | ----- | ----- | 33,400 | 73,500 | 26,200 | 4,230 | 12,960 | 6,040 | 11,250 | 11,250 | 60,400 | 6,880 |
| 15. | ----- | ----- | 35,400 | 58,300 | 31,000 | 4,230 | 18,090 | 5,650 | 9,160 | 9,160 | 36,400 | 6,450 |
| 16. | ----- | ----- | 31,000 | 41,100 | 57,800 | 4,230 | 16,660 | 5,280 | 9,160 | 7,780 | 28,000 | 7,330 |
| 17. | ----- | ----- | 24,400 | 34,700 | 54,800 | 3,900 | 12,960 | 4,920 | 8,230 | 6,880 | 23,240 | 7,330 |
| 18. | ----- | ----- | 22,080 | 28,000 | 37,000 | 3,900 | 10,700 | 4,570 | 7,330 | 9,160 | 27,400 | 28,800 |
| 19. | ----- | ----- | 16,950 | 28,000 | 26,000 | 3,900 | 8,920 | 7,330 | 6,450 | 9,160 | 36,700 | 45,700 |
| 20. | ----- | ----- | 18,660 | 26,800 | 25,000 | 3,580 | 8,460 | 10,170 | 5,650 | 7,330 | 46,700 | 29,100 |
| 21. | ----- | ----- | ----- | 24,400 | 20,940 | 3,580 | 7,780 | 9,660 | 5,650 | 8,230 | 39,500 | 27,400 |
| 22. | ----- | ----- | ----- | 23,240 | 18,090 | 3,580 | 9,160 | 10,170 | 7,100 | 7,330 | 31,600 | 23,240 |
| 23. | ----- | ----- | ----- | 30,300 | 15,810 | 3,900 | 20,940 | 9,660 | 10,170 | 6,880 | 25,600 | 17,520 |
| 24. | ----- | ----- | ----- | 112,700 | 14,670 | 3,900 | 24,110 | 8,230 | 8,690 | 6,450 | 21,510 | 15,810 |
| 25. | ----- | ----- | ----- | 146,100 | 12,960 | 3,580 | 28,800 | 6,880 | 7,330 | 5,280 | 18,660 | 14,100 |
| 26. | ----- | ----- | ----- | 104,300 | 11,820 | 3,580 | 29,100 | 14,670 | 6,450 | 4,920 | 16,380 | 12,960 |
| 27. | ----- | ----- | ----- | 73,500 | 11,250 | 3,280 | 33,800 | 12,390 | 5,650 | 4,570 | 15,240 | 11,820 |
| 28. | ----- | ----- | 52,800 | 51,300 | 10,170 | 3,000 | 23,820 | 8,230 | 6,450 | 4,570 | 14,100 | 11,250 |
| 29. | ----- | ----- | ----- | 38,700 | 9,660 | 3,280 | 23,240 | 6,880 | 13,810 | 4,570 | 12,960 | 9,160 |
| 30. | ----- | ----- | ----- | 32,200 | 8,690 | 3,280 | 26,200 | 6,880 | 51,800 | 3,900 | 11,820 | 8,690 |
| 31. | ----- | ----- | ----- | 29,100 | ----- | 3,000 | ----- | 6,880 | 96,300 | ----- | 11,820 | ----- |

Estimated monthly discharge of Susquehanna River at Danville, Pa., 1899-1903.

[Drainage area, 11,070 square miles.]

| Month. | Discharge in second-feet. | | | Run-off. | |
|-----------------------|---------------------------|----------|--------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1899. | | | | | |
| March (25-31) ----- | 44,800 | 26,200 | 31,663 | 2.860 | 0.744 |
| April ----- | 60,400 | 13,530 | 31,048 | 2.804 | 3.128 |
| May ----- | 11,820 | 4,570 | 7,293 | .659 | .760 |
| June ----- | 6,450 | 2,470 | 3,579 | .323 | .360 |
| July ----- | 4,570 | 2,010 | 2,710 | .245 | .282 |
| August ----- | 5,650 | 1,440 | 2,121 | .192 | .221 |
| September ----- | 3,280 | 1,120 | 1,940 | .175 | .195 |
| October ----- | 1,620 | 1,120 | 1,371 | .124 | .143 |
| November ----- | 19,230 | 1,620 | 7,828 | .707 | .789 |
| December (1-30) ----- | 29,100 | 3,580 | 13,798 | 1.246 | 1.390 |
| The period ----- | 60,400 | 1,120 | 10,335 | .934 | 8.012 |

Estimated monthly discharge of Susquehanna River at Danville, Pa., 1899-1903.

| Month. | Discharge in second-feet. | | | Run-off. | |
|---|---------------------------|----------|--------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1900. | | | | | |
| January (21-31) ^a | 72,300 | 17,520 | 34,677 | 3.132 | 1.165 |
| February (9-28) ^a | 81,800 | 11,250 | 36,229 | 3.273 | 2.434 |
| March | 104,300 | 11,250 | 27,861 | 2.517 | 2.902 |
| April | 50,000 | 16,380 | 29,393 | 2.655 | 2.962 |
| May | 14,950 | 3,900 | 7,911 | .715 | .824 |
| June | 7,330 | 2,230 | 3,819 | .345 | .385 |
| July | 3,900 | 1,620 | 2,320 | .210 | .242 |
| August | 2,470 | 1,120 | 1,564 | .141 | .162 |
| September | 1,810 | 830 | 1,200 | .108 | .120 |
| October | 2,010 | 970 | 1,184 | .107 | .123 |
| November | 123,600 | 1,440 | 11,109 | 1.004 | 1.120 |
| December (1-16 and 26-31) ^a .. | 41,600 | 12,960 | 24,352 | 2.191 | 1.793 |
| The year | 123,600 | 830 | 15,127 | 1.366 | 13.989 |
| 1901. | | | | | |
| January (1-2) ^a | 34,100 | 16,950 | 25,525 | 2.306 | 0.172 |
| February ^a | | | | | |
| March (12-31) ^a | 129,600 | 22,080 | 55,636 | 5.026 | 3.735 |
| April | 104,300 | 21,510 | 37,287 | 3.368 | 3.758 |
| May | 100,300 | 12,960 | 25,179 | 2.274 | 2.622 |
| June | 83,000 | 6,880 | 19,781 | 1.787 | 1.994 |
| July | 6,450 | 2,470 | 4,085 | .369 | .425 |
| August | 54,300 | 2,720 | 12,232 | 1.105 | 1.274 |
| September | 13,530 | 3,280 | 6,118 | .553 | .617 |
| October | 8,000 | 3,580 | 5,588 | .505 | .582 |
| November | 24,400 | 2,720 | 6,376 | .576 | .643 |
| December | 228,400 | 7,330 | 39,769 | 3.592 | 4.141 |
| The year | 228,400 | 2,470 | 19,798 | 1.788 | 19.963 |

^a River frozen, for days not included.

*Estimated monthly discharge of Susquehanna River at Danville, Pa., 1899-^a
1903—Continued.*

| Month. | Discharge in second-feet. | | | Run-off. | |
|---|---------------------------|----------|--------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1902. | | | | | |
| January (1-5, 9-12, 23-31) ^a | 50,400 | 15,240 | 27,594 | 2.493 | 1.669 |
| February (1-2, 28) ^a | 84,800 | 12,100 | 36,713 | 3.316 | .370 |
| March | 304,800 | 20,940 | 84,379 | 7.622 | 8.787 |
| April | 77,000 | 7,780 | 24,663 | 2.228 | 2.486 |
| May | 9,660 | 3,900 | 6,184 | .559 | .644 |
| June | 8,690 | 4,570 | 6,087 | .550 | .614 |
| July | 64,600 | 9,660 | 32,516 | 2.937 | 3.386 |
| August | 34,700 | 4,230 | 12,112 | 1.094 | 1.261 |
| September | 30,000 | 2,470 | 6,325 | .571 | .637 |
| October | 42,000 | 7,780 | 19,723 | 1.782 | 2.054 |
| November | 24,700 | 5,650 | 9,697 | .876 | .977 |
| December | 98,300 | 8,690 | 28,995 | 2.619 | 3.019 |
| The year | 304,800 | 2,470 | 24,582 | 2.221 | 25.904 |
| 1903. | | | | | |
| January (4-11, 31) ^a | 98,300 | 16,950 | 33,574 | 3.033 | 1.015 |
| February (1-20, 28) ^a | 103,600 | 16,950 | 43,752 | 3.952 | 3.086 |
| March | 146,100 | 23,240 | 63,459 | 5.732 | 6.608 |
| April | 57,800 | 8,690 | 27,165 | 2.454 | 2.728 |
| May | 8,230 | 3,000 | 4,612 | .417 | .481 |
| June | 33,800 | 2,470 | 12,031 | 1.087 | 1.213 |
| July | 21,510 | 4,570 | 10,347 | .935 | 1.081 |
| August | 96,300 | 5,650 | 14,242 | 1.286 | 1.483 |
| September | 60,400 | 3,900 | 12,764 | 1.153 | 1.286 |
| October | 129,600 | 3,580 | 30,648 | 2.768 | 3.191 |
| November | 45,700 | 6,450 | 13,380 | 1.209 | 1.349 |
| December (1-5) | 13,500 | 7,780 | 10,098 | .912 | .170 |
| The year | 146,100 | 2,470 | 23,006 | 2.078 | 23.701 |

^aRiver frozen, for days not included.

WEST BRANCH OF SUSQUEHANNA RIVER AT WILLIAMSPORT, PA.

This station was established March 1, 1895, by George D. Snyder, who was at that time city engineer. On August 16, 1901, a standard chain gage was installed on the upper side of the Market Street Bridge. It is read once each day by Henry H. Guise, who is employed in the city engineer's office. The length of the chain from the end of the weight to the marker is 40.29 feet. Discharge measurements are made from the lower side of the Market street iron highway bridge. The initial point for soundings is the face of the abutment on the left bank. The channel is straight for several hundred feet above and below the station, is broken by four bridge piers, and is about 1,000 feet wide at the station. There is a dam about one-half mile above the station. Both banks are high and rocky. The bed of the stream is composed of gravel and silt, and will probably change to some extent in the shore spans. The current velocity is sufficient for accurate measurement, except at extreme low stages. The bench mark is a cut in the face of the left abutment 10.07 feet above gage datum.

Discharge measurements of West Branch of Susquehanna River at Williamsport, Pa., 1901-1904.

| Date. | Hydrographer. | Gage height. | Area of section. | Mean velocity. | Dis-charge. |
|----------|--------------------|--------------|------------------|---------------------|--------------------|
| 1901. | | <i>Feet.</i> | <i>Sq. feet.</i> | <i>Ft. per sec.</i> | <i>Sec.-feet.</i> |
| Aug. 16 | E. G. Paul | 0.90 | 2,851 | 0.68 | 1,932 |
| Oct. 25 | do | .66 | 2,510 | .72 | 1,807 ² |
| 1902. | | | | | |
| Apr. 20 | E. G. Paul | 3.90 | 5,188 | 1.80 | 9,318 |
| Sept. 18 | do | .41 | 1,997 | .54 | 1,006 |
| 1903. | | | | | |
| Mar. 6 | E. C. Murphy | 7.12 | 8,629 | 2.80 | 24,138 |
| Apr. 3 | do | 5.24 | 6,840 | 2.14 | 14,675 |
| June 4 | J. C. Hoyt | .85 | 2,769 | .70 | 1,954 |
| June 27 | E. D. Walker | 6.40 | 9,130 | 2.22 | 20,400 |
| Oct. 7 | W. C. Sawyer | 1.77 | 3,270 | 1.08 | 3,525 |
| 1904. | | | | | |
| July 19 | R. J. Taylor | 2.07 | 3,874 | 1.09 | 4,220 |
| Sept. 14 | J. C. Hoyt | 0.52 | 2,550 | 0.53 | 1,340 |
| Sept. 30 | do | 1.10 | 3,040 | 0.67 | 2,060 |

Mean daily gage height, in feet, of West Branch of Susquehanna River at Williamsport, Pa., 1895-1904.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|------|------|------|------|------|-------|-------|------|-------|------|------|------|
| 1895. | | | | | | | | | | | | |
| 1 | | | 8.0 | 6.0 | 2.1 | 2.4 | 4.5 | 0.3 | 0.4 | 0.1 | -0.1 | 1.5 |
| 2 | | | 9.0 | 6.0 | 1.9 | 2.1 | 3.7 | .2 | .4 | .1 | - .1 | 1.6 |
| 3 | | | 10.5 | 7.2 | 1.9 | 1.9 | 3.0 | .2 | .3 | .2 | .0 | 1.5 |
| 4 | | | 9.5 | 6.5 | 1.9 | 1.8 | 2.3 | .1 | .3 | .3 | .0 | 1.4 |
| 5 | | | 9.0 | 5.8 | 1.8 | 1.5 | 1.7 | .1 | .2 | .3 | - .1 | 1.4 |
| 6 | | | 6.5 | 5.4 | 1.8 | 1.5 | 1.5 | .0 | .2 | .2 | - .1 | 1.3 |
| 7 | | | 4.5 | 6.0 | 1.6 | 1.4 | 1.5 | .0 | .1 | .1 | .0 | 1.0 |
| 8 | | | 4.5 | 7.0 | 2.2 | 1.2 | 1.3 | .3 | .0 | .2 | + | 1.1 |
| 9 | | | 5.0 | 11.0 | 2.9 | .8 | 1.2 | .3 | .0 | .2 | .1 | 1.1 |
| 10 | | | 5.2 | 12.0 | 3.2 | .5 | 1.6 | .3 | .3 | .1 | .3 | 1.0 |
| 11 | | | 5.3 | 11.0 | 2.8 | .4 | 1.5 | .4 | 1.6 | .1 | .3 | 1.0 |
| 12 | | | 5.5 | 7.9 | 2.7 | .2 | 1.5 | .7 | 1.8 | .2 | .4 | .9 |
| 13 | | | 5.5 | 6.5 | 2.8 | .2 | 1.6 | 1.8 | .9 | .2 | .4 | .8 |
| 14 | | | 5.2 | 8.0 | 4.3 | .4 | 1.5 | 1.5 | .7 | .2 | .3 | .6 |
| 15 | | | 6.0 | 10.5 | 3.8 | .8 | 1.4 | .5 | .5 | .2 | .3 | .4 |
| 16 | | | 6.5 | 8.5 | 3.3 | .8 | 1.3 | .6 | .4 | .3 | .2 | .3 |
| 17 | | | 5.5 | 6.0 | 3.0 | .7 | 1.2 | .7 | .6 | .2 | .2 | .3 |
| 18 | | | 4.7 | 5.3 | 2.8 | .7 | 1.1 | .9 | .1 | .2 | .2 | .3 |
| 19 | | | 4.7 | 5.3 | 2.6 | .6 | 1.0 | 1.1 | .2 | .2 | .2 | .2 |
| 20 | | | 4.5 | 5.3 | 2.8 | .6 | .8 | 1.1 | .2 | .2 | .3 | .2 |
| 21 | | | 4.2 | 4.5 | 2.2 | .6 | .7 | 1.1 | .1 | .2 | .3 | .2 |
| 22 | | | 4.5 | 3.6 | 2.0 | .4 | .9 | 1.2 | .0 | .2 | .3 | 1.6 |
| 23 | | | 5.0 | 3.4 | 1.9 | 1.0 | .8 | 1.3 | - .1 | .2 | .2 | 2.4 |
| 24 | | | 5.5 | 3.2 | 1.8 | 1.4 | .8 | 1.4 | - .2 | .1 | .2 | 2.6 |
| 25 | | | 6.0 | 2.9 | 1.7 | 1.7 | .9 | 1.4 | - .2 | .0 | .4 | 2.4 |
| 26 | | | 8.7 | 2.6 | 1.7 | 1.3 | 1.0 | 1.5 | - .2 | - .1 | .5 | 2.2 |
| 27 | | | 9.2 | 2.6 | 2.0 | 1.7 | - .2 | 1.3 | - .1 | - .1 | 2.9 | 2.4 |
| 28 | | | 7.7 | 2.5 | 3.5 | 6.2 | .0 | 1.3 | - .1 | - .1 | 3.1 | 7.0 |
| 29 | | | 6.7 | 2.5 | 3.6 | 4.9 | + | 1.3 | .0 | - .1 | 2.3 | 6.5 |
| 30 | | | 6.5 | 2.2 | 3.2 | 4.0 | .1 | 1.4 | + | - .1 | 2.1 | 4.5 |
| 31 | | | 6.3 | | 3.0 | | .4 | 1.4 | | - .2 | | 5.4 |
| 1896. | | | | | | | | | | | | |
| 1 | 6.8 | 1.9 | 6.5 | 13.0 | 3.5 | 1.8 | 3.1 | 6.5 | .5 | 6.8 | 2.3 | 4.0 |
| 2 | 4.5 | 2.0 | 6.6 | 11.0 | 3.4 | 2.0 | 2.7 | 6.7 | .4 | 6.8 | 2.3 | 3.8 |
| 3 | 4.1 | 2.4 | 6.1 | 10.0 | 3.1 | 1.7 | 2.3 | 6.9 | .4 | 5.8 | 2.3 | 3.3 |
| 4 | 3.8 | 4.1 | 4.7 | 8.5 | 3.0 | 1.4 | 2.0 | 5.9 | .4 | 4.5 | 2.1 | 3.1 |
| 5 | 3.5 | 4.1 | 3.9 | 7.1 | 2.8 | 1.3 | 2.3 | 4.8 | .4 | 3.2 | 2.5 | 2.9 |
| 6 | 3.3 | 3.9 | 4.1 | 6.1 | 2.6 | 1.2 | 2.4 | 4.0 | .5 | 1.7 | 7.5 | 2.4 |
| 7 | 3.1 | 10.8 | 4.0 | 5.8 | 2.4 | 1.4 | 2.3 | 3.5 | .5 | 1.5 | 6.9 | 2.0 |
| 8 | 2.9 | 9.2 | 3.9 | 5.6 | 2.3 | 1.6 | 2.1 | 3.7 | .6 | 1.3 | 6.2 | 1.7 |
| 9 | 2.4 | 6.8 | 3.9 | 5.1 | 2.2 | 2.6 | 2.0 | 3.2 | .7 | .9 | 5.4 | 3.2 |
| 10 | 2.4 | 6.1 | 3.8 | 4.7 | 2.1 | 5.3 | 3.3 | 2.9 | .6 | .8 | 4.5 | 4.4 |
| 11 | 2.3 | 5.3 | 3.6 | 4.8 | 1.9 | 4.3 | 3.0 | 2.7 | .4 | .8 | 4.3 | 5.0 |
| 12 | 2.1 | 4.3 | 3.1 | 5.3 | 1.9 | 3.4 | 2.6 | 2.5 | .4 | .7 | 3.9 | 4.2 |
| 13 | 2.0 | 4.1 | 2.4 | 5.7 | 1.6 | 2.9 | 2.2 | 2.2 | .4 | 9.8 | 4.0 | 4.0 |
| 14 | 2.0 | 3.7 | 2.7 | 7.8 | 1.6 | 2.5 | 1.9 | 2.5 | .4 | 10.8 | 4.0 | 3.5 |
| 15 | 1.8 | 3.7 | 2.4 | 8.3 | 1.5 | 2.2 | 1.7 | 2.3 | .5 | 9.8 | 3.6 | 3.3 |
| 16 | 1.7 | 4.6 | 2.0 | 7.5 | 1.5 | 2.2 | 1.8 | 2.1 | .6 | 8.2 | 3.1 | 3.2 |
| 17 | 1.5 | 4.3 | 2.4 | 6.8 | 1.5 | 2.1 | 1.9 | 1.8 | .6 | 6.5 | 3.1 | 2.9 |
| 18 | 1.4 | 3.6 | 2.5 | 6.1 | 1.6 | 4.1 | 2.2 | 1.5 | .9 | 6.1 | 3.0 | 2.9 |
| 19 | 1.3 | 3.2 | 2.4 | 5.7 | 1.4 | 4.0 | 2.3 | 1.4 | .6 | 5.4 | 2.8 | 2.7 |
| 20 | 1.3 | 1.7 | 3.6 | 5.2 | 1.3 | 3.5 | 1.8 | 1.2 | 1.5 | 4.7 | 2.7 | 2.5 |
| 21 | 1.4 | 1.5 | 3.8 | 4.7 | 1.4 | 3.0 | 1.6 | 1.0 | 2.0 | 4.0 | 2.7 | 2.2 |
| 22 | 1.4 | 2.2 | 3.8 | 4.7 | 1.3 | 2.6 | 1.7 | .9 | 1.6 | 3.7 | 2.7 | 2.2 |
| 23 | 1.4 | 1.9 | 4.5 | 4.5 | 1.3 | 2.4 | 1.8 | .9 | .7 | 3.6 | 2.6 | 2.1 |
| 24 | 1.6 | 2.3 | 4.2 | 4.4 | 1.1 | 2.1 | 2.0 | .8 | .6 | 3.5 | 2.6 | 2.4 |
| 25 | 2.5 | 3.2 | 4.1 | 4.1 | 1.0 | 3.5 | 2.5 | 1.0 | .3 | 3.4 | 2.8 | 2.2 |
| 26 | 2.7 | 3.1 | 4.2 | 4.2 | 1.1 | 7.0 | 3.1 | 1.0 | .3 | 3.3 | 2.8 | 2.0 |
| 27 | 2.9 | 2.3 | 4.8 | 4.1 | 1.1 | 6.2 | 3.8 | .9 | .4 | 3.2 | 2.8 | 1.8 |
| 28 | 2.9 | 2.6 | 5.6 | 3.8 | 1.2 | 5.1 | 3.9 | .6 | .5 | 3.0 | 2.8 | 1.5 |
| 29 | 2.5 | 4.0 | 7.1 | 3.7 | 1.2 | 4.4 | 5.0 | .6 | .6 | 2.7 | 3.3 | 1.3 |
| 30 | 2.2 | | 10.8 | 3.7 | 1.0 | 3.8 | 5.8 | .6 | 1.3 | 2.5 | 4.0 | 1.6 |
| 31 | 2.0 | | 13.9 | | 1.5 | | 6.8 | .5 | | 2.5 | | 1.8 |

Mean daily gage height, in feet, of West Branch of Susquehanna River at
Williamsport, Pa., 1895-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|------|-------|------|-------|------|-------|-------|------|-------|------|-------|------|
| 1897. | | | | | | | | | | | | |
| 1 | 1.9 | 1.6 | 4.0 | 4.3 | 2.6 | 1.9 | 1.0 | 3.1 | 0.7 | 0.9 | 0.4 | 4.4 |
| 2 | 2.0 | 1.5 | 3.5 | 4.0 | 3.9 | 1.8 | 1.0 | 3.0 | .7 | .9 | 1.0 | 3.8 |
| 3 | 2.1 | 1.5 | 3.1 | 3.7 | 5.2 | 1.8 | 1.0 | 2.5 | .6 | .8 | 4.8 | 3.4 |
| 4 | 2.1 | 1.5 | 5.1 | 3.4 | 8.8 | 2.4 | .9 | 2.2 | .6 | .7 | 4.1 | 3.1 |
| 5 | 2.8 | 1.5 | 7.0 | 3.2 | 8.5 | 2.3 | .9 | 2.1 | .5 | .6 | 3.1 | 4.0 |
| 6 | 3.9 | 1.5 | 7.4 | 3.3 | 7.9 | 2.0 | .7 | 2.0 | .4 | .5 | 2.7 | 4.5 |
| 7 | 3.5 | 3.7 | 10.4 | 3.6 | 7.2 | 1.7 | .7 | 2.4 | .3 | .5 | 2.3 | 5.0 |
| 8 | 3.0 | 4.1 | 9.1 | 3.8 | 6.1 | 1.6 | .7 | 2.2 | .3 | .4 | 1.9 | 4.7 |
| 9 | 3.0 | 3.9 | 7.6 | 4.0 | 5.5 | 1.6 | .7 | 2.1 | .2 | .3 | 1.8 | 4.1 |
| 10 | 3.0 | 3.7 | 6.9 | 8.0 | 4.9 | 1.8 | .8 | 1.7 | .2 | .3 | 2.0 | 3.8 |
| 11 | 3.0 | 3.5 | 7.8 | 8.8 | 4.6 | 1.8 | .8 | 1.6 | .0 | .3 | 2.1 | 3.6 |
| 12 | 3.2 | 3.6 | 8.6 | 7.8 | 4.5 | 1.7 | 1.0 | 2.0 | .0 | .3 | 2.9 | 3.8 |
| 13 | 2.9 | 3.3 | 8.8 | 6.7 | 4.4 | 1.5 | .9 | 1.9 | .1 | .4 | 2.6 | 4.0 |
| 14 | 1.8 | 3.0 | 8.6 | 5.9 | 6.5 | 1.4 | .9 | 1.7 | .1 | .5 | 2.4 | 4.1 |
| 15 | 1.7 | 2.7 | 7.7 | 5.6 | 7.4 | 1.3 | .9 | 1.5 | .1 | .5 | 2.2 | 4.8 |
| 16 | 2.2 | 2.7 | 6.7 | 6.6 | 7.1 | 1.2 | 1.0 | 1.3 | .2 | .5 | 2.1 | 7.4 |
| 17 | 2.2 | 2.7 | 6.1 | 7.8 | 6.9 | 1.1 | 1.0 | 1.1 | .3 | .4 | 2.3 | 7.7 |
| 18 | 2.2 | 2.8 | 5.1 | 6.9 | 5.4 | 1.1 | 1.1 | 1.0 | .4 | .3 | 4.9 | 6.7 |
| 19 | 2.5 | 3.6 | 5.3 | 6.1 | 4.8 | 1.1 | 1.1 | .8 | .5 | .3 | 4.5 | 6.3 |
| 20 | 2.2 | 3.6 | 5.4 | 5.4 | 4.8 | 1.3 | 1.1 | 1.0 | .5 | .3 | 3.8 | 5.9 |
| 21 | 1.4 | 3.7 | 8.3 | 4.9 | 4.6 | 1.5 | 1.1 | 1.1 | .5 | .4 | 3.4 | 5.3 |
| 22 | 1.6 | 3.9 | 8.8 | 4.4 | 4.4 | 1.2 | 1.2 | 1.0 | .6 | .5 | 3.0 | 4.9 |
| 23 | 2.0 | 5.1 | 8.5 | 4.0 | 3.8 | 1.1 | 1.2 | .9 | .7 | .6 | 2.7 | 4.6 |
| 24 | 2.2 | 8.8 | 8.8 | 3.7 | 3.2 | 1.1 | 2.0 | 3.5 | .8 | .7 | 2.5 | 3.8 |
| 25 | 2.4 | 7.8 | 11.3 | 3.4 | 3.0 | 1.1 | 2.3 | 2.8 | 2.4 | .6 | 2.3 | 3.6 |
| 26 | 2.2 | 6.3 | 10.2 | 3.1 | 2.8 | 1.2 | 2.5 | 2.2 | 2.3 | .6 | 2.0 | 3.3 |
| 27 | 2.3 | 5.2 | 8.4 | 3.1 | 2.7 | 1.2 | 2.0 | 1.5 | 2.2 | .6 | 2.5 | 3.0 |
| 28 | 1.5 | 4.3 | 7.1 | 3.0 | 2.6 | 1.2 | 3.1 | 1.2 | 2.0 | .5 | 3.5 | 3.1 |
| 29 | 1.8 | ----- | 6.2 | 2.9 | 2.4 | 1.2 | 4.6 | 1.0 | 1.7 | .5 | 5.7 | 2.4 |
| 30 | 1.9 | ----- | 5.3 | 2.7 | 2.2 | 1.0 | 4.8 | .8 | 1.1 | .4 | 5.0 | 2.0 |
| 31 | 1.8 | ----- | 4.7 | ----- | 2.0 | ----- | 3.8 | .8 | ----- | .4 | ----- | 2.2 |
| 1898. | | | | | | | | | | | | |
| 1 | 2.0 | 2.9 | 3.5 | 8.2 | 4.6 | 3.5 | 2.0 | 1.0 | 1.1 | .6 | 3.3 | 1.8 |
| 2 | 1.9 | 2.6 | 3.2 | 6.9 | 4.1 | 3.1 | 1.6 | .9 | 1.0 | .5 | 3.0 | 1.9 |
| 3 | 1.7 | 2.5 | 3.2 | 6.1 | 4.0 | 2.8 | 1.4 | 1.0 | .9 | .5 | 2.7 | 1.9 |
| 4 | 1.7 | 2.1 | 3.1 | 5.3 | 3.8 | 2.5 | 1.3 | 1.3 | .9 | .5 | 2.4 | 2.1 |
| 5 | 1.8 | 2.8 | 3.0 | 4.8 | 3.4 | 2.2 | 1.1 | 2.8 | .8 | .6 | 2.2 | 2.3 |
| 6 | 2.0 | 2.9 | 2.9 | 4.4 | 3.5 | 2.0 | 1.0 | 2.9 | .8 | 1.1 | 2.0 | 2.6 |
| 7 | 2.1 | 3.1 | 2.8 | 4.0 | 3.8 | 1.8 | .9 | 2.0 | .7 | 1.0 | 2.0 | 2.6 |
| 8 | 2.1 | 3.0 | 3.0 | 3.7 | 3.8 | 1.8 | .8 | 1.5 | .7 | 1.3 | 1.8 | 2.5 |
| 9 | 2.1 | 2.9 | 3.1 | 3.5 | 3.9 | 1.6 | .8 | 1.3 | .9 | 1.2 | 1.8 | 2.2 |
| 10 | 2.1 | 2.9 | 3.8 | 3.3 | 4.1 | 1.4 | .8 | 1.2 | 1.0 | 1.2 | 1.8 | 2.0 |
| 11 | 2.5 | 3.1 | 4.7 | 3.2 | 3.7 | 1.6 | .7 | 1.1 | .8 | 1.1 | 4.8 | 1.8 |
| 12 | 2.6 | 3.8 | 6.3 | 3.0 | 3.4 | 1.8 | .7 | 1.0 | .6 | 1.1 | 9.4 | 1.6 |
| 13 | 2.9 | 8.4 | 9.0 | 2.9 | 3.2 | 2.0 | .7 | 1.0 | .7 | 1.2 | 7.3 | 1.8 |
| 14 | 9.6 | 8.0 | 9.4 | 2.7 | 3.0 | 2.5 | .6 | 1.7 | .6 | 1.3 | 6.3 | 1.6 |
| 15 | 8.7 | 7.1 | 9.4 | 2.7 | 3.0 | 3.4 | .6 | 1.4 | .6 | 1.5 | 5.3 | 1.5 |
| 16 | 7.5 | 6.3 | 7.2 | 3.5 | 2.9 | 3.1 | .6 | 1.2 | .6 | 1.4 | 4.9 | 1.4 |
| 17 | 8.2 | 4.7 | 6.2 | 3.5 | 3.0 | 2.5 | .5 | 1.0 | .5 | 1.3 | 4.1 | 1.3 |
| 18 | 7.2 | 4.6 | 5.8 | 3.5 | 3.0 | 2.0 | .5 | 1.0 | .5 | 1.2 | 3.6 | 1.4 |
| 19 | 6.1 | 4.3 | 5.4 | 3.2 | 4.0 | 1.9 | .5 | 1.4 | .4 | 1.3 | 3.4 | 1.5 |
| 20 | 5.3 | 4.8 | 9.0 | 3.1 | 3.9 | 1.8 | .5 | 6.8 | .5 | 2.3 | 3.2 | 1.7 |
| 21 | 5.6 | 5.3 | 10.8 | 3.0 | 5.1 | 1.7 | .7 | 4.8 | .4 | 2.7 | 3.0 | 2.0 |
| 22 | 6.2 | 6.4 | 10.2 | 3.0 | 4.8 | 1.6 | .8 | 3.9 | .5 | 4.2 | 2.8 | 2.6 |
| 23 | 7.0 | 6.0 | 14.9 | 2.9 | 5.1 | 1.6 | .8 | 3.0 | .4 | 9.0 | 2.7 | 5.3 |
| 24 | 9.9 | 5.3 | 21.0 | 4.0 | 5.1 | 1.4 | .7 | 2.5 | .4 | 8.9 | 2.6 | 8.3 |
| 25 | 9.3 | 5.0 | 14.8 | 7.7 | 6.0 | 1.3 | .7 | 2.1 | .4 | 7.0 | 2.4 | 7.3 |
| 26 | 7.6 | 4.6 | 10.4 | 8.7 | 6.3 | 1.2 | .7 | 2.1 | .5 | 5.0 | 2.3 | 6.3 |
| 27 | 6.8 | 4.2 | 9.6 | 8.2 | 5.6 | 1.1 | 1.9 | 1.9 | .5 | 4.7 | 2.1 | 5.3 |
| 28 | 6.0 | 3.8 | 7.1 | 6.4 | 5.3 | 1.0 | 1.9 | 1.8 | .6 | 5.0 | 1.9 | 4.7 |
| 29 | 6.3 | ----- | 6.3 | 5.7 | 4.8 | 2.1 | 1.3 | 1.7 | .5 | 4.7 | 1.8 | 4.3 |
| 30 | 5.7 | ----- | 9.9 | 5.1 | 4.3 | 2.7 | 1.0 | 1.6 | .6 | 4.2 | 1.8 | 4.1 |
| 31 | 4.1 | ----- | 10.1 | ----- | 3.9 | ----- | 1.0 | 1.5 | ----- | 3.6 | ----- | 3.9 |

Mean daily gage height, in feet, of West Branch of Susquehanna River at Williamsport, Pa., 1895-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|---------|------|-------|------|-------|------|-------|-------|------|-------|------|-------|------|
| 1899. | | | | | | | | | | | | |
| 1..... | 3.9 | 3.0 | 7.8 | 6.8 | 2.9 | 2.4 | 1.2 | 0.4 | 1.4 | 0.4 | 0.4 | 1.5 |
| 2..... | 3.9 | 2.8 | 7.3 | 6.4 | 2.8 | 2.4 | 1.1 | .3 | 1.5 | .5 | 3.8 | 1.5 |
| 3..... | 3.9 | 2.6 | 7.3 | 6.0 | 2.7 | 2.3 | 1.0 | .3 | 1.5 | .5 | 3.8 | 1.6 |
| 4..... | 3.8 | 2.5 | 7.8 | 5.3 | 2.7 | 2.2 | .9 | .1 | 1.5 | .4 | 3.8 | 1.6 |
| 5..... | 4.8 | 2.6 | 11.8 | 4.5 | 2.9 | 2.1 | .8 | .2 | 1.5 | .4 | 3.4 | 1.9 |
| 6..... | 7.0 | 2.8 | 13.1 | 4.3 | 2.5 | 1.9 | .7 | .1 | 1.4 | .4 | 2.9 | 1.6 |
| 7..... | 8.0 | 2.8 | 11.3 | 4.3 | 2.3 | 1.7 | .7 | .0 | 1.3 | .4 | 2.4 | 1.5 |
| 8..... | 6.3 | 2.9 | 9.1 | 6.8 | 2.2 | 1.5 | .7 | .0 | 1.3 | .4 | 2.1 | 1.7 |
| 9..... | 5.3 | 2.9 | 7.3 | 7.8 | 2.3 | 1.3 | .6 | .1 | 1.2 | .4 | 1.9 | 1.6 |
| 10..... | 4.3 | 2.8 | 6.3 | 7.8 | 2.4 | 1.3 | .6 | .1 | 1.2 | .4 | 2.0 | 1.7 |
| 11..... | 4.0 | 2.7 | 5.4 | 6.8 | 2.4 | 1.2 | .6 | .2 | 1.1 | .4 | 2.1 | 1.7 |
| 12..... | 3.9 | 2.6 | 6.3 | 6.3 | 2.7 | 1.2 | .6 | .2 | 1.0 | .4 | 2.2 | 1.9 |
| 13..... | 3.8 | 2.4 | 7.3 | 6.8 | 2.5 | 1.1 | .6 | .8 | .9 | .4 | 2.3 | 7.0 |
| 14..... | 4.3 | 2.3 | 7.8 | 7.3 | 2.4 | 1.0 | .6 | .6 | .8 | .3 | 2.6 | 7.5 |
| 15..... | 4.8 | 2.3 | 7.1 | 7.3 | 2.3 | 1.0 | .6 | .4 | .7 | .3 | 2.9 | 6.3 |
| 16..... | 5.3 | 2.4 | 6.1 | 6.8 | 2.2 | 1.0 | .6 | .2 | .7 | .3 | 3.1 | 5.5 |
| 17..... | 5.8 | 2.5 | 5.8 | 6.3 | 2.0 | .9 | .6 | .3 | .6 | .3 | 3.2 | 4.7 |
| 18..... | 5.8 | 2.6 | 5.8 | 5.1 | 2.7 | .9 | .8 | .3 | .5 | .3 | 3.6 | 4.0 |
| 19..... | 5.6 | 2.8 | 7.5 | 4.9 | 6.8 | .8 | 1.1 | .2 | .5 | .3 | 3.5 | 3.9 |
| 20..... | 4.5 | 3.2 | 9.3 | 4.6 | 7.3 | .8 | 1.4 | .1 | .4 | .3 | 3.5 | 3.8 |
| 21..... | 3.9 | 3.3 | 8.8 | 4.4 | 6.1 | .7 | 1.7 | .0 | .4 | .3 | 3.2 | 4.3 |
| 22..... | 3.9 | 4.2 | 7.6 | 4.2 | 4.9 | .5 | 1.2 | .2 | .3 | .3 | 2.9 | 4.9 |
| 23..... | 3.8 | 5.3 | 6.8 | 4.0 | 4.1 | .6 | 1.0 | .1 | .3 | .3 | 2.6 | 4.3 |
| 24..... | 3.8 | 6.8 | 7.0 | 3.7 | 3.6 | .5 | .8 | .1 | .4 | .3 | 2.4 | 4.5 |
| 25..... | 4.0 | 7.3 | 5.8 | 3.5 | 3.1 | 1.3 | .7 | .1 | .3 | .3 | 2.3 | 4.8 |
| 26..... | 4.2 | 6.3 | 5.8 | 3.3 | 2.9 | 1.0 | .6 | .2 | .3 | .3 | 2.2 | 5.0 |
| 27..... | 3.6 | 5.3 | 5.8 | 3.7 | 2.7 | 1.3 | .6 | 1.4 | .3 | .2 | 2.1 | 4.5 |
| 28..... | 3.5 | 8.3 | 5.6 | 3.6 | 2.5 | 1.2 | .4 | 2.5 | .3 | .2 | 1.9 | 4.3 |
| 29..... | 3.4 | ----- | 6.5 | 3.3 | 2.4 | 1.3 | .3 | 2.0 | .4 | .2 | 1.9 | 3.8 |
| 30..... | 3.2 | ----- | 8.3 | 3.1 | 2.4 | 1.3 | .4 | 1.7 | .4 | .1 | 1.7 | 3.7 |
| 31..... | 3.0 | ----- | 7.8 | ----- | 2.5 | ----- | .4 | 1.5 | ----- | .1 | ----- | 3.5 |
| 1900. | | | | | | | | | | | | |
| 1..... | 3.3 | 2.9 | 4.0 | 3.9 | 3.3 | 3.3 | 1.3 | .6 | .8 | .1 | 1.0 | 5.8 |
| 2..... | 3.2 | 2.8 | 9.0 | 3.8 | 3.1 | 2.9 | 1.5 | .6 | .7 | .1 | 1.0 | 5.0 |
| 3..... | 3.1 | 2.8 | 8.2 | 4.2 | 2.9 | 3.2 | 1.3 | .6 | .6 | .1 | .9 | 4.8 |
| 4..... | 3.0 | 2.9 | 7.1 | 4.5 | 2.7 | 3.5 | 1.0 | .5 | .5 | .2 | .9 | 4.3 |
| 5..... | 2.9 | 2.9 | 6.0 | 4.8 | 2.6 | 3.5 | .9 | .5 | .5 | .2 | .9 | 6.8 |
| 6..... | 2.8 | 3.3 | 5.2 | 4.5 | 2.5 | 3.0 | 1.0 | .4 | .4 | .2 | .9 | 7.2 |
| 7..... | 2.6 | 3.0 | 5.3 | 5.0 | 2.3 | 2.7 | 1.1 | .4 | .3 | .2 | .8 | 5.8 |
| 8..... | 2.5 | 3.0 | 7.1 | 6.5 | 2.2 | 2.5 | 1.1 | .3 | .3 | .3 | .8 | 5.7 |
| 9..... | 2.6 | 4.5 | 6.5 | 6.8 | 2.0 | 2.4 | 1.0 | .3 | .3 | .4 | .8 | 4.8 |
| 10..... | 2.6 | 6.0 | 6.2 | 6.1 | 2.0 | 2.2 | .9 | .3 | .3 | .9 | .8 | 4.5 |
| 11..... | 2.6 | 5.5 | 7.0 | 5.5 | 2.0 | 2.0 | 1.0 | .2 | .3 | 1.1 | .8 | 4.2 |
| 12..... | 2.7 | 5.0 | 6.3 | 4.8 | 2.0 | 1.9 | 1.1 | .1 | .2 | 1.0 | .9 | 3.5 |
| 13..... | 2.8 | 5.0 | 5.1 | 4.5 | 2.0 | 1.8 | 1.0 | .1 | .2 | 1.0 | .9 | 3.0 |
| 14..... | 2.9 | 8.7 | 4.5 | 4.3 | 2.0 | 1.6 | 1.7 | .2 | .2 | 1.0 | .9 | 2.9 |
| 15..... | 3.0 | 8.5 | 4.1 | 4.1 | 2.3 | 1.7 | 1.3 | .1 | .2 | .9 | .9 | 2.8 |
| 16..... | 3.0 | 6.5 | 3.5 | 3.9 | 2.3 | 1.9 | 1.1 | .1 | .1 | 1.1 | .8 | 2.3 |
| 17..... | 3.0 | 5.5 | 2.8 | 3.9 | 2.0 | 1.7 | .9 | .2 | .1 | 1.2 | .8 | 1.9 |
| 18..... | 3.3 | 4.7 | 2.7 | 5.1 | 2.0 | 1.6 | .8 | .2 | .2 | 1.1 | .7 | 1.8 |
| 19..... | 3.8 | 3.8 | 2.5 | 6.9 | 2.0 | 1.5 | .8 | .2 | .2 | .9 | .7 | 2.1 |
| 20..... | 4.5 | 3.6 | 3.1 | 6.8 | 2.5 | 1.4 | .7 | .2 | .2 | .8 | .7 | 2.0 |
| 21..... | 13.0 | 3.5 | 7.0 | 6.2 | 2.5 | 1.3 | .7 | .3 | .2 | .7 | .8 | 2.0 |
| 22..... | 13.0 | 5.5 | 6.1 | 5.5 | 2.3 | 1.2 | .6 | .7 | .2 | .7 | 1.0 | 1.9 |
| 23..... | 10.0 | 9.8 | 5.0 | 5.5 | 2.0 | 1.2 | .6 | 1.0 | .1 | .7 | 1.4 | 1.9 |
| 24..... | 8.0 | 7.4 | 5.5 | 5.9 | 1.8 | 1.1 | .6 | .9 | .1 | .7 | 1.5 | 1.8 |
| 25..... | 6.5 | 5.4 | 6.0 | 5.7 | 1.7 | 1.0 | .6 | .9 | .1 | .9 | 2.7 | 1.9 |
| 26..... | 5.8 | 5.2 | 5.2 | 5.2 | 1.8 | 1.1 | .5 | .9 | .1 | 1.8 | 4.8 | 2.1 |
| 27..... | 5.0 | 3.2 | 4.9 | 4.7 | 2.0 | 1.0 | .7 | 1.0 | .1 | 1.5 | 17.0 | 2.4 |
| 28..... | 4.5 | 3.9 | 4.5 | 4.2 | 1.9 | 0.9 | 1.0 | .9 | .1 | 1.4 | 12.0 | 2.3 |
| 29..... | 4.0 | ----- | 4.5 | 3.8 | 1.9 | 0.8 | .9 | 1.0 | .1 | 1.3 | 8.0 | 2.3 |
| 30..... | 4.1 | ----- | 4.4 | 3.6 | 4.0 | 0.8 | .8 | 1.0 | .1 | 1.1 | 5.5 | 2.3 |
| 31..... | 3.3 | ----- | 4.1 | ----- | 3.6 | ----- | .7 | .9 | ----- | 1.1 | ----- | 2.2 |

Mean daily gage height, in feet, of West Branch of Susquehanna River at Williamsport, Pa., 1895-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|------|-------|-------|-------|-------|-------|-------|------|-------|------|-------|-------|
| 1901. | | | | | | | | | | | | |
| 1. | 2.30 | 1.60 | .90 | 5.50 | 4.00 | 9.80 | 3.10 | 1.20 | 3.00 | 1.80 | 0.70 | 3.00 |
| 2. | 2.30 | 1.40 | 1.00 | 4.80 | 3.80 | 7.20 | 2.60 | 1.10 | 3.50 | 1.50 | .60 | 2.80 |
| 3. | 1.90 | 1.40 | 1.30 | 4.50 | 4.00 | 7.00 | 2.30 | 1.00 | 6.80 | 2.00 | .60 | 3.00 |
| 4. | 1.10 | 1.40 | 1.40 | 6.00 | 4.60 | 6.50 | 2.20 | .80 | 5.70 | 1.50 | .70 | 2.60 |
| 5. | 1.00 | 1.60 | 2.10 | 6.20 | 4.20 | 5.70 | 2.10 | .70 | 4.60 | 1.40 | .60 | 2.30 |
| 6. | 1.00 | 1.80 | 3.00 | 7.00 | 4.00 | 5.10 | 2.00 | .70 | 4.10 | 1.30 | .60 | 2.00 |
| 7. | 1.10 | 2.50 | 3.70 | 9.50 | 3.70 | 5.00 | 1.90 | .80 | 3.30 | 1.20 | .60 | 1.80 |
| 8. | 1.10 | 1.90 | 3.00 | 11.50 | 3.50 | 5.50 | 1.80 | 1.80 | 2.70 | .90 | .60 | 1.80 |
| 9. | 1.40 | 1.40 | 2.60 | 11.20 | 3.10 | 5.30 | 1.60 | 1.90 | 2.40 | .80 | .50 | 1.80 |
| 10. | 1.50 | 1.30 | 3.00 | 9.50 | 3.30 | 5.00 | 1.50 | 1.70 | 2.20 | .90 | .50 | 2.80 |
| 11. | 1.80 | 1.30 | 7.00 | 8.20 | 3.40 | 4.50 | 1.40 | 1.50 | 2.00 | .90 | .40 | 6.90 |
| 12. | 2.10 | 1.90 | 10.50 | 7.20 | 3.40 | 4.10 | 1.30 | 1.40 | 2.00 | .90 | .50 | 6.10 |
| 13. | 3.60 | 2.40 | 9.20 | 6.20 | 3.40 | 3.90 | 1.10 | 1.10 | 2.00 | 1.00 | .60 | 5.50 |
| 14. | 4.50 | 2.10 | 7.50 | 5.80 | 3.60 | 3.30 | 1.10 | .90 | 2.30 | 1.30 | .60 | 5.20 |
| 15. | 4.20 | 1.50 | 6.50 | 5.50 | 3.60 | 3.00 | 1.10 | .80 | 2.50 | 1.10 | 1.50 | 20.17 |
| 16. | 4.00 | 1.40 | 6.80 | 5.30 | 3.50 | 3.60 | 1.00 | .90 | 2.80 | .80 | 1.20 | 18.20 |
| 17. | 3.70 | 1.30 | 6.00 | 4.80 | 3.30 | 3.40 | 1.00 | 3.30 | 2.70 | 1.10 | 1.30 | 12.00 |
| 18. | 3.50 | 1.20 | 5.50 | 4.20 | 3.50 | 2.90 | 1.20 | 3.30 | 3.00 | 1.00 | 1.50 | 8.80 |
| 19. | 2.90 | 1.20 | 5.00 | 4.20 | 3.40 | 2.70 | 1.20 | 4.50 | 3.00 | .90 | 1.30 | 7.00 |
| 20. | 2.40 | 1.30 | 6.20 | 4.00 | 3.20 | 2.60 | 1.10 | 4.20 | 2.80 | .80 | 1.10 | 5.50 |
| 21. | 2.00 | 1.40 | 7.50 | 12.00 | 3.00 | 2.90 | 1.00 | 4.00 | 2.50 | .80 | 1.00 | 5.00 |
| 22. | 1.90 | 1.30 | 9.50 | 15.20 | 1.80 | 4.00 | .90 | 4.60 | 2.30 | .70 | .90 | 4.40 |
| 23. | 2.20 | 1.20 | 8.50 | 12.50 | 5.80 | 4.50 | .70 | 4.00 | 2.00 | .60 | .80 | 3.70 |
| 24. | 2.60 | 1.00 | 7.50 | 9.70 | 5.50 | 4.40 | .70 | 5.40 | 1.90 | .60 | 1.60 | 3.60 |
| 25. | 2.40 | .90 | 6.50 | 8.50 | 5.50 | 4.20 | .70 | 7.80 | 1.80 | .60 | 5.60 | 3.60 |
| 26. | 2.50 | .90 | 7.80 | 7.50 | 5.00 | 3.80 | .80 | 6.80 | 1.50 | .60 | 6.70 | 3.70 |
| 27. | 2.60 | 1.00 | 10.50 | 6.50 | 5.00 | 3.50 | .90 | 5.20 | 1.40 | .60 | 5.70 | 3.90 |
| 28. | 2.60 | 1.00 | 11.20 | 5.50 | 7.60 | 3.60 | 1.00 | 4.30 | 1.20 | .60 | 4.40 | 3.40 |
| 29. | 2.70 | ----- | 9.20 | 5.00 | 11.50 | 3.70 | 1.10 | 3.50 | 1.50 | .70 | 3.60 | 3.20 |
| 30. | 2.60 | ----- | 7.80 | 4.50 | 14.00 | 3.50 | 1.20 | 3.00 | 1.90 | .80 | 3.50 | 3.00 |
| 31. | 1.70 | ----- | 6.20 | ----- | 12.30 | ----- | 1.20 | 2.70 | ----- | .70 | ----- | 3.40 |
| 1902. | | | | | | | | | | | | |
| 1. | 3.20 | 4.30 | 20.38 | 6.00 | 2.50 | 1.30 | 8.30 | 5.00 | .50 | 2.70 | 1.90 | 1.00 |
| 2. | 2.90 | 4.20 | 21.10 | 5.70 | 2.50 | 1.20 | 7.40 | 4.90 | .60 | 4.10 | 1.70 | 1.30 |
| 3. | 2.60 | 5.00 | 16.45 | 5.30 | 2.40 | 1.20 | 6.40 | 4.60 | .50 | 3.10 | 1.60 | 1.50 |
| 4. | 2.50 | 4.70 | 13.00 | 4.90 | 2.70 | 1.10 | 9.70 | 4.30 | .50 | 2.50 | 1.50 | 2.20 |
| 5. | 2.40 | 4.50 | 10.00 | 4.50 | 2.70 | 1.10 | 10.80 | 3.80 | .50 | 2.40 | 1.40 | 2.40 |
| 6. | 2.30 | 4.00 | 8.10 | 4.30 | 2.90 | 1.30 | 8.60 | 3.30 | .40 | 2.30 | 1.40 | 2.50 |
| 7. | 2.30 | 3.90 | 6.80 | 4.50 | 2.90 | 1.20 | 8.80 | 3.10 | .40 | 2.20 | 1.30 | 2.30 |
| 8. | 2.30 | 3.70 | 5.90 | 4.70 | 3.20 | 1.20 | 7.30 | 3.00 | .40 | 2.20 | 1.40 | 2.30 |
| 9. | 2.40 | 3.60 | 5.30 | 13.30 | 3.40 | 1.10 | 6.30 | 2.80 | .40 | 2.00 | 1.40 | 2.80 |
| 10. | 2.40 | 3.40 | 5.50 | 16.60 | 3.20 | 1.00 | 6.00 | 2.60 | .60 | 1.80 | 1.30 | 1.90 |
| 11. | 2.40 | 3.30 | 6.30 | 12.90 | 3.00 | 1.10 | 7.70 | 2.40 | .50 | 1.60 | 1.30 | 2.00 |
| 12. | 2.40 | 3.00 | 7.10 | 10.30 | 2.80 | 1.10 | 7.20 | 2.20 | .50 | 1.40 | 1.20 | 2.30 |
| 13. | 2.40 | 2.90 | 9.60 | 8.40 | 2.60 | 1.30 | 6.30 | 2.50 | .60 | 1.20 | 1.20 | 3.10 |
| 14. | 2.30 | 3.00 | 12.20 | 7.30 | 2.50 | 1.40 | 5.00 | 2.10 | .50 | 1.00 | 1.10 | 4.40 |
| 15. | 2.10 | 2.60 | 10.80 | 6.30 | 2.40 | 1.60 | 4.20 | 1.90 | .40 | 1.20 | 1.00 | 3.60 |
| 16. | 2.10 | 2.30 | 8.40 | 5.50 | 2.20 | 1.80 | 3.60 | 1.80 | .40 | 1.30 | 1.00 | 3.00 |
| 17. | 2.00 | 2.10 | 13.80 | 5.00 | 2.00 | 1.90 | 3.10 | 1.60 | .40 | 1.60 | .90 | 5.80 |
| 18. | 2.00 | 2.10 | 12.70 | 4.70 | 1.90 | 2.00 | 3.30 | 1.50 | .40 | 1.50 | .90 | 8.10 |
| 19. | 1.80 | 2.50 | 10.00 | 4.30 | 1.80 | 2.00 | 3.70 | 1.40 | .30 | 1.40 | .90 | 6.40 |
| 20. | 1.60 | 2.20 | 8.10 | 3.90 | 1.70 | 1.80 | 4.40 | 1.30 | .20 | 1.30 | .80 | 5.30 |
| 21. | 2.00 | 1.90 | 6.80 | 4.40 | 1.70 | 1.80 | 5.80 | 1.20 | .20 | 1.30 | .90 | 5.10 |
| 22. | 5.30 | 2.20 | 6.00 | 3.50 | 1.70 | 1.70 | 6.80 | 1.40 | .20 | 1.20 | .90 | 8.00 |
| 23. | 6.73 | 1.90 | 5.40 | 3.20 | 1.60 | 1.50 | 6.30 | 1.30 | .20 | 1.10 | .90 | 10.70 |
| 24. | 4.50 | 1.80 | 5.00 | 2.90 | 1.60 | 1.40 | 5.70 | 1.10 | .20 | 1.00 | .90 | 9.10 |
| 25. | 4.50 | 1.80 | 4.50 | 2.80 | 1.60 | a .60 | 5.90 | 1.00 | .50 | 1.00 | 1.00 | 7.20 |
| 26. | 4.00 | 2.00 | 4.20 | 3.30 | 1.60 | 1.50 | 5.80 | .90 | .90 | .90 | 1.10 | 6.00 |
| 27. | 4.10 | 3.10 | 3.90 | 2.50 | 1.70 | 1.90 | 6.10 | .80 | 2.30 | .90 | 1.10 | 5.40 |
| 28. | 4.00 | 10.89 | 3.70 | 2.40 | 1.80 | 2.80 | 5.50 | .40 | 2.60 | 1.30 | 1.10 | 4.10 |
| 29. | 3.90 | ----- | 3.90 | 2.30 | 1.60 | 2.60 | 5.20 | .50 | 2.80 | 1.20 | 1.00 | 4.40 |
| 30. | 4.10 | ----- | 5.60 | 2.50 | 1.50 | 4.30 | 4.50 | .60 | 2.30 | 1.50 | 1.00 | 3.60 |
| 31. | 4.00 | ----- | 6.20 | ----- | 1.40 | ----- | 5.20 | .50 | ----- | 1.70 | ----- | 2.50 |

a Splash on dam.

Mean daily gage height, in feet, of West Branch of Susquehanna River at Williamsport, Pa., 1895-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|-------|----------------|----------------|-------|------|-------|-------|------|-------|------|-------|-------------|
| 1903. | | | | | | | | | | | | |
| 1 | 3.00 | 9.80 | 17.07 | 5.80 | 2.40 | 1.00 | 4.60 | 2.70 | 5.80 | 1.00 | 1.90 | 2.00 |
| 2 | 2.50 | 6.00 | 14.30 | 5.60 | 2.30 | .50 | 4.20 | 2.30 | 5.30 | 1.00 | 1.70 | 2.00 |
| 3 | 3.00 | 7.50 | 10.20 | 5.30 | 2.20 | .90 | 4.00 | 2.00 | 4.60 | .90 | 1.70 | 2.00 |
| 4 | 4.30 | <i>a</i> 10.60 | 8.30 | 5.00 | 2.00 | .60 | 4.40 | 1.80 | 4.00 | .90 | 1.60 | 1.80 |
| 5 | 4.90 | 15.50 | 7.20 | 5.10 | 2.00 | .60 | 4.00 | 2.50 | 3.50 | 1.00 | 1.50 | 1.80 |
| 6 | 5.30 | 13.20 | 7.10 | 4.70 | 2.00 | .60 | 3.70 | 3.60 | 3.10 | 1.40 | 1.60 | 1.80 |
| 7 | 5.00 | 10.10 | 7.20 | 4.50 | 2.00 | .70 | 6.00 | 3.80 | 2.70 | 1.70 | 1.50 | 1.70 |
| 8 | 4.40 | 7.80 | 7.60 | 4.50 | 1.70 | 1.00 | 5.30 | 4.00 | 2.50 | 2.00 | 1.50 | 1.70 |
| 9 | 3.70 | 6.70 | <i>b</i> 12.20 | 5.00 | 1.60 | 1.40 | 4.20 | 3.50 | 2.40 | 5.90 | 1.50 | 1.60 |
| 10 | 2.20 | 5.80 | 12.70 | 5.40 | 1.40 | 1.40 | 3.50 | 2.90 | 2.60 | 7.80 | 1.40 | 1.70 |
| 11 | 2.20 | 5.10 | 11.00 | 5.60 | 1.40 | 2.10 | 3.00 | 2.60 | 2.80 | 6.20 | 1.40 | 1.70 |
| 12 | 4.30 | 5.20 | 11.10 | 5.30 | 1.40 | 2.20 | 3.00 | 2.40 | 3.40 | 5.50 | 1.40 | 1.40 |
| 13 | 4.20 | 6.20 | 10.60 | 5.80 | 1.30 | 3.70 | 3.00 | 2.20 | 3.00 | 4.60 | 1.30 | 1.50 |
| 14 | 4.20 | 6.70 | 8.90 | 6.10 | 1.30 | 3.40 | 2.70 | 2.00 | 2.50 | 4.00 | 1.20 | 1.90 |
| 15 | 4.20 | 6.40 | 7.80 | 9.60 | 1.30 | 3.60 | 2.40 | 1.70 | 2.30 | 3.60 | 1.20 | 1.50 |
| 16 | 4.20 | 6.30 | 6.90 | 11.70 | 1.20 | 4.00 | 2.20 | 1.60 | 2.00 | 3.30 | 1.30 | 1.00 |
| 17 | 4.10 | 6.30 | 6.20 | 10.70 | 1.20 | 3.70 | 2.00 | 1.80 | 1.90 | 3.00 | 2.80 | 1.00 |
| 18 | 3.70 | 6.00 | 5.70 | 9.10 | 1.20 | 3.40 | 2.00 | 1.80 | 2.50 | 4.20 | 12.00 | 1.00 |
| 19 | 3.70 | 4.40 | 5.30 | 7.60 | 1.20 | 2.90 | 5.40 | 1.60 | 2.60 | 5.30 | 9.20 | 1.00 |
| 20 | 3.60 | 4.00 | 4.70 | 6.50 | 1.20 | 2.60 | 8.00 | 1.50 | 2.50 | 5.00 | 7.40 | 1.00 |
| 21 | 3.70 | 4.10 | 4.40 | 5.70 | 1.20 | 2.50 | 6.20 | 1.60 | 2.30 | 4.60 | 5.50 | 1.60 |
| 22 | 3.40 | 4.00 | 4.60 | 5.10 | 1.10 | 2.50 | 5.50 | 2.20 | 2.00 | 4.00 | 4.90 | 2.10 |
| 23 | 3.20 | 4.50 | 5.30 | 4.60 | 1.10 | 2.60 | 5.00 | 1.80 | 1.80 | 3.60 | 4.40 | 2.00 |
| 24 | 3.10 | 3.80 | 13.30 | 4.20 | 1.00 | 4.10 | 4.20 | 1.50 | 1.60 | 3.20 | 4.10 | 1.90 |
| 25 | 3.10 | 3.90 | 12.20 | 4.00 | .90 | 6.10 | 3.60 | 1.50 | 1.50 | 3.00 | 3.80 | 1.80 |
| 26 | 3.00 | 3.80 | 9.50 | 3.50 | .90 | 9.20 | 3.20 | 1.40 | 1.50 | 2.80 | 3.40 | 1.70 |
| 27 | 3.00 | 3.60 | 7.70 | 3.40 | 1.00 | 7.00 | 2.70 | 1.50 | 1.30 | 2.60 | 3.00 | 2.00 |
| 28 | 3.00 | <i>c</i> 9.85 | 6.50 | 3.10 | 1.00 | 5.40 | 2.30 | 1.80 | 1.20 | 2.30 | 2.50 | 2.00 |
| 29 | 2.80 | ----- | 5.60 | 2.90 | 1.10 | 4.50 | 2.10 | 3.90 | 1.20 | 2.20 | 2.10 | 2.40 |
| 30 | 3.00 | ----- | 5.00 | 2.70 | 1.10 | 5.20 | 2.50 | 7.20 | 1.10 | 2.00 | 1.70 | 2.30 |
| 31 | 11.00 | ----- | 4.90 | ----- | 1.10 | ----- | 2.80 | 6.50 | ----- | 2.00 | ----- | 2.40 |
| 1904. | | | | | | | | | | | | |
| 1 | 2.2 | 3.8 | 2.7 | 6.2 | 7.8 | 3.6 | 2.3 | 1.0 | .4 | .8 | 1.0 | 0.6 |
| 2 | 2.2 | 3.4 | 7.0 | 16.8 | 7.0 | 3.7 | 2.1 | .9 | .4 | 1.0 | 1.0 | .5 |
| 3 | 2.0 | 3.0 | 7.5 | 13.6 | 6.2 | 3.7 | 1.9 | .9 | .4 | 1.0 | 1.0 | .5 |
| 4 | 2.0 | 2.8 | 19.0 | 9.8 | 5.5 | 3.5 | 1.7 | .9 | .3 | .9 | 1.0 | .4 |
| 5 | 1.8 | 3.0 | 16.5 | 8.0 | 5.0 | 6.1 | 1.5 | .8 | .3 | .8 | .9 | <i>g</i> .4 |
| 6 | 1.8 | 2.4 | 9.2 | 6.8 | 4.5 | 4.5 | 1.5 | .7 | .3 | .8 | .9 | .4 |
| 7 | 1.7 | 2.6 | 7.4 | 6.4 | 4.2 | 3.7 | 1.7 | .7 | .2 | .7 | .8 | .4 |
| 8 | 1.7 | <i>d</i> 5.0 | 17.4 | 6.0 | 3.9 | 3.4 | 1.8 | .7 | .2 | .7 | .7 | .4 |
| 9 | 1.7 | <i>e</i> 10.5 | 13.5 | 6.0 | 3.6 | 3.2 | 3.4 | .6 | .2 | .6 | .6 | .4 |
| 10 | 1.7 | <i>e</i> 7.6 | 9.8 | 8.8 | 3.3 | 3.2 | 4.4 | .5 | .2 | .6 | .6 | .4 |
| 11 | 1.7 | <i>e</i> 6.0 | 7.6 | 9.2 | 3.2 | 3.3 | 8.1 | .5 | .2 | .6 | .7 | .4 |
| 12 | 1.7 | <i>e</i> 5.2 | 6.5 | 7.9 | 3.0 | 3.3 | 6.7 | .4 | .5 | .5 | .7 | .4 |
| 13 | 1.7 | <i>c</i> 4.3 | 5.8 | 7.2 | 2.8 | 2.9 | 5.4 | .4 | .6 | .7 | .7 | .3 |
| 14 | 1.7 | 3.8 | 5.3 | 6.6 | 2.5 | 2.7 | 4.6 | .5 | .5 | 1.2 | .8 | .3 |
| 15 | 1.6 | 4.0 | 5.0 | 5.8 | 3.0 | 2.4 | 3.8 | .5 | .5 | 1.5 | .8 | .3 |
| 16 | 1.6 | <i>f</i> 3.8 | 4.4 | 5.2 | 3.4 | 2.6 | 3.4 | .5 | .6 | 1.4 | .7 | .3 |
| 17 | 1.5 | <i>f</i> 3.6 | 4.1 | 5.2 | 3.3 | 3.1 | 3.0 | .3 | .5 | 1.3 | .7 | .3 |
| 18 | 1.5 | <i>f</i> 3.5 | 3.8 | 5.1 | 3.2 | 2.8 | 2.5 | .3 | .5 | 1.2 | .7 | .2 |
| 19 | 1.5 | 3.3 | 4.0 | 5.0 | 4.7 | 2.6 | 2.1 | .3 | .4 | 1.1 | .7 | .2 |
| 20 | 1.5 | <i>f</i> 3.0 | 4.5 | 4.5 | 7.7 | 2.3 | 2.0 | .4 | .3 | 1.0 | .7 | .2 |
| 21 | 1.4 | 2.9 | 6.5 | 4.2 | 7.2 | 2.3 | 1.7 | .5 | .3 | 1.1 | .6 | .2 |
| 22 | 1.5 | 2.8 | 6.7 | 3.9 | 6.0 | 3.0 | 1.5 | .5 | .2 | 1.5 | .6 | .2 |
| 23 | 7.7 | 2.7 | 6.6 | 3.6 | 5.2 | 3.7 | 1.3 | .9 | .2 | 1.7 | .6 | .2 |
| 24 | 13.3 | 3.7 | <i>h</i> 9.9 | 3.3 | 4.7 | 4.0 | 1.3 | 1.0 | .2 | 1.6 | .7 | .3 |
| 25 | 9.8 | 4.2 | 10.3 | 3.2 | 4.4 | 3.2 | 1.2 | 1.2 | .2 | 1.5 | .6 | .3 |
| 26 | 7.0 | 3.8 | 11.3 | 3.6 | 4.2 | 2.8 | 1.1 | 1.0 | .3 | 1.5 | .6 | .3 |
| 27 | 5.4 | 3.0 | 12.6 | 4.3 | 4.0 | 2.3 | 1.1 | .9 | .6 | 1.4 | .6 | .4 |
| 28 | 4.9 | 2.7 | 10.6 | 5.1 | 3.8 | 2.1 | 1.1 | .7 | 1.0 | 1.3 | .6 | 1.8 |
| 29 | 3.5 | 2.5 | 8.0 | 6.8 | 3.5 | 1.9 | 1.1 | .6 | 1.0 | 1.3 | .5 | 5.4 |
| 30 | 3.2 | ----- | 6.9 | 8.4 | 3.3 | 1.7 | 1.0 | .6 | 1.1 | 1.2 | .5 | 5.5 |
| 31 | 3.6 | ----- | 6.0 | ----- | 3.3 | ----- | 1.0 | .5 | ----- | 1.1 | ----- | 4.4 |

a 16.00, 11 p. m.

b 13.2, 11 p. m.

c 15.00, 12 p. m., rising 1 foot in 2 hours.


d Ice running.

e Slush ice running.

f Anchor ice running.

g River frozen December 5 to 28, 1904.

h 18 feet at noon.



*Rating table for West Branch of Susquehanna River at Williamsport, Pa., for
1895 to 1904.*

| Gage height. | Discharge. | Gage height. | Discharge. | Gage height. | Discharge. | Gage height. | Discharge. |
|-----------------|---------------------|-----------------|---------------------|-----------------|---------------------|-----------------|---------------------|
| <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> |
| -0.2 | 410 | 2.2 | 4,530 | 6.0 | 18,330 | 10.6 | 47,400 |
| .0 | 600 | 2.3 | 4,770 | 6.2 | 19,330 | 10.8 | 49,000 |
| .1 | 710 | 2.4 | 5,010 | 6.4 | 20,340 | 11.0 | 50,600 |
| .2 | 830 | 2.5 | 5,250 | 6.6 | 21,360 | 11.2 | 52,200 |
| .3 | 970 | 2.6 | 5,500 | 6.8 | 22,380 | 11.4 | 53,800 |
| .4 | 1,120 | 2.7 | 5,760 | 7.0 | 23,400 | 11.6 | 55,500 |
| .5 | 1,280 | 2.8 | 6,020 | 7.2 | 24,600 | 11.8 | 57,200 |
| .6 | 1,440 | 2.9 | 6,300 | 7.4 | 25,700 | 12.0 | 58,900 |
| .7 | 1,610 | 3.0 | 6,580 | 7.6 | 26,900 | 12.2 | 60,700 |
| .8 | 1,780 | 3.2 | 7,170 | 7.8 | 28,100 | 12.4 | 62,500 |
| .9 | 1,960 | 3.4 | 7,780 | 8.0 | 29,300 | 12.6 | 64,300 |
| 1.0 | 2,140 | 3.6 | 8,400 | 8.2 | 30,500 | 12.8 | 66,100 |
| 1.1 | 2,320 | 3.8 | 9,030 | 8.4 | 31,800 | 13.0 | 67,900 |
| 1.2 | 2,510 | 4.0 | 9,690 | 8.6 | 33,100 | 13.2 | 69,800 |
| 1.3 | 2,700 | 4.2 | 10,400 | 8.8 | 34,400 | 13.4 | 71,700 |
| 1.4 | 2,890 | 4.4 | 11,150 | 9.0 | 35,800 | 13.6 | 73,600 |
| 1.5 | 3,080 | 4.6 | 11,940 | 9.2 | 37,200 | 13.8 | 75,500 |
| 1.6 | 3,270 | 4.8 | 12,750 | 9.4 | 38,600 | 14.0 | 77,500 |
| 1.7 | 3,460 | 5.0 | 13,600 | 9.6 | 40,000 | 14.5 | 82,600 |
| 1.8 | 3,660 | 5.2 | 14,500 | 9.8 | 41,400 | 15.0 | 87,800 |
| 1.9 | 3,860 | 5.4 | 15,420 | 10.0 | 42,800 | | |
| 2.0 | 4,070 | 5.6 | 16,370 | 10.2 | 44,300 | | |
| 2.1 | 4,300 | 5.8 | 17,340 | 10.4 | 45,800 | | |

Mean daily discharge, in second-feet, of West Branch of Susquehanna River at Williamsport, Pa., 1895-1904.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|--------|--------|--------|--------|--------|--------|--------|--------|-------|--------|--------|--------|
| 1895. | | | | | | | | | | | | |
| 1 | | | 29,300 | 18,330 | 4,300 | 5,010 | 11,540 | 970 | 1,120 | 710 | 500 | 3,080 |
| 2 | | | 35,800 | 18,330 | 3,860 | 4,300 | 8,710 | 830 | 1,120 | 710 | 500 | 3,270 |
| 3 | | | 46,600 | 24,600 | 3,860 | 3,860 | 6,580 | 830 | 970 | 830 | 600 | 3,080 |
| 4 | | | 39,300 | 20,850 | 3,860 | 3,860 | 4,770 | 710 | 970 | 970 | 600 | 2,890 |
| 5 | | | 35,800 | 17,340 | 3,660 | 3,080 | 3,460 | 710 | 830 | 970 | 500 | 2,890 |
| 6 | | | 20,850 | 15,420 | 3,660 | 3,080 | 3,080 | 600 | 830 | 830 | 500 | 2,700 |
| 7 | | | 11,540 | 18,330 | 3,270 | 2,890 | 3,080 | 600 | 710 | 710 | 600 | 2,140 |
| 8 | | | 11,540 | 23,400 | 4,530 | 2,510 | 2,700 | 970 | 600 | 830 | 710 | 2,320 |
| 9 | | | 13,600 | 50,600 | 6,300 | 1,780 | 2,510 | 970 | 600 | 830 | 710 | 2,320 |
| 10 | | | 14,500 | 58,900 | 7,170 | 1,280 | 3,270 | 970 | 970 | 710 | 970 | 2,140 |
| 11 | | | 14,960 | 50,600 | 6,020 | 1,120 | 3,080 | 1,120 | 3,270 | 710 | 970 | 2,140 |
| 12 | | | 15,890 | 28,700 | 5,760 | 830 | 3,080 | 1,610 | 3,660 | 830 | 1,120 | 1,960 |
| 13 | | | 15,890 | 20,850 | 6,020 | 830 | 3,270 | 3,660 | 1,960 | 830 | 1,120 | 1,780 |
| 14 | | | 14,500 | 29,300 | 10,770 | 1,120 | 3,080 | 3,080 | 1,610 | 830 | 970 | 1,440 |
| 15 | | | 18,330 | 46,600 | 9,030 | 1,780 | 2,890 | 1,280 | 1,280 | 830 | 970 | 1,120 |
| 16 | | | 20,850 | 32,400 | 7,470 | 1,780 | 2,700 | 1,440 | 1,120 | 970 | 830 | 970 |
| 17 | | | 15,890 | 18,330 | 6,580 | 1,610 | 2,510 | 1,610 | 1,440 | 830 | 830 | 970 |
| 18 | | | 13,600 | 14,960 | 6,020 | 1,610 | 2,320 | 1,960 | 710 | 830 | 830 | 970 |
| 19 | | | 12,340 | 14,960 | 5,500 | 1,440 | 2,140 | 2,320 | 830 | 830 | 830 | 830 |
| 20 | | | 11,540 | 14,960 | 6,020 | 1,440 | 1,780 | 2,320 | 830 | 830 | 970 | 830 |
| 21 | | | 10,400 | 11,540 | 4,530 | 1,440 | 1,610 | 2,320 | 710 | 830 | 970 | 830 |
| 22 | | | 11,540 | 8,400 | 4,070 | 1,120 | 1,960 | 2,510 | 600 | 830 | 970 | 3,270 |
| 23 | | | 13,600 | 7,780 | 3,860 | 2,140 | 1,780 | 2,700 | 500 | 830 | 830 | 5,010 |
| 24 | | | 15,890 | 7,170 | 3,660 | 2,890 | 1,780 | 2,890 | 410 | 710 | 830 | 5,500 |
| 25 | | | 18,330 | 6,300 | 3,460 | 3,460 | 1,960 | 2,890 | 410 | 600 | 1,120 | 5,010 |
| 26 | | | 33,700 | 5,500 | 3,460 | 2,700 | 2,140 | 3,080 | 410 | 500 | 1,280 | 4,530 |
| 27 | | | 37,200 | 5,500 | 4,070 | 3,460 | 410 | 2,700 | 500 | 500 | 6,300 | 5,010 |
| 28 | | | 27,500 | 5,250 | 8,090 | 19,330 | 600 | 2,700 | 500 | 500 | 6,870 | 23,400 |
| 29 | | | 21,870 | 5,250 | 8,400 | 13,170 | 710 | 2,700 | 600 | 500 | 4,770 | 20,850 |
| 30 | | | 20,850 | 4,530 | 7,170 | 9,690 | 710 | 2,890 | 830 | 500 | 4,300 | 11,540 |
| 31 | | | 19,830 | | 6,580 | | 1,120 | 2,890 | | 410 | | 15,420 |
| 1896. | | | | | | | | | | | | |
| 1 | 22,380 | 3,860 | 20,850 | 67,900 | 8,090 | 3,660 | 6,870 | 20,850 | 1,280 | 22,380 | 4,770 | 9,690 |
| 2 | 11,540 | 4,070 | 21,360 | 50,600 | 7,780 | 4,070 | 5,760 | 21,870 | 1,120 | 22,380 | 4,770 | 9,030 |
| 3 | 10,040 | 5,010 | 18,830 | 42,800 | 6,870 | 3,460 | 4,770 | 22,890 | 1,120 | 17,340 | 4,770 | 7,470 |
| 4 | 9,030 | 10,040 | 12,340 | 32,400 | 6,580 | 2,890 | 4,070 | 17,830 | 1,120 | 11,540 | 4,300 | 6,870 |
| 5 | 8,090 | 10,040 | 9,360 | 24,000 | 6,020 | 2,700 | 4,770 | 12,750 | 1,120 | 7,170 | 5,250 | 6,300 |
| 6 | 7,470 | 9,360 | 10,040 | 18,830 | 5,500 | 2,510 | 5,010 | 9,690 | 1,280 | 3,460 | 26,300 | 5,010 |
| 7 | 6,870 | 49,000 | 9,690 | 17,340 | 5,010 | 2,890 | 4,770 | 8,090 | 1,280 | 3,080 | 22,890 | 4,070 |
| 8 | 6,300 | 37,200 | 9,360 | 16,370 | 4,770 | 3,270 | 4,300 | 8,710 | 1,440 | 2,700 | 19,330 | 3,460 |
| 9 | 5,010 | 22,380 | 9,360 | 14,050 | 4,530 | 5,500 | 4,070 | 7,170 | 1,610 | 1,960 | 15,420 | 7,170 |
| 10 | 5,010 | 18,830 | 9,030 | 12,340 | 4,300 | 14,960 | 7,470 | 6,300 | 1,440 | 1,960 | 11,540 | 11,150 |
| 11 | 4,770 | 14,960 | 8,400 | 12,750 | 3,860 | 10,770 | 6,580 | 5,760 | 1,120 | 1,780 | 10,770 | 13,600 |
| 12 | 4,300 | 10,770 | 6,870 | 14,960 | 3,860 | 7,780 | 5,500 | 5,250 | 1,120 | 1,610 | 9,360 | 10,400 |
| 13 | 4,070 | 10,040 | 5,010 | 16,850 | 3,270 | 6,300 | 4,530 | 4,530 | 1,120 | 41,400 | 9,690 | 9,690 |
| 14 | 4,070 | 8,710 | 5,760 | 28,100 | 3,270 | 5,250 | 3,860 | 5,250 | 1,120 | 49,000 | 9,690 | 8,090 |
| 15 | 3,660 | 8,710 | 5,010 | 31,100 | 3,080 | 4,530 | 3,460 | 4,770 | 1,280 | 41,400 | 8,400 | 7,470 |
| 16 | 3,460 | 11,940 | 4,070 | 26,300 | 3,080 | 4,530 | 3,660 | 4,300 | 1,440 | 30,500 | 6,870 | 7,170 |
| 17 | 3,080 | 10,770 | 5,010 | 22,380 | 3,080 | 4,300 | 3,860 | 3,660 | 1,440 | 20,850 | 6,870 | 6,300 |
| 18 | 2,890 | 8,400 | 5,250 | 18,830 | 3,270 | 10,040 | 4,530 | 3,080 | 1,960 | 18,830 | 6,580 | 6,300 |
| 19 | 2,700 | 7,170 | 5,010 | 16,850 | 2,890 | 9,690 | 4,770 | 2,890 | 1,440 | 15,420 | 6,020 | 5,760 |
| 20 | 2,700 | 3,460 | 8,400 | 14,500 | 2,700 | 8,090 | 3,660 | 2,510 | 3,080 | 12,340 | 5,760 | 5,250 |
| 21 | 2,890 | 3,080 | 9,030 | 12,340 | 2,890 | 6,580 | 3,270 | 2,140 | 4,070 | 9,690 | 5,760 | 4,530 |
| 22 | 2,890 | 4,530 | 9,030 | 12,340 | 2,700 | 5,500 | 3,460 | 1,960 | 3,270 | 8,710 | 5,760 | 4,530 |
| 23 | 2,890 | 3,860 | 11,540 | 11,540 | 2,700 | 5,010 | 3,660 | 1,960 | 1,610 | 8,400 | 5,500 | 4,300 |
| 24 | 3,270 | 4,770 | 10,400 | 11,150 | 2,320 | 4,300 | 4,070 | 1,780 | 1,440 | 8,090 | 5,500 | 5,010 |
| 25 | 5,250 | 7,170 | 10,040 | 10,040 | 2,140 | 8,090 | 5,250 | 2,140 | 970 | 7,780 | 6,020 | 4,530 |
| 26 | 5,760 | 6,870 | 10,400 | 10,400 | 2,320 | 23,400 | 6,870 | 2,140 | 970 | 7,470 | 6,020 | 4,070 |
| 27 | 6,300 | 4,770 | 12,750 | 10,040 | 2,320 | 19,330 | 9,030 | 1,120 | 1,120 | 7,170 | 6,020 | 3,660 |
| 28 | 6,300 | 5,500 | 16,370 | 9,030 | 2,510 | 14,050 | 9,360 | 1,440 | 1,280 | 6,580 | 6,020 | 3,080 |
| 29 | 5,250 | 9,690 | 24,000 | 8,710 | 2,510 | 11,150 | 13,600 | 1,440 | 1,440 | 5,760 | 7,470 | 2,700 |
| 30 | 4,530 | | 49,000 | 8,710 | 2,140 | 9,030 | 17,340 | 1,440 | 2,700 | 5,250 | 9,690 | 3,270 |
| 31 | 4,070 | | 76,500 | | 3,080 | | 22,380 | 1,280 | | 5,250 | | 3,660 |

Mean daily discharge, in second-feet, of West Branch of Susquehanna River at Williamsport, Pa., 1895-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|--------|--------|--------|---------|--------|--------|-------|--------|--------|-------|--------|--------|--------|
| 1897.. | | | | | | | | | | | | |
| 1. | 3,860 | 3,270 | 9,690 | 10,770 | 5,500 | 3,860 | 2,140 | 6,870 | 1,610 | 1,960 | 1,120 | 11,150 |
| 2. | 4,070 | 3,080 | 8,090 | 9,690 | 9,360 | 3,660 | 2,140 | 6,580 | 1,610 | 1,960 | 2,140 | 9,030 |
| 3. | 4,300 | 3,080 | 6,870 | 8,710 | 14,500 | 3,660 | 2,140 | 5,250 | 1,440 | 1,780 | 12,750 | 7,780 |
| 4. | 4,300 | 3,080 | 14,050 | 7,780 | 34,400 | 5,010 | 1,960 | 4,530 | 1,440 | 1,610 | 10,040 | 6,870 |
| 5. | 6,020 | 3,080 | 23,400 | 7,170 | 32,400 | 4,770 | 1,960 | 4,300 | 1,280 | 1,440 | 6,870 | 9,690 |
| 6. | 9,360 | 3,080 | 25,700 | 7,470 | 28,700 | 4,070 | 1,610 | 4,070 | 1,120 | 1,280 | 5,760 | 11,540 |
| 7. | 8,090 | 8,710 | 45,800 | 8,400 | 24,600 | 3,460 | 1,610 | 5,010 | 970 | 1,280 | 4,770 | 13,600 |
| 8. | 6,580 | 10,040 | 36,500 | 9,030 | 18,830 | 3,270 | 1,610 | 4,530 | 970 | 1,120 | 3,860 | 12,340 |
| 9. | 6,580 | 9,360 | 26,900 | 9,690 | 15,890 | 3,270 | 1,610 | 4,300 | 830 | 970 | 3,660 | 10,040 |
| 10. | 6,580 | 8,710 | 22,890 | 29,300 | 13,170 | 3,660 | 1,780 | 3,460 | 830 | 970 | 4,070 | 9,030 |
| 11. | 6,580 | 8,090 | 28,100 | 34,400 | 11,940 | 3,660 | 1,780 | 3,270 | 600 | 970 | 4,300 | 8,400 |
| 12. | 7,170 | 8,400 | 33,100 | 28,100 | 11,540 | 3,460 | 2,140 | 4,070 | 600 | 970 | 6,300 | 9,030 |
| 13. | 6,300 | 7,470 | 34,400 | 21,870 | 11,150 | 3,080 | 1,960 | 3,860 | 710 | 1,120 | 5,500 | 9,690 |
| 14. | 3,660 | 6,580 | 33,100 | 17,830 | 20,850 | 2,890 | 1,960 | 3,460 | 710 | 1,280 | 5,010 | 10,040 |
| 15. | 3,460 | 5,760 | 27,500 | 16,370 | 25,700 | 2,700 | 1,960 | 3,080 | 710 | 1,280 | 4,530 | 12,750 |
| 16. | 4,530 | 5,760 | 21,870 | 21,360 | 24,000 | 2,510 | 2,140 | 2,700 | 830 | 1,280 | 4,300 | 25,700 |
| 17. | 4,530 | 5,760 | 18,830 | 28,100 | 22,890 | 2,320 | 2,140 | 2,320 | 970 | 1,120 | 4,770 | 27,500 |
| 18. | 4,530 | 6,020 | 14,050 | 22,890 | 15,420 | 2,320 | 2,320 | 2,140 | 1,120 | 970 | 13,170 | 21,870 |
| 19. | 5,250 | 8,400 | 14,960 | 18,830 | 12,750 | 2,320 | 2,320 | 1,780 | 1,280 | 970 | 11,540 | 19,830 |
| 20. | 4,530 | 8,400 | 15,420 | 15,420 | 12,750 | 2,700 | 2,320 | 2,140 | 1,280 | 970 | 9,090 | 17,830 |
| 21. | 2,890 | 8,710 | 31,100 | 13,170 | 11,940 | 3,080 | 2,320 | 2,320 | 1,280 | 1,120 | 7,080 | 14,960 |
| 22. | 3,270 | 9,360 | 34,400 | 11,150 | 11,150 | 2,510 | 2,510 | 2,140 | 1,440 | 1,280 | 6,580 | 13,170 |
| 23. | 4,070 | 14,050 | 32,400 | 9,690 | 9,030 | 2,320 | 2,510 | 1,960 | 1,610 | 1,610 | 5,760 | 11,940 |
| 24. | 4,530 | 34,400 | 34,400 | 8,710 | 7,170 | 2,320 | 4,070 | 8,090 | 1,780 | 1,610 | 5,250 | 9,030 |
| 25. | 5,010 | 28,100 | 53,000 | 7,780 | 6,580 | 2,320 | 4,770 | 6,020 | 5,010 | 1,440 | 4,770 | 8,400 |
| 26. | 4,530 | 19,830 | 44,300 | 6,870 | 6,020 | 2,510 | 5,250 | 4,530 | 4,770 | 1,440 | 4,070 | 7,470 |
| 27. | 4,770 | 14,500 | 31,800 | 6,870 | 5,760 | 2,510 | 4,070 | 3,080 | 4,530 | 1,440 | 5,250 | 6,580 |
| 28. | 3,080 | 10,770 | 24,000 | 6,580 | 5,500 | 2,510 | 6,870 | 2,510 | 4,070 | 1,280 | 8,090 | 6,580 |
| 29. | 3,660 | ----- | 19,830 | 6,300 | 5,010 | 2,510 | 11,940 | 2,140 | 3,460 | 1,280 | 16,850 | 5,010 |
| 30. | 3,860 | ----- | 14,960 | 5,760 | 4,530 | 2,140 | 12,750 | 1,780 | 2,320 | 1,120 | 13,600 | 4,070 |
| 31. | 3,660 | ----- | 12,340 | ----- | 4,070 | ----- | 9,030 | 1,780 | ----- | 1,120 | ----- | 4,530 |
| 1898. | | | | | | | | | | | | |
| 1. | 4,070 | 6,300 | 8,090 | 30,500 | 11,940 | 8,090 | 4,070 | 2,140 | 2,330 | 1,440 | 7,470 | 3,660 |
| 2. | 3,860 | 5,500 | 7,170 | 22,890 | 10,040 | 6,870 | 3,270 | 1,960 | 2,140 | 1,280 | 6,580 | 3,860 |
| 3. | 3,460 | 5,250 | 7,170 | 18,830 | 9,690 | 6,020 | 2,890 | 2,140 | 1,960 | 1,280 | 5,760 | 3,860 |
| 4. | 3,460 | 4,300 | 6,870 | 14,960 | 9,030 | 5,250 | 2,700 | 2,700 | 1,960 | 1,280 | 5,010 | 4,300 |
| 5. | 3,660 | 6,020 | 6,580 | 12,750 | 7,780 | 4,530 | 2,320 | 6,020 | 1,780 | 1,440 | 4,530 | 4,770 |
| 6. | 4,070 | 6,300 | 6,300 | 11,150 | 8,090 | 4,070 | 2,140 | 6,300 | 1,780 | 2,320 | 4,070 | 5,500 |
| 7. | 4,300 | 6,870 | 6,020 | 9,690 | 9,030 | 3,660 | 1,960 | 4,070 | 1,610 | 2,140 | 4,070 | 5,500 |
| 8. | 4,300 | 6,580 | 6,580 | 8,710 | 9,030 | 3,660 | 1,780 | 3,080 | 1,610 | 2,700 | 3,660 | 5,250 |
| 9. | 4,300 | 6,300 | 6,870 | 8,090 | 9,360 | 3,270 | 1,780 | 2,700 | 1,960 | 2,510 | 3,660 | 4,530 |
| 10. | 4,300 | 6,300 | 9,030 | 7,470 | 10,040 | 2,890 | 1,870 | 2,510 | 2,140 | 2,510 | 3,660 | 4,070 |
| 11. | 5,250 | 6,870 | 12,340 | 7,170 | 8,710 | 3,270 | 1,610 | 2,320 | 1,780 | 2,320 | 12,570 | 3,660 |
| 12. | 5,500 | 9,030 | 19,830 | 6,580 | 7,780 | 3,660 | 1,610 | 2,140 | 1,440 | 2,320 | 38,600 | 3,270 |
| 13. | 6,300 | 31,800 | 35,800 | 6,300 | 7,170 | 4,070 | 1,610 | 2,140 | 1,610 | 2,510 | 25,100 | 3,660 |
| 14. | 40,000 | 29,300 | 38,600 | 5,760 | 6,580 | 5,250 | 1,440 | 3,460 | 1,440 | 2,700 | 19,830 | 3,270 |
| 15. | 33,700 | 24,000 | 38,600 | 5,760 | 6,580 | 7,780 | 1,440 | 2,890 | 1,440 | 3,080 | 14,960 | 3,080 |
| 16. | 26,300 | 19,830 | 24,600 | 8,090 | 6,300 | 6,870 | 1,440 | 2,510 | 1,440 | 2,890 | 13,170 | 2,890 |
| 17. | 30,500 | 12,340 | 19,830 | 8,090 | 6,580 | 5,250 | 1,280 | 2,140 | 1,280 | 2,700 | 10,040 | 2,700 |
| 18. | 24,600 | 11,940 | 17,340 | 8,090 | 6,580 | 4,070 | 1,280 | 2,140 | 1,280 | 2,510 | 8,400 | 2,890 |
| 19. | 18,830 | 10,770 | 15,420 | 7,170 | 9,690 | 3,860 | 1,280 | 2,890 | 1,120 | 2,700 | 7,780 | 3,080 |
| 20. | 14,960 | 12,750 | 35,800 | 6,870 | 9,360 | 3,660 | 1,280 | 22,380 | 1,280 | 4,770 | 7,170 | 3,460 |
| 21. | 16,370 | 14,960 | 49,000 | 6,580 | 14,050 | 3,460 | 1,610 | 12,750 | 1,120 | 5,760 | 6,580 | 4,070 |
| 22. | 19,830 | 20,340 | 44,300 | 6,580 | 12,750 | 3,270 | 1,780 | 9,360 | 1,280 | 10,400 | 6,020 | 5,000 |
| 23. | 23,400 | 18,830 | 86,800 | 6,300 | 14,050 | 3,270 | 1,780 | 6,580 | 1,120 | 35,800 | 5,760 | 14,960 |
| 24. | 42,100 | 14,960 | 162,600 | 9,690 | 14,050 | 2,890 | 1,610 | 5,250 | 1,120 | 35,100 | 5,500 | 31,100 |
| 25. | 37,900 | 13,600 | 85,800 | 27,500 | 18,830 | 2,700 | 1,610 | 4,300 | 1,120 | 23,400 | 5,010 | 25,100 |
| 26. | 26,900 | 11,940 | 45,800 | 33,700 | 19,830 | 2,510 | 1,610 | 4,300 | 1,280 | 13,600 | 4,770 | 19,830 |
| 27. | 22,880 | 10,400 | 40,000 | 30,500 | 16,370 | 2,320 | 3,860 | 3,860 | 1,280 | 12,340 | 4,300 | 14,960 |
| 28. | 18,830 | 9,030 | 24,000 | 20,340 | 14,960 | 2,140 | 3,860 | 3,660 | 1,440 | 13,600 | 3,860 | 12,340 |
| 29. | 14,960 | ----- | 19,830 | 16,850 | 12,750 | 4,300 | 2,700 | 3,460 | 1,280 | 12,340 | 3,660 | 10,770 |
| 30. | 12,340 | ----- | 42,100 | 14,050 | 10,770 | 5,760 | 2,140 | 3,270 | 1,440 | 10,400 | 3,660 | 10,440 |
| 31. | 10,040 | ----- | 43,500 | ----- | 9,360 | ----- | 2,140 | 3,080 | ----- | 8,400 | ----- | 9,360 |

Mean daily discharge, in second-feet, of West Branch of Susquehanna River at Williamsport, Pa., 1895-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|--------|--------|--------|--------|--------|-------|-------|-------|-------|-------|---------|--------|
| 1899. | | | | | | | | | | | | |
| 1. | 9,360 | 6,580 | 28,100 | 22,380 | 6,300 | 5,010 | 2,510 | 1,120 | 2,890 | 1,120 | 1,120 | 3,080 |
| 2. | 9,360 | 6,020 | 25,100 | 20,340 | 6,020 | 5,010 | 2,320 | 970 | 3,080 | 1,280 | 9,030 | 3,080 |
| 3. | 9,360 | 5,500 | 25,100 | 18,330 | 5,760 | 4,770 | 2,140 | 970 | 3,080 | 1,280 | 9,030 | 3,270 |
| 4. | 9,030 | 5,250 | 28,100 | 14,960 | 5,760 | 4,530 | 1,960 | 710 | 3,080 | 1,120 | 9,030 | 3,270 |
| 5. | 12,750 | 5,500 | 57,200 | 11,540 | 6,300 | 4,300 | 1,780 | 830 | 3,080 | 1,120 | 7,780 | 3,860 |
| 6. | 23,400 | 6,020 | 68,800 | 10,770 | 5,250 | 3,860 | 1,610 | 710 | 2,890 | 1,120 | 6,300 | 3,270 |
| 7. | 29,300 | 6,020 | 53,000 | 10,770 | 4,770 | 3,460 | 1,610 | 600 | 2,700 | 1,120 | 5,010 | 3,080 |
| 8. | 19,830 | 6,300 | 36,500 | 22,380 | 4,530 | 3,080 | 1,610 | 600 | 2,700 | 1,120 | 4,300 | 3,460 |
| 9. | 14,960 | 6,300 | 25,100 | 28,100 | 4,770 | 2,700 | 1,440 | 710 | 2,510 | 1,120 | 3,860 | 3,270 |
| 10. | 10,770 | 6,020 | 19,830 | 28,100 | 5,010 | 2,700 | 1,440 | 710 | 2,510 | 1,120 | 4,070 | 3,460 |
| 11. | 9,690 | 5,760 | 15,420 | 22,380 | 5,010 | 2,510 | 1,440 | 830 | 2,320 | 1,120 | 4,300 | 3,460 |
| 12. | 9,360 | 5,500 | 19,830 | 19,830 | 5,760 | 2,510 | 1,440 | 830 | 2,140 | 1,120 | 4,530 | 3,860 |
| 13. | 9,030 | 5,010 | 25,100 | 22,380 | 5,250 | 2,320 | 1,440 | 1,780 | 1,960 | 1,120 | 4,770 | 23,400 |
| 14. | 10,770 | 4,770 | 28,100 | 25,100 | 5,010 | 2,140 | 1,440 | 1,440 | 1,780 | 970 | 5,500 | 26,300 |
| 15. | 12,750 | 4,770 | 24,000 | 25,100 | 4,770 | 2,140 | 1,440 | 1,120 | 1,610 | 970 | 6,300 | 19,830 |
| 16. | 14,960 | 5,010 | 18,830 | 22,380 | 4,530 | 2,140 | 1,440 | 830 | 1,610 | 970 | 6,870 | 15,890 |
| 17. | 17,340 | 5,250 | 17,340 | 19,830 | 4,070 | 1,960 | 1,440 | 970 | 1,440 | 970 | 7,170 | 12,340 |
| 18. | 17,340 | 5,500 | 17,340 | 14,050 | 5,760 | 1,960 | 1,780 | 970 | 1,280 | 970 | 8,400 | 9,690 |
| 19. | 16,370 | 6,020 | 26,300 | 13,170 | 22,380 | 1,780 | 2,320 | 830 | 1,280 | 970 | 8,090 | 9,360 |
| 20. | 11,540 | 7,170 | 37,900 | 11,940 | 25,100 | 1,780 | 2,890 | 710 | 1,120 | 970 | 8,090 | 9,030 |
| 21. | 9,360 | 7,470 | 34,400 | 11,150 | 18,830 | 1,610 | 3,460 | 600 | 1,120 | 970 | 7,170 | 10,770 |
| 22. | 9,360 | 10,400 | 26,900 | 10,400 | 13,170 | 1,280 | 2,510 | 830 | 970 | 970 | 6,300 | 13,170 |
| 23. | 9,030 | 14,960 | 22,380 | 9,690 | 10,040 | 1,440 | 2,140 | 710 | 970 | 970 | 5,500 | 10,770 |
| 24. | 9,030 | 22,380 | 23,400 | 8,710 | 8,400 | 1,280 | 1,780 | 710 | 1,120 | 970 | 5,010 | 11,540 |
| 25. | 9,690 | 25,100 | 17,340 | 8,090 | 6,870 | 2,700 | 1,610 | 710 | 970 | 970 | 4,770 | 12,750 |
| 26. | 10,400 | 19,830 | 17,340 | 7,470 | 6,300 | 2,140 | 1,440 | 830 | 970 | 830 | 4,530 | 13,600 |
| 27. | 8,400 | 14,960 | 17,340 | 8,710 | 5,760 | 2,700 | 1,440 | 2,890 | 970 | 830 | 4,300 | 11,540 |
| 28. | 8,090 | 31,100 | 16,370 | 8,400 | 5,250 | 2,510 | 1,120 | 5,250 | 970 | 830 | 3,860 | 10,770 |
| 29. | 7,780 | ----- | 10,350 | 7,470 | 5,010 | 2,700 | 970 | 4,070 | 1,120 | 890 | 3,860 | 9,030 |
| 30. | 7,170 | ----- | 31,100 | 6,870 | 5,010 | 2,700 | 1,120 | 3,460 | 1,120 | 710 | 3,460 | 8,710 |
| 31. | 6,580 | ----- | 28,100 | ----- | 5,250 | ----- | 1,120 | 3,080 | ----- | 710 | ----- | 8,090 |
| 1900. | | | | | | | | | | | | |
| 1. | 7,470 | 6,300 | 9,690 | 9,360 | 7,470 | 7,470 | 2,700 | 1,440 | 1,780 | 710 | 2,140 | 17,340 |
| 2. | 7,170 | 6,020 | 35,800 | 9,030 | 6,870 | 6,300 | 3,080 | 1,440 | 1,610 | 710 | 2,140 | 13,600 |
| 3. | 6,870 | 6,020 | 30,500 | 10,400 | 6,300 | 7,170 | 2,700 | 1,440 | 1,440 | 710 | 1,960 | 12,750 |
| 4. | 6,580 | 6,300 | 24,000 | 11,540 | 5,760 | 8,090 | 2,140 | 1,280 | 1,280 | 830 | 1,960 | 10,770 |
| 5. | 6,300 | 6,300 | 18,330 | 12,750 | 5,500 | 8,090 | 1,960 | 1,280 | 1,280 | 830 | 1,960 | 22,380 |
| 6. | 6,020 | 7,470 | 14,500 | 11,540 | 5,250 | 6,580 | 2,140 | 1,120 | 1,120 | 830 | 1,960 | 24,600 |
| 7. | 5,500 | 6,580 | 14,960 | 13,600 | 4,770 | 5,760 | 2,320 | 1,120 | 970 | 830 | 1,780 | 17,340 |
| 8. | 5,250 | 6,580 | 24,000 | 20,850 | 4,530 | 5,250 | 2,320 | 970 | 970 | 970 | 1,780 | 16,850 |
| 9. | 5,500 | 11,540 | 20,850 | 22,380 | 4,070 | 5,010 | 2,140 | 970 | 970 | 1,120 | 1,780 | 12,750 |
| 10. | 5,500 | 18,330 | 19,330 | 18,830 | 4,070 | 4,530 | 1,960 | 830 | 970 | 1,960 | 1,780 | 11,540 |
| 11. | 5,500 | 15,890 | 23,400 | 15,890 | 4,070 | 4,070 | 2,140 | 830 | 970 | 2,320 | 1,780 | 10,400 |
| 12. | 5,760 | 13,600 | 19,830 | 12,750 | 4,070 | 3,860 | 2,320 | 710 | 830 | 2,140 | 1,960 | 8,090 |
| 13. | 6,020 | 13,600 | 14,050 | 11,540 | 4,070 | 3,660 | 2,140 | 710 | 830 | 2,140 | 1,960 | 6,580 |
| 14. | 6,300 | 33,700 | 11,540 | 10,770 | 4,070 | 3,270 | 3,460 | 830 | 830 | 2,140 | 1,960 | 6,300 |
| 15. | 6,580 | 32,400 | 10,040 | 10,040 | 4,770 | 3,460 | 2,700 | 710 | 830 | 1,960 | 1,960 | 6,020 |
| 16. | 6,580 | 20,850 | 8,090 | 9,360 | 4,770 | 3,860 | 2,320 | 710 | 710 | 2,320 | 1,780 | 4,770 |
| 17. | 6,580 | 15,890 | 6,020 | 9,360 | 4,070 | 3,460 | 1,960 | 830 | 710 | 2,510 | 1,780 | 3,860 |
| 18. | 7,470 | 12,340 | 5,760 | 14,050 | 4,070 | 3,270 | 1,780 | 830 | 830 | 2,320 | 1,610 | 3,660 |
| 19. | 9,030 | 9,030 | 5,250 | 22,890 | 4,070 | 3,080 | 1,780 | 830 | 830 | 1,960 | 1,610 | 4,300 |
| 20. | 11,540 | 8,400 | 6,870 | 22,380 | 5,250 | 2,890 | 1,610 | 830 | 830 | 1,780 | 1,610 | 4,070 |
| 21. | 67,900 | 8,090 | 23,400 | 19,330 | 5,250 | 2,700 | 1,610 | 970 | 830 | 1,610 | 1,780 | 4,070 |
| 22. | 67,900 | 15,890 | 18,830 | 15,890 | 4,770 | 2,510 | 1,440 | 1,610 | 830 | 1,610 | 2,140 | 3,860 |
| 23. | 42,800 | 41,400 | 13,600 | 15,890 | 4,070 | 2,510 | 1,440 | 2,140 | 710 | 1,610 | 2,890 | 3,860 |
| 24. | 29,300 | 25,700 | 15,890 | 17,830 | 3,660 | 2,320 | 1,440 | 1,960 | 710 | 1,610 | 3,080 | 3,660 |
| 25. | 20,850 | 15,420 | 18,830 | 16,850 | 3,460 | 2,140 | 1,440 | 1,960 | 710 | 1,960 | 5,760 | 3,860 |
| 26. | 17,340 | 14,500 | 14,500 | 14,500 | 3,660 | 2,320 | 1,280 | 1,960 | 710 | 3,660 | 12,750 | 4,300 |
| 27. | 13,600 | 7,170 | 13,170 | 12,340 | 4,070 | 2,140 | 1,610 | 2,140 | 710 | 3,080 | 110,100 | 5,010 |
| 28. | 11,540 | 9,360 | 11,540 | 10,400 | 3,860 | 1,960 | 2,140 | 1,960 | 710 | 2,890 | 58,900 | 4,770 |
| 29. | 9,690 | ----- | 11,540 | 9,030 | 3,860 | 1,780 | 1,960 | 2,140 | 710 | 2,700 | 29,300 | 4,770 |
| 30. | 10,040 | ----- | 11,150 | 8,400 | 9,690 | 1,780 | 1,780 | 2,140 | 710 | 2,320 | 15,890 | 4,770 |
| 31. | 7,470 | ----- | 10,040 | ----- | 8,400 | ----- | 1,610 | 1,960 | ----- | 2,320 | ----- | 4,530 |

*Mean daily discharge, in second-feet, of West Branch of Susquehanna River at
Williamsport, Pa., 1895-1904—Continued.*

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|--------|--------|---------|---------|--------|--------|--------|--------|--------|--------|--------|---------|
| 1901. | | | | | | | | | | | | |
| 1. | 4,770 | 3,270 | 1,960 | 15,890 | 9,690 | 41,400 | 6,870 | 2,510 | 6,580 | 3,660 | 1,610 | 6,580 |
| 2. | 4,770 | 2,890 | 2,140 | 12,750 | 9,030 | 24,600 | 5,500 | 2,320 | 8,090 | 3,080 | 1,440 | 6,020 |
| 3. | 3,860 | 2,890 | 2,700 | 11,540 | 9,690 | 23,400 | 4,770 | 2,140 | 22,380 | 4,070 | 1,440 | 6,580 |
| 4. | 2,320 | 2,890 | 2,890 | 18,330 | 11,940 | 20,850 | 4,530 | 1,780 | 16,850 | 3,080 | 1,610 | 5,500 |
| 5. | 2,140 | 3,270 | 4,300 | 19,330 | 10,400 | 16,850 | 4,300 | 1,610 | 11,940 | 2,890 | 1,440 | 4,770 |
| 6. | 2,140 | 3,660 | 6,580 | 23,400 | 9,690 | 14,050 | 4,070 | 1,610 | 10,040 | 2,700 | 1,440 | 4,070 |
| 7. | 2,320 | 5,250 | 8,710 | 39,300 | 8,710 | 13,600 | 3,860 | 1,780 | 7,470 | 2,510 | 1,440 | 3,660 |
| 8. | 2,320 | 3,860 | 6,580 | 54,600 | 8,090 | 15,890 | 3,660 | 3,660 | 5,760 | 1,960 | 1,440 | 3,660 |
| 9. | 2,890 | 2,890 | 5,500 | 52,200 | 6,870 | 14,960 | 3,270 | 3,860 | 5,010 | 1,780 | 1,280 | 3,660 |
| 10. | 3,080 | 2,700 | 6,580 | 39,300 | 7,470 | 13,600 | 3,080 | 3,460 | 4,530 | 1,960 | 1,280 | 6,020 |
| 11. | 3,660 | 2,700 | 23,400 | 30,500 | 7,780 | 11,540 | 2,890 | 3,080 | 4,070 | 1,960 | 1,120 | 22,890 |
| 12. | 4,300 | 3,860 | 46,600 | 24,600 | 7,780 | 10,040 | 2,700 | 2,890 | 4,070 | 1,960 | 1,280 | 18,830 |
| 13. | 8,400 | 5,010 | 37,200 | 19,330 | 7,780 | 9,360 | 2,320 | 2,320 | 4,070 | 2,140 | 1,440 | 15,890 |
| 14. | 11,540 | 4,300 | 26,300 | 17,340 | 8,400 | 7,470 | 2,320 | 1,960 | 4,770 | 2,700 | 1,440 | 14,500 |
| 15. | 10,400 | 3,080 | 20,850 | 15,890 | 8,400 | 6,580 | 2,320 | 1,780 | 5,250 | 2,320 | 3,080 | 150,900 |
| 16. | 9,690 | 2,890 | 22,380 | 14,960 | 8,090 | 8,400 | 2,140 | 1,960 | 6,020 | 1,780 | 2,510 | 124,900 |
| 17. | 8,710 | 2,700 | 18,330 | 12,750 | 7,470 | 7,780 | 2,140 | 7,470 | 5,760 | 2,320 | 2,700 | 58,900 |
| 18. | 8,090 | 2,510 | 15,890 | 10,400 | 8,090 | 6,300 | 2,510 | 7,470 | 6,580 | 2,140 | 3,080 | 34,400 |
| 19. | 6,300 | 2,510 | 13,600 | 10,400 | 7,780 | 5,760 | 2,510 | 11,540 | 6,580 | 1,960 | 2,700 | 23,400 |
| 20. | 5,010 | 2,700 | 19,330 | 9,690 | 7,170 | 5,500 | 2,320 | 10,400 | 6,020 | 1,780 | 2,320 | 15,890 |
| 21. | 4,070 | 2,890 | 26,300 | 58,900 | 6,580 | 6,300 | 2,140 | 9,690 | 5,250 | 1,780 | 2,140 | 13,600 |
| 22. | 3,860 | 2,700 | 39,300 | 89,900 | 3,660 | 9,690 | 1,960 | 11,940 | 4,770 | 1,610 | 1,960 | 11,150 |
| 23. | 4,530 | 2,510 | 32,400 | 63,400 | 17,340 | 11,540 | 1,610 | 9,690 | 4,070 | 1,440 | 1,780 | 8,710 |
| 24. | 5,500 | 2,140 | 26,300 | 40,700 | 15,890 | 11,150 | 1,610 | 15,420 | 3,860 | 1,440 | 3,270 | 8,400 |
| 25. | 5,010 | 1,960 | 20,850 | 32,400 | 15,890 | 10,400 | 1,610 | 28,100 | 3,660 | 1,440 | 16,370 | 8,400 |
| 26. | 5,250 | 1,960 | 28,100 | 26,300 | 13,600 | 9,030 | 1,780 | 22,380 | 3,080 | 1,440 | 21,870 | 8,710 |
| 27. | 5,500 | 2,140 | 46,600 | 20,850 | 13,600 | 8,090 | 1,960 | 14,500 | 2,890 | 1,440 | 16,850 | 9,360 |
| 28. | 5,500 | 2,140 | 52,200 | 15,890 | 26,900 | 8,400 | 2,140 | 10,770 | 2,510 | 1,440 | 11,150 | 7,780 |
| 29. | 5,760 | ----- | 37,200 | 13,600 | 54,600 | 8,710 | 2,320 | 8,090 | 3,080 | 1,610 | 8,400 | 7,170 |
| 30. | 5,500 | ----- | 28,100 | 11,540 | 77,500 | 8,090 | 2,510 | 6,580 | 3,860 | 1,780 | 8,090 | 6,580 |
| 31. | 3,460 | ----- | 19,330 | ----- | 61,600 | ----- | 2,510 | 5,760 | ----- | 1,610 | ----- | 7,780 |
| 1902. | | | | | | | | | | | | |
| 1. | 7,170 | 10,770 | 154,100 | 18,330 | 5,250 | 2,700 | 31,100 | 13,600 | 1,280 | 5,760 | 3,860 | 2,140 |
| 2. | 6,300 | 10,400 | 164,100 | 16,850 | 5,250 | 2,510 | 25,700 | 13,170 | 1,440 | 10,040 | 3,460 | 2,700 |
| 3. | 5,500 | 13,600 | 103,750 | 14,960 | 5,010 | 2,510 | 20,340 | 11,940 | 1,280 | 6,870 | 3,270 | 3,080 |
| 4. | 5,250 | 12,340 | 67,900 | 13,170 | 5,760 | 2,320 | 40,700 | 10,770 | 1,280 | 5,250 | 3,080 | 4,530 |
| 5. | 5,010 | 11,540 | 42,800 | 11,540 | 5,760 | 2,320 | 49,000 | 9,690 | 1,280 | 5,010 | 2,890 | 5,010 |
| 6. | 4,770 | 9,690 | 29,900 | 10,770 | 6,300 | 2,700 | 33,100 | 7,470 | 1,120 | 4,770 | 2,890 | 5,250 |
| 7. | 4,770 | 9,360 | 22,380 | 11,540 | 6,300 | 2,510 | 34,400 | 6,870 | 1,120 | 4,530 | 2,700 | 4,770 |
| 8. | 4,770 | 8,710 | 17,830 | 12,840 | 7,170 | 2,510 | 25,100 | 6,580 | 1,120 | 4,530 | 2,890 | 4,770 |
| 9. | 5,010 | 8,400 | 14,960 | 70,700 | 7,780 | 2,320 | 19,830 | 6,020 | 1,120 | 4,070 | 2,890 | 6,020 |
| 10. | 5,010 | 7,780 | 15,890 | 105,500 | 7,170 | 2,140 | 18,330 | 5,500 | 1,440 | 3,660 | 2,700 | 3,860 |
| 11. | 5,010 | 7,470 | 19,830 | 6,700 | 6,580 | 2,320 | 27,500 | 5,010 | 1,280 | 3,270 | 2,700 | 4,070 |
| 12. | 5,010 | 6,580 | 24,000 | 45,000 | 6,020 | 2,320 | 24,600 | 4,530 | 1,280 | 2,890 | 2,510 | 4,770 |
| 13. | 5,010 | 6,300 | 40,000 | 31,800 | 5,500 | 2,700 | 19,830 | 5,250 | 1,440 | 2,510 | 2,510 | 6,870 |
| 14. | 4,770 | 6,580 | 60,700 | 25,100 | 5,250 | 2,890 | 13,600 | 4,300 | 1,280 | 2,140 | 2,320 | 11,150 |
| 15. | 4,300 | 5,500 | 49,000 | 19,830 | 5,010 | 3,270 | 10,400 | 3,860 | 1,120 | 2,510 | 2,140 | 8,400 |
| 16. | 4,300 | 4,770 | 31,800 | 15,890 | 4,530 | 3,660 | 8,400 | 3,660 | 1,120 | 2,700 | 2,140 | 6,580 |
| 17. | 4,070 | 4,300 | 75,500 | 13,600 | 4,070 | 3,860 | 6,870 | 3,270 | 1,120 | 3,270 | 1,960 | 17,340 |
| 18. | 4,070 | 4,300 | 65,200 | 12,840 | 3,860 | 4,070 | 7,470 | 3,080 | 1,120 | 3,080 | 1,960 | 29,900 |
| 19. | 3,660 | 5,250 | 42,800 | 10,770 | 3,660 | 4,070 | 8,710 | 2,890 | 970 | 2,890 | 1,960 | 20,340 |
| 20. | 3,270 | 4,530 | 29,900 | 9,360 | 3,460 | 3,660 | 11,150 | 2,700 | 830 | 2,700 | 1,780 | 14,960 |
| 21. | 4,070 | 3,860 | 22,380 | 11,150 | 3,460 | 3,660 | 17,340 | 2,510 | 830 | 2,700 | 1,960 | 14,050 |
| 22. | 14,960 | 4,530 | 18,330 | 8,090 | 3,460 | 3,460 | 22,380 | 2,890 | 830 | 2,510 | 1,960 | 29,300 |
| 23. | 22,130 | 3,860 | 15,420 | 7,170 | 3,270 | 3,080 | 19,830 | 2,700 | 830 | 2,320 | 1,960 | 48,200 |
| 24. | 11,540 | 3,660 | 13,600 | 6,300 | 3,270 | 2,890 | 16,850 | 2,320 | 830 | 2,140 | 1,960 | 36,500 |
| 25. | 11,540 | 3,660 | 11,540 | 6,020 | 3,270 | 1,440 | 17,830 | 2,140 | 1,280 | 2,140 | 2,140 | 24,600 |
| 26. | 9,690 | 4,070 | 10,400 | 7,470 | 3,270 | 3,080 | 17,340 | 1,960 | 1,960 | 2,320 | 2,320 | 18,330 |
| 27. | 10,040 | 6,870 | 9,360 | 5,250 | 3,460 | 3,860 | 18,830 | 1,780 | 4,770 | 1,960 | 2,320 | 15,420 |
| 28. | 9,690 | 49,800 | 8,710 | 5,010 | 3,660 | 6,020 | 15,890 | 1,120 | 5,500 | 2,700 | 2,320 | 10,040 |
| 29. | 9,360 | ----- | 9,360 | 4,770 | 3,270 | 5,500 | 14,500 | 1,280 | 6,020 | 2,510 | 2,140 | 11,150 |
| 30. | 10,040 | ----- | 16,370 | 5,250 | 3,080 | 10,770 | 11,540 | 1,440 | 4,770 | 3,080 | ----- | 8,400 |
| 31. | 9,690 | ----- | 19,330 | ----- | 2,890 | ----- | 14,500 | 1,280 | ----- | 3,460 | ----- | 5,250 |

Mean daily discharge, in second-feet, of West Branch of Susquehanna River at Williamsport, Pa., 1895-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|--------|--------|---------|---------|--------|--------|--------|--------|--------|--------|--------|-------|
| 1903. | | | | | | | | | | | | |
| 1. | 6,580 | 41,400 | 110,700 | 17,340 | 5,010 | 2,140 | 11,940 | 5,760 | 17,340 | 2,140 | 3,860 | 4,070 |
| 2. | 5,250 | 18,330 | 80,500 | 16,370 | 4,770 | 1,280 | 10,400 | 4,770 | 14,960 | 2,140 | 3,460 | 4,070 |
| 3. | 6,580 | 26,300 | 44,300 | 14,960 | 4,530 | 1,960 | 9,690 | 4,070 | 11,940 | 1,960 | 3,460 | 4,070 |
| 4. | 10,770 | 47,400 | 31,100 | 13,600 | 4,070 | 1,440 | 11,150 | 3,660 | 9,690 | 1,960 | 3,270 | 3,660 |
| 5. | 13,170 | 93,100 | 24,600 | 14,050 | 4,070 | 1,440 | 9,690 | 5,250 | 8,090 | 2,140 | 3,080 | 3,660 |
| 6. | 14,960 | 69,800 | 24,000 | 12,340 | 4,070 | 1,440 | 8,710 | 8,400 | 6,870 | 2,890 | 3,270 | 3,660 |
| 7. | 13,600 | 43,500 | 24,600 | 11,540 | 4,070 | 1,610 | 18,330 | 9,030 | 5,760 | 3,460 | 3,080 | 3,460 |
| 8. | 11,150 | 28,100 | 26,900 | 11,540 | 3,460 | 2,140 | 14,960 | 9,690 | 5,250 | 4,070 | 3,080 | 3,460 |
| 9. | 8,710 | 21,870 | 60,700 | 13,600 | 3,270 | 2,890 | 10,400 | 8,090 | 5,010 | 17,830 | 3,080 | 3,270 |
| 10. | 4,530 | 17,340 | 65,200 | 15,420 | 2,890 | 2,890 | 8,090 | 6,300 | 5,500 | 28,100 | 2,890 | 3,460 |
| 11. | 4,530 | 14,050 | 50,600 | 16,370 | 2,890 | 4,300 | 6,580 | 5,500 | 6,020 | 19,330 | 2,890 | 3,460 |
| 12. | 10,770 | 14,500 | 51,400 | 14,960 | 2,890 | 4,530 | 6,580 | 5,010 | 7,780 | 15,890 | 2,890 | 2,890 |
| 13. | 10,400 | 19,330 | 47,400 | 17,340 | 2,700 | 8,710 | 6,580 | 4,530 | 6,580 | 11,940 | 2,700 | 2,700 |
| 14. | 10,400 | 21,870 | 35,100 | 18,830 | 2,700 | 7,780 | 5,760 | 4,070 | 5,250 | 9,690 | 2,510 | 3,860 |
| 15. | 10,400 | 20,340 | 28,100 | 40,000 | 2,700 | 8,400 | 5,010 | 3,460 | 4,770 | 8,400 | 2,510 | 3,080 |
| 16. | 10,040 | 19,830 | 22,890 | 56,300 | 2,510 | 9,690 | 4,530 | 3,270 | 4,070 | 7,470 | 2,700 | 2,140 |
| 17. | 10,400 | 19,830 | 19,330 | 48,200 | 2,510 | 8,710 | 4,070 | 3,660 | 3,860 | 6,580 | 6,020 | 2,140 |
| 18. | 8,710 | 18,330 | 16,850 | 36,500 | 2,510 | 7,780 | 4,070 | 3,660 | 5,250 | 10,400 | 58,900 | 2,140 |
| 19. | 8,710 | 11,150 | 14,360 | 26,900 | 2,510 | 6,300 | 15,420 | 3,270 | 5,500 | 14,960 | 37,200 | 2,140 |
| 20. | 8,400 | 9,690 | 12,340 | 20,850 | 2,510 | 5,500 | 29,300 | 3,080 | 5,250 | 13,600 | 25,700 | 2,140 |
| 21. | 8,710 | 10,040 | 11,150 | 16,850 | 2,510 | 5,250 | 19,330 | 3,270 | 4,770 | 11,940 | 15,890 | 3,270 |
| 22. | 7,780 | 9,690 | 11,940 | 14,050 | 2,320 | 5,250 | 15,890 | 4,530 | 4,070 | 9,690 | 13,170 | 4,300 |
| 23. | 7,170 | 11,540 | 14,960 | 11,940 | 2,320 | 5,500 | 13,600 | 3,660 | 3,660 | 8,400 | 11,150 | 4,070 |
| 24. | 6,870 | 9,030 | 70,700 | 10,400 | 2,140 | 10,040 | 10,400 | 3,080 | 3,270 | 7,170 | 10,040 | 3,860 |
| 25. | 6,870 | 9,360 | 60,700 | 9,690 | 1,960 | 18,830 | 8,400 | 3,080 | 3,080 | 6,580 | 9,030 | 3,660 |
| 26. | 6,580 | 9,030 | 39,300 | 8,090 | 1,960 | 37,200 | 7,170 | 2,890 | 3,080 | 6,020 | 7,780 | 3,460 |
| 27. | 6,580 | 8,400 | 27,500 | 7,780 | 2,140 | 23,400 | 5,760 | 3,080 | 2,700 | 5,500 | 6,580 | 4,070 |
| 28. | 6,580 | 41,700 | 20,850 | 6,870 | 2,140 | 15,420 | 4,770 | 3,660 | 2,510 | 4,770 | 5,250 | 4,070 |
| 29. | 6,020 | ----- | 16,370 | 6,300 | 2,320 | 11,540 | 4,300 | 9,360 | 2,510 | 4,530 | 4,300 | 5,010 |
| 30. | 6,580 | ----- | 13,600 | 5,760 | 2,320 | 14,500 | 5,250 | 24,600 | 2,320 | 4,070 | 3,460 | 4,770 |
| 31. | 50,600 | ----- | 13,170 | ----- | 2,320 | ----- | 6,020 | 20,850 | ----- | 4,070 | ----- | 5,010 |
| 1904. | | | | | | | | | | | | |
| 1. | 4,530 | 9,030 | 5,760 | 19,330 | 28,100 | 8,400 | 4,770 | 2,140 | 1,120 | 1,780 | 2,140 | 1,440 |
| 2. | 4,530 | 7,780 | 23,400 | 107,800 | 23,400 | 8,710 | 4,300 | 1,960 | 1,120 | 2,140 | 2,140 | 1,280 |
| 3. | 4,070 | 6,580 | 26,300 | 73,600 | 19,330 | 8,710 | 3,860 | 1,960 | 1,120 | 2,140 | 2,140 | 1,280 |
| 4. | 4,070 | 6,020 | 135,100 | 41,400 | 15,890 | 8,090 | 3,460 | 1,960 | 970 | 1,960 | 2,140 | 1,120 |
| 5. | 3,660 | 6,580 | 104,300 | 29,300 | 13,600 | 18,830 | 3,080 | 1,780 | 970 | 1,780 | 1,960 | 1,120 |
| 6. | 3,660 | 5,010 | 37,200 | 22,880 | 11,540 | 11,540 | 3,080 | 1,610 | 970 | 1,780 | 1,960 | 1,120 |
| 7. | 3,460 | 5,500 | 25,700 | 20,340 | 10,400 | 8,710 | 3,460 | 1,610 | 830 | 1,610 | 1,780 | 1,120 |
| 8. | 3,460 | 13,600 | 115,000 | 18,330 | 9,360 | 7,780 | 3,660 | 1,610 | 830 | 1,610 | 1,610 | 1,120 |
| 9. | 3,460 | 46,600 | 72,600 | 18,330 | 8,400 | 7,170 | 7,780 | 1,440 | 830 | 1,440 | 1,440 | 1,120 |
| 10. | 3,460 | 26,900 | 41,400 | 34,400 | 7,470 | 7,170 | 11,150 | 1,280 | 830 | 1,440 | 1,440 | 1,120 |
| 11. | 3,460 | 18,330 | 26,900 | 37,200 | 7,170 | 7,470 | 29,950 | 1,280 | 830 | 1,440 | 1,610 | 1,120 |
| 12. | 3,460 | 14,500 | 20,850 | 28,700 | 6,580 | 7,470 | 21,870 | 1,120 | 1,280 | 1,280 | 1,610 | 1,120 |
| 13. | 3,460 | 10,770 | 17,340 | 24,600 | 6,020 | 6,300 | 15,420 | 1,120 | 1,440 | 1,610 | 1,610 | 970 |
| 14. | 3,460 | 9,030 | 14,960 | 21,360 | 5,250 | 5,760 | 11,940 | 1,280 | 1,280 | 2,510 | 1,780 | 970 |
| 15. | 3,270 | 9,690 | 13,600 | 17,340 | 6,580 | 5,010 | 9,030 | 1,280 | 1,280 | 3,080 | 1,780 | 970 |
| 16. | 3,270 | 9,030 | 11,150 | 14,500 | 7,780 | 5,500 | 7,780 | 1,280 | 1,440 | 2,890 | 1,610 | 970 |
| 17. | 3,080 | 8,400 | 10,040 | 14,500 | 7,470 | 6,870 | 6,580 | 970 | 1,280 | 2,700 | 1,610 | 970 |
| 18. | 3,080 | 8,090 | 9,030 | 14,050 | 7,170 | 6,020 | 5,250 | 970 | 1,280 | 2,510 | 1,610 | 830 |
| 19. | 3,080 | 7,470 | 9,690 | 13,600 | 12,340 | 5,500 | 4,300 | 970 | 1,120 | 2,320 | 1,610 | 830 |
| 20. | 3,080 | 6,580 | 11,540 | 11,540 | 27,500 | 4,770 | 4,070 | 1,120 | 970 | 2,140 | 1,610 | 830 |
| 21. | 2,890 | 6,300 | 20,850 | 10,400 | 24,600 | 4,770 | 3,460 | 1,280 | 970 | 2,320 | 1,440 | 830 |
| 22. | 3,080 | 6,020 | 21,870 | 9,360 | 18,330 | 6,580 | 3,080 | 1,280 | 830 | 3,080 | 1,440 | 830 |
| 23. | 27,500 | 5,760 | 21,360 | 8,400 | 14,500 | 8,710 | 2,700 | 1,960 | 830 | 3,460 | 1,440 | 830 |
| 24. | 70,700 | 8,710 | 42,100 | 7,470 | 12,340 | 9,690 | 2,700 | 2,140 | 830 | 3,270 | 1,610 | 970 |
| 25. | 41,400 | 10,400 | 45,000 | 7,170 | 11,150 | 7,170 | 2,510 | 2,510 | 830 | 3,080 | 1,440 | 970 |
| 26. | 23,400 | 9,030 | 53,000 | 8,400 | 10,400 | 6,020 | 2,320 | 2,140 | 970 | 3,080 | 1,440 | 970 |
| 27. | 15,420 | 6,580 | 64,300 | 10,770 | 9,690 | 4,770 | 2,320 | 1,960 | 1,440 | 2,890 | 1,440 | 1,120 |
| 28. | 13,170 | 5,760 | 47,400 | 14,050 | 9,030 | 4,300 | 2,320 | 1,610 | 2,140 | 2,700 | 1,440 | 3,660 |
| 29. | 8,090 | 5,250 | 29,300 | 22,380 | 8,090 | 3,860 | 2,320 | 1,440 | 2,140 | 2,700 | 1,280 | 7,640 |
| 30. | 7,170 | ----- | 22,890 | 31,800 | 7,470 | 3,460 | 2,140 | 1,440 | 2,320 | 2,510 | 1,280 | 8,010 |
| 31. | 8,400 | ----- | 18,330 | ----- | 7,470 | ----- | 2,140 | 1,280 | ----- | 2,320 | ----- | 4,220 |

Estimated monthly discharge of West Branch of Susquehanna River at Williamsport, Pa., 1895-1904.

[Drainage area, 5,640 square miles.]

| Month. | Discharge in second-feet. | | | Run-off. | |
|------------------|---------------------------|----------|--------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1895. | | | | | |
| March | 46,600 | 10,400 | 20,751 | 3.679 | 4.241 |
| April | 58,900 | 4,530 | 20,166 | 3.576 | 3.990 |
| May | 10,770 | 3,270 | 5,513 | .978 | 1.128 |
| June | 19,330 | 830 | 3,480 | .617 | .688 |
| July | 11,540 | 410 | 2,946 | .522 | .602 |
| August | 3,660 | 600 | 1,898 | .336 | .387 |
| September | 3,660 | 410 | 1,030 | .183 | .204 |
| October | 970 | 410 | 746 | .132 | .152 |
| November | 6,870 | 500 | 1,462 | .259 | .289 |
| December | 23,400 | 830 | 4,523 | .802 | .924 |
| The period | 58,900 | 410 | 6,252 | 1.108 | 12.605 |
| 1896. | | | | | |
| January | 22,380 | 2,700 | 5,705 | 1.012 | 1.167 |
| February | 49,000 | 3,080 | 10,861 | 1.926 | 2.077 |
| March | 76,500 | 4,070 | 13,809 | 2.448 | 2.822 |
| April | 67,900 | 8,710 | 20,118 | 3.567 | 3.980 |
| May | 8,090 | 2,140 | 3,853 | .683 | .787 |
| June | 23,400 | 2,510 | 7,454 | 1.322 | 1.475 |
| July | 22,380 | 3,270 | 6,276 | 1.113 | 1.283 |
| August | 22,890 | 1,280 | 6,382 | 1.132 | 1.305 |
| September | 4,070 | 970 | 1,560 | .277 | .309 |
| October | 49,000 | 1,610 | 13,137 | 2.329 | 2.685 |
| November | 26,300 | 4,300 | 8,770 | 1.554 | 1.734 |
| December | 13,600 | 2,700 | 6,245 | 1.107 | 1.276 |
| The year | 76,500 | 970 | 8,681 | 1.539 | 20.899 |

Estimated monthly discharge of West Branch of Susquehanna River at Williamsport, Pa., 1895-1904—Continued.

[Drainage area, 5,640 square miles,]

| Month. | Discharge in second-feet. | | | Run-off. | |
|-----------------|---------------------------|----------|--------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1897. | | | | | |
| January | 9,360 | 2,890 | 4,955 | 0.878 | 1.012 |
| February | 34,400 | 3,080 | 9,495 | 1.684 | 1.754 |
| March | 53,000 | 6,870 | 25,589 | 4.537 | 5.231 |
| April | 34,400 | 5,760 | 13,869 | 2.459 | 2.744 |
| May | 34,400 | 4,070 | 14,294 | 2.534 | 2.921 |
| June | 5,010 | 2,140 | 3,046 | .540 | .602 |
| July | 12,750 | 1,610 | 3,409 | .604 | .696 |
| August | 8,090 | 1,780 | 3,712 | .658 | .759 |
| September | 5,010 | 600 | 1,706 | .302 | .337 |
| October | 1,960 | 970 | 1,286 | .228 | .263 |
| November | 16,850 | 1,120 | 6,716 | 1.191 | 1.329 |
| December | 27,500 | 4,070 | 11,475 | 2.034 | 2.345 |
| The year | 53,000 | 600 | 8,295 | 1.471 | 19.993 |
| 1898. | | | | | |
| January | 42,100 | 3,460 | 15,799 | 2.801 | 3.230 |
| February | 31,800 | 4,300 | 12,211 | 2.165 | 2.254 |
| March | 162,600 | 6,020 | 31,357 | 5.560 | 6.410 |
| April | 33,700 | 5,760 | 12,900 | 2.287 | 2.552 |
| May | 19,830 | 6,300 | 10,536 | 1.868 | 2.154 |
| June | 8,090 | 2,140 | 4,289 | .760 | .848 |
| July | 4,070 | 1,280 | 2,056 | .364 | .420 |
| August | 22,380 | 1,960 | 4,467 | .792 | .914 |
| September | 2,330 | 1,120 | 1,529 | .271 | .302 |
| October | 35,800 | 1,280 | 7,372 | 1.307 | 1.507 |
| November | 38,600 | 3,660 | 8,513 | 1.509 | 1.684 |
| December | 31,100 | 2,700 | 7,590 | 1.346 | 1.552 |
| The year | 162,600 | 1,120 | 9,885 | 1.752 | 23.827 |

Estimated monthly discharge of West Branch of Susquehanna River at Williamsport, Pa., 1895-1904—Continued.

| Month. | Discharge in second-feet. | | | Run-off. | |
|-----------------|---------------------------|----------|--------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-foot per square mile. | Depth in inches. |
| 1899. | | | | | |
| January | 29,300 | 6,580 | 12,005 | 2.128 | 2.453 |
| February | 31,100 | 4,770 | 9,303 | 1.649 | 1.717 |
| March | 68,800 | 15,420 | 27,500 | 4.876 | 5.622 |
| April | 28,100 | 6,870 | 15,693 | 2.782 | 3.104 |
| May | 25,100 | 4,070 | 7,484 | 1.327 | 1.530 |
| June | 5,010 | 1,280 | 2,724 | .483 | .539 |
| July | 3,460 | 970 | 1,748 | .310 | .357 |
| August | 5,250 | 600 | 1,335 | .237 | .273 |
| September | 3,080 | 970 | 1,845 | .327 | .365 |
| October | 1,280 | 710 | 1,008 | .179 | .206 |
| November | 9,030 | 1,120 | 5,744 | 1.018 | 1.136 |
| December | 26,300 | 3,080 | 9,258 | 1.641 | 1.892 |
| The year | 68,800 | 600 | 7,971 | 1.413 | 19.194 |
| 1900. | | | | | |
| January | 67,900 | 5,250 | 13,934 | 2.470 | 2.848 |
| February | 41,400 | 6,020 | 14,095 | 2.499 | 2.602 |
| March | 35,800 | 5,250 | 15,639 | 2.773 | 3.197 |
| April | 22,890 | 8,400 | 13,992 | 2.481 | 2.768 |
| May | 9,690 | 3,460 | 4,923 | .873 | 1.006 |
| June | 8,090 | 1,780 | 4,043 | .717 | .800 |
| July | 3,460 | 1,280 | 2,046 | .363 | .418 |
| August | 2,140 | 710 | 1,311 | .232 | .267 |
| September | 1,780 | 710 | 931 | .165 | .184 |
| October | 3,660 | 710 | 1,821 | .323 | .372 |
| November | 110,100 | 1,610 | 9,328 | 1.654 | 1.845 |
| December | 24,600 | 3,660 | 8,562 | 1.518 | 1.750 |
| The year | 110,100 | 710 | 7,551 | 1.339 | 18.057 |

Estimated monthly discharge of West Branch of Susquehanna River at Williamport, Pa., 1895-1904—Continued.

| Month. | Discharge in second-feet. | | | Run-off. | |
|-----------------|---------------------------|----------|--------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1901. | | | | | |
| January | 11,540 | 2,140 | 5,182 | 0.919 | 1.060 |
| February | 5,250 | 1,960 | 3,010 | .534 | .556 |
| March | 52,200 | 2,140 | 20,920 | 3.709 | 4.280 |
| April | 89,900 | 9,690 | 27,533 | 4.882 | 5.447 |
| May | 77,500 | 3,660 | 15,403 | 2.731 | 3.148 |
| June | 41,400 | 5,500 | 12,311 | 2.183 | 2.436 |
| July | 6,870 | 1,610 | 2,911 | .516 | .595 |
| August | 28,100 | 1,610 | 7,049 | 1.250 | 1.441 |
| September | 22,380 | 2,510 | 6,296 | 1.116 | 1.245 |
| October | 4,070 | 1,440 | 2,122 | .376 | .423 |
| November | 21,870 | 1,120 | 4,266 | .756 | .844 |
| December | 150,900 | 3,660 | 20,276 | 3.595 | 4.145 |
| The year | 150,900 | 1,120 | 10,606 | 1.881 | 25.630 |
| 1902. | | | | | |
| January | 22,130 | 3,270 | 7,090 | 1.257 | 1.449 |
| February | 49,800 | 3,660 | 8,517 | 1.510 | 1.572 |
| March | 164,100 | 8,710 | 39,585 | 7.019 | 8.092 |
| April | 105,500 | 4,770 | 20,096 | 3.563 | 3.975 |
| May | 7,780 | 2,890 | 4,711 | .835 | .963 |
| June | 10,770 | 1,440 | 3,371 | .598 | .667 |
| July | 49,000 | 6,870 | 20,095 | 3.563 | 4.108 |
| August | 13,600 | 1,120 | 4,868 | .863 | .995 |
| September | 6,020 | 830 | 1,722 | .305 | .340 |
| October | 10,040 | 1,960 | 3,546 | .629 | .725 |
| November | 3,860 | 1,780 | 2,461 | .436 | .486 |
| December | 48,200 | 2,140 | 12,508 | 2.217 | 2.556 |
| The year | 164,100 | 830 | 10,714 | 1.899 | 25.928 |

Estimated monthly discharge of West Branch of Susquehanna River at Williamsport, Pa., 1895-1904—Continued.

| Month. | Discharge in second-feet. | | | Run-off. | |
|-----------------|---------------------------|----------|--------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1903. | | | | | |
| January | 50,600 | 4,530 | 9,948 | 1.763 | 2.032 |
| February | 93,100 | 8,400 | 24,459 | 4.337 | 4.516 |
| March | 110,700 | 11,150 | 35,220 | 6.245 | 7.200 |
| April | 56,300 | 5,760 | 17,825 | 3.160 | 3.526 |
| May | 5,010 | 1,960 | 2,938 | .521 | .601 |
| June | 37,200 | 1,280 | 7,929 | 1.407 | 1.569 |
| July | 29,300 | 4,070 | 9,747 | 1.728 | 1.992 |
| August | 24,600 | 2,890 | 6,019 | 1.067 | 1.230 |
| September | 17,340 | 2,320 | 5,890 | 1.044 | 1.165 |
| October | 28,100 | 1,960 | 8,313 | 1.474 | 1.699 |
| November | 58,900 | 2,510 | 8,773 | 1.555 | 1.735 |
| December | 5,010 | 2,140 | 3,519 | .624 | .719 |
| The year | 110,700 | 1,280 | 11,715 | 2.077 | 27.984 |
| 1904. | | | | | |
| January | 70,700 | 2,890 | 9,477 | 1.68 | 1.94 |
| February | 46,600 | 5,010 | 10,320 | 1.83 | 1.97 |
| March | 135,100 | 5,760 | 36,070 | 6.40 | 7.38 |
| April | 107,800 | 7,170 | 23,760 | 4.21 | 4.70 |
| May | 28,100 | 5,250 | 12,080 | 2.14 | 2.47 |
| June | 18,830 | 3,460 | 7,170 | 1.27 | 1.42 |
| July | 29,950 | 2,140 | 6,219 | 1.10 | 1.27 |
| August | 2,510 | 970 | 1,541 | .273 | .315 |
| September | 2,320 | 830 | 1,170 | .207 | .231 |
| October | 3,460 | 1,280 | 2,309 | .409 | .472 |
| November | 2,140 | 1,280 | 1,648 | .292 | .326 |
| December | 8,010 | 1,120 | 1,660 | .294 | .339 |
| The year | 135,100 | 830 | 9,450 | 1.68 | 22.83 |

WEST BRANCH OF SUSQUEHANNA RIVER AT ALLENWOOD, PA.

Observations of height of water on the West Branch have been made by the Weather Bureau at Lock Haven, Pa., 47 miles above Allenwood. The drainage area is given as 3,740 square miles, and the width of river 1,125 feet. The gage is in two sections. The lower section is painted on the side wall of the canal lock and the upper is on the highway bridge over the river. The elevation of the zero is 555.7 feet. The highest water was 18 feet, on June 1, 1889, and the danger line is at 10 feet.

A gaging station was established on the West Branch by E. G. Paul on March 25, 1899, at Allenwood, Pa., 20 miles above the junction with the main stream. Measurements are made from the public highway bridge, one-fourth of a mile east of the railroad station at Allenwood. The wire gage is 42.15 feet from zero to the end of the weight, and is referred to a pine-board scale fastened to ironwork of the bridge and divided into feet and tenths. The initial point of soundings is at the end of the iron guard rail on the right bank. The channel is straight for one-half a mile above and below the station. The current is sluggish, but unobstructed. The banks are low and subject to overflow at time of high water. The bed of the stream is rocky and permanent. The observer is Frank L. Allen, a farmer, living 200 feet from the gage. A bench mark was established on September 24, 1900. It consists of a copper bolt set in the capstone of the wing wall on the lower side of the west end of the bridge, and is 33.19 feet above datum of the gage.

This station was discontinued in April, 1902, the station at Williamsport taking its place.

*Discharge measurements of West Branch of Susquehanna River at Allenwood,
Pa., 1899-1902.*

| Date. | Hydrographer. | Gage height. | Area of section. | Mean velocity. | Dis- charge. |
|----------|------------------|-----------------|-------------------------|-----------------------------|--------------------------|
| 1899. | | <i>Feet.</i> | <i>Square feet.</i> | <i>Feet per second.</i> | <i>Second- feet.</i> |
| Mar. 24 | E. G. Paul ----- | 7.00 | 7,885 | 4.06 | 32,031 |
| June 8 | ----do ----- | 3.00 | 3,367 | 1.18 | 3,988 |
| July 28 | ----do ----- | 2.05 | 2,625 | .52 | 1,360 |
| Sept. 15 | ----do ----- | 1.90 | 2,437 | .51 | 1,234 |
| Oct. 17 | ----do ----- | 1.70 | 2,137 | .39 | 842 |
| 1900. | | | | | |
| May 18 | E. G. Paul ----- | 3.20 | 3,729 | 1.29 | 4,812 |
| Sept. 24 | ----do ----- | 1.30 | 327 | 1.56 | 511 |
| 1901. | | | | | |
| Aug. 17 | E. G. Paul ----- | 4.10 | 4,460 | 1.99 | 8,857 |
| Oct. 26 | ----do ----- | 2.30 | 2,824 | .81 | 2,308 |
| 1902. | | | | | |
| Apr. 21 | E. G. Paul ----- | 4.40 | 4,736 | 2.09 | 9,896 |

Mean daily gage height, in feet, of West Branch of Susquehanna River at Allen-wood, Pa., 1899-1902.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|-------|-------|------|------|------|-------|-------|------|-------|------|-------|------|
| 1899. | | | | | | | | | | | | |
| 1 | | | | 6.70 | 3.80 | 3.50 | 2.90 | 2.00 | 2.70 | 2.00 | 2.20 | 2.90 |
| 2 | | | | 6.30 | 3.80 | 3.50 | 2.70 | 2.00 | 2.70 | 2.00 | 3.60 | 2.80 |
| 3 | | | | 5.80 | 3.80 | 3.40 | 2.50 | 2.00 | 2.70 | 1.90 | 4.20 | 2.70 |
| 4 | | | | 5.35 | 3.90 | 3.40 | 2.50 | 1.80 | 2.50 | 1.90 | 5.20 | 2.70 |
| 5 | | | | 5.05 | 3.80 | 3.30 | 2.40 | 1.70 | 2.40 | 1.90 | 4.60 | 2.70 |
| 6 | | | | 4.90 | 3.60 | 3.20 | 2.40 | 1.70 | 2.30 | 1.90 | 4.00 | 2.60 |
| 7 | | | | 4.80 | 3.50 | 3.00 | 2.30 | 1.70 | 2.10 | 1.90 | 3.40 | 2.60 |
| 8 | | | | 6.45 | 3.30 | 3.00 | 2.40 | 1.70 | 2.00 | 1.90 | 3.20 | 2.60 |
| 9 | | | | 7.80 | 3.40 | 2.90 | 2.20 | 1.70 | 2.00 | 1.90 | 3.00 | 2.60 |
| 10 | | | | 7.40 | 3.50 | 2.90 | 2.00 | 1.70 | 2.00 | 1.80 | 3.00 | 2.60 |
| 11 | | | | 6.60 | 3.60 | 2.70 | 2.10 | 1.70 | 1.90 | 1.80 | 3.00 | 2.60 |
| 12 | | | | 6.20 | 3.70 | 2.60 | 2.30 | 1.70 | 1.90 | 1.80 | 3.20 | 5.30 |
| 13 | | | | 6.50 | 3.50 | 2.60 | 2.20 | 1.90 | 1.90 | 1.70 | 3.30 | 8.40 |
| 14 | | | | 7.00 | 3.40 | 2.60 | 2.20 | 1.90 | 1.90 | 1.70 | 3.40 | 7.40 |
| 15 | | | | 6.90 | 3.30 | 2.50 | 2.30 | 1.90 | 1.90 | 1.70 | 3.50 | 6.50 |
| 16 | | | | 6.80 | 3.20 | 2.50 | 2.20 | 1.90 | 1.90 | 1.70 | 3.60 | 5.80 |
| 17 | | | | 6.40 | 3.40 | 2.50 | 2.30 | 1.90 | 1.90 | 1.70 | 3.80 | 5.10 |
| 18 | | | | 5.60 | 3.80 | 2.40 | 2.40 | 1.90 | 1.90 | 1.70 | 3.90 | 4.90 |
| 19 | | | | 5.40 | 7.40 | 2.40 | 2.60 | 1.80 | 1.90 | 1.70 | 4.10 | 4.80 |
| 20 | | | | 5.00 | 6.50 | 2.40 | 2.80 | 1.70 | 1.90 | 1.70 | 4.30 | 4.70 |
| 21 | | | | 4.80 | 5.75 | 2.40 | 3.00 | 1.70 | 1.90 | 1.60 | 4.10 | 4.30 |
| 22 | | | | 4.70 | 5.15 | 2.30 | 2.70 | 1.70 | 1.90 | 1.60 | 4.00 | 4.20 |
| 23 | | | 7.00 | 4.50 | 4.70 | 2.20 | 2.50 | 1.70 | 1.90 | 1.60 | 3.90 | 4.20 |
| 24 | | | 7.00 | 4.40 | 4.35 | 2.20 | 2.30 | 1.60 | 1.90 | 1.60 | 3.80 | 5.15 |
| 25 | | | 6.70 | 4.30 | 4.00 | 2.80 | 2.20 | 1.60 | 1.90 | 1.60 | 3.70 | 7.25 |
| 26 | | | 6.30 | 4.30 | 3.80 | 2.50 | 2.20 | 1.60 | 1.90 | 1.60 | 3.60 | 5.60 |
| 27 | | | 6.40 | 4.30 | 3.60 | 2.60 | 2.10 | 1.70 | 2.00 | 1.60 | 3.40 | 5.00 |
| 28 | | | 6.20 | 4.20 | 3.50 | 2.70 | 2.00 | 3.70 | 2.00 | 1.60 | 3.30 | 4.50 |
| 29 | | | 6.70 | 4.30 | 3.40 | 2.70 | 1.90 | 3.00 | 2.00 | 1.60 | 3.20 | 4.10 |
| 30 | | | 7.80 | 4.10 | 3.40 | 2.80 | 1.80 | 2.60 | 2.00 | 1.60 | 3.10 | 3.60 |
| 31 | | | 7.35 | | 3.50 | | 2.00 | 2.60 | | 1.60 | | 3.40 |
| 1900. | | | | | | | | | | | | |
| 1 | 4.50 | 3.20 | 7.55 | 5.00 | 4.30 | 3.90 | 2.10 | 1.90 | 2.00 | 1.30 | 2.10 | 5.75 |
| 2 | 5.50 | 3.20 | 9.60 | 5.30 | 4.20 | 3.90 | 2.30 | 1.80 | 1.90 | 1.30 | 2.10 | 5.40 |
| 3 | 5.70 | 3.40 | 7.70 | 5.40 | 4.20 | 3.90 | 2.60 | 1.80 | 1.90 | 1.20 | 2.10 | 5.00 |
| 4 | 5.80 | 3.40 | 7.00 | 5.80 | 4.00 | 4.00 | 2.50 | 1.80 | 1.80 | 1.20 | 2.10 | 5.80 |
| 5 | 5.90 | 3.50 | 6.00 | 5.90 | 3.80 | 4.10 | 2.30 | 1.70 | 1.80 | 1.20 | 2.10 | 5.90 |
| 6 | 5.90 | 3.60 | 5.40 | 6.20 | 3.50 | 3.90 | 2.30 | 1.70 | 1.70 | 1.20 | 2.00 | 6.40 |
| 7 | 5.90 | 3.80 | 5.80 | 6.40 | 3.30 | 3.60 | 2.20 | 1.70 | 1.70 | 1.20 | 1.90 | 6.70 |
| 8 | 4.70 | 4.50 | 5.90 | 6.20 | 3.30 | 3.50 | 2.20 | 1.60 | 1.70 | 1.20 | 1.90 | 6.00 |
| 9 | 3.70 | 5.00 | 6.10 | 7.30 | 3.20 | 3.40 | 2.20 | 1.60 | 1.60 | 1.80 | 1.90 | 5.50 |
| 10 | 3.90 | 5.30 | 6.40 | 6.00 | 3.20 | 3.30 | 2.30 | 1.50 | 1.60 | 2.20 | 1.90 | 4.90 |
| 11 | 4.20 | 5.60 | 6.90 | 5.70 | 3.20 | 3.20 | 2.50 | 1.40 | 1.60 | 2.20 | 1.90 | 4.60 |
| 12 | 4.50 | 5.30 | 6.20 | 5.30 | 3.20 | 3.00 | 2.70 | 1.50 | 1.50 | 2.10 | 1.90 | 4.20 |
| 13 | 4.40 | 6.00 | 5.40 | 4.90 | 3.50 | 3.00 | 2.90 | 1.50 | 1.50 | 2.10 | 1.90 | 4.00 |
| 14 | 4.20 | 7.70 | 5.00 | 4.80 | 3.40 | 3.00 | 2.80 | 1.40 | 1.40 | 2.10 | 1.90 | 3.80 |
| 15 | 4.00 | 7.30 | 4.00 | 4.80 | 3.40 | 3.00 | 2.60 | 1.40 | 1.40 | 2.10 | 1.90 | 3.60 |
| 16 | 4.00 | 6.50 | 4.00 | 4.60 | 3.30 | 3.00 | 2.60 | 1.40 | 1.40 | 2.10 | 1.80 | 3.30 |
| 17 | 4.00 | 6.20 | 3.90 | 4.70 | 3.20 | 2.90 | 2.50 | 1.40 | 1.30 | 2.10 | 1.80 | 3.20 |
| 18 | 4.20 | 5.40 | 3.80 | 6.00 | 3.20 | 2.80 | 2.40 | 1.40 | 1.30 | 2.20 | 1.80 | 3.20 |
| 19 | 4.50 | 5.60 | 3.70 | 7.00 | 3.50 | 2.70 | 2.20 | 1.40 | 1.30 | 2.10 | 1.70 | 3.10 |
| 20 | 5.30 | 5.90 | 6.20 | 6.90 | 3.50 | 2.70 | 2.00 | 1.40 | 1.30 | 2.00 | 1.70 | 3.10 |
| 21 | 13.20 | 6.00 | 7.10 | 6.30 | 3.30 | 2.60 | 2.00 | 1.40 | 1.30 | 1.90 | 1.70 | 3.10 |
| 22 | 12.20 | 8.20 | 6.90 | 6.20 | 3.20 | 2.50 | 1.80 | 2.30 | 1.30 | 1.90 | 1.90 | 3.00 |
| 23 | 8.50 | 10.15 | 6.60 | 6.00 | 3.00 | 2.40 | 1.90 | 2.30 | 1.30 | 2.10 | 2.40 | 3.00 |
| 24 | 6.50 | 7.85 | 6.10 | 6.30 | 3.00 | 2.40 | 1.90 | 2.30 | 1.30 | 2.20 | 3.00 | 3.00 |
| 25 | 6.30 | 6.50 | 5.90 | 6.00 | 3.00 | 2.30 | 1.90 | 2.30 | 1.30 | 2.40 | 5.00 | 3.00 |
| 26 | 6.10 | 5.00 | 5.50 | 5.60 | 3.00 | 2.30 | 1.90 | 2.30 | 1.30 | 2.50 | 7.70 | 3.00 |
| 27 | 5.30 | 5.00 | 5.20 | 5.30 | 3.40 | 2.30 | 2.20 | 2.20 | 1.30 | 2.60 | 15.75 | 3.00 |
| 28 | 4.60 | 4.80 | 5.10 | 4.80 | 3.20 | 2.20 | 2.20 | 2.20 | 1.30 | 2.40 | 10.05 | 3.00 |
| 29 | 4.60 | | 5.00 | 4.60 | 3.00 | 2.20 | 2.20 | 2.10 | 1.30 | 2.40 | 8.25 | 3.00 |
| 30 | 4.50 | | 4.90 | 4.40 | 3.00 | 2.10 | 2.20 | 2.10 | 1.30 | 2.30 | 6.60 | 3.00 |
| 31 | 3.20 | | 4.80 | | 3.20 | | 2.00 | 2.00 | | 2.20 | | |


Mean daily gage height, in feet, of West Branch of Susquehanna River at Allenwood, Pa., 1899-1902—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|------|------|-------|------------------|-------|-------|-------|------|-------|------|------|-------|
| 1901. | | | | | | | | | | | | |
| 1 | 3.00 | 2.50 | 3.00 | 5.80 | 4.70 | 8.50 | 2.90 | 2.50 | 4.10 | 3.30 | 2.40 | 4.00 |
| 2 | 3.00 | 2.50 | 3.00 | 5.60 | 4.60 | 7.70 | 2.90 | 2.40 | 4.20 | 3.20 | 2.60 | 3.90 |
| 3 | 3.00 | 2.50 | 2.90 | 5.20 | 5.00 | 7.20 | 2.80 | 2.40 | 4.20 | 3.10 | 2.80 | 3.70 |
| 4 | 3.00 | 2.50 | 3.00 | 6.50 | 5.20 | 6.70 | 2.80 | 2.30 | 4.30 | 3.10 | 3.00 | 3.60 |
| 5 | 3.00 | 2.60 | 3.50 | 6.80 | 5.00 | 5.70 | 2.80 | 2.20 | 4.40 | 3.00 | 3.10 | 3.40 |
| 6 | 2.80 | 2.80 | 4.80 | 7.00 | 4.90 | 5.00 | 2.70 | 2.20 | 4.40 | 3.10 | 3.10 | 3.40 |
| 7 | 2.70 | 3.00 | 5.20 | 9.15 | 4.70 | 5.70 | 2.70 | 2.30 | 4.20 | 3.20 | 2.20 | 3.20 |
| 8 | 2.50 | 2.50 | 5.50 | 10.00 | 4.60 | 5.90 | 2.70 | 2.50 | 4.10 | 3.30 | 2.40 | 5.00 |
| 9 | 2.50 | 3.00 | 5.80 | 11.15 | 4.40 | 6.00 | 2.70 | 3.10 | 3.90 | 3.40 | 2.40 | 7.20 |
| 10 | 2.90 | 3.50 | 4.80 | 9.30 | 4.00 | 5.90 | 2.70 | 3.00 | 3.90 | 3.40 | 3.40 | 6.50 |
| 11 | 3.40 | 4.00 | 9.50 | 8.30 | 4.20 | 5.60 | 2.70 | 2.90 | 3.80 | 3.60 | 3.60 | 6.30 |
| 12 | 3.80 | 4.00 | 9.70 | 7.00 | 4.30 | 5.20 | 2.60 | 2.80 | 3.80 | 3.60 | 3.40 | 6.20 |
| 13 | 4.50 | 3.80 | 9.10 | 6.80 | 4.30 | 5.00 | 2.60 | 2.80 | 3.80 | 3.70 | 3.30 | 5.90 |
| 14 | 4.90 | 4.20 | 8.50 | 6.40 | 4.40 | 4.90 | 2.50 | 2.70 | 3.80 | 3.40 | 3.20 | 8.00 |
| 15 | 4.50 | 4.00 | 7.40 | 6.30 | 4.50 | 4.80 | 2.50 | 2.70 | 3.60 | 3.20 | 3.20 | 20.15 |
| 16 | 4.20 | 3.80 | 6.80 | 5.80 | 4.50 | 4.40 | 2.50 | 2.60 | 3.70 | 3.00 | 3.10 | 17.70 |
| 17 | 4.00 | 3.50 | 6.20 | 5.40 | 4.70 | 4.30 | 2.40 | 4.10 | 3.80 | 2.90 | 3.10 | 11.30 |
| 18 | 4.00 | 3.20 | 5.80 | 5.20 | 4.60 | 4.10 | 2.40 | 4.30 | 3.90 | 2.80 | 3.00 | 7.40 |
| 19 | 3.90 | 3.00 | 7.20 | 5.10 | 4.80 | 4.00 | 2.20 | 4.50 | 3.80 | 2.70 | 3.00 | 7.00 |
| 20 | 3.50 | 3.00 | 8.00 | 6.30 | 4.40 | 4.00 | 2.20 | 4.70 | 3.60 | 2.50 | 2.90 | 5.90 |
| 21 | 3.20 | 3.20 | 8.00 | 11.45 | 4.20 | 3.90 | 2.10 | 4.60 | 3.50 | 2.40 | 2.80 | 5.40 |
| 22 | 3.00 | 3.00 | 8.00 | 14.35 | 4.20 | 3.80 | 2.10 | 6.40 | 3.50 | 2.30 | 2.60 | 5.10 |
| 23 | 3.00 | 3.90 | 8.00 | 11.65 | 5.20 | 3.70 | 2.00 | 7.90 | 3.30 | 2.30 | 2.40 | 4.80 |
| 24 | 2.80 | 3.00 | 7.60 | 10.20 | 6.20 | 3.50 | 2.00 | 7.70 | 3.30 | 2.30 | 5.00 | 4.50 |
| 25 | 2.50 | 3.00 | 7.20 | 9.30 | 5.80 | 3.30 | 2.00 | 6.80 | 3.20 | 2.30 | 6.70 | 4.40 |
| 26 | 2.50 | 3.00 | 9.40 | 8.50 | 6.00 | 3.30 | 2.00 | 6.20 | 3.20 | 2.30 | 5.90 | 4.30 |
| 27 | 2.50 | 3.00 | 11.20 | 7.40 | 6.40 | 3.10 | 2.20 | 5.70 | 3.00 | 2.30 | 5.50 | 4.20 |
| 28 | 2.50 | 3.00 | 11.20 | 5.80 | 7.10 | 3.10 | 2.20 | 4.80 | 2.80 | 2.20 | 4.80 | 4.10 |
| 29 | 2.50 | | 8.70 | 5.30 | 11.15 | 2.90 | 2.40 | 4.30 | 2.70 | 2.20 | 4.00 | 4.10 |
| 30 | 2.50 | | 7.00 | 5.00 | 13.00 | 2.90 | 2.50 | 4.20 | 2.80 | 2.20 | 4.20 | 4.00 |
| 31 | 2.50 | | 6.60 | | 10.40 | | 2.50 | 4.10 | | 2.30 | | 3.90 |
| 1902. | | | | | | | | | | | | |
| 1 | 3.80 | 5.40 | 21.00 | 6.40 | | | | | | | | |
| 2 | 3.80 | 5.20 | 19.40 | 6.50 | | | | | | | | |
| 3 | 3.60 | 4.90 | 15.50 | 6.50 | | | | | | | | |
| 4 | 3.60 | 4.90 | 11.50 | 6.40 | | | | | | | | |
| 5 | 3.50 | 4.90 | 8.20 | 5.80 | | | | | | | | |
| 6 | 3.50 | 4.90 | 6.80 | (^a) | | | | | | | | |
| 7 | 3.50 | 4.80 | 6.40 | | | | | | | | | |
| 8 | 3.50 | 4.80 | 5.50 | | | | | | | | | |
| 9 | 3.40 | 4.80 | 4.90 | | | | | | | | | |
| 10 | 3.40 | 4.80 | 6.40 | | | | | | | | | |
| 11 | 3.40 | 4.80 | 7.60 | | | | | | | | | |
| 12 | 3.30 | 4.70 | 8.40 | | | | | | | | | |
| 13 | 3.20 | 4.70 | 10.00 | | | | | | | | | |
| 14 | 3.20 | 4.60 | 8.90 | | | | | | | | | |
| 15 | 3.20 | 4.50 | 8.60 | | | | | | | | | |
| 16 | 3.20 | 4.70 | 8.80 | | | | | | | | | |
| 17 | 3.20 | 4.70 | 12.20 | | | | | | | | | |
| 18 | 3.10 | 4.70 | 10.00 | | | | | | | | | |
| 19 | 3.10 | 4.70 | 8.60 | | | | | | | | | |
| 20 | 3.10 | 4.70 | 7.40 | | | | | | | | | |
| 21 | 3.40 | 4.70 | 6.70 | | | | | | | | | |
| 22 | 7.40 | 4.70 | 6.40 | | | | | | | | | |
| 23 | 6.80 | 6.50 | 5.70 | | | | | | | | | |
| 24 | 6.60 | 7.00 | 5.40 | | | | | | | | | |
| 25 | 6.50 | 7.40 | 5.20 | | | | | | | | | |
| 26 | 6.30 | 5.50 | 4.80 | | | | | | | | | |
| 27 | 6.20 | 5.90 | 4.70 | | | | | | | | | |
| 28 | 5.90 | 9.70 | 5.00 | | | | | | | | | |
| 29 | 5.90 | | 5.60 | | | | | | | | | |
| 30 | 5.80 | | 6.10 | | | | | | | | | |
| 31 | 5.40 | | 6.20 | | | | | | | | | |

^a Discontinued.

Rating table for West Branch of Susquehanna River at Allenwood, Pa., for 1900 to 1902.

| Gage height. | Discharge. | Gage height. | Discharge. | Gage height. | Discharge. | Gage height. | Discharge. |
|--------------|---------------------|--------------|---------------------|--------------|---------------------|--------------|---------------------|
| <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> |
| 1.2 | 430 | 3.5 | 5,970 | 5.8 | 20,500 | 9.2 | 59,800 |
| 1.3 | 510 | 3.6 | 6,400 | 5.9 | 21,350 | 9.4 | 62,700 |
| 1.4 | 600 | 3.7 | 6,830 | 6.0 | 22,200 | 9.6 | 65,700 |
| 1.5 | 690 | 3.8 | 7,260 | 6.1 | 23,100 | 9.8 | 68,800 |
| 1.6 | 790 | 3.9 | 7,700 | 6.2 | 24,000 | 10.0 | 72,000 |
| 1.7 | 900 | 4.0 | 8,160 | 6.3 | 24,900 | 10.2 | 75,300 |
| 1.8 | 1,040 | 4.1 | 8,630 | 6.4 | 25,900 | 10.4 | 78,600 |
| 1.9 | 1,220 | 4.2 | 9,110 | 6.5 | 26,900 | 10.6 | 82,000 |
| 2.0 | 1,410 | 4.3 | 9,610 | 6.6 | 27,900 | 10.8 | 85,500 |
| 2.1 | 1,610 | 4.4 | 10,140 | 6.7 | 28,900 | 11.0 | 89,000 |
| 2.2 | 1,830 | 4.5 | 10,710 | 6.8 | 29,900 | 11.2 | 92,600 |
| 2.3 | 2,070 | 4.6 | 11,300 | 6.9 | 31,000 | 11.4 | 96,300 |
| 2.4 | 2,320 | 4.7 | 11,930 | 7.0 | 32,000 | 11.6 | 100,000 |
| 2.5 | 2,580 | 4.8 | 12,600 | 7.2 | 34,200 | 11.8 | 103,800 |
| 2.6 | 2,850 | 4.9 | 13,300 | 7.4 | 36,500 | 12.0 | 107,600 |
| 2.7 | 3,130 | 5.0 | 14,030 | 7.6 | 38,800 | 12.2 | 111,500 |
| 2.8 | 3,420 | 5.1 | 14,780 | 7.8 | 41,200 | 12.4 | 115,500 |
| 2.9 | 3,730 | 5.2 | 15,550 | 8.0 | 43,600 | 12.6 | 119,500 |
| 3.0 | 4,050 | 5.3 | 16,350 | 8.2 | 46,100 | 12.8 | 123,700 |
| 3.1 | 4,400 | 5.4 | 17,170 | 8.4 | 48,700 | 13.0 | 128,000 |
| 3.2 | 4,770 | 5.5 | 17,990 | 8.6 | 51,400 | | |
| 3.3 | 5,150 | 5.6 | 18,820 | 8.8 | 54,100 | | |
| 3.4 | 5,550 | 5.7 | 19,650 | 9.0 | 56,900 | | |



RATING CURVE FOR WEST BRANCH OF SUSQUEHANNA RIVER AT ALLENWOOD, PA.

Mean daily discharge, in second-feet, of West Branch of Susquehanna River at Allenwood, Pa., 1899-1902.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|---------|--------|--------|--------|--------|-------|-------|-------|-------|-------|---------|--------|
| 1899. | | | | | | | | | | | | |
| 1 | | | | 28,900 | 7,260 | 5,970 | 3,730 | 1,410 | 3,130 | 1,410 | 1,830 | 3,730 |
| 2 | | | | 24,900 | 7,260 | 5,970 | 3,130 | 1,410 | 3,130 | 1,410 | 6,400 | 3,420 |
| 3 | | | | 20,500 | 7,260 | 5,550 | 2,580 | 1,410 | 3,130 | 1,220 | 9,110 | 3,130 |
| 4 | | | | 16,760 | 7,700 | 5,550 | 2,580 | 1,040 | 2,580 | 1,220 | 15,550 | 3,130 |
| 5 | | | | 14,400 | 7,260 | 5,150 | 2,320 | 900 | 2,320 | 1,220 | 11,300 | 3,130 |
| 6 | | | | 13,300 | 6,400 | 4,770 | 2,320 | 900 | 2,070 | 1,220 | 8,160 | 2,850 |
| 7 | | | | 12,600 | 5,970 | 4,050 | 2,070 | 900 | 1,610 | 1,220 | 5,550 | 2,850 |
| 8 | | | | 26,400 | 5,150 | 4,050 | 2,320 | 900 | 1,410 | 1,220 | 4,770 | 2,850 |
| 9 | | | | 41,200 | 5,550 | 3,730 | 1,830 | 900 | 1,410 | 1,220 | 4,050 | 2,850 |
| 10 | | | | 36,500 | 5,970 | 3,730 | 1,410 | 900 | 1,410 | 1,040 | 4,050 | 2,850 |
| 11 | | | | 27,900 | 6,400 | 3,130 | 1,610 | 900 | 1,220 | 1,040 | 4,050 | 2,850 |
| 12 | | | | 24,000 | 6,830 | 2,850 | 2,070 | 900 | 1,220 | 1,040 | 4,770 | 16,350 |
| 13 | | | | 26,900 | 5,970 | 2,850 | 1,830 | 1,220 | 1,220 | 900 | 5,150 | 48,700 |
| 14 | | | | 32,000 | 5,550 | 2,850 | 1,830 | 1,228 | 1,220 | 900 | 5,550 | 36,500 |
| 15 | | | | 31,000 | 5,150 | 2,580 | 2,070 | 1,220 | 1,220 | 900 | 5,970 | 26,900 |
| 16 | | | | 29,900 | 4,700 | 2,580 | 1,830 | 1,220 | 1,220 | 900 | 6,400 | 20,500 |
| 17 | | | | 25,900 | 5,550 | 2,580 | 2,070 | 1,220 | 1,220 | 900 | 7,260 | 14,780 |
| 18 | | | | 18,820 | 7,260 | 2,320 | 2,320 | 1,220 | 1,220 | 900 | 7,700 | 13,300 |
| 19 | | | | 17,170 | 36,500 | 2,320 | 2,850 | 1,040 | 1,220 | 900 | 8,630 | 12,600 |
| 20 | | | | 14,030 | 26,900 | 2,320 | 3,420 | 900 | 1,220 | 900 | 9,610 | 11,930 |
| 21 | | | | 12,600 | 20,075 | 2,320 | 4,050 | 900 | 1,220 | 790 | 8,630 | 9,610 |
| 22 | | | | 11,930 | 15,160 | 2,070 | 3,130 | 900 | 1,220 | 790 | 8,160 | 9,110 |
| 23 | | | 32,000 | 10,710 | 11,930 | 1,830 | 2,580 | 900 | 1,220 | 790 | 7,700 | 9,110 |
| 24 | | | 32,000 | 10,140 | 9,870 | 1,830 | 2,070 | 790 | 1,220 | 790 | 7,260 | 15,160 |
| 25 | | | 28,900 | 9,610 | 8,160 | 3,420 | 1,830 | 790 | 1,220 | 790 | 6,830 | 34,700 |
| 26 | | | 24,900 | 9,610 | 7,260 | 2,580 | 1,830 | 790 | 1,220 | 790 | 6,400 | 18,820 |
| 27 | | | 25,900 | 9,610 | 6,400 | 2,850 | 1,610 | 900 | 1,410 | 790 | 5,550 | 14,030 |
| 28 | | | 24,000 | 9,110 | 5,970 | 3,130 | 1,410 | 6,830 | 1,410 | 790 | 5,150 | 10,710 |
| 29 | | | 28,900 | 9,610 | 5,550 | 3,130 | 1,220 | 4,050 | 1,410 | 790 | 4,770 | 8,630 |
| 30 | | | 41,200 | 8,630 | 5,550 | 3,420 | 1,040 | 2,850 | 1,410 | 790 | 4,400 | 6,400 |
| 31 | | | 35,900 | | 5,970 | | 1,410 | 2,850 | | 790 | | 5,550 |
| 1900. | | | | | | | | | | | | |
| 1 | 10,710 | 4,770 | 38,200 | 14,030 | 9,610 | 7,700 | 1,610 | 1,220 | 1,410 | 510 | 1,610 | 20,070 |
| 2 | 17,990 | 4,770 | 65,700 | 16,350 | 9,110 | 7,700 | 2,070 | 1,040 | 1,220 | 510 | 1,610 | 17,170 |
| 3 | 19,650 | 5,550 | 40,000 | 17,170 | 9,110 | 7,700 | 2,850 | 1,040 | 1,220 | 430 | 1,610 | 14,030 |
| 4 | 20,500 | 5,550 | 32,000 | 20,500 | 8,160 | 8,160 | 2,580 | 1,040 | 1,040 | 430 | 1,610 | 20,500 |
| 5 | 21,350 | 5,970 | 22,200 | 21,350 | 7,260 | 8,630 | 2,070 | 900 | 1,040 | 430 | 1,610 | 21,350 |
| 6 | 21,350 | 6,400 | 17,170 | 24,000 | 5,970 | 7,700 | 2,070 | 900 | 900 | 430 | 1,410 | 25,900 |
| 7 | 21,350 | 7,260 | 20,500 | 25,900 | 5,150 | 6,400 | 1,830 | 900 | 900 | 430 | 1,220 | 28,900 |
| 8 | 11,930 | 10,710 | 21,350 | 24,000 | 5,150 | 5,970 | 1,830 | 790 | 900 | 430 | 1,220 | 22,200 |
| 9 | 6,830 | 14,030 | 23,100 | 35,300 | 4,770 | 5,550 | 1,830 | 790 | 790 | 1,040 | 1,220 | 17,990 |
| 10 | 7,700 | 16,350 | 25,900 | 22,200 | 4,770 | 5,150 | 2,070 | 690 | 790 | 1,830 | 1,220 | 13,300 |
| 11 | 9,190 | 18,820 | 31,000 | 19,650 | 4,770 | 4,770 | 2,580 | 600 | 790 | 1,830 | 1,220 | 11,300 |
| 12 | 10,710 | 16,350 | 24,000 | 16,350 | 4,770 | 4,050 | 3,130 | 690 | 690 | 1,610 | 1,220 | 9,110 |
| 13 | 10,140 | 22,200 | 17,170 | 13,300 | 5,970 | 4,050 | 3,730 | 690 | 690 | 1,610 | 1,220 | 8,160 |
| 14 | 9,110 | 40,000 | 14,030 | 12,600 | 5,550 | 4,050 | 3,420 | 600 | 600 | 1,610 | 1,220 | 7,260 |
| 15 | 8,160 | 35,300 | 8,160 | 12,600 | 5,550 | 4,050 | 2,850 | 600 | 600 | 1,610 | 1,220 | 6,400 |
| 16 | 8,160 | 26,900 | 8,160 | 11,300 | 5,150 | 4,050 | 2,850 | 600 | 600 | 1,610 | 1,040 | 5,150 |
| 17 | 8,160 | 24,000 | 7,700 | 11,930 | 4,770 | 3,730 | 2,580 | 600 | 510 | 1,610 | 1,040 | 4,770 |
| 18 | 9,110 | 17,170 | 7,260 | 22,200 | 4,770 | 3,420 | 2,320 | 600 | 510 | 1,830 | 1,040 | 4,770 |
| 19 | 10,710 | 18,820 | 6,830 | 32,000 | 5,970 | 3,130 | 1,830 | 600 | 510 | 1,610 | 900 | 4,400 |
| 20 | 16,350 | 21,350 | 24,000 | 31,000 | 5,970 | 3,130 | 1,410 | 600 | 510 | 1,410 | 900 | 4,400 |
| 21 | 132,300 | 22,200 | 33,100 | 24,900 | 5,150 | 2,850 | 1,410 | 600 | 510 | 1,220 | 900 | 4,400 |
| 22 | 111,500 | 46,100 | 31,000 | 24,000 | 4,770 | 2,580 | 1,220 | 2,070 | 510 | 1,220 | 1,220 | 4,050 |
| 23 | 50,000 | 74,500 | 27,900 | 22,200 | 4,050 | 2,320 | 1,220 | 2,070 | 510 | 1,610 | 2,320 | 4,050 |
| 24 | 26,900 | 41,800 | 23,100 | 24,900 | 4,050 | 2,320 | 1,220 | 2,070 | 510 | 1,830 | 4,050 | 4,050 |
| 25 | 24,900 | 26,900 | 21,300 | 22,200 | 4,050 | 2,070 | 1,220 | 2,070 | 510 | 2,320 | 14,030 | 4,050 |
| 26 | 23,100 | 14,030 | 17,990 | 18,820 | 4,050 | 2,070 | 1,220 | 2,070 | 510 | 2,580 | 40,000 | 4,650 |
| 27 | 16,350 | 14,030 | 15,550 | 16,350 | 5,550 | 2,070 | 1,830 | 1,830 | 510 | 2,580 | 193,400 | 4,050 |
| 28 | 11,300 | 12,600 | 14,780 | 12,600 | 4,770 | 1,830 | 1,830 | 1,830 | 510 | 2,320 | 72,800 | 4,050 |
| 29 | 11,300 | | 14,030 | 11,300 | 4,050 | 1,830 | 1,830 | 1,610 | 510 | 2,320 | 46,750 | 4,050 |
| 30 | 10,710 | | 13,300 | 10,140 | 4,050 | 1,610 | 1,830 | 1,610 | 510 | 2,070 | 27,900 | 4,050 |
| 31 | 4,770 | | 12,600 | | 4,770 | | 1,410 | 1,410 | | 1,830 | | |

*Estimated monthly discharge of West Branch of Susquehanna River at Allenwood,
Pa., 1899-1902.*

[Drainage area, 6,538 square miles.]

| Month. | Discharge in second-feet. | | | Run-off. | |
|---------------------|---------------------------|----------|--------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1899. | | | | | |
| March (23-31) | 41,200 | 24,000 | 30,411 | 4.651 | 1.557 |
| April | 41,200 | 8,630 | 19,488 | 2.981 | 3.326 |
| May | 36,500 | 4,770 | 8,985 | 1.374 | 1.584 |
| June | 5,970 | 1,830 | 3,383 | .517 | .577 |
| July | 4,050 | 1,040 | 2,205 | .337 | .388 |
| August | 6,830 | 790 | 1,438 | .218 | .251 |
| September | 3,130 | 1,220 | 1,579 | .242 | .270 |
| October | 1,410 | 790 | 980 | .150 | .173 |
| November | 15,550 | 4,050 | 6,690 | 1.023 | 1.141 |
| December | 48,700 | 2,850 | 12,162 | 1.860 | 2.144 |
| The period | 48,700 | 790 | 8,731 | 1.335 | 11.411 |
| 1900. | | | | | |
| January | 132,300 | 4,770 | 22,007 | 3.366 | 3.881 |
| February | 74,500 | 4,770 | 20,515 | 3.138 | 3.268 |
| March | 65,700 | 6,830 | 21,907 | 3.351 | 3.863 |
| April | 35,300 | 10,140 | 19,705 | 3.014 | 3.363 |
| May | 9,610 | 4,050 | 5,536 | .847 | .976 |
| June | 8,630 | 1,610 | 4,355 | .666 | .743 |
| July | 3,730 | 1,220 | 2,056 | .314 | .362 |
| August | 2,070 | 600 | 1,120 | .171 | .197 |
| September | 1,410 | 510 | 711 | .109 | .122 |
| October | 2,850 | 430 | 1,451 | .222 | .256 |
| November | 193,400 | 900 | 14,291 | 2.186 | 2.439 |
| December | 28,900 | 4,050 | 10,266 | 1.570 | 1.752 |
| The year | 193,400 | 430 | 10,327 | 1.578 | 21.222 |

Estimated monthly discharge of West Branch of Susquehanna River at Allenwood, Pa., 1899-1902—Continued.

| Month. | Discharge in second-feet. | | | Run-off. | |
|-----------------|---------------------------|----------|--------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-foot per square mile. | Depth in inches. |
| 1901. | | | | | |
| January | 13,300 | 2,580 | 5,054 | 0.773 | 0.891 |
| February | 9,110 | 2,580 | 4,891 | .748 | .779 |
| March | 92,600 | 3,730 | 35,284 | 5.397 | 6.222 |
| April | 158,400 | 14,030 | 43,702 | 6.684 | 7.457 |
| May | 128,000 | 8,160 | 22,106 | 3.381 | 3.898 |
| June | 50,000 | 3,730 | 14,822 | 2.267 | 2.529 |
| July | 3,730 | 1,410 | 2,524 | .386 | .445 |
| August | 42,400 | 1,830 | 10,313 | 1.577 | 1.818 |
| September | 10,140 | 3,130 | 6,886 | 1.053 | 1.175 |
| October | 6,830 | 1,830 | 3,785 | .579 | .668 |
| November | 28,900 | 1,830 | 6,715 | 1.027 | 1.146 |
| December | 326,000 | 4,770 | 35,785 | 5.473 | 6.310 |
| The year | 326,000 | 1,410 | 15,989 | 2.445 | 33.591 |
| 1902. | | | | | |
| January | 36,500 | 4,400 | 11,809 | 1.806 | 2.082 |
| February | 67,200 | 10,710 | 17,151 | 2.623 | 2.731 |
| March | 377,200 | 11,930 | 61,798 | 9.452 | 10.897 |

JUNIATA RIVER AT NEWPORT, PA.

Juniata River rises in Center County, Pa., and flows in a general southeasterly direction into Susquehanna River 15 miles above Harrisburg. Its drainage area is mountainous and for the most part covered with forest growth.

This station was established at Newport, about 15 miles above the mouth of Juniata River, March 21, 1899, by E. G. Paul. The standard boxed chain gage was located on the covered wagon bridge which was 800 feet east of the public square at Newport, Pa. It was attached to the bridge timbers inside of the bridge near the right bank. The length of the chain from the end of the weight to the marker was 39.54 feet. The gage is read once each day by A. R. Bortel. Bench mark No. 1 is on the extreme east end of the stone doorsill, south front of Butz's store building, near end of bridge; its elevation is 28.83 feet above gage datum. Bench mark No. 2 is on shelf in southeast corner of underpinning of store of J. M. Ewing; its elevation is 27.37 feet above gage datum. This bench mark was set by the Pennsylvania Railroad, and according to their records its elevation is 390.69 feet above sea level. Discharge measurements were made from the lower side of the four-span wagon bridge to which the gage was attached. The initial point for soundings was the end of the woodwork of the bridge on the right bank downstream side. In the fall of 1904 this bridge was replaced by a steel structure. During its construction the stage of the river was obtained by means of a temporary gage staff attached to the exposed end of a sewer near the bridge. This gage was set at the same elevation as the old one. As soon as the bridge is completed a standard chain gage will be put in place. The channel is straight for one-half mile above and below the station. Both banks are high and are not subject to overflow. There is a single channel, broken by three bridge piers. The piers do not interfere with the flow of the stream and there is little eddying and boiling near them. The bed is of hard material and is probably permanent. There is a good measurable velocity at all stages.

Discharge measurements of Juniata River at Newport, Pa., 1899-1904.

| Date. | Hydrographer. | Gage height. | Area of section. | Mean velocity. | Discharge. |
|----------|---------------------------|--------------|------------------|---------------------|-------------------|
| 1899. | | <i>Feet.</i> | <i>Sq. feet.</i> | <i>Ft. per sec.</i> | <i>Sec. feet.</i> |
| Mar. 21 | E. G. Paul | 6.60 | 3,486 | 3.75 | 13,094 |
| June 9 | do | 3.20 | 1,158 | 1.64 | 1,903 |
| July 31 | do | 2.90 | 849 | .80 | 682 |
| Sept. 14 | do | 4.55 | 1,755 | 2.64 | 4,625 |
| Oct. 18 | do | 2.90 | 661 | 1.25 | 829 |
| 1900. | | | | | |
| May 17 | E. G. Paul | 3.40 | 1,139 | 1.56 | 1,778 |
| Sept. 22 | do | 2.80 | 723 | .58 | 418 |
| 1901. | | | | | |
| Aug. 14 | E. G. Paul | 3.40 | 1,080 | 1.77 | 1,915 |
| Oct. 24 | do | 3.10 | 881 | 1.46 | 1,288 |
| 1902. | | | | | |
| Apr. 19 | E. G. Paul | 5.00 | 2,093 | 3.24 | 6,779 |
| Sept. 17 | do | 2.84 | 702 | 1.05 | 734 |
| 1903. | | | | | |
| Mar. 9 | E. C. Murphy | 6.21 | 2,978 | 3.64 | 10,843 |
| Apr. 2 | do | 6.21 | 2,988 | 3.53 | 10,555 |
| May 7 | do | 3.96 | 1,409 | 3.10 | 2,963 |
| June 3 | J. C. Hoyt | 3.40 | 1,102 | 1.38 | 1,525 |
| Oct. 6 | W. C. Sawyer | 3.40 | 1,044 | 1.58 | 1,655 |
| Nov. 3 | Brundage and Sawyer | 3.33 | 1,062 | 1.51 | 1,604 |
| 1904. | | | | | |
| July 16 | N. C. Grover | 4.28 | 1,520 | 2.73 | 4,152 |

Mean daily gage height, in feet, of Juniata River at Newport, Pa., 1899-1904.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|-------|-------|-------|------|------|-------|-------|------|-------|------|-------|------|
| 1899. | | | | | | | | | | | | |
| 1 | | | | 7.00 | 3.40 | 3.11 | 2.70 | 3.00 | 3.50 | 3.20 | 2.70 | 3.30 |
| 2 | | | | 6.10 | 3.40 | 3.60 | 2.70 | 3.00 | 3.50 | 3.10 | 4.00 | 3.30 |
| 3 | | | | 5.50 | 3.60 | 3.50 | 2.60 | 3.00 | 3.40 | 3.10 | 4.90 | 3.30 |
| 4 | | | | 5.10 | 3.70 | 3.40 | 2.50 | 3.00 | 3.40 | 3.10 | 4.60 | 3.30 |
| 5 | | | | 4.90 | 3.50 | 3.30 | 3.00 | 3.00 | 3.20 | 3.00 | 4.20 | 3.30 |
| 6 | | | | 4.50 | 3.40 | 3.40 | 3.00 | 3.00 | 3.50 | 3.00 | 3.90 | 3.20 |
| 7 | | | | 4.30 | 3.40 | 3.30 | 3.00 | 3.30 | 3.30 | 3.00 | 3.70 | 3.10 |
| 8 | | | | 5.00 | 3.40 | 3.20 | 3.00 | 3.50 | 3.30 | 3.00 | 3.50 | 3.10 |
| 9 | | | | 7.80 | 3.60 | 3.20 | 3.10 | 3.30 | 3.30 | 2.90 | 3.50 | 3.10 |
| 10 | | | | 6.90 | 3.60 | 2.80 | 3.30 | 3.20 | 3.50 | 2.90 | 3.40 | 3.10 |
| 11 | | | | 5.80 | 4.00 | 2.80 | 3.30 | 3.10 | 3.30 | 2.90 | 3.30 | 3.10 |
| 12 | | | | 5.50 | 4.10 | 2.80 | 3.30 | 3.10 | 3.40 | 2.90 | 3.30 | 3.70 |
| 13 | | | | 5.10 | 4.00 | 2.80 | 3.10 | 3.40 | 4.80 | 2.90 | 3.30 | 4.80 |
| 14 | | | | 4.90 | 3.80 | 2.70 | 3.10 | 3.10 | 4.80 | 2.90 | 3.20 | 5.50 |
| 15 | | | | 4.80 | 3.80 | 2.70 | 3.10 | 3.10 | 3.80 | 2.90 | 3.20 | 5.10 |
| 16 | | | | 4.70 | 3.60 | 2.70 | 3.00 | 3.00 | 3.50 | 2.90 | 3.20 | 4.80 |
| 17 | | | | 5.50 | 3.70 | 2.70 | 2.90 | 3.00 | 3.30 | 2.90 | 3.20 | 4.30 |
| 18 | | | | 4.40 | 4.10 | 2.70 | 2.90 | 3.00 | 3.10 | 2.90 | 3.10 | 4.00 |
| 19 | | | | 4.30 | 8.00 | 2.60 | 2.90 | 3.00 | 3.10 | 2.90 | 3.10 | 4.00 |
| 20 | | | | 4.10 | 7.30 | 2.60 | 3.00 | 3.10 | 3.10 | 2.90 | 3.10 | 3.70 |
| 21 | | | 6.50 | 4.00 | 7.60 | 2.60 | 3.00 | 3.00 | 3.10 | 2.90 | 3.10 | 3.70 |
| 22 | | | 6.00 | 3.90 | 5.10 | 2.60 | 3.00 | 3.00 | 3.10 | 2.90 | 3.10 | 5.00 |
| 23 | | | 5.70 | 3.80 | 4.70 | 2.50 | 3.00 | 2.90 | 3.10 | 2.80 | 3.10 | 5.00 |
| 24 | | | 6.00 | 3.80 | 4.40 | 2.50 | 3.00 | 2.90 | 3.10 | 2.80 | 3.40 | 5.00 |
| 25 | | | 5.50 | 3.70 | 4.00 | 2.50 | 3.00 | 2.90 | 3.10 | 2.80 | 4.00 | 5.80 |
| 26 | | | 5.20 | 3.60 | 3.70 | 2.50 | 3.00 | 2.90 | 3.10 | 2.80 | 4.00 | 5.50 |
| 27 | | | 5.10 | 3.60 | 3.70 | 2.50 | 2.80 | 2.90 | 3.10 | 2.80 | 3.80 | 4.50 |
| 28 | | | 5.10 | 3.60 | 3.70 | 2.50 | 2.90 | 4.40 | 3.20 | 2.80 | 3.60 | 4.80 |
| 29 | | | 8.80 | 3.50 | 3.70 | 2.70 | 2.90 | 4.10 | 3.30 | 2.80 | 3.50 | 4.10 |
| 30 | | | 10.30 | 3.40 | 4.10 | 2.70 | 2.90 | 5.00 | 3.30 | 2.70 | 3.40 | 4.10 |
| 31 | | | 8.30 | | 3.11 | | 2.90 | 4.40 | | 2.70 | | 4.10 |
| 1900. | | | | | | | | | | | | |
| 1 | 4.10 | 3.70 | 5.50 | 4.50 | 4.10 | 3.30 | 3.30 | 3.00 | 3.30 | 2.80 | 3.00 | 4.40 |
| 2 | 4.10 | 3.40 | 12.90 | 4.50 | 4.10 | 3.30 | 3.20 | 3.00 | 3.20 | 2.90 | 3.00 | 4.10 |
| 3 | 4.60 | 3.40 | 8.00 | 4.50 | 4.00 | 3.40 | 3.10 | 3.00 | 3.20 | 2.90 | 3.00 | 3.90 |
| 4 | 5.00 | 3.50 | 6.00 | 4.40 | 3.90 | 3.70 | 3.10 | 3.00 | 3.10 | 2.90 | 3.00 | 3.90 |
| 5 | 5.00 | 3.80 | 5.50 | 4.50 | 3.80 | 3.60 | 3.10 | 3.00 | 2.90 | 2.90 | 2.90 | 5.50 |
| 6 | 4.70 | 4.40 | 5.40 | 4.60 | 3.70 | 3.40 | 3.10 | 3.00 | 2.90 | 2.90 | 2.90 | 7.00 |
| 7 | 5.20 | 4.10 | 6.00 | 4.50 | 3.70 | 3.40 | 3.10 | 2.90 | 2.90 | 2.90 | 3.00 | 6.30 |
| 8 | 4.00 | 4.20 | 6.40 | 4.40 | 3.70 | 3.50 | 3.10 | 2.90 | 2.80 | 2.90 | 3.00 | 5.20 |
| 9 | 4.20 | 5.10 | 5.60 | 4.40 | 3.60 | 3.40 | 3.10 | 2.90 | 2.80 | 2.90 | 3.00 | 4.60 |
| 10 | 4.10 | 5.00 | 5.40 | 4.40 | 3.60 | 3.50 | 3.10 | 2.80 | 2.80 | 2.90 | 3.00 | 4.50 |
| 11 | 4.10 | 4.80 | 5.10 | 4.40 | 3.50 | 3.40 | 3.10 | 2.80 | 2.80 | 2.90 | 2.90 | 4.30 |
| 12 | 4.80 | 4.60 | 5.10 | 4.30 | 3.50 | 3.30 | 3.10 | 2.80 | 2.80 | 3.00 | 2.90 | 4.20 |
| 13 | 4.60 | 5.40 | 4.90 | 4.30 | 3.50 | 3.30 | 3.10 | 2.80 | 2.80 | 3.00 | 2.90 | 4.00 |
| 14 | 4.20 | 9.40 | 4.80 | 4.30 | 3.50 | 3.30 | 3.00 | 2.80 | 2.80 | 3.00 | 2.90 | 3.80 |
| 15 | 3.90 | 7.60 | 4.70 | 4.30 | 3.50 | 3.30 | 3.00 | 2.80 | 2.80 | 3.00 | 3.00 | 3.70 |
| 16 | 3.50 | 5.90 | 4.60 | 4.10 | 3.50 | 3.30 | 3.00 | 2.80 | 2.80 | 3.00 | 3.00 | 3.70 |
| 17 | 4.10 | 5.30 | 4.10 | 4.00 | 3.40 | 3.30 | 3.00 | 2.80 | 2.80 | 3.00 | 3.00 | 3.60 |
| 18 | 3.80 | 4.90 | 4.10 | 4.00 | 3.40 | 3.30 | 3.00 | 2.80 | 2.80 | 3.00 | 3.00 | 3.30 |
| 19 | 4.20 | 4.10 | 4.10 | 4.40 | 3.50 | 3.30 | 2.90 | 2.80 | 2.80 | 3.00 | 3.00 | 3.50 |
| 20 | 4.90 | 4.20 | 4.40 | 4.70 | 3.70 | 3.30 | 2.90 | 2.80 | 2.80 | 3.00 | 3.00 | 3.70 |
| 21 | 10.60 | 4.40 | 6.50 | 4.50 | 4.00 | 3.30 | 2.90 | 2.80 | 2.80 | 3.00 | 3.00 | 3.80 |
| 22 | 10.20 | 11.70 | 6.50 | 4.50 | 3.70 | 3.30 | 2.90 | 2.80 | 2.80 | 3.00 | 3.00 | 3.80 |
| 23 | 7.20 | 11.10 | 5.70 | 4.50 | 3.70 | 3.30 | 2.90 | 2.80 | 2.80 | 2.90 | 3.10 | 3.60 |
| 24 | 6.00 | 8.20 | 5.70 | 4.70 | 3.60 | 3.30 | 3.20 | 2.80 | 2.80 | 3.70 | 3.10 | 3.40 |
| 25 | 5.20 | 5.90 | 5.60 | 4.70 | 3.50 | 3.20 | 3.10 | 3.30 | 2.80 | 3.40 | 4.00 | 3.80 |
| 26 | 5.00 | 4.50 | 5.40 | 4.70 | 3.50 | 3.20 | 3.10 | 3.30 | 2.80 | 3.30 | 6.30 | 3.50 |
| 27 | 4.80 | 4.40 | 5.10 | 4.40 | 3.20 | 3.60 | 3.10 | 3.70 | 2.80 | 3.30 | 11.60 | 3.30 |
| 28 | 4.40 | 4.60 | 5.00 | 4.30 | 3.30 | 3.40 | 3.10 | 3.40 | 2.80 | 3.20 | 8.00 | 3.20 |
| 29 | 4.40 | | 4.80 | 4.20 | 3.30 | 3.30 | 3.10 | 3.30 | 2.80 | 3.20 | 5.70 | 3.20 |
| 30 | 4.20 | | 4.60 | 4.20 | 3.30 | 3.30 | 3.00 | 3.70 | 2.80 | 3.10 | 4.80 | 3.20 |
| 31 | 4.10 | | 4.50 | | 3.30 | | 3.00 | 3.60 | | 3.00 | | 3.20 |

Mean daily gage height, in feet, of Juniata River at Newport, Pa., 1899-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|---------|------|-------|-------|-------|-------|-------|--------|------|-------|------|-------|-------|
| 1901. | | | | | | | | | | | | |
| 1..... | 3.40 | 3.40 | 3.50 | 5.10 | 4.80 | 8.80 | 4.10 | 3.50 | 5.40 | 3.60 | 3.00 | 3.60 |
| 2..... | 3.30 | 3.30 | 3.50 | 4.90 | 4.70 | 7.70 | 4.20 | 3.50 | 5.40 | 3.40 | 3.00 | 3.50 |
| 3..... | 3.30 | 3.30 | 3.60 | 4.90 | 4.50 | 7.10 | 4.20 | 3.50 | 5.20 | 3.50 | 3.00 | 4.20 |
| 4..... | 3.10 | 3.40 | 3.60 | 7.60 | 4.60 | 6.10 | α 4.00 | 3.30 | 5.00 | 3.50 | 3.00 | 4.20 |
| 5..... | 3.30 | 3.80 | 4.40 | 9.00 | 4.50 | 5.20 | α 3.90 | 3.10 | 4.60 | 3.50 | 3.00 | 4.20 |
| 6..... | 3.40 | 4.30 | 4.80 | 10.50 | 4.40 | 5.00 | α 3.80 | 3.10 | 4.20 | 3.40 | 3.00 | 4.20 |
| 7..... | 3.20 | 4.80 | 4.70 | 11.00 | 4.20 | 4.90 | α 3.70 | 4.50 | 4.00 | 3.30 | 3.00 | 4.20 |
| 8..... | 3.60 | 4.80 | 4.40 | 10.90 | 4.10 | 5.80 | α 3.60 | 6.20 | 3.90 | 3.20 | 3.00 | 3.70 |
| 9..... | 3.30 | 4.30 | 4.20 | 9.50 | 4.00 | 5.10 | α 3.50 | 5.00 | 3.70 | 3.20 | 3.00 | 4.20 |
| 10..... | 3.20 | 4.30 | 5.00 | 7.90 | 4.20 | 4.60 | α 3.40 | 4.10 | 3.60 | 3.10 | 3.00 | 5.00 |
| 11..... | 3.20 | 4.00 | 15.90 | 7.00 | 4.70 | 4.50 | 3.30 | 4.00 | 3.70 | 3.10 | 3.00 | 7.00 |
| 12..... | 3.50 | 3.80 | 15.40 | 6.20 | 4.80 | 4.50 | 3.30 | 3.70 | 4.10 | 3.20 | 3.00 | 6.20 |
| 13..... | 3.80 | 3.80 | 10.40 | 5.80 | 4.80 | 4.50 | 3.30 | 3.50 | 4.00 | 3.30 | 3.00 | 5.10 |
| 14..... | 3.80 | 4.30 | 7.80 | 5.40 | 4.70 | 4.50 | 3.40 | 3.40 | 3.80 | 3.40 | 3.00 | 5.20 |
| 15..... | 3.80 | 3.80 | 7.20 | 5.20 | 4.60 | 4.40 | 3.40 | 3.40 | 3.80 | 3.40 | 3.00 | 18.00 |
| 16..... | 3.80 | 3.80 | 6.50 | 5.60 | 4.40 | 4.40 | 3.50 | 3.40 | 3.80 | 3.30 | 3.00 | 18.00 |
| 17..... | 3.80 | 3.60 | 5.80 | 5.60 | 4.10 | 4.50 | 4.90 | 3.40 | 3.70 | 3.30 | 3.00 | 10.80 |
| 18..... | 3.80 | 3.50 | 5.50 | 5.40 | 4.20 | 5.00 | 5.00 | 4.10 | 3.80 | 3.30 | 3.00 | 13.65 |
| 19..... | 3.80 | 3.50 | 5.10 | 5.40 | 4.10 | 4.60 | 5.20 | 4.30 | 3.90 | 3.20 | 3.00 | 6.30 |
| 20..... | 3.80 | 3.50 | 5.00 | 5.40 | 4.10 | 4.40 | 4.80 | 5.30 | 3.70 | 3.20 | 3.00 | 5.30 |
| 21..... | 3.80 | 3.50 | 5.90 | 10.50 | 4.10 | 4.30 | 4.10 | 4.10 | 3.60 | 3.10 | 3.00 | 12.05 |
| 22..... | 3.90 | 3.50 | 6.90 | 13.80 | 4.50 | 4.60 | 3.80 | 4.10 | 3.50 | 3.10 | 3.00 | 4.10 |
| 23..... | 4.10 | 3.60 | 6.50 | 11.50 | 13.00 | 5.30 | 3.70 | 4.10 | 3.40 | 3.10 | 3.00 | 4.40 |
| 24..... | 3.70 | 3.70 | 5.80 | 9.00 | 9.50 | 5.60 | 3.50 | 5.50 | 3.20 | 3.10 | 3.80 | 4.40 |
| 25..... | 3.50 | 3.90 | 5.50 | 7.60 | 9.00 | 5.00 | 3.40 | 5.50 | 3.30 | 3.00 | 4.90 | 4.60 |
| 26..... | 3.40 | 3.40 | 5.30 | 6.80 | 10.60 | 4.60 | 3.70 | 5.10 | 3.30 | 3.00 | 4.80 | 4.80 |
| 27..... | 3.70 | 3.40 | 5.50 | 6.00 | 8.60 | 4.40 | 3.50 | 4.90 | 3.20 | 3.00 | 4.00 | 4.50 |
| 28..... | 3.70 | 3.50 | 6.60 | 5.60 | 10.30 | 4.20 | 3.50 | 4.30 | 3.20 | 3.00 | 4.00 | 4.50 |
| 29..... | 3.60 | ----- | 6.50 | 5.30 | 12.60 | 4.00 | 3.40 | 4.20 | 3.50 | 3.00 | 3.90 | 5.20 |
| 30..... | 3.50 | ----- | 5.90 | 5.00 | 13.30 | 4.00 | 3.40 | 4.30 | 3.50 | 3.00 | 3.70 | 6.40 |
| 31..... | 3.60 | ----- | 5.40 | ----- | 11.60 | ----- | 3.40 | 4.30 | ----- | 3.00 | ----- | 7.70 |
| 1902. | | | | | | | | | | | | |
| 1..... | 6.40 | 4.20 | 25.30 | 5.80 | 4.00 | 3.20 | 5.40 | 4.40 | 3.00 | 4.90 | 4.00 | 3.60 |
| 2..... | 5.60 | 4.20 | 19.50 | 5.70 | 3.80 | 3.20 | 6.30 | 4.00 | 3.00 | 4.90 | 3.80 | 3.60 |
| 3..... | 5.00 | 4.60 | 15.50 | 5.40 | 3.80 | 3.20 | 6.10 | 3.50 | 2.90 | 3.50 | 3.70 | 4.30 |
| 4..... | 5.40 | 3.90 | 12.00 | 5.30 | 3.90 | 3.20 | 6.40 | 4.00 | 2.90 | 3.50 | 3.60 | 5.30 |
| 5..... | 4.30 | 4.50 | 9.30 | 5.00 | 3.90 | 3.20 | 6.70 | 4.00 | 2.90 | 3.50 | 3.60 | 5.50 |
| 6..... | 4.20 | 3.60 | 7.10 | 5.00 | 3.90 | 3.20 | 5.60 | 4.00 | 2.90 | 4.00 | 3.50 | 4.90 |
| 7..... | 4.20 | 3.60 | 6.50 | 5.20 | 3.90 | 3.20 | 5.40 | 3.80 | 2.90 | 4.00 | 3.40 | 4.50 |
| 8..... | 4.20 | 3.70 | 6.00 | 14.65 | 3.90 | 3.10 | 5.00 | 3.80 | 2.90 | 3.80 | 3.30 | 4.50 |
| 9..... | 4.10 | 5.10 | 5.50 | 18.50 | 3.90 | 3.10 | 4.50 | 3.80 | 2.90 | 3.50 | 3.40 | 4.20 |
| 10..... | 4.10 | 5.80 | 6.20 | 18.50 | 3.90 | 3.10 | 4.80 | 4.00 | 3.10 | 3.40 | 3.40 | 4.40 |
| 11..... | 4.10 | 5.80 | 8.40 | 12.50 | 3.70 | 3.10 | 4.60 | 4.60 | 3.10 | 3.40 | 3.40 | 4.20 |
| 12..... | 4.00 | 5.70 | 9.50 | 10.00 | 3.50 | 3.10 | 4.00 | 3.90 | 3.00 | 4.60 | 3.30 | 5.30 |
| 13..... | 3.90 | 5.00 | 13.30 | 8.10 | 3.50 | 3.20 | 3.90 | 3.80 | 3.00 | 6.40 | 3.30 | 7.70 |
| 14..... | 3.90 | 4.50 | 14.10 | 7.00 | 3.30 | 3.30 | 3.90 | 3.60 | 2.90 | 6.00 | 3.30 | 4.80 |
| 15..... | 3.70 | 4.30 | 9.60 | 6.50 | 3.30 | 3.30 | 3.80 | 3.30 | 2.90 | 4.70 | 3.30 | 6.40 |
| 16..... | 3.50 | 5.10 | 9.00 | 5.50 | 3.30 | 4.30 | 3.60 | 3.40 | 2.90 | 4.40 | 3.20 | 5.80 |
| 17..... | 3.80 | 5.10 | 15.30 | 5.00 | 3.40 | 3.80 | 3.00 | 3.40 | 2.90 | 4.00 | 3.20 | 7.70 |
| 18..... | 3.80 | 5.10 | 12.50 | 5.00 | 3.40 | 3.90 | 3.60 | 3.30 | 2.90 | 3.80 | 3.20 | 7.00 |
| 19..... | 7.50 | 5.10 | 9.50 | 4.90 | 3.40 | 3.50 | 3.60 | 3.30 | 2.80 | 3.80 | 3.20 | 6.40 |
| 20..... | 4.00 | 4.90 | 8.00 | 4.70 | 3.40 | 3.30 | 3.50 | 3.20 | 2.90 | 3.50 | 3.20 | 5.70 |
| 21..... | 4.00 | 4.80 | 6.50 | 4.60 | 3.40 | 3.40 | 3.60 | 3.10 | 2.90 | 3.40 | 3.20 | 6.20 |
| 22..... | 9.50 | 4.80 | 6.00 | 4.50 | 3.40 | 3.10 | 3.70 | 3.20 | 2.80 | 3.30 | 3.20 | 9.50 |
| 23..... | 8.20 | 4.90 | 5.50 | 4.40 | 3.40 | 3.10 | 3.60 | 3.10 | 2.80 | 3.40 | 3.20 | 10.80 |
| 24..... | 6.20 | 4.40 | 5.50 | 4.30 | 3.40 | 3.10 | 3.50 | 3.30 | 2.80 | 3.30 | 3.20 | 8.60 |
| 25..... | 5.00 | 4.50 | 5.10 | 4.20 | 3.40 | 3.10 | 4.10 | 3.20 | 3.00 | 3.20 | 3.20 | 7.40 |
| 26..... | 4.60 | 9.00 | 5.00 | 4.10 | 3.40 | 4.00 | 3.80 | 3.20 | 3.30 | 3.20 | 3.30 | 6.30 |
| 27..... | 5.70 | 9.90 | 4.80 | 3.80 | 3.60 | 3.80 | 3.50 | 2.90 | 4.20 | 3.20 | 3.50 | 5.80 |
| 28..... | 7.50 | 14.90 | 4.50 | 3.80 | 3.40 | 3.90 | 3.50 | 4.30 | 3.60 | 3.80 | 3.70 | 5.30 |
| 29..... | 5.60 | ----- | 4.20 | 4.00 | 3.30 | 3.90 | 3.60 | 4.70 | 3.50 | 5.70 | 3.80 | 4.80 |
| 30..... | 5.00 | ----- | 5.80 | 4.10 | 3.30 | 4.70 | 4.20 | 3.30 | 3.50 | 5.00 | 3.80 | 4.70 |
| 31..... | 4.50 | ----- | 6.00 | ----- | 3.20 | ----- | 4.20 | 2.90 | ----- | 4.40 | ----- | 4.70 |

α Estimated.


Mean daily gage height, in feet, of Juniata River at Newport, Pa., 1899-1904—
Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|--------------------|-------------------|-------|-------|------|-------|-------|------|-------|-------------------|-------|------|
| 1903. | | | | | | | | | | | | |
| 1 | 4.60 | 8.20 | 15.50 | 7.00 | 3.80 | 3.50 | 9.50 | 3.50 | 6.10 | 3.40 | 3.50 | 3.30 |
| 2 | 5.30 | 6.90 | 12.10 | 6.30 | 3.80 | 3.40 | 6.10 | 3.50 | 5.60 | 3.40 | 3.50 | 3.30 |
| 3 | 5.30 | 6.70 | 9.00 | 5.60 | 4.10 | 3.40 | 5.20 | 3.40 | 5.10 | 3.30 | 3.30 | 3.20 |
| 4 | 7.90 | 10.10 | 7.50 | 5.20 | 4.10 | 3.40 | 4.80 | 3.40 | 4.50 | 3.30 | 3.30 | 3.20 |
| 5 | 7.50 | 14.50 | 6.70 | 5.20 | 4.00 | 3.30 | 4.50 | 3.50 | 4.30 | 3.30 | 3.30 | 3.20 |
| 6 | 6.60 | 11.50 | 6.30 | 5.10 | 4.00 | 3.30 | 5.00 | 3.50 | 4.20 | 3.40 | 3.30 | 3.20 |
| 7 | 6.00 | 8.50 | 6.00 | 4.80 | 4.00 | 3.30 | 9.50 | 3.80 | 4.10 | 3.40 | 3.30 | 3.20 |
| 8 | 5.00 | 7.10 | 5.80 | 5.30 | 3.80 | 4.00 | 6.80 | 4.00 | 4.00 | 3.90 | 3.30 | 3.20 |
| 9 | 5.50 | 6.50 | 6.40 | 5.60 | 3.80 | 4.20 | 5.40 | 3.80 | 4.30 | 3.80 | 3.30 | 3.30 |
| 10 | 4.70 | 5.80 | 6.90 | 5.80 | 3.80 | 4.20 | 4.90 | 3.70 | 5.00 | 5.40 | 3.30 | 3.35 |
| 11 | 4.30 | 5.90 | 6.60 | 5.60 | 3.70 | 4.30 | 4.50 | 3.50 | 4.70 | 4.80 | 3.30 | 3.30 |
| 12 | 4.00 | 6.10 | 6.30 | 5.40 | 3.60 | 4.30 | 4.40 | 3.50 | 4.90 | 4.50 | 3.30 | 3.10 |
| 13 | 3.80 | 6.60 | 5.90 | 5.50 | 3.60 | 5.00 | 4.50 | 3.40 | 4.60 | 4.20 | 3.30 | 3.10 |
| 14 | 4.40 | 6.30 | 5.50 | 6.60 | 3.60 | 4.70 | 4.40 | 3.30 | 4.20 | 4.10 | 3.30 | 3.20 |
| 15 | 4.50 | 5.90 | 5.30 | 13.10 | 3.50 | 4.80 | 4.40 | 3.30 | 4.00 | 3.90 | 3.30 | 3.30 |
| 16 | 4.30 | 5.80 | 5.00 | 15.60 | 3.50 | 4.70 | 4.20 | 4.20 | 3.90 | 3.90 | 3.30 | 3.20 |
| 17 | 4.40 | 10.20 | 4.90 | 14.00 | 3.50 | 4.60 | 4.00 | 3.90 | 3.90 | 3.80 | 3.40 | 3.20 |
| 18 | 4.30 | 7.90 | 4.90 | 9.40 | 3.50 | 4.30 | 5.00 | 3.50 | 4.30 | 4.20 | 3.50 | 3.50 |
| 19 | 4.40 | 6.70 | 4.70 | 8.00 | 3.50 | 4.10 | 7.50 | 3.50 | 4.60 | 4.40 | 3.50 | 3.70 |
| 20 | 4.30 | 6.00 | 4.50 | 7.10 | 3.50 | 4.10 | 6.00 | 3.40 | 4.10 | 4.20 | 3.60 | 3.70 |
| 21 | 4.90 | 5.40 | 4.50 | 6.50 | 3.50 | 4.10 | 5.20 | 3.40 | 4.00 | 4.00 | 3.70 | 3.90 |
| 22 | 4.30 | 5.40 | 4.70 | 5.80 | 3.50 | 4.30 | 4.70 | 3.50 | 3.90 | 3.90 | 3.60 | 3.90 |
| 23 | 4.80 | 5.40 | 5.80 | 5.40 | 3.50 | 4.30 | 4.40 | 3.50 | 3.80 | 3.80 | 3.50 | 3.90 |
| 24 | 4.80 | 5.00 | 12.70 | 5.20 | 3.50 | 4.80 | 4.30 | 3.30 | 3.70 | 3.70 | 3.50 | 3.90 |
| 25 | 4.80 | 5.30 | 12.20 | 4.90 | 3.50 | 6.00 | 4.10 | 3.40 | 3.60 | ^a 3.60 | 3.50 | 3.90 |
| 26 | 4.60 | 5.10 | 8.50 | 4.80 | 3.40 | 5.60 | 3.90 | 3.40 | 3.50 | ^a 3.60 | 3.40 | 3.90 |
| 27 | 4.40 | 5.00 | 7.10 | 4.80 | 3.50 | 5.00 | 3.80 | 3.50 | 3.50 | 3.50 | 3.40 | 3.90 |
| 28 | 4.40 | 8.90 | 6.30 | 4.30 | 3.50 | 4.50 | 3.80 | 3.50 | 3.50 | 3.50 | 3.40 | 3.90 |
| 29 | 5.30 | ----- | 5.60 | 4.10 | 3.50 | 4.60 | 3.70 | 3.70 | 3.40 | 3.50 | 3.30 | 3.90 |
| 30 | 8.00 | ----- | 5.50 | 4.10 | 3.50 | 4.90 | 3.50 | 8.00 | 3.40 | 3.50 | 3.30 | 3.90 |
| 31 | 10.20 | ----- | 6.20 | ----- | 3.50 | ----- | 3.50 | 6.70 | ----- | 3.50 | ----- | 4.20 |
| 1904. | | | | | | | | | | | | |
| 1 | 4.20 | 4.00 | 7.50 | 6.70 | 6.70 | 4.90 | 3.70 | 3.30 | 3.00 | 2.90 | 2.90 | 2.50 |
| 2 | 4.20 | 5.00 | 12.00 | 13.40 | 6.10 | 5.60 | 3.70 | 3.30 | 3.00 | 2.90 | 2.90 | 2.80 |
| 3 | 4.50 | 5.00 | 7.20 | 9.40 | 5.70 | 6.00 | 3.70 | 3.70 | 3.00 | 2.90 | 2.90 | 2.90 |
| 4 | 4.60 | 5.00 | 13.50 | 7.70 | 5.30 | 5.40 | 3.70 | 3.60 | 3.00 | 2.90 | 2.90 | 3.20 |
| 5 | 4.60 | 8.00 | 8.90 | 6.70 | 5.00 | 5.90 | 3.70 | 3.60 | 3.00 | 2.90 | 2.90 | 2.90 |
| 6 | 4.60 | 8.50 | 6.00 | 5.70 | 4.80 | 5.90 | 3.70 | 3.50 | 3.00 | 2.90 | 2.80 | 3.10 |
| 7 | 4.60 | 11.50 | 5.50 | 5.70 | 4.70 | 5.40 | 4.40 | 3.90 | 2.90 | 2.90 | 2.80 | 3.20 |
| 8 | 4.50 | ^a 8.50 | 14.00 | 5.30 | 4.60 | 4.70 | 5.10 | 3.50 | 2.90 | 2.90 | 2.80 | 3.20 |
| 9 | 4.50 | 6.50 | 10.00 | 5.30 | 4.50 | 4.60 | 5.80 | 3.30 | 3.00 | 2.90 | 2.80 | 3.20 |
| 10 | 4.50 | 5.00 | 7.20 | 6.30 | 4.40 | 4.50 | 7.20 | 3.30 | 3.00 | 2.90 | 2.80 | 3.10 |
| 11 | 4.40 | 4.60 | 6.00 | 6.30 | 4.30 | 5.10 | 8.70 | 3.20 | 3.00 | 2.90 | 2.90 | 3.10 |
| 12 | 4.20 | 4.20 | 6.00 | 6.00 | 4.20 | 4.60 | 7.10 | 3.20 | 3.00 | 2.90 | 2.90 | 3.10 |
| 13 | 4.10 | 4.00 | 5.20 | 5.70 | 4.20 | 4.40 | 5.50 | 3.10 | 3.00 | 2.90 | 2.90 | 3.10 |
| 14 | 4.10 | 3.90 | 5.20 | 5.30 | 4.20 | 4.20 | 5.30 | 3.10 | 2.90 | 2.90 | 2.90 | 3.10 |
| 15 | 4.10 | 4.10 | 5.00 | 5.00 | 4.20 | 4.00 | 4.70 | 3.10 | 2.90 | 2.90 | 2.90 | 3.10 |
| 16 | 4.10 | 4.20 | 4.80 | 4.80 | 4.20 | 4.00 | 4.70 | 3.10 | 3.00 | 2.90 | 2.90 | 3.10 |
| 17 | 4.00 | 4.40 | 4.50 | 4.80 | 4.20 | 4.40 | 4.10 | 3.00 | 3.00 | 2.90 | 2.90 | 3.10 |
| 18 | 4.00 | 5.00 | 4.50 | 4.70 | 4.30 | 3.90 | 3.90 | 3.20 | 3.00 | 2.90 | 2.90 | 3.10 |
| 19 | 4.00 | 4.60 | 4.80 | 4.40 | 4.50 | 3.90 | 3.80 | 3.10 | 3.00 | 2.90 | 2.90 | 3.10 |
| 20 | 4.00 | 4.70 | 4.50 | 4.40 | 6.70 | 3.90 | 3.90 | 3.20 | 2.90 | 2.90 | 2.80 | 3.10 |
| 21 | 4.00 | 4.70 | 5.80 | 4.30 | 5.90 | 3.70 | 3.70 | 3.20 | 2.90 | 3.30 | 2.80 | 3.10 |
| 22 | 4.00 | 5.00 | 5.50 | 4.20 | 5.50 | 5.70 | 3.60 | 3.20 | 2.90 | 3.30 | 2.80 | 3.10 |
| 23 | 5.40 | 5.00 | 5.80 | 4.20 | 4.90 | 5.50 | 3.50 | 3.20 | 2.90 | 3.20 | 2.80 | 3.10 |
| 24 | ^b 11.00 | 5.40 | 8.00 | 4.00 | 4.60 | 5.30 | 3.80 | 3.20 | 2.90 | 3.10 | 2.70 | 3.20 |
| 25 | 7.00 | 7.20 | 7.50 | 4.00 | 4.50 | 4.40 | 3.80 | 3.10 | 2.90 | 3.10 | 2.70 | 3.20 |
| 26 | 5.50 | 7.40 | 6.90 | 4.00 | 4.60 | 4.00 | 3.70 | 3.10 | 2.90 | 3.00 | 2.70 | 3.20 |
| 27 | 4.50 | 5.90 | 6.20 | 4.20 | 4.70 | 3.50 | 3.70 | 3.00 | 2.90 | 2.90 | 2.70 | 3.50 |
| 28 | 4.10 | 4.80 | 6.20 | 4.60 | 4.50 | 3.80 | 3.50 | 3.00 | 2.90 | 2.90 | 2.60 | 3.70 |
| 29 | 3.80 | 4.50 | 5.60 | 6.50 | 4.40 | 3.70 | 3.40 | 3.10 | 2.90 | 2.90 | 2.60 | 3.80 |
| 30 | 3.70 | ----- | 5.20 | 7.50 | 4.20 | 3.70 | 3.30 | 3.10 | 2.90 | 2.90 | 2.50 | 3.80 |
| 31 | 3.80 | ----- | 5.00 | ----- | 4.60 | ----- | 3.30 | 3.00 | ----- | 2.90 | ----- | 3.80 |

^a Interpolated.^b Ice moved out.

Rating table for Juniata River at Newport, Pa., from 1899 to 1904.

| Gage height. | Discharge. | Gage height. | Discharge. | Gage height. | Discharge. | Gage height. | Discharge. |
|--------------|---------------------|--------------|---------------------|--------------|---------------------|--------------|---------------------|
| <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> |
| 2.5 | 230 | 4.7 | 5,180 | 6.9 | 14,570 | 10.2 | 38,500 |
| 2.6 | 320 | 4.8 | 5,510 | 7.0 | 15,170 | 10.4 | 40,300 |
| 2.7 | 430 | 4.9 | 5,850 | 7.1 | 15,770 | 10.6 | 42,200 |
| 2.8 | 570 | 5.0 | 6,200 | 7.2 | 16,370 | 10.8 | 44,100 |
| 2.9 | 750 | 5.1 | 6,550 | 7.3 | 16,970 | 11.0 | 46,000 |
| 3.0 | 950 | 5.2 | 6,910 | 7.4 | 17,570 | 11.2 | 48,000 |
| 3.1 | 1,160 | 5.3 | 7,270 | 7.5 | 18,170 | 11.4 | 50,100 |
| 3.2 | 1,370 | 5.4 | 7,640 | 7.6 | 18,770 | 11.6 | 52,200 |
| 3.3 | 1,580 | 5.5 | 8,010 | 7.7 | 19,380 | 11.8 | 54,300 |
| 3.4 | 1,790 | 5.6 | 8,390 | 7.8 | 20,000 | 12.0 | 56,400 |
| 3.5 | 2,000 | 5.7 | 8,770 | 7.9 | 20,640 | 12.2 | 58,600 |
| 3.6 | 2,210 | 5.8 | 9,150 | 8.0 | 21,300 | 12.4 | 60,800 |
| 3.7 | 2,430 | 5.9 | 9,540 | 8.2 | 22,700 | 12.6 | 63,100 |
| 3.8 | 2,650 | 6.0 | 9,930 | 8.4 | 24,100 | 12.8 | 65,400 |
| 3.9 | 2,880 | 6.1 | 10,330 | 8.6 | 25,500 | 13.0 | 67,700 |
| 4.0 | 3,120 | 6.2 | 10,740 | 8.8 | 27,000 | 13.2 | 70,100 |
| 4.1 | 3,380 | 6.3 | 11,200 | 9.0 | 28,500 | 13.4 | 72,600 |
| 4.2 | 3,650 | 6.4 | 11,720 | 9.2 | 30,100 | 13.6 | 75,100 |
| 4.3 | 3,930 | 6.5 | 12,270 | 9.4 | 31,700 | 13.8 | 77,600 |
| 4.4 | 4,220 | 6.6 | 12,830 | 9.6 | 33,400 | | |
| 4.5 | 4,530 | 6.7 | 13,400 | 9.8 | 35,100 | | |
| 4.6 | 4,850 | 6.8 | 13,980 | 10.0 | 36,800 | | |



RATING CURVE FOR JUNIATA RIVER AT NEWPORT, PA.

Mean daily discharge, in second-feet, of Juniata River at Newport, Pa., 1899-1904.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|--------|--------|--------|--------|--------|-------|-------|-------|-------|-------|--------|--------|
| 1899. | | | | | | | | | | | | |
| 1 | | | | 15,170 | 1,790 | 1,160 | 430 | 950 | 2,000 | 1,370 | 430 | 1,580 |
| 2 | | | | 10,330 | 1,790 | 2,210 | 430 | 950 | 2,000 | 1,160 | 3,120 | 1,580 |
| 3 | | | | 8,010 | 2,210 | 2,000 | 320 | 950 | 1,790 | 1,160 | 5,850 | 1,580 |
| 4 | | | | 6,550 | 2,430 | 1,790 | 230 | 950 | 1,790 | 1,160 | 4,850 | 1,580 |
| 5 | | | | 5,850 | 2,000 | 1,580 | 950 | 950 | 1,370 | 950 | 3,650 | 1,580 |
| 6 | | | | 4,530 | 1,790 | 1,790 | 950 | 950 | 1,580 | 950 | 2,880 | 1,370 |
| 7 | | | | 3,930 | 1,790 | 1,580 | 950 | 1,580 | 1,580 | 950 | 2,430 | 1,160 |
| 8 | | | | 8,390 | 1,790 | 1,370 | 950 | 2,000 | 1,580 | 950 | 2,000 | 1,160 |
| 9 | | | | 20,000 | 2,210 | 1,370 | 1,160 | 1,580 | 1,580 | 750 | 2,000 | 1,160 |
| 10 | | | | 14,570 | 2,210 | 570 | 1,580 | 1,370 | 1,580 | 750 | 1,790 | 1,160 |
| 11 | | | | 9,150 | 3,120 | 570 | 1,580 | 1,160 | 1,580 | 750 | 1,580 | 1,160 |
| 12 | | | | 8,010 | 3,380 | 570 | 1,580 | 1,160 | 1,790 | 750 | 1,580 | 2,430 |
| 13 | | | | 6,550 | 3,120 | 570 | 1,160 | 1,790 | 5,510 | 750 | 1,580 | 5,510 |
| 14 | | | | 5,850 | 2,650 | 430 | 1,160 | 1,160 | 5,510 | 750 | 1,370 | 8,010 |
| 15 | | | | 5,510 | 2,650 | 430 | 1,160 | 1,160 | 2,650 | 750 | 1,370 | 6,550 |
| 16 | | | | 5,180 | 2,210 | 430 | 950 | 950 | 2,000 | 750 | 1,370 | 5,510 |
| 17 | | | | 8,010 | 2,430 | 430 | 750 | 950 | 1,580 | 750 | 1,370 | 3,930 |
| 18 | | | | 4,220 | 3,380 | 430 | 750 | 950 | 1,160 | 750 | 1,160 | 3,120 |
| 19 | | | | 3,930 | 21,300 | 320 | 750 | 950 | 1,160 | 750 | 1,160 | 3,120 |
| 20 | | | | 3,380 | 16,970 | 320 | 950 | 1,160 | 1,160 | 750 | 1,160 | 2,430 |
| 21 | | | | 12,270 | 18,770 | 320 | 950 | 950 | 1,160 | 750 | 1,160 | 2,430 |
| 22 | | | | 9,930 | 2,880 | 6,550 | 320 | 950 | 1,160 | 750 | 1,160 | 6,200 |
| 23 | | | | 8,770 | 2,650 | 5,180 | 230 | 950 | 750 | 1,160 | 570 | 1,160 |
| 24 | | | | 9,930 | 2,650 | 4,220 | 230 | 950 | 750 | 1,160 | 570 | 1,790 |
| 25 | | | | 8,010 | 2,430 | 3,120 | 230 | 950 | 750 | 1,160 | 570 | 3,120 |
| 26 | | | | 6,910 | 2,210 | 2,430 | 230 | 950 | 750 | 1,160 | 570 | 3,120 |
| 27 | | | | 6,550 | 2,210 | 2,430 | 230 | 570 | 750 | 1,160 | 570 | 2,650 |
| 28 | | | | 6,550 | 2,210 | 2,430 | 230 | 750 | 4,220 | 1,370 | 570 | 2,210 |
| 29 | | | | 27,000 | 2,000 | 2,430 | 430 | 750 | 3,380 | 1,580 | 570 | 2,000 |
| 30 | | | | 39,400 | 1,790 | 3,380 | 430 | 750 | 6,200 | 1,580 | 430 | 1,790 |
| 31 | | | | 23,400 | | 1,160 | | 750 | 4,220 | | 430 | |
| 1900. | | | | | | | | | | | | |
| 1 | 3,380 | 2,430 | 9,540 | 4,530 | 3,380 | 1,580 | 1,580 | 950 | 1,580 | 570 | 950 | 4,220 |
| 2 | 3,380 | 1,790 | 66,500 | 4,530 | 3,380 | 1,580 | 1,370 | 950 | 1,370 | 750 | 950 | 3,380 |
| 3 | 4,850 | 1,790 | 21,300 | 4,530 | 3,120 | 1,790 | 1,160 | 950 | 1,370 | 750 | 950 | 2,880 |
| 4 | 6,200 | 2,000 | 9,930 | 4,220 | 2,880 | 2,430 | 1,160 | 950 | 1,160 | 750 | 950 | 2,880 |
| 5 | 6,200 | 2,650 | 8,010 | 4,530 | 2,650 | 2,210 | 1,160 | 950 | 750 | 750 | 750 | 8,010 |
| 6 | 5,180 | 4,220 | 7,640 | 4,850 | 2,430 | 1,790 | 1,160 | 950 | 750 | 750 | 750 | 15,170 |
| 7 | 6,910 | 3,380 | 9,930 | 4,530 | 2,430 | 1,790 | 1,160 | 750 | 750 | 750 | 950 | 11,200 |
| 8 | 3,120 | 3,650 | 11,720 | 4,220 | 2,430 | 1,580 | 1,160 | 750 | 570 | 750 | 950 | 6,910 |
| 9 | 3,650 | 6,550 | 8,390 | 4,220 | 2,210 | 1,790 | 1,160 | 750 | 570 | 750 | 950 | 4,850 |
| 10 | 3,380 | 8,390 | 7,640 | 4,220 | 2,210 | 2,000 | 1,160 | 570 | 570 | 750 | 950 | 4,530 |
| 11 | 3,380 | 5,510 | 6,550 | 4,220 | 2,000 | 1,790 | 1,160 | 570 | 570 | 750 | 750 | 3,930 |
| 12 | 5,510 | 4,850 | 6,550 | 3,930 | 2,000 | 1,580 | 1,160 | 570 | 570 | 950 | 750 | 3,650 |
| 13 | 4,850 | 7,640 | 5,850 | 3,930 | 2,000 | 1,580 | 1,160 | 570 | 570 | 950 | 750 | 3,120 |
| 14 | 3,650 | 31,700 | 5,510 | 3,930 | 2,000 | 1,580 | 950 | 570 | 570 | 950 | 750 | 2,650 |
| 15 | 2,880 | 18,770 | 5,180 | 3,930 | 2,000 | 1,580 | 950 | 570 | 570 | 950 | 950 | 2,430 |
| 16 | 2,000 | 9,540 | 4,850 | 3,380 | 2,000 | 1,580 | 950 | 570 | 570 | 950 | 950 | 2,430 |
| 17 | 3,380 | 7,270 | 3,380 | 3,120 | 1,790 | 1,580 | 950 | 570 | 570 | 950 | 950 | 2,210 |
| 18 | 2,650 | 5,850 | 3,380 | 3,120 | 1,790 | 1,580 | 950 | 570 | 570 | 950 | 950 | 1,580 |
| 19 | 3,650 | 3,380 | 3,380 | 4,220 | 2,000 | 1,580 | 750 | 570 | 570 | 950 | 950 | 2,000 |
| 20 | 5,850 | 3,650 | 4,220 | 5,180 | 2,430 | 1,580 | 750 | 570 | 570 | 950 | 950 | 2,430 |
| 21 | 42,200 | 4,220 | 12,270 | 4,530 | 3,120 | 1,580 | 750 | 570 | 570 | 950 | 950 | 2,650 |
| 22 | 38,500 | 53,200 | 12,270 | 4,530 | 2,430 | 1,580 | 750 | 570 | 570 | 950 | 950 | 2,650 |
| 23 | 16,370 | 47,000 | 8,770 | 4,530 | 2,430 | 1,580 | 750 | 570 | 570 | 750 | 1,160 | 2,210 |
| 24 | 9,930 | 22,700 | 8,770 | 5,180 | 2,210 | 1,580 | 1,370 | 570 | 570 | 2,430 | 1,160 | 1,790 |
| 25 | 6,910 | 9,540 | 8,390 | 5,180 | 2,000 | 1,370 | 1,160 | 1,580 | 570 | 1,790 | 3,120 | 2,650 |
| 26 | 6,200 | 4,530 | 7,640 | 5,180 | 2,000 | 1,370 | 1,160 | 1,580 | 570 | 1,580 | 11,200 | 2,000 |
| 27 | 5,510 | 4,220 | 6,550 | 4,220 | 1,370 | 2,210 | 1,160 | 2,430 | 570 | 1,580 | 52,200 | 1,580 |
| 28 | 4,220 | 4,850 | 6,200 | 3,930 | 1,580 | 1,790 | 1,160 | 1,790 | 570 | 1,370 | 21,300 | 1,370 |
| 29 | 4,220 | | 5,510 | 3,650 | 1,580 | 1,580 | 1,160 | 1,580 | 570 | 1,370 | 8,770 | 1,370 |
| 30 | 3,650 | | 4,850 | 3,650 | 1,580 | 1,580 | 950 | 2,430 | 570 | 1,160 | 5,510 | 1,370 |
| 31 | 3,380 | | 4,530 | | 1,580 | | | 2,210 | | 950 | | 1,370 |

Mean daily discharge, in second-feet, of Juniata River, at Newport, Pa., 1899-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|--------|--------|---------|---------|--------|--------|--------|--------|-------|--------|-------|---------|
| 1901. | | | | | | | | | | | | |
| 1 | 1,790 | 1,790 | 2,000 | 6,550 | 5,510 | 27,000 | 3,380 | 2,000 | 7,640 | 2,210 | 950 | 2,210 |
| 2 | 1,580 | 1,580 | 2,000 | 5,850 | 5,180 | 19,380 | 3,650 | 2,000 | 7,640 | 1,790 | 950 | 2,000 |
| 3 | 1,580 | 1,580 | 2,210 | 5,850 | 4,530 | 15,770 | 3,650 | 2,000 | 6,910 | 2,000 | 950 | 3,650 |
| 4 | 1,160 | 1,790 | 2,210 | 18,770 | 4,850 | 10,390 | 3,120 | 1,580 | 6,200 | 2,000 | 950 | 3,650 |
| 5 | 1,580 | 2,650 | 4,220 | 28,500 | 4,530 | 6,910 | 2,880 | 1,160 | 4,850 | 2,000 | 950 | 3,650 |
| 6 | 1,790 | 3,930 | 5,510 | 41,200 | 4,220 | 6,200 | 2,650 | 1,160 | 3,650 | 1,790 | 950 | 3,650 |
| 7 | 1,370 | 3,930 | 5,180 | 46,000 | 3,650 | 5,850 | 2,430 | 4,530 | 3,120 | 1,580 | 950 | 3,650 |
| 8 | 2,210 | 3,930 | 4,220 | 45,000 | 3,380 | 7,270 | 2,210 | 10,740 | 2,880 | 1,370 | 950 | 2,430 |
| 9 | 1,580 | 3,930 | 3,650 | 32,500 | 3,120 | 6,550 | 2,000 | 6,200 | 2,430 | 1,370 | 950 | 3,650 |
| 10 | 1,370 | 3,930 | 6,200 | 20,640 | 3,650 | 4,850 | 1,790 | 3,380 | 2,210 | 1,160 | 950 | 6,200 |
| 11 | 1,370 | 3,120 | 106,500 | 15,170 | 5,180 | 4,530 | 1,580 | 3,120 | 2,430 | 1,160 | 950 | 15,170 |
| 12 | 2,000 | 2,650 | 99,200 | 10,740 | 5,510 | 4,530 | 1,580 | 2,430 | 3,380 | 1,370 | 950 | 10,740 |
| 13 | 2,650 | 2,650 | 40,300 | 9,150 | 5,510 | 4,530 | 1,580 | 2,000 | 3,120 | 1,580 | 950 | 6,550 |
| 14 | 2,650 | 3,930 | 20,000 | 7,640 | 5,180 | 4,530 | 1,790 | 1,790 | 2,650 | 1,790 | 950 | 6,910 |
| 15 | 2,650 | 2,650 | 16,370 | 6,910 | 4,850 | 4,220 | 1,790 | 1,790 | 2,650 | 1,790 | 950 | 140,100 |
| 16 | 2,650 | 2,650 | 12,270 | 8,390 | 4,220 | 4,220 | 2,000 | 1,790 | 2,650 | 1,580 | 950 | 140,100 |
| 17 | 2,650 | 2,210 | 9,150 | 8,390 | 3,380 | 4,530 | 5,850 | 1,790 | 2,430 | 1,580 | 950 | 44,100 |
| 18 | 2,650 | 2,000 | 8,010 | 7,640 | 3,650 | 6,200 | 6,200 | 3,380 | 2,650 | 1,580 | 950 | 75,000 |
| 19 | 2,650 | 2,000 | 6,550 | 7,640 | 3,380 | 4,850 | 6,910 | 3,930 | 2,880 | 1,370 | 950 | 11,200 |
| 20 | 2,650 | 2,000 | 6,200 | 7,640 | 3,380 | 4,220 | 5,510 | 7,270 | 2,430 | 1,370 | 950 | 7,270 |
| 21 | 2,650 | 2,000 | 9,540 | 41,200 | 3,380 | 3,930 | 3,380 | 3,380 | 2,210 | 1,160 | 950 | 57,000 |
| 22 | 2,880 | 2,000 | 14,570 | 77,600 | 4,530 | 4,850 | 2,650 | 3,380 | 2,000 | 1,160 | 950 | 3,380 |
| 23 | 3,380 | 2,210 | 12,270 | 51,100 | 67,700 | 7,270 | 2,430 | 3,380 | 1,790 | 1,160 | 950 | 4,220 |
| 24 | 2,430 | 2,430 | 9,150 | 28,500 | 32,500 | 8,390 | 2,000 | 8,010 | 1,370 | 1,160 | 2,650 | 4,220 |
| 25 | 2,000 | 2,880 | 8,010 | 18,770 | 28,500 | 6,200 | 1,790 | 8,010 | 1,580 | 950 | 5,850 | 4,220 |
| 26 | 1,790 | 1,790 | 7,270 | 13,980 | 42,200 | 4,850 | 2,430 | 6,550 | 1,580 | 950 | 5,510 | 5,510 |
| 27 | 2,430 | 1,790 | 8,010 | 9,930 | 25,500 | 4,220 | 2,000 | 5,850 | 1,370 | 950 | 3,120 | 4,530 |
| 28 | 2,430 | 2,000 | 12,830 | 8,393 | 39,400 | 3,650 | 2,000 | 3,930 | 1,370 | 950 | 3,120 | 4,530 |
| 29 | 2,210 | | 12,270 | 7,270 | 63,100 | 3,120 | 1,790 | 3,650 | 2,000 | 950 | 2,430 | 6,910 |
| 30 | 2,000 | | 9,540 | 6,200 | 71,800 | 5,120 | 1,790 | 3,930 | 2,000 | 950 | 2,880 | 11,720 |
| 31 | 2,210 | | 7,640 | | 52,200 | | 1,790 | 3,930 | | 950 | | 19,380 |
| 1902. | | | | | | | | | | | | |
| 1 | 11,720 | 3,650 | 292,500 | 9,150 | 3,120 | 1,370 | 7,640 | 4,220 | 950 | 5,850 | 3,120 | 2,210 |
| 2 | 8,390 | 3,650 | 166,900 | 8,770 | 2,650 | 1,370 | 11,200 | 3,120 | 950 | 5,850 | 2,650 | 2,210 |
| 3 | 6,200 | 4,850 | 100,600 | 7,640 | 2,650 | 1,370 | 10,390 | 2,000 | 750 | 2,000 | 2,430 | 3,930 |
| 4 | 7,640 | 2,880 | 56,400 | 7,270 | 2,880 | 1,370 | 11,720 | 3,120 | 750 | 2,000 | 2,210 | 7,270 |
| 5 | 3,930 | 4,530 | 30,900 | 6,200 | 2,880 | 1,370 | 13,400 | 3,120 | 750 | 2,000 | 2,210 | 8,010 |
| 6 | 3,650 | 2,210 | 15,770 | 6,200 | 2,880 | 1,370 | 8,390 | 3,120 | 750 | 3,120 | 2,000 | 5,850 |
| 7 | 3,650 | 2,210 | 12,270 | 6,910 | 2,880 | 1,370 | 7,640 | 2,650 | 750 | 3,120 | 1,790 | 4,530 |
| 8 | 3,650 | 2,430 | 9,930 | 88,700 | 2,880 | 1,160 | 6,200 | 2,650 | 750 | 2,650 | 1,580 | 4,530 |
| 9 | 3,380 | 6,550 | 8,010 | 148,800 | 2,880 | 1,160 | 4,530 | 2,650 | 750 | 2,000 | 1,790 | 3,650 |
| 10 | 3,380 | 9,150 | 10,740 | 148,800 | 2,880 | 1,160 | 5,510 | 3,120 | 1,160 | 1,790 | 1,790 | 4,220 |
| 11 | 3,380 | 9,150 | 24,100 | 61,900 | 2,430 | 1,160 | 4,850 | 4,850 | 1,160 | 1,790 | 1,790 | 3,650 |
| 12 | 3,120 | 8,770 | 32,500 | 36,800 | 2,000 | 1,160 | 3,120 | 2,880 | 950 | 4,850 | 1,580 | 7,270 |
| 13 | 2,880 | 6,200 | 71,300 | 22,000 | 2,000 | 1,370 | 2,880 | 2,650 | 950 | 11,720 | 1,580 | 19,380 |
| 14 | 2,880 | 4,530 | 81,400 | 15,170 | 1,580 | 1,580 | 2,880 | 2,210 | 750 | 9,930 | 1,580 | 5,510 |
| 15 | 2,430 | 3,930 | 33,400 | 12,270 | 1,580 | 1,580 | 2,650 | 1,580 | 750 | 5,180 | 1,580 | 11,720 |
| 16 | 2,000 | 6,550 | 28,500 | 8,010 | 1,580 | 3,930 | 2,210 | 1,790 | 750 | 4,220 | 1,370 | 9,150 |
| 17 | 2,650 | 6,550 | 97,700 | 6,200 | 1,790 | 2,650 | 2,210 | 1,790 | 750 | 3,120 | 1,370 | 19,380 |
| 18 | 2,650 | 6,550 | 61,900 | 6,200 | 1,790 | 2,880 | 2,210 | 1,580 | 750 | 2,650 | 1,370 | 15,170 |
| 19 | 18,170 | 6,550 | 32,500 | 5,850 | 1,790 | 2,000 | 2,210 | 1,580 | 570 | 2,650 | 1,370 | 11,720 |
| 20 | 3,120 | 5,850 | 21,300 | 5,180 | 1,790 | 1,580 | 2,000 | 1,370 | 750 | 2,000 | 1,370 | 8,770 |
| 21 | 3,120 | 5,510 | 12,270 | 4,850 | 1,790 | 1,790 | 2,210 | 1,160 | 750 | 1,790 | 1,370 | 10,740 |
| 22 | 32,500 | 5,510 | 9,930 | 4,530 | 1,790 | 1,160 | 2,430 | 1,370 | 570 | 1,580 | 1,370 | 32,500 |
| 23 | 22,700 | 5,850 | 8,010 | 4,220 | 1,790 | 1,160 | 2,210 | 1,160 | 570 | 1,790 | 1,370 | 44,100 |
| 24 | 10,740 | 4,220 | 8,010 | 3,930 | 1,790 | 1,160 | 2,000 | 1,580 | 570 | 1,580 | 1,370 | 25,500 |
| 25 | 6,200 | 4,530 | 6,550 | 3,650 | 1,790 | 1,160 | 3,380 | 1,370 | 950 | 1,370 | 1,370 | 17,570 |
| 26 | 4,850 | 28,500 | 6,200 | 3,380 | 1,790 | 3,120 | 2,650 | 1,370 | 1,580 | 1,370 | 1,580 | 11,200 |
| 27 | 8,770 | 35,900 | 5,510 | 2,650 | 2,210 | 2,650 | 2,000 | 750 | 3,650 | 1,370 | 2,000 | 9,150 |
| 28 | 18,170 | 92,100 | 4,530 | 2,650 | 1,790 | 2,880 | 2,000 | 3,930 | 2,210 | 2,650 | 2,430 | 7,270 |
| 29 | 8,390 | | 3,650 | 3,120 | 1,580 | 2,880 | 2,210 | 5,180 | 2,000 | 8,770 | 2,650 | 5,510 |
| 30 | 6,200 | | 9,150 | 3,380 | 1,580 | 5,180 | 3,650 | 1,580 | 2,000 | 6,200 | 2,650 | 5,180 |
| 31 | 4,530 | | 9,930 | | 1,370 | | 3,650 | 750 | | 4,220 | | 5,180 |

Mean daily discharge, in second-feet, of Juniata River at Newport, Pa., 1899-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|--------|--------|---------|---------|--------|-------|--------|--------|--------|-------|-------|-------|
| 1903. | | | | | | | | | | | | |
| 1 | 4,850 | 22,700 | 100,600 | 15,170 | 2,650 | 2,000 | 32,500 | 2,000 | 10,330 | 1,790 | 2,000 | 1,580 |
| 2 | 7,270 | 14,570 | 57,500 | 11,200 | 2,650 | 1,790 | 10,330 | 2,000 | 8,390 | 1,790 | 2,000 | 1,580 |
| 3 | 7,270 | 13,400 | 28,500 | 8,390 | 3,380 | 1,790 | 6,910 | 1,790 | 6,550 | 1,580 | 1,580 | 1,370 |
| 4 | 20,640 | 37,600 | 18,170 | 6,910 | 3,380 | 1,790 | 5,510 | 1,790 | 4,530 | 1,580 | 1,580 | 1,370 |
| 5 | 18,170 | 86,700 | 13,400 | 6,910 | 3,120 | 1,580 | 4,530 | 2,000 | 3,930 | 1,580 | 1,580 | 1,370 |
| 6 | 12,830 | 51,100 | 11,200 | 6,550 | 3,120 | 1,580 | 6,200 | 2,000 | 3,650 | 1,790 | 1,580 | 1,370 |
| 7 | 9,930 | 24,800 | 9,930 | 5,510 | 3,120 | 1,580 | 32,500 | 2,650 | 3,380 | 1,790 | 1,580 | 1,370 |
| 8 | 6,200 | 15,770 | 9,150 | 7,270 | 2,650 | 3,120 | 13,980 | 3,120 | 3,120 | 2,880 | 1,580 | 1,370 |
| 9 | 8,010 | 12,270 | 11,720 | 8,390 | 2,650 | 3,650 | 7,640 | 2,650 | 3,930 | 5,510 | 1,580 | 1,580 |
| 10 | 5,180 | 9,150 | 14,570 | 9,150 | 2,650 | 3,650 | 5,850 | 2,430 | 6,200 | 7,640 | 1,580 | 1,680 |
| 11 | 3,930 | 7,270 | 12,830 | 7,390 | 2,430 | 3,930 | 4,530 | 2,000 | 5,180 | 5,510 | 1,580 | 1,580 |
| 12 | 3,120 | 10,330 | 11,200 | 8,010 | 2,210 | 6,200 | 4,530 | 1,790 | 4,850 | 4,530 | 1,580 | 1,160 |
| 13 | 2,650 | 12,830 | 9,540 | 8,010 | 2,210 | 5,180 | 4,220 | 1,580 | 3,650 | 3,650 | 1,580 | 1,160 |
| 14 | 4,220 | 11,200 | 8,010 | 12,830 | 2,210 | 5,180 | 4,220 | 1,580 | 3,650 | 3,380 | 1,580 | 1,370 |
| 15 | 4,530 | 9,540 | 7,270 | 68,900 | 2,000 | 5,510 | 4,220 | 1,580 | 3,120 | 2,880 | 1,580 | 1,580 |
| 16 | 3,930 | 13,980 | 6,200 | 102,100 | 2,000 | 5,180 | 3,650 | 3,650 | 2,880 | 2,880 | 1,580 | 1,370 |
| 17 | 4,220 | 38,500 | 5,850 | 80,100 | 2,000 | 4,850 | 3,120 | 2,880 | 2,880 | 2,650 | 1,790 | 1,370 |
| 18 | 3,930 | 20,640 | 5,850 | 31,700 | 2,000 | 3,930 | 6,200 | 2,000 | 3,930 | 3,650 | 2,000 | 2,000 |
| 19 | 4,220 | 13,400 | 5,180 | 21,300 | 2,000 | 3,380 | 18,170 | 2,000 | 4,850 | 4,220 | 2,000 | 2,430 |
| 20 | 3,930 | 9,930 | 4,530 | 15,770 | 2,000 | 3,380 | 9,930 | 1,790 | 3,380 | 3,650 | 2,210 | 2,430 |
| 21 | 5,850 | 7,640 | 4,530 | 12,270 | 2,000 | 3,380 | 6,910 | 1,790 | 3,120 | 3,120 | 2,430 | 2,880 |
| 22 | 5,850 | 7,640 | 5,180 | 9,150 | 2,000 | 3,930 | 5,180 | 2,000 | 2,880 | 2,880 | 2,210 | 2,880 |
| 23 | 5,510 | 7,640 | 9,150 | 7,640 | 2,000 | 3,930 | 4,220 | 2,000 | 2,650 | 2,650 | 2,000 | 2,880 |
| 24 | 5,510 | 6,200 | 64,200 | 6,910 | 2,000 | 5,510 | 3,930 | 1,580 | 2,430 | 2,430 | 2,000 | 2,880 |
| 25 | 5,510 | 7,270 | 58,600 | 5,850 | 2,000 | 9,930 | 3,380 | 1,790 | 2,210 | 2,210 | 2,000 | 2,880 |
| 26 | 4,850 | 6,550 | 24,800 | 5,510 | 1,790 | 8,390 | 2,880 | 1,790 | 2,000 | 2,210 | 1,790 | 2,880 |
| 27 | 4,220 | 6,200 | 15,770 | 5,510 | 2,000 | 6,200 | 2,650 | 2,000 | 2,000 | 2,000 | 1,790 | 2,880 |
| 28 | 4,220 | 27,700 | 11,200 | 3,930 | 2,000 | 4,530 | 2,650 | 2,000 | 2,000 | 2,000 | 1,790 | 2,880 |
| 29 | 7,270 | ----- | 8,390 | 3,380 | 2,000 | 4,850 | 2,430 | 2,430 | 1,790 | 2,000 | 1,580 | 2,880 |
| 30 | 21,300 | ----- | 8,010 | 3,380 | 2,000 | 5,850 | 2,000 | 21,300 | 1,790 | 2,000 | 1,580 | 2,880 |
| 31 | 38,500 | ----- | 10,740 | ----- | 2,000 | ----- | 2,000 | 13,400 | ----- | 2,000 | ----- | 3,650 |
| 1904. | | | | | | | | | | | | |
| 1 | 3,650 | 3,120 | 18,170 | 13,400 | 13,400 | 5,850 | 2,430 | 1,580 | 950 | 750 | 750 | 230 |
| 2 | 3,650 | 6,200 | 56,400 | 72,600 | 10,330 | 8,390 | 2,430 | 1,580 | 950 | 750 | 750 | 570 |
| 3 | 4,530 | 6,200 | 16,370 | 31,700 | 8,770 | 9,930 | 2,430 | 2,430 | 950 | 750 | 750 | 750 |
| 4 | 4,850 | 6,200 | 73,850 | 19,380 | 7,270 | 7,640 | 2,430 | 2,210 | 950 | 750 | 750 | 1,370 |
| 5 | 4,850 | 21,300 | 27,700 | 13,400 | 6,200 | 9,540 | 2,430 | 2,210 | 950 | 750 | 750 | 750 |
| 6 | 4,850 | 24,800 | 9,930 | 8,770 | 5,510 | 9,540 | 2,430 | 2,000 | 950 | 750 | 570 | 1,160 |
| 7 | 4,850 | 51,100 | 8,010 | 8,770 | 5,180 | 7,640 | 4,220 | 2,880 | 750 | 750 | 570 | 1,370 |
| 8 | 4,530 | 24,800 | 80,100 | 7,270 | 4,850 | 5,180 | 6,550 | 2,000 | 750 | 750 | 570 | 1,370 |
| 9 | 4,530 | 12,270 | 36,800 | 7,270 | 4,530 | 4,850 | 9,150 | 1,580 | 950 | 750 | 570 | 1,370 |
| 10 | 4,530 | 6,200 | 16,370 | 11,200 | 4,220 | 4,530 | 16,370 | 1,580 | 950 | 750 | 570 | 1,160 |
| 11 | 4,220 | 4,850 | 9,930 | 11,200 | 3,930 | 6,550 | 26,200 | 1,370 | 950 | 750 | 750 | 1,160 |
| 12 | 3,650 | 3,650 | 9,930 | 9,930 | 3,650 | 4,850 | 15,770 | 1,370 | 950 | 750 | 750 | 1,160 |
| 13 | 3,380 | 3,120 | 6,910 | 8,770 | 3,650 | 4,220 | 8,010 | 1,160 | 950 | 750 | 750 | 1,160 |
| 14 | 3,380 | 2,880 | 6,910 | 7,270 | 3,650 | 3,650 | 7,270 | 1,160 | 750 | 750 | 750 | 1,160 |
| 15 | 3,380 | 3,380 | 6,200 | 6,200 | 3,650 | 3,120 | 5,180 | 1,160 | 750 | 750 | 750 | 1,160 |
| 16 | 3,380 | 3,650 | 5,510 | 5,510 | 3,650 | 3,120 | 5,180 | 1,160 | 950 | 750 | 750 | 1,160 |
| 17 | 3,120 | 4,220 | 4,530 | 5,510 | 3,650 | 4,200 | 3,380 | 950 | 950 | 750 | 750 | 1,160 |
| 18 | 3,120 | 6,200 | 4,530 | 5,180 | 3,930 | 2,880 | 2,880 | 1,370 | 950 | 750 | 750 | 1,160 |
| 19 | 3,120 | 4,850 | 5,510 | 4,220 | 4,530 | 2,880 | 2,650 | 1,160 | 950 | 750 | 750 | 1,160 |
| 20 | 3,120 | 5,180 | 4,530 | 4,220 | 13,400 | 2,880 | 2,880 | 1,370 | 750 | 750 | 570 | 1,160 |
| 21 | 3,120 | 5,180 | 9,150 | 3,930 | 9,540 | 2,430 | 2,430 | 1,370 | 750 | 1,580 | 570 | 1,160 |
| 22 | 3,120 | 6,200 | 8,010 | 3,650 | 8,010 | 8,770 | 2,210 | 1,370 | 750 | 1,580 | 570 | 1,160 |
| 23 | 7,640 | 6,200 | 9,150 | 3,650 | 5,850 | 8,010 | 2,000 | 1,370 | 750 | 1,370 | 570 | 1,160 |
| 24 | 46,000 | 7,640 | 21,300 | 3,120 | 4,850 | 7,270 | 2,650 | 1,370 | 750 | 1,160 | 430 | 1,370 |
| 25 | 15,170 | 16,370 | 18,170 | 3,120 | 4,530 | 4,220 | 2,650 | 1,160 | 750 | 1,160 | 430 | 1,370 |
| 26 | 8,010 | 17,570 | 14,570 | 3,120 | 4,850 | 3,120 | 2,430 | 1,160 | 750 | 950 | 430 | 1,370 |
| 27 | 4,500 | 9,540 | 10,740 | 3,650 | 5,180 | 2,000 | 2,430 | 950 | 750 | 750 | 430 | 2,000 |
| 28 | 3,380 | 5,510 | 10,740 | 4,850 | 4,530 | 2,650 | 2,000 | 950 | 750 | 750 | 320 | 2,430 |
| 29 | 2,650 | 4,530 | 8,390 | 12,270 | 4,220 | 2,430 | 1,790 | 1,160 | 750 | 750 | 320 | 2,650 |
| 30 | 2,430 | ----- | 6,910 | 18,170 | 3,650 | 2,430 | 1,580 | 1,160 | 750 | 750 | 230 | 2,650 |
| 31 | 2,650 | ----- | 6,200 | ----- | 4,850 | ----- | 1,580 | 950 | ----- | 750 | ----- | 2,650 |

Estimated monthly discharge of Juniata River at Newport, Pa., 1899-1904.

[Drainage area, 3,476 square miles.]

| Month. | Discharge in second-feet. | | | Run-off. | |
|---------------------|---------------------------|----------|--------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1899. | | | | | |
| March (21-31) | 39,400 | 6,550 | 14,429 | 4.151 | 1.698 |
| April | 20,000 | 1,790 | 6,042 | 1.738 | 1.939 |
| May | 21,300 | 1,160 | 4,301 | 1.237 | 1.426 |
| June | 2,210 | 230 | 760 | .219 | .244 |
| July | 1,580 | 230 | 904 | .260 | .300 |
| August | 6,200 | 750 | 1,525 | .439 | .506 |
| September | 5,510 | 1,160 | 1,787 | .514 | .573 |
| October | 1,370 | 430 | 774 | .223 | .257 |
| November | 5,850 | 430 | 2,095 | .603 | .673 |
| December | 9,150 | 1,160 | 3,628 | 1.044 | 1.204 |
| The period | 39,400 | 230 | 3,624 | 1.043 | 8.820 |
| 1900. | | | | | |
| January | 42,200 | 2,000 | 7,263 | 2.089 | 2.408 |
| February | 53,200 | 1,790 | 10,188 | 2.931 | 3.052 |
| March | 66,500 | 3,380 | 9,523 | 2.740 | 3.159 |
| April | 5,180 | 3,120 | 4,264 | 1.227 | 1.369 |
| May | 3,380 | 1,370 | 2,226 | .640 | .738 |
| June | 2,430 | 1,370 | 1,692 | .487 | .543 |
| July | 1,580 | 750 | 1,074 | .309 | .356 |
| August | 2,430 | 570 | 971 | .279 | .322 |
| September | 1,580 | 570 | 695 | .200 | .223 |
| October | 2,430 | 570 | 1,016 | .292 | .337 |
| November | 52,200 | 750 | 4,137 | 1.190 | 1.328 |
| December | 15,170 | 1,370 | 3,596 | 1.035 | 1.193 |
| The year | 66,500 | 570 | 3,887 | 1.118 | 15.028 |

Estimated monthly discharge of Juniata River at Newport, Pa., 1899-1904—Con.

| Month. | Discharge in second-feet. | | | Run-off. | |
|-----------------|---------------------------|----------|--------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1901. | | | | | |
| January | 3,380 | 1,160 | 2,161 | 0.622 | 0.717 |
| February | 3,930 | 1,580 | 2,571 | .740 | .771 |
| March | 106,500 | 2,000 | 15,260 | 4.390 | 5.061 |
| April | 77,600 | 5,850 | 20,104 | 5.784 | 6.453 |
| May | 71,300 | 3,120 | 16,683 | 4.799 | 5.533 |
| June | 27,000 | 3,120 | 6,869 | 1.976 | 2.205 |
| July | 6,910 | 1,580 | 2,794 | .804 | .927 |
| August | 10,740 | 1,160 | 3,808 | 1.096 | 1.264 |
| September | 7,640 | 1,370 | 3,069 | .883 | .985 |
| October | 2,210 | 950 | 1,411 | .406 | .468 |
| November | 5,850 | 950 | 1,580 | .455 | .508 |
| December | 140,100 | 2,000 | 19,940 | 5.737 | 6.614 |
| The year | 140,100 | 950 | 8,021 | 2.308 | 31.506 |
| 1902. | | | | | |
| January | 32,500 | 2,000 | 7,259 | 2.088 | 2.407 |
| February | 92,100 | 2,210 | 10,316 | 2.968 | 3.091 |
| March | 292,500 | 3,650 | 41,044 | 11.808 | 13.614 |
| April | 148,800 | 2,650 | 21,813 | 6.275 | 7.001 |
| May | 3,120 | 1,370 | 2,135 | .614 | .708 |
| June | 5,180 | 1,160 | 1,870 | .538 | .600 |
| July | 13,400 | 2,000 | 4,586 | 1.319 | 1.521 |
| August | 5,180 | 750 | 2,331 | .671 | .774 |
| September | 3,650 | 570 | 1,043 | .300 | .335 |
| October | 11,720 | 1,370 | 3,586 | 1.032 | 1.190 |
| November | 3,120 | 1,370 | 1,823 | .524 | .585 |
| December | 44,100 | 2,210 | 10,711 | 3.081 | 3.552 |
| The year | 292,500 | 570 | 9,043 | 2.602 | 35.378 |

Estimated monthly discharge of Juniata River at Newport, Pa., 1899-1904—Cont'd.

| Month. | Discharge in second-feet. | | | Run-off. | |
|-----------------|---------------------------|----------|--------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1903. | | | | | |
| January | 38,500 | 2,650 | 7,988 | 2.298 | 2.649 |
| February | 86,700 | 6,200 | 18,304 | 5.266 | 5.484 |
| March | 100,600 | 4,530 | 18,444 | 5.306 | 6.117 |
| April | 102,100 | 3,380 | 16,857 | 4.850 | 5.411 |
| May | 3,380 | 1,790 | 2,330 | .670 | .772 |
| June | 9,930 | 1,580 | 4,150 | 1.194 | 1.332 |
| July | 32,500 | 2,000 | 7,322 | 2.106 | 2.428 |
| August | 21,300 | 1,580 | 3,090 | .889 | 1.025 |
| September | 10,330 | 1,790 | 3,915 | 1.126 | 1.256 |
| October | 7,640 | 1,580 | 2,917 | .839 | .967 |
| November | 2,430 | 1,580 | 1,776 | .511 | .570 |
| December | 3,650 | 1,160 | 2,050 | .590 | .680 |
| The year | 102,100 | 1,160 | 7,429 | 2.137 | 28.691 |
| 1904. | | | | | |
| January | 46,000 | 2,430 | 5,722 | 1.65 | 1.90 |
| February | 51,100 | 2,880 | 9,756 | 2.81 | 3.03 |
| March | 80,100 | 4,530 | 17,150 | 4.93 | 5.68 |
| April | 72,600 | 3,120 | 10,710 | 3.08 | 3.44 |
| May | 13,400 | 3,650 | 5,742 | 1.65 | 1.90 |
| June | 9,930 | 2,000 | 5,160 | 1.48 | 1.65 |
| July | 26,200 | 1,580 | 4,968 | 1.43 | 1.65 |
| August | 2,880 | 950 | 1,460 | .420 | .484 |
| September | 950 | 750 | 850 | .245 | .273 |
| October | 1,580 | 750 | 856 | .246 | .284 |
| November | 750 | 230 | 607 | .175 | .195 |
| December | 2,650 | 230 | 1,344 | .386 | .445 |
| The year | 80,100 | 230 | 5,360 | 1.54 | 20.93 |

^aFrozen January 1 to 23. Rating table assumed to apply correctly.

SUSQUEHANNA RIVER AT HARRISBURG, PA.

In 1890 regular daily observations of fluctuations of the water surface of the Susquehanna River at Harrisburg were started by E. Mather, president of the Harrisburg water board. These observa-

tions have been continued since that time and have been furnished through the courtesy of Mr. Mather.

The gage, the zero of which is the low-water mark of 1803, is located at the pump house of the waterworks in the pump well, which is connected with the river by two large mains. The original readings are taken in feet and inches, and for convenience in computations have been reduced to feet and tenths.

The first discharge measurement was made at this station in March, 1897, by Mr. E. G. Paul, who has carried on systematic measurements there since that date. The measuring section is at the lower side of the Walnut street toll bridge. The initial point for soundings is the upright at the end of the hand rail on the downstream side on the left bank.

At this point the river is divided into two channels by Fosters Island, which at the measuring section is about 1,200 feet wide. Its banks are low and sloping and during extreme floods the island is submerged.

At ordinary stages the left channel is 1,350 feet wide and is broken by six bridge piers. The right channel is 1,300 feet wide and is broken by seven piers. The main banks of the river are high. The bed is composed of a hard material and is permanent, except in the spans adjacent to the island. The velocity never becomes too sluggish to measure.

During the spring and summer of 1903 a new bridge was built across Susquehanna River at Market street, which is about 1,200 feet below the gaging section. The piers of this new bridge obstruct the channel of the river by between 10 and 15 per cent of the total cross section. The result of this obstruction, as shown by the discharge measurements taken since the erection of the piers, has been to back up the water, thus increasing the gage height at the Walnut street station. On account of this backwater the measurements taken during 1903 show that, in order to use the standard rating table after June 1, 1903, and until January 1, 1904, a deduction of 14 per cent is necessary in the daily discharges. The following table gives the data from which this deduction was made:

| Date. | Gage height. | Observed discharge. | Standard rating table discharge. | Difference. | Difference. |
|-----------------|--------------|---------------------|----------------------------------|---------------------|------------------|
| | <i>Feet.</i> | <i>Second-feet.</i> | <i>Second-feet.</i> | <i>Second-feet.</i> | <i>Per cent.</i> |
| May 8..... | 2.30 | 16,280 | 15,980 | 300 | — 2 |
| June 2..... | 1.50 | 8,390 | 9,520 | 1,130 | 12 |
| October 5..... | 1.65 | 9,116 | 10,560 | 1,440 | 13 |
| November 2..... | 3.08 | 20,245 | 24,350 | 4,100 | 16 |

About January 1, 1904, the old piers which were standing at the site of the new bridge at Market street were removed, so that the river channel was left in such a condition that the stage of the river at Walnut street bridge returned to the same condition that existed before the 1903 bridge was built.

In the summer of 1904 certain changes and improvements were made at the pumping station, and a partial dam was made in the river just below the pumping station. The effect of this dam was to raise the apparent stage of the water at the gage. A correction was applied to measurements of discharge made prior to July 18, 1904, so as to eliminate the effect of the dam and alterations at the pump house upon the gage readings.

On July 18, 1904, a standard chain gage was attached to the guard rail on the upstream side of the Walnut Street Bridge in the left-hand span. The datum of this gage is the low-water mark of 1803, and it is believed that it records truly the stage of the river to that datum, and that the changes in bridges below and at the pumping station above do not affect the records obtained from it.

The length of chain is 39.38 feet; the bench mark is on the left abutment at the top upstream outer corner of the bridge seat; its elevation is 32.99 feet above low water of 1803.

Observations at the gage in the pumping station are made by the engineer, C. M. Nagle, each morning before starting the pump. Observations at the standard chain gage are made by Thomas Numbers, toll collector, once daily.

The following pages give the data which have been collected at Harrisburg gaging station since its establishment; also the results of the computation of these data.

Discharge measurements of Susquehanna River at Harrisburg, Pa., 1897-1904.

| Date. | Hydrographer. | Gage height. | Area of section. | Mean velocity. | Discharge. |
|----------|------------------|--------------|---------------------|-------------------------|---------------------|
| 1897. | | <i>Feet.</i> | <i>Square feet.</i> | <i>Feet per second.</i> | <i>Second-feet.</i> |
| Mar. 31 | E. G. Paul | 5.42 | 17,048 | 3.45 | 58,859 |
| May 15 |do | 7.83 | 24,351 | 4.35 | 105,888 |
| Aug. 30 |do | 1.50 | 7,444 | 1.29 | 9,568 |
| Sept. 16 |do | .58 | 3,756 | 1.06 | 3,962 |
| Nov. 17 |do | 2.50 | 9,325 | 1.91 | 17,824 |

Discharge measurements of Susquehanna River at Harrisburg, Pa., 1897-1904—
Continued.

| Date. | Hydrographer. | Gage height. | Area of section. | Mean velocity. | Discharge. |
|----------|------------------------------|--------------|---------------------|-------------------------|----------------------|
| | | <i>Feet.</i> | <i>Square feet.</i> | <i>Feet per second.</i> | <i>Second-feet.</i> |
| 1898. | | | | | |
| Feb. 25 | E. G. Paul | 6.58 | 19,420 | 3.91 | 76,250 |
| Mar. 24 | do | 15.75 | 43,715 | 5.73 | 250,485 |
| Mar. 25 | do | 10.75 | 29,587 | 5.06 | 149,589 |
| Mar. 26 | do | 14.65 | 39,725 | 5.62 | 223,374 |
| July 10 | do | .83 | 4,400 | 1.22 | 5,466 |
| Sept. 22 | do | .92 | 4,834 | 1.44 | 6,993 |
| Oct. 7 | do | .72 | 4,459 | 1.31 | 6,121 |
| 1899. | | | | | |
| June 11 | E. G. Paul | 1.75 | 7,656 | 1.53 | 11,746 |
| July 29 | do | .91 | 4,524 | 1.44 | 6,534 |
| Sept. 12 | do | .75 | 4,845 | 1.12 | 5,404 |
| Oct. 25 | do | .16 | 3,699 | .98 | 3,625 |
| 1900. | | | | | |
| May 16 | E. G. Paul | 2.42 | 9,404 | 1.87 | 17,621 |
| Sept. 21 | do | .08 | 3,313 | .80 | 2,655 |
| Sept. 28 | do | .04 | 3,223 | .72 | 2,357 |
| 1901. | | | | | |
| Aug. 12 | E. G. Paul | 2.70 | 9,775 | 2.05 | 20,023 |
| Oct. 23 | do | 1.85 | 7,737 | 1.62 | 12,556 |
| 1902. | | | | | |
| Apr. 17 | E. G. Paul | 5.40 | 17,476 | 3.46 | 60,534 |
| Sept. 15 | do | 1.10 | 5,023 | 1.39 | 6,982 |
| 1903. | | | | | |
| May 8 | E. C. Murphy | 2.30 | 9,810 | 1.65 | 16,280 |
| June 2 | Hoyt and Holmes | 1.50 | 7,577 | 1.11 | 8,390 |
| Oct. 5 | Paul and Sawyer | 1.65 | 7,290 | 1.25 | 9,116 |
| Nov. 2 | E. G. Paul and others | 3.08 | 10,325 | 1.96 | 20,245 |
| 1904. | | | | | |
| Mar. 9 | Sawyer and Tillinghast | 15.60 | | | ^a 261,860 |
| July 15 | N. C. Grover | 3.08 | 11,870 | 2.22 | 26,408 |
| Sept. 13 | J. C. Hoyt | 1.10 | 6,646 | .90 | 5,950 |
| Sept. 29 | do | 1.78 | 8,730 | 1.34 | 11,660 |
| Oct. 1 | N. C. Grover | 1.85 | 8,460 | 1.48 | 12,560 |
| Nov. 4 | Hoyt and Comstock | 1.82 | 8,972 | 1.39 | 12,600 |

^a River running full of ice. Measurement approximate.

Mean daily gage height, in feet, of Susquehanna River at Harrisburg, Pa., 1891-1904.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|-------|-------|-------|-------|------|-------|-------|------|-------|------|-------|------|
| 1891. | | | | | | | | | | | | |
| 1 | 2.83 | 10.58 | 11.00 | 8.25 | 3.58 | 2.00 | 2.75 | 3.25 | 4.67 | 1.75 | 2.50 | 4.25 |
| 2 | 3.00 | 11.50 | 9.00 | 9.00 | 3.50 | 1.92 | 2.50 | 3.17 | 4.00 | 1.67 | 2.50 | 4.00 |
| 3 | 3.33 | 11.50 | 7.33 | 8.58 | 3.42 | 2.00 | 2.58 | 3.08 | 3.67 | 1.67 | 2.33 | 3.67 |
| 4 | 4.50 | 11.17 | 6.67 | 8.75 | 3.42 | 2.00 | 3.17 | 2.92 | 3.33 | 1.58 | 2.25 | 3.50 |
| 5 | 5.25 | 10.17 | 5.67 | 8.42 | 3.25 | 2.00 | 4.08 | 3.00 | 3.00 | 1.58 | 2.25 | 4.58 |
| 6 | 5.00 | 8.92 | 5.67 | 8.00 | 3.08 | 2.00 | 3.50 | 3.08 | 3.00 | 1.58 | 2.25 | 8.75 |
| 7 | 5.50 | 7.67 | 5.25 | 7.17 | 3.00 | 2.08 | 3.08 | 3.00 | 3.83 | 1.58 | 2.17 | 9.50 |
| 8 | 5.42 | 7.50 | 5.00 | 6.42 | 3.00 | 2.17 | 2.67 | 3.33 | 4.67 | 1.75 | 2.17 | 8.33 |
| 9 | 4.92 | 7.50 | 4.67 | 6.00 | 2.92 | 2.58 | 2.75 | 3.08 | 4.50 | 2.58 | 2.00 | 7.00 |
| 10 | 4.50 | 7.42 | 4.67 | 5.67 | 2.75 | 2.58 | 2.67 | 2.83 | 4.08 | 3.00 | 2.00 | 6.00 |
| 11 | 4.08 | 7.50 | 6.16 | 5.33 | 2.67 | 3.00 | 2.92 | 2.75 | 3.83 | 2.83 | 2.00 | 5.42 |
| 12 | 4.25 | 7.42 | 7.08 | 6.08 | 2.67 | 2.75 | 2.83 | 2.58 | 3.50 | 2.67 | 2.67 | 5.00 |
| 13 | 6.00 | 7.00 | 8.50 | 7.33 | 2.58 | 2.67 | 2.75 | 2.58 | 3.08 | 2.67 | 3.67 | 4.17 |
| 14 | 8.75 | 6.42 | 9.67 | 9.00 | 2.50 | 2.67 | 2.50 | 2.58 | 3.00 | 2.58 | 4.00 | 4.33 |
| 15 | 7.92 | 5.92 | 10.75 | 8.50 | 2.50 | 2.58 | 2.25 | 2.50 | 3.00 | 2.42 | 4.25 | 4.00 |
| 16 | 7.50 | 5.58 | 10.00 | 8.00 | 2.42 | 2.50 | 2.17 | 2.50 | 2.67 | 2.33 | 4.08 | 3.83 |
| 17 | 6.67 | 5.92 | 8.83 | 7.67 | 2.42 | 2.42 | 2.00 | 2.50 | 2.67 | 2.08 | 3.75 | 3.75 |
| 18 | 6.00 | 14.25 | 7.75 | 7.42 | 2.33 | 2.33 | 1.83 | 2.42 | 2.58 | 2.00 | 4.00 | 3.67 |
| 19 | 5.67 | 19.00 | 6.83 | 6.83 | 2.25 | 2.33 | 1.92 | 2.25 | 2.58 | 1.83 | 4.83 | 4.58 |
| 20 | 5.08 | 17.83 | 6.17 | 6.75 | 2.25 | 2.33 | 2.08 | 2.42 | 2.50 | 1.92 | 4.75 | 5.00 |
| 21 | 4.83 | 13.25 | 5.92 | 6.33 | 2.04 | 3.33 | 2.08 | 2.25 | 2.25 | 2.17 | 4.67 | 4.75 |
| 22 | 4.50 | 11.75 | 6.33 | 5.92 | 2.00 | 3.58 | 2.08 | 2.08 | 2.17 | 2.50 | 4.25 | 4.17 |
| 23 | 7.08 | 11.50 | 6.67 | 5.50 | 2.13 | 5.42 | 2.00 | 2.00 | 2.08 | 3.25 | 4.17 | 3.83 |
| 24 | 9.17 | 10.25 | 8.08 | 5.17 | 2.25 | 6.17 | 2.00 | 3.08 | 2.08 | 4.67 | 5.08 | 3.92 |
| 25 | 9.50 | 9.00 | 10.33 | 5.00 | 2.33 | 5.58 | 4.33 | 6.50 | 2.00 | 4.17 | 5.42 | 4.58 |
| 26 | 9.42 | 8.25 | 10.83 | 4.75 | 2.29 | 4.58 | 4.00 | 6.58 | 1.92 | 3.67 | 6.42 | 6.33 |
| 27 | 8.42 | 11.33 | 10.08 | 4.67 | 2.25 | 4.33 | 3.83 | 5.25 | 1.83 | 3.17 | 6.17 | 8.25 |
| 28 | 7.50 | 13.08 | 8.92 | 4.25 | 2.21 | 3.75 | 3.33 | 5.67 | 1.75 | 3.00 | 5.42 | 9.33 |
| 29 | 7.00 | ----- | 7.83 | 4.08 | 2.17 | 3.50 | 3.00 | 6.00 | 1.75 | 2.83 | 5.00 | 8.58 |
| 30 | 7.08 | ----- | 7.50 | 3.83 | 2.08 | 3.50 | 2.75 | 5.53 | 1.75 | 2.67 | 4.67 | 7.83 |
| 31 | 9.83 | ----- | 7.67 | ----- | 2.00 | ----- | 3.92 | 5.17 | ----- | 2.58 | ----- | 8.50 |
| 1892. | | | | | | | | | | | | |
| 1 | 8.50 | 2.83 | 4.50 | 9.75 | 3.00 | 5.92 | 4.67 | 1.92 | 2.92 | 1.08 | .50 | 1.92 |
| 2 | 8.25 | 2.92 | 4.00 | 9.00 | 2.83 | 5.50 | 4.33 | 2.00 | 2.50 | 1.25 | .50 | 1.83 |
| 3 | 8.75 | 2.92 | 3.58 | 8.50 | 2.83 | 5.17 | 3.75 | 1.83 | 2.33 | 1.42 | .50 | 1.75 |
| 4 | 9.33 | 3.08 | 3.25 | 11.75 | 2.83 | 7.58 | 3.67 | 2.00 | 2.17 | 1.25 | .50 | 1.58 |
| 5 | 8.83 | 3.08 | 3.00 | 14.33 | 4.50 | 12.50 | 3.50 | 3.00 | 2.00 | 1.08 | .50 | 1.58 |
| 6 | 8.00 | 3.00 | 2.67 | 14.67 | 5.83 | 12.00 | 3.58 | 2.83 | 1.83 | 1.08 | .50 | 1.50 |
| 7 | 7.83 | 3.00 | 2.83 | 13.17 | 7.58 | 11.25 | 3.42 | 2.83 | 1.83 | 1.00 | .50 | 1.50 |
| 8 | 6.83 | 2.92 | 2.83 | 11.33 | 7.58 | 9.00 | 3.42 | 3.00 | 1.75 | 1.00 | .50 | 1.50 |
| 9 | 5.33 | 2.75 | 3.83 | 9.50 | 7.83 | 7.67 | 3.42 | 2.67 | 1.67 | 1.00 | .75 | 1.58 |
| 10 | 5.67 | 2.50 | 5.25 | 7.83 | 6.67 | 7.00 | 3.00 | 2.42 | 1.50 | 1.00 | .92 | 1.67 |
| 11 | 4.17 | 2.58 | 6.17 | 7.00 | 5.58 | 7.42 | 2.83 | 2.17 | 1.50 | 1.00 | 1.00 | 2.42 |
| 12 | 3.67 | 2.50 | 5.92 | 6.42 | 5.00 | 7.00 | 2.50 | 2.08 | 1.42 | .92 | 1.17 | 4.25 |
| 13 | 3.75 | 2.00 | 5.67 | 5.67 | 4.75 | 6.42 | 2.17 | 2.42 | 1.42 | .92 | 1.17 | 4.00 |
| 14 | 5.50 | 1.82 | 5.00 | 5.33 | 4.25 | 5.42 | 2.17 | 2.50 | 1.50 | .83 | 1.17 | 3.50 |
| 15 | 11.82 | 1.75 | 4.42 | 4.75 | 4.17 | 4.67 | 2.33 | 3.50 | 2.33 | .83 | 1.25 | 3.08 |
| 16 | 13.17 | 1.83 | 4.00 | 4.75 | 4.17 | 4.17 | 2.42 | 4.17 | 2.33 | .83 | 1.25 | 2.83 |
| 17 | 10.83 | 1.67 | 3.50 | 4.33 | 4.42 | 3.75 | 2.42 | 4.00 | 2.08 | .83 | 1.25 | 2.92 |
| 18 | 9.08 | 1.75 | 3.33 | 4.33 | 4.83 | 3.58 | 2.25 | 3.50 | 1.83 | .83 | 1.25 | 2.67 |
| 19 | 7.75 | 2.00 | 3.08 | 4.00 | 4.92 | 3.50 | 2.25 | 2.83 | 1.67 | .83 | 1.92 | 2.58 |
| 20 | 7.67 | 2.33 | 3.00 | 3.83 | 5.67 | 3.50 | 2.08 | 2.67 | 1.50 | .83 | 2.50 | 2.50 |
| 21 | 7.00 | 2.17 | 2.92 | 3.67 | 7.25 | 3.67 | 2.00 | 2.33 | 1.50 | .83 | 2.50 | 2.42 |
| 22 | 6.17 | 2.50 | 2.67 | 3.50 | 8.25 | 4.00 | 1.75 | 2.17 | 1.50 | .83 | 2.92 | 2.08 |
| 23 | 5.33 | 2.67 | 2.50 | 3.42 | 8.83 | 3.67 | 1.67 | 1.90 | 1.33 | .83 | 3.58 | 1.50 |
| 24 | 4.75 | 3.17 | 2.50 | 3.50 | 8.75 | 3.50 | 1.67 | 1.83 | 1.17 | .83 | 3.33 | .92 |
| 25 | 4.50 | 3.50 | 2.67 | 3.50 | 8.25 | 3.67 | 1.67 | 1.92 | 1.17 | .75 | 2.92 | 1.08 |
| 26 | 4.33 | 4.33 | 3.50 | 3.58 | 7.33 | 4.17 | 1.58 | 2.17 | 1.25 | .58 | 2.50 | 2.58 |
| 27 | 3.58 | 4.50 | 4.50 | 3.58 | 6.67 | 3.58 | 1.50 | 2.00 | 1.25 | .58 | 2.08 | 2.00 |
| 28 | 2.50 | 4.83 | 10.83 | 3.50 | 6.50 | 3.25 | 1.50 | 2.00 | 1.25 | .58 | 2.00 | 2.25 |
| 29 | 2.08 | 4.67 | 13.00 | 3.33 | 6.33 | 3.50 | 1.50 | 2.00 | 1.08 | .58 | 2.00 | 2.25 |
| 30 | 2.83 | ----- | 12.00 | 3.17 | 7.08 | 4.83 | 1.42 | 2.25 | 1.08 | .58 | 1.92 | 2.25 |
| 31 | 2.83 | ----- | 10.58 | ----- | 6.42 | ----- | 1.67 | 3.00 | ----- | .50 | ----- | 2.17 |

Mean daily gage height, in feet, of Susquehanna River at Harrisburg, Pa., 1891-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|------|-------|-------|-------|-------|-------|-------|------|-------|------|-------|------|
| 1893. | | | | | | | | | | | | |
| 1 | 2.00 | 2.67 | 2.58 | 6.08 | 4.92 | 3.67 | 2.33 | .92 | 3.58 | 2.00 | 2.17 | 4.00 |
| 2 | 2.50 | 3.00 | 2.58 | 6.00 | 4.83 | 3.67 | 2.17 | .83 | 4.17 | 2.00 | 2.17 | 3.83 |
| 3 | 2.83 | 4.00 | 2.75 | 6.42 | 5.50 | 3.50 | 2.08 | .83 | 3.92 | 1.83 | 2.17 | 3.67 |
| 4 | 2.85 | 4.17 | 2.75 | 7.50 | 6.83 | 3.58 | 1.92 | .83 | 3.50 | 1.67 | 2.17 | 3.67 |
| 5 | 2.75 | 5.00 | 2.75 | 7.92 | 16.17 | 3.58 | 1.92 | .75 | 2.67 | 1.50 | 2.33 | 3.67 |
| 6 | 2.67 | 5.08 | 2.50 | 8.92 | 16.50 | 3.17 | 1.67 | .75 | 2.25 | 1.50 | 3.00 | 3.50 |
| 7 | 2.50 | 5.00 | 2.50 | 9.50 | 14.58 | 3.00 | 1.67 | .67 | 2.00 | 1.42 | 3.25 | 3.17 |
| 8 | 2.50 | 5.33 | 2.67 | 8.83 | 12.00 | 3.00 | 1.58 | .67 | 1.75 | 1.42 | 2.83 | 3.00 |
| 9 | 2.50 | 5.42 | 3.08 | 8.00 | 9.92 | 3.00 | 1.50 | .58 | 1.67 | 1.42 | 2.75 | 3.00 |
| 10 | 2.50 | 6.42 | 6.50 | 8.42 | 8.25 | 2.83 | 1.50 | .58 | 1.50 | 1.33 | 2.50 | 2.92 |
| 11 | 2.25 | 7.75 | 12.50 | 10.00 | 7.00 | 2.67 | 1.50 | .50 | 1.50 | 1.33 | 2.50 | 2.83 |
| 12 | 2.25 | 11.58 | 13.83 | 9.42 | 6.17 | 2.58 | 1.50 | .50 | 1.67 | 1.33 | 2.42 | 2.83 |
| 13 | 2.08 | 7.50 | 14.50 | 8.42 | 5.50 | 2.50 | 1.50 | .42 | 2.00 | 1.25 | 2.33 | 2.83 |
| 14 | 2.08 | 6.50 | 14.58 | 7.75 | 5.00 | 2.33 | 1.50 | .42 | 2.00 | 1.67 | 2.17 | 2.50 |
| 15 | 2.08 | 5.58 | 13.00 | 7.42 | 4.75 | 2.08 | 1.75 | .42 | 1.83 | 4.67 | 2.08 | 2.00 |
| 16 | 2.00 | 5.25 | 12.25 | 8.08 | 4.58 | 2.00 | 1.83 | .33 | 2.00 | 5.33 | 2.00 | 2.25 |
| 17 | 2.00 | 7.75 | 10.50 | 8.83 | 5.92 | 1.92 | 1.83 | .33 | 2.50 | 5.25 | 1.92 | 2.42 |
| 18 | 2.00 | 6.75 | 8.83 | 8.92 | 8.50 | 1.83 | 1.67 | .33 | 2.67 | 4.25 | 1.83 | 5.75 |
| 19 | 2.00 | 5.83 | 7.33 | 7.75 | 9.75 | 1.75 | 1.67 | .33 | 4.42 | 3.83 | 1.75 | 8.83 |
| 20 | 2.00 | 5.33 | 6.67 | 6.92 | 9.00 | 1.75 | 1.67 | .67 | 3.67 | 3.42 | 1.75 | 7.08 |
| 21 | 2.00 | 4.67 | 5.92 | 7.00 | 7.58 | 1.75 | 1.67 | .58 | 3.25 | 3.00 | 1.67 | 6.00 |
| 22 | 2.00 | 4.25 | 5.58 | 10.00 | 7.00 | 1.58 | 1.50 | .50 | 2.83 | 2.50 | 1.58 | 5.92 |
| 23 | 2.00 | 3.50 | 5.67 | 10.92 | 6.25 | 1.58 | 1.42 | .42 | 2.50 | 2.50 | 1.58 | 4.42 |
| 24 | 2.00 | 3.00 | 6.83 | 10.50 | 5.58 | 1.75 | 1.33 | .42 | 2.33 | 2.33 | 1.67 | 3.92 |
| 25 | 2.00 | 3.00 | 7.25 | 8.92 | 5.42 | 1.75 | 1.25 | .33 | 2.33 | 2.25 | 1.67 | 3.83 |
| 26 | 2.00 | 3.00 | 7.75 | 7.67 | 4.92 | 2.00 | 1.17 | .42 | 2.17 | 2.25 | 1.58 | 3.83 |
| 27 | 2.00 | 2.92 | 9.42 | 6.83 | 4.50 | 2.25 | 1.08 | .50 | 2.00 | 2.25 | 1.58 | 4.83 |
| 28 | 2.00 | 2.75 | 8.67 | 6.17 | 4.33 | 2.50 | 1.08 | .50 | 2.00 | 2.00 | 1.75 | 5.92 |
| 29 | 2.00 | ----- | 7.83 | 5.67 | 4.17 | 2.75 | 1.83 | 1.00 | 2.00 | 2.00 | 2.83 | 5.83 |
| 30 | 2.33 | ----- | 7.83 | 5.17 | 3.92 | 2.50 | .92 | 3.00 | 2.00 | 2.00 | 3.67 | 5.17 |
| 31 | 2.50 | ----- | 6.50 | ----- | 3.67 | ----- | .92 | 3.08 | ----- | 2.17 | ----- | 4.67 |
| 1894. | | | | | | | | | | | | |
| 1 | 4.50 | 2.41 | 3.16 | 3.83 | 4.58 | 9.50 | 2.58 | 1.08 | .33 | 1.91 | 5.08 | 2.41 |
| 2 | 4.50 | 2.53 | 3.33 | 3.66 | 4.50 | 9.66 | 2.41 | 1.08 | .33 | 1.83 | 5.25 | 2.33 |
| 3 | 4.00 | 2.25 | 3.50 | 3.50 | 4.16 | 9.16 | 2.33 | 1.33 | .33 | 1.58 | 5.41 | 2.50 |
| 4 | 3.66 | 2.16 | 3.75 | 3.25 | 3.83 | 8.58 | 2.25 | 1.50 | .33 | 1.58 | 7.50 | 2.91 |
| 5 | 3.50 | 2.08 | 4.08 | 3.16 | 3.50 | 8.41 | 2.00 | 1.66 | .25 | 1.41 | 7.66 | 3.50 |
| 6 | 3.33 | 2.00 | 5.66 | 3.00 | 3.16 | 7.91 | 2.00 | 1.58 | .25 | 1.41 | 7.58 | 3.58 |
| 7 | 3.41 | 2.00 | 7.66 | 2.91 | 3.25 | 6.75 | 1.83 | 1.50 | .33 | 1.33 | 7.16 | 3.58 |
| 8 | 5.16 | 2.00 | 11.33 | 2.83 | 3.33 | 6.00 | 1.83 | 1.50 | .33 | 1.33 | 7.00 | 3.33 |
| 9 | 5.25 | 2.08 | 12.16 | 2.75 | 3.50 | 5.50 | 1.75 | 1.08 | .41 | 1.25 | 6.50 | 3.00 |
| 10 | 4.58 | 3.50 | 10.83 | 2.75 | 3.50 | 5.00 | 1.66 | 1.08 | 1.00 | 1.33 | 6.00 | 3.00 |
| 11 | 3.75 | 5.00 | 8.50 | 2.83 | 3.50 | 4.66 | 1.58 | 1.08 | 1.91 | 2.08 | 5.50 | 3.33 |
| 12 | 3.33 | 6.00 | 9.83 | 3.00 | 3.08 | 4.00 | 1.50 | 1.00 | 1.50 | 4.91 | 5.33 | 4.00 |
| 13 | 2.50 | 5.66 | 7.16 | 3.25 | 2.91 | 3.75 | 1.41 | 1.00 | 1.33 | 5.58 | 4.66 | 4.33 |
| 14 | 3.16 | 4.58 | 7.00 | 3.66 | 2.75 | 3.66 | 1.41 | 1.00 | 1.25 | 5.08 | 4.50 | 5.75 |
| 15 | 3.16 | 4.33 | 6.41 | 6.33 | 2.50 | 3.66 | 1.33 | 1.00 | 1.25 | 4.66 | 4.00 | 6.16 |
| 16 | 2.83 | 3.66 | 5.83 | 7.58 | 2.50 | 3.58 | 1.33 | 1.00 | 1.16 | 4.16 | 3.91 | 6.33 |
| 17 | 2.66 | 3.33 | 5.50 | 9.08 | 2.33 | 3.41 | 1.25 | 1.00 | 1.08 | 3.83 | 3.66 | 5.75 |
| 18 | 2.83 | 3.33 | 5.08 | 9.08 | 2.33 | 3.16 | 1.16 | 1.00 | 1.08 | 3.66 | 3.50 | 5.16 |
| 19 | 2.83 | 3.33 | 4.83 | 8.50 | 2.33 | 3.00 | 1.08 | .91 | 2.16 | 3.41 | 3.25 | 4.66 |
| 20 | 3.00 | 4.16 | 4.58 | 7.50 | 5.33 | 3.50 | 1.08 | .91 | 4.08 | 3.00 | 3.16 | 4.33 |
| 21 | 2.83 | 5.66 | 4.50 | 6.75 | 16.33 | 3.41 | 1.08 | .83 | 5.00 | 2.75 | 3.08 | 4.08 |
| 22 | 2.83 | 5.33 | 4.33 | 8.50 | 25.58 | 3.08 | 1.08 | .83 | 5.50 | 2.50 | 3.25 | 3.83 |
| 23 | 2.58 | 5.16 | 4.50 | 9.41 | 21.41 | 2.83 | 1.00 | .75 | 5.66 | 2.33 | 3.16 | 3.58 |
| 24 | 2.41 | 4.33 | 4.66 | 9.58 | 15.25 | 2.50 | 1.08 | .75 | 4.83 | 2.16 | 3.00 | 3.50 |
| 25 | 2.41 | 3.33 | 5.50 | 9.91 | 11.83 | 2.50 | 1.25 | .75 | 4.00 | 2.33 | 3.00 | 3.33 |
| 26 | 2.41 | 2.91 | 7.00 | 9.00 | 11.33 | 2.66 | 1.41 | .75 | 3.41 | 3.58 | 2.83 | 3.08 |
| 27 | 2.41 | 2.33 | 6.33 | 7.25 | 11.66 | 2.58 | 1.50 | .66 | 3.00 | 4.75 | 2.66 | 3.00 |
| 28 | 2.50 | 2.50 | 5.50 | 6.00 | 9.50 | 2.66 | 1.50 | .66 | 2.58 | 4.83 | 2.58 | 3.00 |
| 29 | 2.58 | ----- | 4.91 | 5.41 | 7.91 | 2.41 | 1.41 | .58 | 2.25 | 4.33 | 2.58 | 4.00 |
| 30 | 2.58 | ----- | 4.33 | 5.00 | 7.00 | 2.75 | 1.16 | .50 | 2.08 | 4.00 | 2.50 | 3.66 |
| 31 | 2.50 | ----- | 4.00 | ----- | 7.50 | ----- | 1.08 | .41 | ----- | 3.75 | ----- | 3.66 |

Mean daily gage height, in feet, of Susquehanna River at Harrisburg, Pa., 1891-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|------|-------|-------|-------|------|-------|-------|------|-------|------|-------|------|
| 1895. | | | | | | | | | | | | |
| 1. | 3.92 | 2.92 | 6.00 | 5.75 | 3.42 | 2.67 | 2.83 | .58 | .75 | .42 | .21 | 3.08 |
| 2. | 4.00 | 2.83 | 8.58 | 5.67 | 3.33 | 2.58 | 2.67 | .67 | .75 | .42 | .21 | 3.08 |
| 3. | 4.25 | 3.00 | 8.08 | 6.17 | 3.25 | 2.50 | 2.92 | .67 | .67 | .33 | .25 | 2.75 |
| 4. | 4.33 | 3.00 | 10.50 | 6.83 | 3.00 | 2.25 | 2.50 | .67 | .67 | .33 | .25 | 2.50 |
| 5. | 4.33 | 7.00 | 7.83 | 6.67 | 2.75 | 2.08 | 2.25 | .58 | .58 | .33 | .33 | 2.25 |
| 6. | 4.33 | 5.67 | 7.67 | 6.17 | 2.67 | 1.92 | 2.00 | .50 | .58 | .33 | .38 | 2.00 |
| 7. | 4.33 | 5.75 | 6.67 | 6.00 | 2.50 | 1.83 | 1.92 | .50 | .75 | .33 | .38 | 1.92 |
| 8. | 4.50 | 5.67 | 6.25 | 5.75 | 2.42 | 1.75 | 1.75 | .83 | .75 | .25 | .42 | 1.92 |
| 9. | 4.75 | 5.50 | 5.83 | 8.08 | 2.25 | 1.75 | 1.58 | .75 | .67 | .25 | .42 | 1.92 |
| 10. | 6.17 | 5.50 | 6.17 | 12.00 | 2.75 | 1.58 | 1.50 | 1.00 | .50 | .21 | .42 | 1.83 |
| 11. | 7.42 | 5.58 | 6.17 | 13.67 | 3.00 | 1.33 | 1.50 | 1.08 | 1.00 | .21 | .42 | 1.50 |
| 12. | 7.83 | 5.92 | 6.33 | 12.50 | 3.33 | 1.42 | 1.42 | 1.08 | 1.50 | .21 | .46 | 1.50 |
| 13. | 8.50 | 5.83 | 6.17 | 10.92 | 3.67 | 1.33 | 1.33 | 1.08 | 1.58 | .33 | .50 | .96 |
| 14. | 7.83 | 5.83 | 6.00 | 9.50 | 4.33 | 1.25 | 1.33 | .92 | 1.42 | .29 | .58 | .75 |
| 15. | 6.75 | 5.67 | 6.50 | 10.00 | 4.33 | 1.25 | 1.25 | 1.33 | 1.00 | .29 | .58 | 1.00 |
| 16. | 6.25 | 5.58 | 6.75 | 9.75 | 4.17 | 1.25 | 1.25 | 1.33 | .83 | .25 | .58 | 1.00 |
| 17. | 5.75 | 5.50 | 6.67 | 8.75 | 4.08 | 1.25 | 1.08 | 1.08 | .67 | .25 | .67 | 1.33 |
| 18. | 5.42 | 5.50 | 6.33 | 7.58 | 3.67 | 1.25 | 1.00 | 1.00 | .58 | .42 | .83 | 1.33 |
| 19. | 5.00 | 5.33 | 5.67 | 6.67 | 3.50 | 1.25 | .92 | 1.00 | .67 | .58 | 1.00 | 1.33 |
| 20. | 4.42 | 5.25 | 5.50 | 6.00 | 3.33 | 1.25 | .92 | .92 | .67 | .50 | 1.00 | 1.33 |
| 21. | 4.42 | 5.17 | 5.33 | 5.50 | 3.17 | 1.17 | .83 | .83 | .67 | .42 | .92 | 1.50 |
| 22. | 4.33 | 5.08 | 5.17 | 5.00 | 3.08 | 1.00 | .83 | .58 | .58 | .42 | .79 | 1.83 |
| 23. | 4.00 | 5.00 | 5.00 | 4.58 | 2.92 | .75 | .83 | .50 | .58 | .33 | .67 | 2.00 |
| 24. | 4.00 | 4.92 | 5.00 | 4.33 | 2.75 | .75 | .83 | .50 | .58 | .25 | .75 | 2.67 |
| 25. | 3.33 | 4.75 | 5.00 | 4.00 | 2.58 | .75 | .83 | .42 | .58 | .25 | .75 | 2.75 |
| 26. | 3.25 | 4.58 | 5.83 | 3.75 | 2.50 | 1.50 | .83 | .33 | .50 | .21 | .75 | 2.83 |
| 27. | 3.08 | 4.80 | 8.00 | 3.58 | 2.50 | 1.50 | .83 | .33 | .50 | .13 | .75 | 3.33 |
| 28. | 3.08 | 4.75 | 9.00 | 3.75 | 2.42 | 1.50 | .83 | .33 | .42 | .08 | 2.67 | 3.50 |
| 29. | 3.08 | ----- | 8.00 | 3.75 | 2.42 | 2.00 | .75 | .33 | .42 | .08 | 2.83 | 5.08 |
| 30. | 3.25 | ----- | 7.17 | 3.50 | 3.08 | 3.50 | .58 | .33 | .42 | .04 | 2.83 | 5.67 |
| 31. | 3.00 | ----- | 6.33 | ----- | 3.00 | ----- | .42 | .50 | ----- | .04 | ----- | 5.67 |
| 1896. | | | | | | | | | | | | |
| 1. | 9.92 | 4.50 | 7.17 | 14.58 | 3.00 | 1.50 | 2.67 | 4.67 | .33 | 5.42 | 2.08 | 3.92 |
| 2. | 9.17 | 3.75 | 9.17 | 14.58 | 3.00 | 1.50 | 2.42 | 4.33 | .33 | 4.25 | 1.92 | 3.92 |
| 3. | 8.42 | 3.58 | 9.75 | 13.75 | 2.83 | 1.75 | 2.08 | 3.83 | .33 | 4.00 | 1.83 | 3.83 |
| 4. | 6.50 | 3.58 | 8.42 | 12.33 | 2.83 | 1.83 | 1.33 | 3.75 | .33 | 3.17 | 1.83 | 3.33 |
| 5. | 5.08 | 3.50 | 7.17 | 10.50 | 2.67 | 1.67 | 1.75 | 3.67 | .25 | 2.67 | 1.83 | 3.00 |
| 6. | 4.00 | 4.00 | 5.50 | 8.83 | 2.50 | 1.67 | 1.67 | 3.58 | .25 | 2.08 | 7.25 | 2.75 |
| 7. | 3.83 | 11.50 | 5.00 | 7.25 | 2.42 | 1.67 | 2.17 | 2.50 | .25 | 1.83 | 10.08 | 2.67 |
| 8. | 3.00 | 12.50 | 4.75 | 6.50 | 2.17 | 1.58 | 2.00 | 2.33 | .25 | 1.67 | 7.75 | 2.50 |
| 9. | 4.67 | 10.33 | 4.50 | 6.17 | 2.08 | 1.42 | 1.92 | 2.33 | .25 | 1.50 | 6.50 | 2.50 |
| 10. | 4.33 | 8.50 | 4.83 | 5.83 | 2.00 | 1.75 | 2.33 | 2.25 | .25 | 1.50 | 5.67 | 2.67 |
| 11. | 4.08 | 6.83 | 5.08 | 5.50 | 2.00 | 2.50 | 2.75 | 2.25 | .25 | 1.50 | 4.75 | 3.42 |
| 12. | 4.00 | 5.33 | 4.67 | 5.50 | 1.92 | 2.58 | 2.75 | 2.00 | .25 | 1.50 | 4.42 | 3.75 |
| 13. | 3.92 | 4.92 | 4.00 | 6.00 | 1.75 | 3.42 | 2.50 | 1.83 | .25 | 1.92 | 4.17 | 4.00 |
| 14. | 4.00 | 4.25 | 3.50 | 6.42 | 1.67 | 3.25 | 2.17 | 1.67 | .33 | 7.33 | 4.00 | 4.25 |
| 15. | 3.83 | 3.75 | 2.67 | 8.00 | 1.67 | 2.92 | 2.00 | 1.67 | .33 | 7.00 | 3.83 | 3.83 |
| 16. | 3.83 | 3.75 | 2.67 | 8.42 | 1.75 | 2.58 | 1.83 | 1.53 | .33 | 9.50 | 3.67 | 3.67 |
| 17. | 3.75 | 3.83 | 2.33 | 8.17 | 1.58 | 2.58 | 1.67 | 1.58 | .50 | 7.67 | 3.50 | 3.42 |
| 18. | 3.58 | 3.58 | 2.50 | 7.33 | 1.50 | 2.83 | 1.58 | 1.58 | .50 | 5.58 | 3.33 | 3.08 |
| 19. | 3.67 | 2.92 | 3.17 | 6.83 | 1.50 | 2.67 | 1.67 | 1.33 | .58 | 4.83 | 3.17 | 2.92 |
| 20. | 4.00 | 3.00 | 4.00 | 6.33 | 1.50 | 3.00 | 1.67 | 1.25 | .58 | 4.08 | 3.00 | 2.58 |
| 21. | 3.67 | 2.33 | 6.00 | 5.75 | 1.50 | 3.17 | 1.92 | 1.00 | .67 | 3.58 | 2.83 | 2.33 |
| 22. | 3.50 | 3.67 | 5.75 | 5.25 | 1.42 | 3.00 | 1.67 | .83 | .83 | 3.42 | 2.67 | 2.00 |
| 23. | 3.50 | 5.42 | 5.75 | 4.83 | 1.42 | 2.42 | 1.58 | .83 | 1.17 | 3.25 | 2.58 | 2.00 |
| 24. | 3.50 | 5.42 | 6.25 | 4.58 | 1.42 | 2.33 | 1.67 | .83 | 1.17 | 3.00 | 2.50 | 1.50 |
| 25. | 4.00 | 3.42 | 5.58 | 4.33 | 1.33 | 2.25 | 1.67 | .83 | .92 | 3.00 | 2.50 | 1.50 |
| 26. | 7.25 | 3.50 | 5.00 | 4.08 | 1.25 | 2.67 | 1.75 | .75 | .75 | 3.00 | 2.33 | 1.50 |
| 27. | 7.33 | 3.67 | 5.25 | 4.00 | 1.17 | 4.75 | 1.92 | .75 | .58 | 2.75 | 2.33 | 1.50 |
| 28. | 6.17 | 3.17 | 6.08 | 3.58 | 1.25 | 4.00 | 2.50 | .67 | .50 | 2.67 | 2.42 | 1.50 |
| 29. | 6.00 | 3.17 | ----- | 3.42 | 1.50 | 3.50 | 2.50 | .58 | .42 | 2.50 | 2.67 | 1.33 |
| 30. | 5.75 | ----- | 9.25 | 3.25 | 1.50 | 3.08 | 3.75 | .50 | .83 | 2.42 | 3.50 | 1.58 |
| 31. | 5.42 | ----- | 12.50 | ----- | 1.50 | ----- | 4.33 | .33 | ----- | 2.25 | ----- | 1.75 |

Mean daily gage height, in feet, of Susquehanna River at Harrisburg, Pa., 1891-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|-------|------|-------|-------|------|-------|-------|------|-------|------|------|------|
| 1897. | | | | | | | | | | | | |
| 1 | 1.83 | 3.33 | 4.25 | 5.00 | 3.08 | 2.92 | 1.42 | 4.00 | 1.25 | 1.75 | .67 | 5.00 |
| 2 | 2.00 | 3.17 | 3.67 | 4.67 | 3.08 | 2.83 | 1.33 | 4.33 | 1.08 | 1.50 | 1.17 | 4.50 |
| 3 | 2.00 | 3.17 | 3.25 | 4.33 | 5.50 | 2.67 | 1.25 | 3.83 | 1.00 | 1.33 | 3.08 | 4.00 |
| 4 | 2.08 | 3.17 | 3.83 | 4.17 | 6.50 | 2.58 | 1.25 | 3.25 | 1.00 | 1.17 | 4.08 | 3.75 |
| 5 | 2.50 | 3.08 | 4.92 | 4.00 | 7.50 | 2.67 | 1.25 | 2.83 | 1.00 | 1.08 | 3.50 | 3.33 |
| 6 | 3.00 | 3.00 | 5.92 | 3.83 | 7.08 | 3.00 | 1.25 | 2.67 | .92 | 1.00 | 3.08 | 4.75 |
| 7 | 3.67 | 4.25 | 7.67 | 3.75 | 7.00 | 2.67 | 1.42 | 2.42 | .83 | 1.00 | 3.00 | 5.17 |
| 8 | 3.67 | 7.50 | 8.58 | 3.75 | 6.33 | 2.50 | 1.42 | 2.67 | .83 | .92 | 2.75 | 5.08 |
| 9 | 3.67 | 6.58 | 8.00 | 3.75 | 5.50 | 2.67 | 1.25 | 2.50 | .83 | .83 | 2.50 | 5.42 |
| 10 | 3.33 | 5.42 | 6.92 | 5.92 | 4.83 | 2.67 | 1.25 | 2.08 | .66 | .67 | 2.41 | 4.92 |
| 11 | 3.08 | 4.83 | 6.50 | 9.00 | 4.50 | 2.67 | 1.17 | 2.08 | .58 | .67 | 2.67 | 4.33 |
| 12 | 2.83 | 4.50 | 7.25 | 9.50 | 4.00 | 2.67 | 1.08 | 2.00 | .67 | .58 | 2.67 | 4.17 |
| 13 | 2.42 | 3.92 | 8.67 | 8.00 | 4.00 | 3.08 | 1.00 | 1.83 | .67 | .75 | 2.50 | 4.17 |
| 14 | 2.00 | 3.83 | 8.42 | 6.83 | 6.00 | 3.50 | 1.08 | 1.75 | .67 | .75 | 2.50 | 4.33 |
| 15 | 2.00 | 3.83 | 7.75 | 6.00 | 7.75 | 3.25 | 1.00 | 1.58 | .50 | .75 | 2.50 | 4.58 |
| 16 | 2.00 | 3.50 | 7.00 | 6.00 | 7.92 | 2.92 | 1.00 | 1.58 | .58 | .75 | 2.50 | 6.58 |
| 17 | 2.00 | 3.50 | 6.92 | 6.58 | 7.33 | 2.67 | 1.17 | 1.50 | .67 | .67 | 2.50 | 7.67 |
| 18 | 2.17 | 3.33 | 5.50 | 7.00 | 6.50 | 2.50 | 1.17 | 1.50 | .75 | .67 | 2.67 | 8.17 |
| 19 | 2.33 | 3.58 | 5.00 | 6.58 | 5.75 | 2.25 | 1.08 | 1.42 | .75 | .58 | 2.92 | 7.33 |
| 20 | 2.00 | 4.08 | 5.33 | 6.00 | 5.00 | 2.17 | 1.08 | 1.42 | .67 | .58 | 3.42 | 6.33 |
| 21 | 1.83 | 4.00 | 7.42 | 5.50 | 4.25 | 2.17 | 1.50 | 1.33 | .58 | .50 | 3.25 | 5.58 |
| 22 | 1.83 | 4.25 | 8.25 | 4.92 | 4.25 | 2.17 | 1.50 | 1.17 | .58 | .58 | 3.17 | 5.00 |
| 23 | 1.92 | 5.92 | 9.75 | 4.50 | 3.58 | 2.00 | 1.33 | 1.17 | .58 | .75 | 2.83 | 4.08 |
| 24 | 1.67 | 7.92 | 9.50 | 4.17 | 3.50 | 1.83 | 1.42 | 1.25 | 1.00 | .75 | 2.50 | 3.83 |
| 25 | 1.67 | 7.50 | 10.17 | 3.83 | 3.75 | 1.75 | 1.58 | 1.67 | 1.50 | 1.00 | 2.50 | 3.42 |
| 26 | 1.50 | 6.50 | 11.50 | 3.67 | 3.75 | 1.75 | 1.75 | 2.67 | 1.50 | 1.00 | 2.50 | 2.83 |
| 27 | 3.33 | 5.50 | 10.67 | 3.58 | 3.50 | 1.67 | 1.75 | 2.08 | 1.83 | 1.00 | 2.33 | 2.75 |
| 28 | 3.33 | 4.50 | 8.00 | 3.50 | 3.58 | 1.58 | 2.17 | 1.75 | 1.92 | .92 | 2.50 | 2.67 |
| 29 | 3.00 | | 7.42 | 3.33 | 3.92 | 1.58 | 3.83 | 1.58 | 2.25 | .83 | 3.50 | 2.67 |
| 30 | 3.25 | | 6.33 | 3.17 | 3.50 | 1.50 | 4.50 | 1.50 | 2.00 | .75 | 4.92 | 2.58 |
| 31 | 3.33 | | 5.58 | | 3.25 | | 4.08 | 1.33 | | .75 | | 2.50 |
| 1898. | | | | | | | | | | | | |
| 1 | 2.66 | 3.91 | 4.66 | 8.66 | 6.00 | 4.33 | 2.00 | 1.41 | 2.66 | .75 | 4.66 | 3.08 |
| 2 | 2.33 | 3.41 | 4.33 | 7.41 | 5.41 | 4.16 | 2.16 | 1.50 | 2.33 | .75 | 4.00 | 3.16 |
| 3 | 2.16 | 3.00 | 4.16 | 6.41 | 4.83 | 3.91 | 2.00 | 1.41 | 3.00 | .66 | 3.66 | 3.08 |
| 4 | 2.66 | 2.66 | 3.91 | 5.75 | 4.66 | 3.58 | 1.75 | 2.33 | 2.50 | .66 | 3.50 | 3.00 |
| 5 | 1.91 | 2.66 | 3.66 | 5.41 | 4.41 | 3.33 | 1.66 | 4.58 | 2.08 | .66 | 3.16 | 3.66 |
| 6 | 1.91 | 2.66 | 3.58 | 4.91 | 4.43 | 3.00 | 1.58 | 5.83 | 1.91 | .66 | 3.00 | 5.00 |
| 7 | 2.25 | 2.66 | 3.50 | 4.50 | 4.66 | 2.83 | 1.50 | 4.00 | 1.66 | .66 | 2.91 | 4.50 |
| 8 | 2.50 | 3.08 | 3.50 | 4.41 | 5.50 | 2.66 | 1.41 | 3.50 | 1.66 | 1.00 | 2.50 | 4.08 |
| 9 | 2.66 | 3.41 | 3.33 | 4.16 | 6.25 | 2.50 | 1.33 | 3.08 | 1.66 | 1.33 | 2.50 | 3.83 |
| 10 | 2.75 | 3.50 | 3.33 | 3.83 | 5.58 | 2.50 | 1.25 | 3.66 | 2.00 | 1.41 | 2.50 | 3.58 |
| 11 | 3.00 | 3.41 | 3.83 | 3.66 | 5.16 | 2.33 | 1.16 | 4.25 | 2.83 | 2.25 | 2.58 | 3.08 |
| 12 | 3.00 | 3.75 | 4.91 | 3.50 | 4.75 | 2.33 | 1.08 | 3.75 | 2.75 | 2.40 | 4.00 | 2.50 |
| 13 | 3.33 | 4.41 | 6.50 | 3.33 | 4.50 | 2.25 | 1.00 | 3.33 | 2.58 | 2.33 | 8.75 | 2.25 |
| 14 | 4.00 | 7.66 | 8.66 | 3.25 | 4.00 | 2.25 | .91 | 2.66 | 2.08 | 2.00 | 8.00 | 2.25 |
| 15 | 6.95 | 8.16 | 9.83 | 3.16 | 4.00 | 2.41 | .83 | 2.50 | 1.91 | 2.00 | 6.58 | 2.08 |
| 16 | 8.08 | 7.50 | 9.33 | 3.66 | 4.25 | 2.75 | .83 | 2.25 | 1.75 | 2.08 | 5.50 | 2.00 |
| 17 | 7.83 | 6.50 | 8.08 | 4.08 | 5.16 | 3.25 | .75 | 2.00 | 1.41 | 2.16 | 4.83 | 2.00 |
| 18 | 7.58 | 5.83 | 7.16 | 3.91 | 6.08 | 3.00 | .66 | 1.91 | 1.33 | 3.25 | 4.33 | 1.91 |
| 19 | 6.58 | 5.00 | 6.33 | 3.66 | 5.33 | 2.66 | .66 | 2.33 | 1.16 | 3.75 | 4.16 | 2.00 |
| 20 | 5.83 | 4.33 | 5.83 | 3.50 | 5.50 | 2.41 | .75 | 3.00 | 1.00 | 4.00 | 4.16 | 2.50 |
| 21 | 5.75 | 4.66 | 7.33 | 3.41 | 6.66 | 2.33 | .91 | 4.41 | .91 | 4.33 | 4.25 | 2.91 |
| 22 | 6.16 | 6.83 | 9.25 | 3.33 | 6.66 | 2.33 | .75 | 4.33 | .91 | 4.25 | 4.58 | 3.08 |
| 23 | 7.41 | 6.91 | 10.91 | 3.16 | 6.50 | 2.08 | .91 | 3.75 | .91 | 7.33 | 4.83 | 3.50 |
| 24 | 9.25 | 7.75 | 15.63 | 3.00 | 6.00 | 2.00 | .83 | 3.41 | .83 | 8.33 | 4.66 | 5.41 |
| 25 | 10.50 | 6.66 | 15.25 | 3.50 | 7.00 | 2.16 | .83 | 3.00 | .83 | 7.41 | 4.33 | 7.83 |
| 26 | 9.50 | 6.25 | 11.66 | 6.66 | 6.50 | 2.08 | .83 | 2.66 | .75 | 6.16 | 4.00 | 7.66 |
| 27 | 8.00 | 5.66 | 9.25 | 10.33 | 6.50 | 2.00 | 1.33 | 2.50 | .91 | 5.66 | 3.91 | 6.33 |
| 28 | 7.00 | 5.00 | 7.75 | 9.50 | 6.16 | 1.91 | 1.16 | 2.41 | .91 | 5.58 | 3.66 | 5.33 |
| 29 | 6.08 | | 6.66 | 8.16 | 5.75 | 1.83 | 1.83 | 4.16 | .75 | 5.66 | 3.50 | 4.83 |
| 30 | 5.50 | | 7.00 | 6.66 | 5.33 | 1.66 | 1.58 | 3.83 | .75 | 6.08 | 3.33 | 4.33 |
| 31 | 4.83 | | 9.00 | | 4.91 | | 1.33 | 3.00 | | 5.33 | | 3.83 |

Mean daily gage height, in feet, of Susquehanna River at Harrisburg, Pa., 1891-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|-------|-------|-------|-------|------|-------|-------|------|-------|------|-------|------|
| 1899. | | | | | | | | | | | | |
| 1 | 3.25 | 2.50 | 8.41 | 7.25 | 3.41 | 2.50 | 1.75 | .75 | 1.83 | 1.08 | .50 | 1.75 |
| 2 | 3.16 | 2.00 | 8.16 | 6.41 | 3.08 | 2.58 | 1.66 | .75 | 1.50 | .83 | 1.66 | 1.58 |
| 3 | 2.75 | 1.91 | 7.83 | 5.83 | 3.08 | 2.50 | 1.66 | .75 | 1.25 | .83 | 2.50 | 1.50 |
| 4 | 3.25 | 2.25 | 7.41 | 5.33 | 3.41 | 2.50 | 1.50 | .75 | 1.08 | .75 | 3.25 | 1.50 |
| 5 | 3.50 | 2.58 | 8.00 | 4.91 | 3.16 | 2.50 | 1.33 | .75 | 1.08 | .66 | 4.50 | 1.50 |
| 6 | 5.00 | 2.66 | 12.50 | 4.41 | 3.16 | 2.33 | .25 | .91 | 1.00 | .66 | 3.91 | 1.50 |
| 7 | 8.00 | 2.83 | 13.00 | 4.25 | 3.00 | 2.68 | .75 | .75 | .91 | .58 | 3.75 | 1.50 |
| 8 | 6.83 | 2.41 | 11.41 | 4.75 | 2.75 | 1.91 | 1.16 | .75 | .91 | .58 | 3.16 | 1.50 |
| 9 | 6.08 | 2.50 | 9.25 | 6.83 | 2.83 | 1.91 | 1.16 | .83 | .83 | .58 | 2.83 | 1.50 |
| 10 | 5.41 | 2.41 | 7.66 | 8.75 | 2.66 | 1.91 | 1.16 | .75 | 1.00 | .66 | 2.50 | 1.50 |
| 11 | 4.58 | 2.41 | 6.50 | 8.41 | 2.75 | 1.75 | 1.41 | .66 | 1.00 | .58 | 2.25 | 1.50 |
| 12 | 4.00 | 4.41 | 5.75 | 7.75 | 2.75 | 1.66 | 1.25 | .66 | .75 | .58 | 2.16 | 1.50 |
| 13 | 3.33 | 4.41 | 5.75 | 6.75 | 2.91 | 1.66 | 1.16 | 1.08 | .83 | .50 | 2.08 | 2.75 |
| 14 | 3.16 | 4.58 | 7.50 | 6.75 | 2.83 | 1.58 | 1.16 | 1.08 | 1.41 | .50 | 2.00 | 5.50 |
| 15 | 3.33 | 4.58 | 8.41 | 8.00 | 2.58 | 1.50 | 1.16 | 1.25 | 1.25 | .51 | 2.25 | 6.33 |
| 16 | 3.66 | 4.66 | 8.00 | 8.00 | 2.50 | 1.50 | 1.08 | .91 | .83 | .41 | 2.41 | 6.00 |
| 17 | 4.83 | 4.83 | 7.41 | 7.83 | 2.50 | 1.41 | 1.00 | .66 | .75 | .41 | 2.41 | 5.33 |
| 18 | 7.00 | 4.83 | 6.41 | 7.33 | 2.58 | 1.25 | 1.25 | .66 | .75 | .41 | 2.41 | 4.58 |
| 19 | 6.33 | 4.91 | 4.33 | 6.83 | 3.75 | 1.25 | 1.25 | .50 | .58 | .41 | 2.83 | 4.08 |
| 20 | 5.66 | 4.75 | 7.16 | 6.00 | 4.75 | 1.25 | 1.25 | .50 | .66 | .33 | 3.00 | 3.75 |
| 21 | 4.91 | 4.91 | 8.50 | 5.41 | 5.16 | 1.25 | 1.25 | .50 | .75 | .33 | 2.91 | 3.75 |
| 22 | 4.33 | 5.33 | 8.16 | 5.08 | 4.25 | 1.16 | 1.33 | .50 | .66 | .33 | 2.58 | 3.83 |
| 23 | 4.25 | 7.50 | 7.50 | 4.91 | 3.91 | 1.08 | 1.33 | .50 | .66 | .33 | 2.50 | 4.50 |
| 24 | 4.08 | 7.50 | 7.16 | 4.50 | 3.58 | 1.00 | 1.33 | .50 | .66 | .16 | 2.25 | 4.25 |
| 25 | 4.16 | 7.16 | 7.41 | 4.41 | 3.16 | 1.41 | 1.16 | .50 | .66 | .16 | 2.25 | 5.83 |
| 26 | 5.25 | 6.83 | 7.41 | 4.00 | 3.00 | 2.00 | 1.00 | .41 | .66 | .25 | 2.25 | 6.75 |
| 27 | 4.50 | 7.33 | 6.83 | 3.91 | 2.91 | 1.66 | 1.00 | .66 | 1.00 | .33 | 2.16 | 5.25 |
| 28 | 3.83 | 9.00 | 6.33 | 3.75 | 2.66 | 1.50 | 1.00 | 4.00 | 1.33 | .33 | 2.00 | 4.58 |
| 29 | 3.25 | ----- | 6.83 | 3.66 | 2.50 | 1.50 | .91 | 2.66 | 1.16 | .41 | 2.00 | 3.83 |
| 30 | 3.00 | ----- | 7.83 | 3.50 | 2.50 | 1.75 | .83 | 2.50 | 1.08 | .83 | 1.83 | 3.00 |
| 31 | 3.00 | ----- | 8.08 | ----- | 2.50 | ----- | .75 | 2.16 | ----- | .83 | ----- | 2.25 |
| 1900. | | | | | | | | | | | | |
| 1 | 1.83 | 2.91 | 4.00 | 4.16 | 4.00 | 2.58 | 1.17 | 1.25 | 1.00 | .04 | .83 | 7.00 |
| 2 | 1.66 | 1.83 | 13.12 | 4.00 | 3.75 | 2.50 | 1.08 | 1.00 | 1.00 | .04 | .83 | 5.83 |
| 3 | 4.50 | 3.91 | 12.33 | 4.16 | 3.50 | 2.33 | 1.00 | 1.00 | .83 | .04 | .75 | 5.25 |
| 4 | 4.91 | 4.00 | 9.50 | 4.41 | 3.33 | 2.17 | 1.08 | .92 | 1.17 | .06 | .75 | 4.50 |
| 5 | 4.83 | 4.66 | 7.91 | 5.33 | 3.08 | 2.50 | 1.33 | .75 | .92 | .04 | .75 | 5.00 |
| 6 | 5.25 | 4.33 | 6.91 | 6.00 | 2.83 | 2.67 | 1.17 | .67 | .83 | .04 | .66 | 7.25 |
| 7 | 5.50 | 5.50 | 6.00 | 5.41 | 2.83 | 2.50 | 1.33 | .67 | .58 | .04 | .66 | 7.41 |
| 8 | 5.33 | 5.00 | 6.16 | 5.08 | 2.75 | 2.17 | 1.17 | .58 | .58 | .08 | .66 | 7.08 |
| 9 | 4.91 | 4.00 | 6.50 | 6.16 | 2.50 | 2.17 | 1.42 | .50 | .58 | .04 | .75 | 6.00 |
| 10 | 4.58 | 4.83 | 5.83 | 6.75 | 2.50 | 2.08 | 1.42 | .58 | .50 | .04 | .58 | 5.25 |
| 11 | 4.50 | 5.75 | 5.66 | 6.50 | 2.42 | 2.00 | 1.33 | .50 | .42 | .04 | .66 | 4.75 |
| 12 | 5.50 | 5.50 | 6.25 | 5.58 | 2.33 | 2.00 | 1.17 | .33 | .33 | .04 | .50 | 4.08 |
| 13 | 4.91 | 5.66 | 5.75 | 5.00 | 2.42 | 1.92 | 1.03 | .33 | .17 | .25 | .58 | 3.83 |
| 14 | 5.25 | 7.66 | 4.66 | 4.50 | 2.42 | 1.92 | 1.08 | .25 | .25 | .83 | .75 | 3.60 |
| 15 | 5.25 | 8.00 | 4.50 | 4.33 | 2.50 | 2.00 | 1.00 | .17 | .25 | .83 | .66 | 2.91 |
| 16 | 5.25 | 8.25 | 4.00 | 4.50 | 2.40 | 2.17 | 1.00 | .17 | .25 | .75 | .66 | 2.85 |
| 17 | 4.66 | 7.41 | 3.66 | 4.41 | 2.33 | 2.17 | 1.00 | .25 | .25 | .58 | .83 | 2.25 |
| 18 | 5.00 | 6.00 | 3.16 | 4.33 | 2.33 | 2.00 | 1.08 | .17 | .17 | .66 | .91 | 2.08 |
| 19 | 4.83 | 4.75 | 3.00 | 5.08 | 2.25 | 1.83 | .92 | .17 | .08 | .66 | .75 | 2.08 |
| 20 | 4.00 | 3.91 | 3.00 | 7.08 | 2.50 | 1.83 | .92 | .17 | .12 | .58 | .91 | 2.08 |
| 21 | 4.25 | 2.16 | 3.91 | 7.33 | 2.92 | 1.82 | .83 | .33 | .08 | .50 | .91 | 2.00 |
| 22 | 10.66 | 3.58 | 6.87 | 6.83 | 2.17 | 1.75 | .75 | .42 | .07 | .50 | .91 | 2.16 |
| 23 | 12.00 | 9.50 | 6.83 | 6.08 | 2.83 | 1.75 | .75 | .83 | .06 | .50 | .83 | 2.41 |
| 24 | 9.16 | 11.16 | 6.00 | 5.83 | 2.58 | 1.58 | .75 | .50 | .04 | .50 | 1.00 | 2.16 |
| 25 | 7.25 | 9.75 | 5.75 | 6.00 | 2.42 | 1.42 | .75 | 1.25 | .04 | 1.00 | 1.08 | 2.33 |
| 26 | 6.08 | 6.83 | 5.83 | 6.25 | 2.25 | 1.33 | .83 | 1.00 | .02 | 1.08 | 1.66 | 2.41 |
| 27 | 5.00 | 5.50 | 5.50 | 5.75 | 2.17 | 1.33 | 1.50 | 1.17 | .00 | 1.00 | 5.91 | 2.00 |
| 28 | 4.50 | 4.50 | 5.25 | 5.08 | 2.00 | 1.33 | 1.25 | 1.50 | -.04 | 1.25 | 13.04 | 2.66 |
| 29 | 4.08 | ----- | 4.83 | 4.58 | 2.00 | 1.33 | 1.25 | 1.33 | -.04 | 1.16 | 12.33 | 2.91 |
| 30 | 3.33 | ----- | 4.50 | 4.17 | 2.00 | 1.17 | 1.42 | 1.00 | +.04 | 1.00 | 8.91 | 2.58 |
| 31 | 2.50 | ----- | 4.41 | ----- | 1.92 | ----- | 1.25 | 1.08 | ----- | .91 | ----- | 2.50 |

Mean daily gage height, in feet, of Susquehanna River at Harrisburg, Pa., 1891-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|---------|-------|-------|-------|-------|-------|-------|-------|------|-------|------|-------|-------|
| 1901. | | | | | | | | | | | | |
| 1..... | 2.25 | 2.58 | 1.75 | 7.16 | 5.16 | 12.58 | 3.08 | 1.66 | 3.50 | 2.08 | 1.41 | 3.08 |
| 2..... | 2.08 | 4.00 | 1.66 | 6.00 | 4.58 | 10.41 | 2.83 | 1.83 | 3.75 | 2.41 | 1.41 | 3.00 |
| 3..... | 1.66 | 3.33 | 1.75 | 5.66 | 4.50 | 8.91 | 2.58 | 1.75 | 4.75 | 2.33 | 1.33 | 2.75 |
| 4..... | 1.66 | 3.25 | 1.83 | 6.25 | 4.41 | 7.83 | 2.33 | 1.58 | 5.16 | 2.33 | 1.33 | 2.75 |
| 5..... | 1.75 | 3.25 | 2.33 | 7.50 | 5.16 | 7.16 | 2.25 | 1.50 | 4.83 | 2.33 | 1.25 | 3.08 |
| 6..... | 1.66 | 3.08 | 2.50 | 7.83 | 5.00 | 6.33 | 2.16 | 1.25 | 4.16 | 2.41 | 1.25 | 2.66 |
| 7..... | 1.41 | 3.16 | 2.58 | 8.66 | 4.58 | 5.50 | 2.33 | 1.66 | 3.58 | 2.16 | 1.25 | 2.75 |
| 8..... | 1.16 | 3.16 | 2.50 | 11.41 | 4.08 | 5.50 | 2.16 | 2.58 | 3.16 | 1.83 | 1.16 | 2.25 |
| 9..... | 1.50 | 3.16 | 3.00 | 12.75 | 3.75 | 6.00 | 2.08 | 2.75 | 2.83 | 1.75 | 1.16 | 2.16 |
| 10..... | 1.50 | 3.00 | 3.25 | 11.50 | 3.66 | 5.75 | 2.08 | 2.50 | 2.50 | 1.75 | 1.16 | 2.58 |
| 11..... | 1.66 | 2.83 | 6.41 | 10.00 | 3.41 | 5.50 | 2.00 | 2.33 | 2.50 | 1.66 | 1.16 | 4.50 |
| 12..... | 2.00 | 2.91 | 11.75 | 8.66 | 3.83 | 5.00 | 1.91 | 2.75 | 2.33 | 1.66 | 1.00 | 7.00 |
| 13..... | 2.00 | 2.83 | 11.83 | 7.50 | 4.16 | 4.66 | 1.91 | 2.41 | 2.41 | 1.66 | 1.08 | 7.00 |
| 14..... | 2.50 | 2.75 | 9.33 | 6.91 | 4.50 | 4.25 | 1.83 | 2.00 | 2.33 | 1.83 | 1.25 | 6.16 |
| 15..... | 3.50 | 2.75 | 7.50 | 6.16 | 5.16 | 3.91 | 1.91 | 1.75 | 2.33 | 2.41 | 1.33 | 9.25 |
| 16..... | 3.33 | 2.58 | 6.66 | 5.91 | 5.08 | 3.50 | 1.75 | 1.66 | 2.25 | 2.66 | 1.58 | 21.41 |
| 17..... | 3.41 | 2.75 | 6.25 | 5.75 | 4.66 | 3.75 | 1.66 | 1.66 | 2.41 | 2.50 | 1.66 | 18.58 |
| 18..... | 2.91 | 2.58 | 5.75 | 5.33 | 4.16 | 3.58 | 2.08 | 1.75 | 2.41 | 2.08 | 1.91 | 14.16 |
| 19..... | 2.58 | 2.50 | 5.25 | 5.00 | 4.00 | 3.50 | 2.41 | 5.50 | 2.50 | 2.08 | 1.91 | 9.83 |
| 20..... | 1.75 | 2.50 | 5.00 | 4.75 | 4.25 | 3.25 | 2.25 | 5.83 | 2.66 | 2.00 | 1.91 | 7.41 |
| 21..... | 1.75 | 2.08 | 5.91 | 5.50 | 4.08 | 3.08 | 2.00 | 5.00 | 2.58 | 2.00 | 1.75 | 6.16 |
| 22..... | 1.83 | 2.00 | 8.50 | 11.00 | 4.00 | 3.25 | 1.83 | 4.08 | 2.58 | 1.91 | 1.75 | 4.83 |
| 23..... | 2.00 | 2.00 | 9.50 | 13.58 | 5.50 | 3.75 | 1.75 | 4.16 | 2.41 | 1.91 | 1.58 | 3.83 |
| 24..... | 1.75 | 1.91 | 9.08 | 12.16 | 8.41 | 3.83 | 1.66 | 4.75 | 2.33 | 1.83 | 1.83 | 3.58 |
| 25..... | 2.00 | 1.91 | 8.00 | 10.16 | 7.50 | 4.00 | 1.58 | 7.75 | 2.08 | 1.83 | 2.50 | 3.75 |
| 26..... | 1.75 | 1.91 | 7.66 | 9.16 | 8.00 | 3.91 | 1.50 | 9.00 | 2.00 | 1.66 | 3.08 | 3.75 |
| 27..... | 2.00 | 1.75 | 8.33 | 8.50 | 7.50 | 3.75 | 1.58 | 7.25 | 1.83 | 1.58 | 5.41 | 3.91 |
| 28..... | 2.00 | 1.75 | 11.75 | 7.25 | 7.00 | 3.50 | 1.66 | 5.75 | 1.75 | 1.66 | 5.25 | 3.91 |
| 29..... | 2.00 | | 12.91 | 6.50 | 8.75 | 3.25 | 1.50 | 4.75 | 1.66 | 1.50 | 4.00 | 3.91 |
| 30..... | 1.75 | | 11.16 | 5.75 | 12.25 | 3.16 | 1.50 | 4.00 | 1.66 | 1.41 | 3.58 | 5.58 |
| 31..... | 1.66 | | 9.00 | | 13.91 | | 1.50 | 3.50 | | 1.41 | | 6.25 |
| 1902. | | | | | | | | | | | | |
| 1..... | 5.25 | 3.58 | 20.33 | 6.25 | 2.75 | 1.75 | 3.58 | 5.83 | 1.25 | 4.83 | 5.50 | 2.41 |
| 2..... | 4.75 | 3.66 | 23.91 | 5.58 | 2.83 | 1.75 | 6.16 | 5.33 | 1.25 | 6.00 | 4.75 | 2.41 |
| 3..... | 4.25 | 3.50 | 23.33 | 5.33 | 2.83 | 1.66 | 7.33 | 5.50 | 1.25 | 5.91 | 4.50 | 2.58 |
| 4..... | 3.83 | 3.25 | 21.41 | 5.00 | 2.66 | 1.66 | 6.66 | 6.25 | 1.25 | 5.66 | 4.00 | 3.33 |
| 5..... | 3.00 | 2.41 | 16.33 | 4.75 | 2.66 | 1.66 | 7.83 | 5.50 | 1.16 | 4.66 | 3.50 | 3.75 |
| 6..... | 3.00 | 2.00 | 12.25 | 4.50 | 2.83 | 1.66 | 7.50 | 4.83 | 1.08 | 4.66 | 3.50 | 3.25 |
| 7..... | 3.00 | 6.08 | 9.50 | 4.50 | 2.75 | 1.50 | 6.83 | 4.50 | 1.00 | 4.66 | 3.25 | 3.50 |
| 8..... | 2.83 | 5.25 | 7.00 | 4.50 | 2.66 | 1.25 | 7.33 | 4.00 | .91 | 4.41 | 3.08 | 3.41 |
| 9..... | 2.75 | 5.00 | 5.25 | 9.00 | 2.66 | 1.50 | 8.50 | 3.58 | .91 | 3.83 | 2.91 | 3.41 |
| 10..... | 3.00 | 5.08 | 5.00 | 14.66 | 2.66 | 1.58 | 7.16 | 3.25 | .91 | 3.83 | 2.75 | 3.16 |
| 11..... | 2.91 | 5.33 | 6.66 | 14.16 | 2.66 | 1.50 | 6.16 | 3.50 | .91 | 3.50 | 2.66 | 3.00 |
| 12..... | 2.66 | 5.16 | 8.33 | 11.58 | 2.50 | 1.50 | 6.16 | 3.58 | 1.25 | 3.58 | 2.41 | 3.00 |
| 13..... | 2.58 | 4.83 | 10.91 | 10.91 | 2.41 | 1.50 | 6.25 | 3.25 | 1.25 | 4.75 | 2.41 | 3.83 |
| 14..... | 2.25 | 4.41 | 13.41 | 8.16 | 2.33 | 1.50 | 5.50 | 3.08 | 1.08 | 4.83 | 2.33 | 3.66 |
| 15..... | 2.25 | 4.41 | 13.58 | 7.08 | 2.25 | 1.75 | 4.58 | 2.83 | 1.16 | 3.75 | 2.33 | 4.00 |
| 16..... | 2.25 | 4.25 | 12.00 | 6.41 | 2.16 | 1.75 | 4.00 | 2.75 | 1.08 | 3.91 | 2.25 | 4.00 |
| 17..... | 2.16 | 4.08 | 12.16 | 5.66 | 2.16 | 2.25 | 3.50 | 2.50 | 1.08 | 3.75 | 2.16 | 5.33 |
| 18..... | 2.00 | 3.83 | 15.00 | 5.08 | 2.00 | 2.41 | 3.25 | 2.50 | 1.00 | 3.16 | 2.16 | 8.58 |
| 19..... | 2.00 | 3.75 | 13.66 | 4.75 | 1.83 | 2.41 | 3.25 | 2.16 | 1.00 | 3.33 | 2.16 | 8.33 |
| 20..... | 2.16 | 3.75 | 11.33 | 4.41 | 1.83 | 2.33 | 3.16 | 2.00 | 1.00 | 3.00 | 1.91 | 7.66 |
| 21..... | 2.16 | 3.75 | 9.50 | 4.08 | 1.75 | 2.16 | 3.33 | 2.00 | 1.00 | 2.91 | 1.83 | 7.16 |
| 22..... | 5.16 | 4.00 | 6.00 | 3.83 | 1.75 | 2.16 | 4.33 | 1.91 | .91 | 2.66 | 1.75 | 8.50 |
| 23..... | 10.00 | 4.00 | 5.50 | 3.50 | 1.83 | 2.16 | 8.08 | 1.91 | .83 | 2.58 | 1.75 | 12.50 |
| 24..... | 6.75 | 4.08 | 5.33 | 3.41 | 1.66 | 2.00 | 8.00 | 1.75 | .83 | 2.41 | 1.66 | 12.66 |
| 25..... | 6.50 | 4.16 | 5.33 | 3.25 | 1.66 | 2.00 | 7.25 | 1.75 | .83 | 2.25 | 1.66 | 11.50 |
| 26..... | 5.41 | 6.41 | 4.66 | 3.00 | 1.66 | 2.00 | 7.75 | 1.58 | 1.66 | 2.41 | 1.91 | 8.25 |
| 27..... | 5.08 | 9.41 | 3.66 | 2.91 | 1.66 | 2.16 | 8.08 | 1.58 | 3.75 | 2.33 | 2.00 | 7.25 |
| 28..... | 5.33 | 9.66 | 3.66 | 2.75 | 1.66 | 2.41 | 6.83 | 1.50 | 5.16 | 2.33 | 2.25 | 6.16 |
| 29..... | 5.33 | | 4.41 | 2.75 | 1.66 | 2.41 | 5.83 | 1.41 | 4.33 | 3.66 | 2.33 | 5.58 |
| 30..... | 4.33 | | 4.41 | 2.75 | 1.66 | 5.00 | 6.16 | 1.25 | 4.33 | 5.66 | 2.41 | 4.83 |
| 31..... | 3.91 | | 5.33 | | 1.75 | | 6.16 | 1.25 | | 6.00 | | 4.58 |

Mean daily gage height, in feet, of Susquehanna River at Harrisburg, Pa., 1891-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|--------------------|--------------------|-------|-------|-------|------|-------|-------|------|-------|-------|-------|------|
| 1903. | | | | | | | | | | | | |
| 1 | 4.16 | 11.50 | 13.41 | 6.50 | 3.41 | 1.50 | 7.33 | 3.50 | 10.29 | 1.75 | 3.16 | 2.50 |
| 2 | 3.66 | 10.50 | 16.83 | 7.25 | 3.25 | 1.50 | 6.00 | 3.33 | 8.33 | 1.75 | 3.08 | 2.41 |
| 3 | 3.83 | 8.75 | 14.50 | 7.50 | 3.00 | 1.50 | 5.16 | 2.91 | 6.83 | 1.75 | 3.00 | 2.33 |
| 4 | 4.83 | 8.91 | 11.00 | 6.75 | 2.58 | 1.50 | 4.66 | 2.66 | 5.66 | 1.58 | 2.83 | 2.16 |
| 5 | 5.58 | 13.83 | 9.00 | 6.50 | 2.50 | 1.50 | 4.08 | 2.41 | 5.16 | 1.58 | 2.83 | 2.08 |
| 6 | 5.91 | 14.58 | 8.75 | 5.75 | 2.33 | 1.50 | 4.41 | 2.50 | 4.58 | 1.50 | 2.66 | 2.00 |
| 7 | 6.33 | 12.25 | 7.66 | 5.75 | 2.33 | 1.50 | 4.66 | 2.91 | 4.00 | 1.41 | 2.58 | 2.00 |
| 8 | 5.83 | 9.33 | 8.16 | 5.75 | 2.25 | 1.50 | 5.33 | 4.75 | 3.33 | 1.83 | 2.50 | 2.00 |
| 9 | 5.00 | 8.25 | 8.00 | 5.75 | 2.16 | 1.66 | 5.33 | 4.66 | 3.66 | 2.66 | 2.50 | 2.33 |
| 10 | 4.33 | 7.00 | 10.58 | 6.83 | 2.16 | 2.25 | 4.33 | 4.08 | 3.83 | 5.00 | 2.41 | 2.16 |
| 11 | 3.41 | 6.00 | 12.50 | 7.00 | 2.16 | 2.25 | 3.83 | 3.66 | 3.50 | 10.66 | 2.41 | 1.91 |
| 12 | 2.91 | 6.16 | 11.41 | 6.83 | 2.16 | 2.25 | 3.16 | 3.50 | 3.50 | 11.25 | 2.41 | 1.91 |
| 13 | 2.66 | 6.50 | 11.91 | 6.50 | 2.08 | 3.16 | 3.25 | 3.50 | 3.50 | 11.08 | 2.41 | 1.91 |
| 14 | 2.25 | 6.66 | 10.83 | 6.50 | 2.08 | 3.66 | 3.25 | 3.50 | 3.33 | 9.25 | 2.33 | 2.00 |
| 15 | 2.25 | 7.50 | 9.75 | 8.83 | 2.08 | 4.08 | 2.75 | 3.00 | 3.50 | 7.33 | 2.33 | 1.00 |
| 16 | 2.66 | 7.66 | 8.33 | 12.66 | 2.08 | 4.33 | 2.75 | 3.16 | 3.16 | 5.91 | 2.33 | 1.00 |
| 17 | 3.00 | 7.66 | 7.83 | 12.75 | 2.08 | 4.41 | 2.58 | 3.50 | 2.83 | 5.16 | 2.33 | 1.00 |
| 18 | 3.16 | 7.00 | 7.16 | 10.66 | 1.83 | 4.25 | 2.33 | 3.33 | 2.83 | 4.83 | 2.50 | 1.33 |
| 19 | 3.16 | 6.00 | 6.50 | 9.33 | 1.83 | 3.83 | 3.08 | 3.16 | 3.16 | 5.33 | 8.66 | 3.16 |
| 20 | 3.16 | 5.25 | 6.50 | 8.00 | 1.75 | 3.41 | 4.50 | 2.83 | 3.33 | 6.50 | 8.25 | 4.00 |
| 21 | 3.16 | 4.08 | 5.50 | 6.50 | 1.75 | 3.33 | 5.66 | 2.58 | 3.00 | 6.58 | 6.50 | 5.66 |
| 22 | 3.25 | 4.50 | 5.66 | 6.33 | 1.66 | 3.33 | 5.41 | 2.50 | 2.83 | 6.16 | 6.16 | 5.58 |
| 23 | 4.16 | 4.50 | 6.00 | 5.83 | 1.66 | 3.66 | 4.53 | 2.33 | 2.66 | 5.50 | 4.66 | 5.58 |
| 24 | 4.00 | 4.33 | 9.41 | 5.66 | 1.66 | 4.33 | 3.91 | 2.41 | 2.50 | 4.33 | 4.33 | 4.58 |
| 25 | 3.91 | 4.16 | 15.16 | 5.25 | 1.66 | 5.58 | 3.58 | 2.33 | 2.41 | 4.41 | 4.00 | 4.41 |
| 26 | 3.50 | 4.08 | 14.16 | 4.58 | 1.66 | 6.50 | 3.16 | 2.16 | 2.33 | 3.66 | 3.75 | 4.00 |
| 27 | 3.50 | 4.58 | 11.00 | 4.50 | 1.66 | 7.16 | 3.00 | 2.16 | 2.16 | 3.75 | 3.33 | 3.50 |
| 28 | 3.58 | 5.50 | 9.58 | 4.00 | 1.66 | 6.50 | 3.00 | 2.25 | 2.08 | 3.66 | 2.50 | 3.08 |
| 29 | 3.75 | ----- | 8.16 | 3.50 | 1.58 | 6.00 | 2.83 | 4.16 | 1.83 | 5.20 | 2.50 | 2.91 |
| 30 | 4.66 | ----- | 6.83 | 3.50 | 1.58 | 5.50 | 3.00 | 5.91 | 1.83 | 3.33 | 2.50 | 2.66 |
| 31 | 8.08 | ----- | 6.83 | ----- | 1.50 | ----- | 3.33 | 9.25 | ----- | 3.16 | ----- | 2.08 |
| 1904. ^a | | | | | | | | | | | | |
| 1 | 2.16 | 4.41 | 9.41 | 6.40 | 7.65 | 3.65 | 1.90 | 1.58 | 1.43 | 1.78 | 2.08 | 1.79 |
| 2 | 2.16 | 4.16 | 11.50 | 10.15 | 6.65 | 3.90 | 1.73 | 1.68 | 1.28 | 1.68 | 1.98 | 1.54 |
| 3 | 4.00 | 4.00 | 11.91 | 13.06 | 6.40 | 4.23 | 1.98 | 1.93 | 1.23 | 1.53 | 1.88 | 1.44 |
| 4 | 3.16 | 4.75 | 13.50 | 11.15 | 5.65 | 4.23 | 1.90 | 1.93 | 1.23 | 1.78 | 1.78 | 1.24 |
| 5 | 3.16 | 3.41 | 22.00 | 9.40 | 4.90 | 3.98 | 1.65 | 1.88 | 1.18 | 1.93 | 1.68 | 1.29 |
| 6 | 2.91 | 4.41 | 19.41 | 7.73 | 4.06 | 4.90 | 1.73 | 1.78 | 1.13 | 1.73 | 1.64 | .94 |
| 7 | 2.91 | 3.75 | 16.33 | 6.73 | 3.98 | 5.23 | 1.73 | 2.08 | 1.08 | 1.58 | 1.60 | 1.29 |
| 8 | 2.83 | 3.83 | 21.16 | 6.15 | 3.81 | 4.73 | 2.23 | 2.03 | .98 | 1.48 | 1.54 | 1.09 |
| 9 | 2.83 | 5.50 | 15.91 | 6.06 | 3.48 | 3.98 | 2.56 | 1.78 | .98 | 1.38 | 1.54 | 1.24 |
| 10 | ^b 2.83 | 9.08 | 15.00 | 6.40 | 3.40 | 3.56 | 2.56 | 1.68 | 1.18 | 1.23 | 1.49 | 1.19 |
| 11 | 3.00 | 9.33 | 12.00 | 8.48 | 3.15 | 4.31 | 4.48 | 1.88 | 1.18 | 1.18 | 1.59 | .84 |
| 12 | 3.58 | 8.41 | 9.16 | 9.15 | 2.98 | 5.40 | 5.06 | 1.63 | 1.18 | 1.23 | 1.54 | .94 |
| 13 | 3.83 | 9.91 | 7.91 | 7.98 | 2.90 | 4.65 | 4.40 | 1.58 | 1.13 | 1.23 | 1.59 | 1.69 |
| 14 | 4.91 | 13.50 | 6.58 | 7.15 | 2.56 | 3.90 | 3.73 | 1.48 | 1.08 | 1.23 | 1.69 | 1.44 |
| 15 | 4.66 | 12.50 | 6.08 | 6.31 | 2.81 | 3.23 | 3.23 | 1.33 | 1.38 | 1.38 | 1.64 | 1.49 |
| 16 | 4.50 | 11.58 | 5.58 | 5.25 | 3.15 | 2.90 | 2.90 | 1.33 | 1.58 | 2.93 | 1.59 | 1.39 |
| 17 | 5.00 | 10.16 | 5.25 | 5.15 | 3.40 | 2.65 | 2.56 | 1.28 | 1.98 | 2.73 | 1.54 | 1.30 |
| 18 | 5.00 | 9.91 | 4.83 | 5.06 | 3.65 | 2.81 | 2.28 | 1.23 | 2.18 | 2.58 | 1.49 | 1.50 |
| 19 | 4.25 | 9.16 | 4.66 | 4.56 | 3.98 | 2.81 | 2.08 | 1.13 | 1.78 | 2.13 | 1.59 | 1.50 |
| 20 | 4.08 | 9.16 | 4.66 | 4.48 | 4.98 | 2.56 | 1.98 | 1.18 | 1.78 | 1.88 | 1.59 | 1.50 |
| 21 | 4.16 | 8.66 | 5.00 | 3.90 | 6.06 | 2.56 | 2.63 | 1.28 | 1.63 | 1.73 | 1.49 | 1.40 |
| 22 | 4.66 | 9.16 | 5.58 | 3.31 | 6.56 | 2.65 | 1.88 | 1.18 | 1.43 | 1.88 | 1.54 | 1.40 |
| 23 | 5.50 | 10.16 | 6.66 | 3.73 | 5.31 | 2.56 | 1.93 | 1.28 | 1.53 | 2.93 | 1.59 | 1.59 |
| 24 | ^c 15.50 | 10.16 | 7.08 | 3.56 | 4.56 | 2.56 | 2.98 | 1.28 | 1.18 | 3.76 | 1.69 | 1.69 |
| 25 | 11.50 | 10.75 | 10.41 | 3.40 | 4.23 | 2.73 | 2.13 | 1.28 | 1.18 | 4.06 | 1.69 | 1.61 |
| 26 | 10.16 | 10.41 | 11.00 | 3.48 | 3.81 | 2.48 | 1.83 | 1.68 | 1.08 | 3.58 | 1.79 | 1.60 |
| 27 | 7.66 | 10.58 | 15.25 | 3.48 | 3.98 | 2.31 | 1.73 | 2.33 | 1.03 | 3.03 | 1.89 | 1.80 |
| 28 | 6.83 | 9.50 | 13.83 | 3.73 | 3.90 | 2.06 | 1.68 | 2.08 | 1.13 | 2.68 | 1.84 | 1.90 |
| 29 | 5.83 | 9.08 | 12.50 | 4.90 | 3.65 | 1.98 | 1.78 | 1.83 | 1.63 | 2.53 | 1.74 | 2.10 |
| 30 | 4.75 | ----- | 10.16 | 6.98 | 3.31 | 1.81 | 1.68 | 1.63 | 1.73 | 2.48 | 1.84 | 9.40 |
| 31 | 4.50 | ----- | 8.41 | ----- | 3.40 | ----- | 1.63 | 1.53 | ----- | 2.28 | ----- | 8.40 |

^aFrom January 1 to July 17, inclusive, gage readings were taken at the pump house. From July 18 to the end of the year the readings were taken at the Walnut Street Bridge. Beginning with April 1 the readings at the pump house were too high by 0.6 foot, owing to the fact that a cofferdam was built just below the intake. This correction has been applied; therefore the gage readings for the complete year are referred to the low-water datum of 1803.

^bRiver frozen over at 5 a. m.

^cSeveral ice gorges existed both above and below Harrisburg from January 24 to March 13. These caused the backing up of the water, thus increasing the gage height.


[illegible]

| | | |
|-----|-----|-----|
| 1 1 | 2 2 | 3 3 |
| 1 2 | 1 3 | 2 3 |
| 1 3 | 2 3 | 3 3 |
| 2 1 | 2 2 | 2 3 |
| 3 1 | 3 2 | 3 3 |
| 3 2 | 3 3 | 3 3 |

| | | |
|--|--|--|
| | | |
| | | |

140,000

AT HARRISBURG



RATING CURVE FOR SUSQUEHANNA RIVER AT HARRISBURG PA.

Rating table for Susquehanna River at Harrisburg, Pa., from 1891 to 1904.

| Gage height. | Discharge. | Gage height. | Discharge. | Gage height. | Discharge. | Gage height. | Discharge. |
|--------------|---------------------|--------------|---------------------|--------------|---------------------|--------------|---------------------|
| <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> |
| -0.05 | 2,330 | 2.4 | 16,950 | 5.8 | 65,000 | 12.0 | 174,500 |
| +0.0 | 2,440 | 2.5 | 17,960 | 6.0 | 68,400 | 12.5 | 183,600 |
| .1 | 2,710 | 2.6 | 19,010 | 6.2 | 71,900 | 13.0 | 193,000 |
| .2 | 3,000 | 2.7 | 20,100 | 6.4 | 75,500 | 13.5 | 202,500 |
| .3 | 3,330 | 2.8 | 21,210 | 6.6 | 79,200 | 14.0 | 212,000 |
| .4 | 3,680 | 2.9 | 22,340 | 6.8 | 82,900 | 14.5 | 221,300 |
| .5 | 4,070 | 3.0 | 23,480 | 7.0 | 86,500 | 15.0 | 231,000 |
| .6 | 4,500 | 3.1 | 24,620 | 7.2 | 90,000 | 15.5 | 242,300 |
| .7 | 4,980 | 3.2 | 25,760 | 7.4 | 93,400 | 16.0 | 254,500 |
| .8 | 5,500 | 3.3 | 26,910 | 7.6 | 96,700 | 16.5 | 267,400 |
| .9 | 6,020 | 3.4 | 28,130 | 7.8 | 100,100 | 17.0 | 280,400 |
| 1.0 | 6,550 | 3.5 | 29,430 | 8.0 | 103,500 | 17.5 | 293,600 |
| 1.1 | 7,090 | 3.6 | 30,800 | 8.2 | 106,900 | 18.0 | 306,700 |
| 1.2 | 7,650 | 3.7 | 32,200 | 8.4 | 110,300 | 19.0 | 334,500 |
| 1.3 | 8,240 | 3.8 | 33,600 | 8.6 | 113,800 | 20.0 | 363,100 |
| 1.4 | 8,850 | 3.9 | 35,000 | 8.8 | 117,300 | 21.0 | 392,600 |
| 1.5 | 9,520 | 4.0 | 36,400 | 9.0 | 120,800 | 22.0 | 423,100 |
| 1.6 | 10,200 | 4.2 | 39,200 | 9.2 | 124,300 | 23.0 | 454,600 |
| 1.7 | 10,930 | 4.4 | 42,200 | 9.4 | 127,800 | 24.0 | 487,000 |
| 1.8 | 11,700 | 4.6 | 45,400 | 9.6 | 131,400 | 25.0 | 520,200 |
| 1.9 | 12,500 | 4.8 | 48,600 | 9.8 | 134,900 | 26.0 | 554,400 |
| 2.0 | 13,300 | 5.0 | 51,900 | 10.0 | 138,400 | 27.0 | 589,400 |
| 2.1 | 14,160 | 5.2 | 55,100 | 10.5 | 147,200 | | |
| 2.2 | 15,050 | 5.4 | 58,400 | 11.0 | 156,300 | | |
| 2.3 | 15,980 | 5.6 | 61,700 | 11.5 | 165,300 | | |

Mean daily discharge, in second-feet, of Susquehanna River at Harrisburg, Pa., 1891-1904.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|---------|---------|---------|---------|---------|---------|--------|--------|--------|--------|--------|---------|
| 1891. | | | | | | | | | | | | |
| 1 | 21,770 | 149,000 | 156,300 | 107,800 | 30,800 | 13,300 | 20,650 | 26,350 | 46,200 | 11,310 | 17,960 | 39,900 |
| 2 | 23,480 | 165,300 | 120,800 | 120,800 | 29,430 | 12,500 | 17,960 | 25,190 | 36,400 | 10,560 | 17,960 | 36,400 |
| 3 | 27,510 | 165,300 | 122,600 | 113,800 | 28,130 | 13,300 | 19,010 | 24,620 | 31,500 | 10,560 | 16,460 | 31,500 |
| 4 | 43,800 | 159,000 | 80,100 | 116,400 | 28,130 | 13,300 | 25,190 | 22,840 | 27,510 | 10,200 | 15,510 | 29,430 |
| 5 | 55,900 | 141,000 | 62,500 | 110,300 | 26,330 | 13,300 | 37,800 | 23,480 | 23,480 | 10,200 | 15,510 | 45,400 |
| 6 | 51,900 | 119,000 | 62,500 | 103,500 | 24,620 | 13,300 | 29,430 | 24,620 | 23,480 | 10,200 | 15,510 | 116,400 |
| 7 | 60,000 | 97,600 | 55,900 | 89,200 | 23,480 | 14,160 | 24,620 | 23,480 | 34,300 | 10,200 | 14,600 | 129,600 |
| 8 | 58,400 | 95,100 | 51,900 | 75,500 | 23,480 | 14,600 | 19,550 | 27,510 | 46,200 | 11,310 | 14,600 | 109,400 |
| 9 | 50,200 | 95,100 | 46,200 | 68,400 | 22,340 | 19,010 | 20,650 | 24,620 | 43,800 | 19,010 | 13,300 | 86,500 |
| 10 | 43,800 | 93,400 | 46,200 | 62,500 | 20,650 | 20,650 | 19,550 | 21,770 | 37,800 | 23,480 | 13,300 | 68,400 |
| 11 | 37,800 | 95,100 | 71,000 | 57,500 | 19,550 | 23,480 | 22,340 | 20,650 | 34,300 | 21,770 | 13,300 | 58,400 |
| 12 | 39,900 | 93,400 | 88,300 | 70,100 | 19,550 | 20,650 | 21,770 | 19,010 | 29,430 | 19,550 | 19,550 | 51,900 |
| 13 | 68,400 | 86,500 | 112,000 | 92,600 | 19,010 | 19,550 | 19,010 | 19,010 | 24,620 | 19,550 | 31,500 | 38,500 |
| 14 | 116,400 | 75,500 | 132,300 | 120,800 | 17,960 | 19,550 | 17,960 | 19,010 | 23,480 | 19,010 | 36,400 | 41,400 |
| 15 | 101,800 | 66,600 | 151,700 | 112,000 | 17,960 | 19,010 | 15,510 | 17,960 | 23,480 | 16,950 | 39,900 | 36,400 |
| 16 | 95,100 | 61,700 | 138,400 | 103,500 | 16,950 | 17,960 | 14,600 | 17,960 | 19,550 | 16,460 | 37,800 | 34,300 |
| 17 | 80,100 | 66,600 | 118,200 | 97,600 | 16,950 | 16,950 | 13,300 | 17,960 | 19,550 | 14,160 | 32,900 | 32,900 |
| 18 | 68,400 | 216,600 | 99,200 | 93,400 | 16,460 | 16,460 | 12,100 | 16,950 | 19,010 | 13,300 | 36,400 | 31,500 |
| 19 | 62,500 | 334,500 | 83,800 | 83,800 | 15,510 | 16,460 | 12,500 | 15,510 | 19,010 | 12,100 | 49,400 | 45,400 |
| 20 | 53,500 | 302,800 | 71,000 | 82,000 | 15,510 | 16,460 | 14,160 | 16,950 | 17,960 | 12,500 | 47,800 | 51,900 |
| 21 | 49,400 | 197,800 | 66,600 | 74,600 | 13,720 | 27,510 | 14,160 | 15,510 | 15,510 | 14,600 | 46,200 | 47,800 |
| 22 | 43,800 | 169,800 | 74,600 | 66,600 | 13,300 | 30,800 | 14,160 | 14,160 | 14,600 | 17,960 | 39,900 | 38,500 |
| 23 | 88,300 | 165,300 | 80,100 | 60,000 | 14,600 | 58,400 | 13,300 | 13,300 | 14,160 | 26,330 | 38,500 | 34,300 |
| 24 | 123,400 | 142,800 | 105,200 | 54,300 | 15,510 | 71,000 | 13,300 | 24,620 | 14,160 | 46,200 | 37,800 | 35,400 |
| 25 | 129,600 | 120,800 | 144,500 | 51,900 | 16,460 | 61,700 | 41,400 | 77,900 | 13,300 | 38,500 | 58,400 | 45,400 |
| 26 | 127,800 | 107,800 | 153,500 | 47,800 | 15,980 | 45,400 | 36,400 | 79,200 | 12,500 | 31,500 | 75,500 | 74,600 |
| 27 | 110,300 | 162,600 | 140,100 | 46,200 | 15,510 | 41,400 | 34,300 | 55,900 | 12,100 | 25,190 | 71,000 | 107,800 |
| 28 | 95,100 | 194,900 | 119,000 | 39,900 | 15,050 | 32,900 | 27,510 | 62,500 | 11,310 | 23,480 | 58,400 | 126,900 |
| 29 | 86,500 | ----- | 101,000 | 37,800 | 14,600 | 29,430 | 23,480 | 68,400 | 11,310 | 21,770 | 51,900 | 113,800 |
| 30 | 88,300 | ----- | 95,100 | 34,300 | 14,160 | 29,430 | 20,650 | 57,500 | 11,310 | 19,550 | 46,200 | 101,000 |
| 31 | 135,800 | ----- | 97,600 | ----- | 13,300 | ----- | 35,000 | 54,200 | ----- | 19,010 | ----- | 112,000 |
| 1892. | | | | | | | | | | | | |
| 1 | 112,000 | 21,770 | 43,800 | 134,000 | 23,480 | 66,600 | 46,200 | 12,500 | 22,340 | 7,090 | 4,070 | 12,500 |
| 2 | 107,800 | 22,340 | 36,400 | 120,800 | 21,770 | 60,000 | 41,400 | 13,300 | 17,960 | 7,940 | 4,070 | 12,100 |
| 3 | 116,400 | 22,340 | 30,800 | 112,000 | 21,770 | 54,300 | 32,900 | 12,100 | 16,460 | 8,850 | 4,070 | 11,310 |
| 4 | 126,900 | 24,620 | 26,330 | 169,800 | 21,770 | 96,700 | 31,500 | 13,300 | 14,600 | 7,940 | 4,070 | 10,200 |
| 5 | 118,200 | 24,620 | 23,480 | 218,600 | 43,800 | 183,600 | 29,430 | 23,480 | 13,300 | 7,090 | 4,070 | 10,200 |
| 6 | 103,500 | 23,480 | 19,550 | 224,200 | 65,800 | 174,500 | 30,800 | 21,770 | 12,100 | 7,090 | 4,070 | 9,520 |
| 7 | 101,000 | 23,480 | 21,770 | 195,800 | 96,700 | 160,800 | 28,130 | 21,770 | 12,100 | 6,550 | 4,070 | 9,520 |
| 8 | 83,800 | 22,340 | 21,770 | 162,600 | 96,700 | 120,800 | 28,130 | 23,480 | 11,310 | 6,550 | 4,070 | 9,520 |
| 9 | 57,500 | 20,650 | 34,300 | 129,600 | 101,000 | 97,600 | 28,130 | 19,550 | 10,560 | 6,550 | 5,240 | 10,200 |
| 10 | 62,500 | 17,960 | 55,900 | 101,000 | 80,100 | 86,500 | 23,480 | 16,950 | 9,520 | 6,550 | 6,020 | 10,560 |
| 11 | 38,500 | 19,010 | 71,000 | 86,500 | 61,700 | 93,400 | 21,770 | 14,600 | 9,520 | 6,550 | 6,550 | 16,950 |
| 12 | 31,500 | 17,960 | 66,600 | 75,500 | 51,900 | 86,500 | 17,960 | 14,160 | 8,850 | 6,020 | 7,370 | 39,900 |
| 13 | 32,900 | 13,300 | 62,500 | 62,500 | 47,800 | 75,500 | 14,600 | 16,950 | 8,850 | 6,020 | 7,370 | 36,400 |
| 14 | 60,000 | 11,700 | 51,900 | 57,500 | 39,900 | 58,400 | 14,600 | 17,960 | 9,520 | 5,760 | 7,370 | 29,430 |
| 15 | 171,700 | 11,310 | 42,200 | 47,800 | 38,500 | 46,200 | 16,460 | 29,430 | 16,460 | 5,760 | 7,940 | 24,620 |
| 16 | 195,800 | 12,100 | 36,400 | 47,800 | 38,500 | 38,500 | 16,950 | 38,500 | 16,460 | 5,760 | 7,940 | 21,770 |
| 17 | 153,500 | 10,560 | 29,430 | 41,400 | 42,200 | 32,900 | 16,950 | 36,400 | 14,160 | 5,760 | 7,940 | 22,340 |
| 18 | 122,500 | 11,310 | 27,510 | 41,400 | 49,400 | 30,800 | 15,510 | 29,430 | 12,100 | 5,760 | 7,940 | 19,550 |
| 19 | 99,200 | 13,300 | 24,620 | 36,400 | 50,200 | 29,430 | 15,510 | 21,770 | 10,560 | 5,760 | 12,500 | 19,610 |
| 20 | 97,600 | 16,460 | 23,480 | 34,300 | 62,500 | 29,430 | 14,160 | 19,550 | 9,520 | 5,760 | 17,960 | 17,960 |
| 21 | 86,500 | 14,600 | 22,340 | 31,500 | 90,800 | 31,500 | 13,300 | 16,460 | 9,520 | 5,760 | 17,960 | 16,950 |
| 22 | 71,000 | 17,960 | 19,550 | 29,430 | 107,800 | 36,400 | 11,310 | 14,600 | 9,520 | 5,760 | 22,340 | 14,160 |
| 23 | 57,500 | 19,550 | 17,960 | 28,130 | 118,200 | 31,500 | 10,560 | 12,500 | 8,540 | 5,760 | 30,800 | 9,520 |
| 24 | 47,800 | 25,190 | 17,960 | 29,430 | 116,400 | 29,430 | 10,560 | 12,100 | 7,370 | 5,760 | 27,510 | 6,020 |
| 25 | 43,800 | 29,430 | 19,550 | 29,430 | 107,800 | 31,500 | 10,560 | 12,500 | 7,370 | 5,240 | 22,340 | 7,090 |
| 26 | 41,400 | 41,400 | 29,430 | 30,800 | 92,600 | 38,500 | 10,200 | 14,600 | 7,940 | 4,500 | 17,960 | 19,010 |
| 27 | 30,800 | 43,800 | 43,800 | 30,800 | 80,100 | 30,800 | 9,520 | 13,300 | 7,940 | 4,500 | 14,160 | 13,300 |
| 28 | 17,960 | 49,400 | 153,500 | 29,430 | 77,300 | 26,330 | 9,520 | 13,300 | 7,940 | 4,500 | 13,300 | 15,510 |
| 29 | 14,160 | 46,200 | 193,000 | 27,510 | 74,600 | 29,430 | 9,520 | 13,300 | 7,090 | 4,500 | 13,300 | 15,510 |
| 30 | 21,770 | ----- | 174,500 | 25,190 | 88,300 | ----- | 8,850 | 15,510 | 7,090 | 4,500 | 12,500 | 15,510 |
| 31 | 21,770 | ----- | 149,000 | ----- | 75,500 | ----- | 10,560 | 23,480 | ----- | 4,070 | ----- | 14,600 |

Mean daily discharge, in second-feet, of Susquehanna River at Harrisburg, Pa.,
1891-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|--------|---------|---------|---------|---------|---------|--------|--------|--------|--------|--------|---------|
| 1893. | | | | | | | | | | | | |
| 1 | 13,300 | 19,550 | 19,010 | 70,100 | 50,200 | 31,500 | 16,460 | 6,020 | 30,800 | 13,300 | 14,600 | 36,400 |
| 2 | 17,960 | 23,480 | 19,010 | 68,400 | 49,400 | 31,500 | 14,600 | 5,760 | 38,500 | 13,300 | 14,600 | 34,300 |
| 3 | 21,770 | 36,400 | 20,650 | 75,500 | 60,000 | 29,430 | 14,160 | 5,760 | 35,000 | 12,100 | 14,600 | 31,500 |
| 4 | 21,770 | 38,500 | 20,650 | 95,100 | 83,800 | 30,800 | 12,500 | 5,760 | 29,430 | 10,560 | 14,600 | 31,500 |
| 5 | 20,650 | 51,900 | 20,650 | 101,800 | 258,400 | 30,800 | 12,500 | 5,240 | 19,550 | 9,520 | 16,460 | 31,500 |
| 6 | 19,550 | 53,500 | 17,960 | 119,000 | 267,400 | 25,190 | 10,560 | 5,240 | 15,510 | 9,520 | 23,480 | 29,430 |
| 7 | 17,960 | 51,900 | 17,960 | 129,600 | 223,200 | 23,480 | 10,560 | 4,740 | 13,300 | 8,850 | 26,330 | 25,190 |
| 8 | 17,960 | 57,500 | 19,550 | 118,200 | 174,500 | 23,480 | 10,200 | 4,740 | 11,310 | 8,850 | 21,770 | 23,480 |
| 9 | 17,960 | 58,400 | 24,620 | 103,500 | 136,600 | 23,480 | 9,520 | 4,500 | 10,560 | 8,850 | 20,650 | 23,480 |
| 10 | 17,960 | 75,500 | 77,300 | 110,300 | 107,800 | 21,770 | 9,520 | 4,500 | 9,520 | 8,540 | 17,960 | 22,340 |
| 11 | 15,510 | 99,200 | 183,600 | 138,400 | 86,500 | 19,550 | 9,520 | 4,070 | 9,520 | 8,540 | 17,960 | 21,770 |
| 12 | 15,510 | 167,100 | 209,200 | 127,800 | 71,000 | 19,010 | 9,520 | 4,070 | 10,560 | 8,540 | 16,950 | 21,770 |
| 13 | 14,160 | 95,100 | 221,300 | 110,300 | 60,000 | 17,960 | 9,520 | 3,680 | 13,300 | 7,940 | 16,460 | 21,770 |
| 14 | 14,160 | 77,300 | 223,200 | 99,200 | 51,900 | 16,460 | 9,520 | 3,680 | 13,300 | 10,560 | 14,600 | 17,960 |
| 15 | 14,160 | 61,700 | 193,000 | 93,400 | 47,800 | 14,160 | 11,310 | 3,680 | 12,100 | 46,200 | 14,160 | 13,300 |
| 16 | 13,300 | 55,900 | 178,900 | 105,200 | 45,400 | 13,300 | 12,100 | 3,500 | 13,300 | 57,500 | 13,300 | 15,510 |
| 17 | 13,300 | 99,200 | 147,200 | 118,200 | 66,600 | 12,500 | 12,100 | 3,500 | 17,960 | 55,900 | 12,500 | 16,950 |
| 18 | 13,300 | 82,000 | 118,200 | 119,000 | 112,000 | 12,100 | 10,560 | 3,500 | 19,550 | 39,900 | 12,100 | 64,100 |
| 19 | 13,300 | 65,800 | 92,600 | 99,200 | 134,000 | 11,310 | 10,560 | 3,500 | 42,200 | 34,300 | 11,310 | 118,200 |
| 20 | 13,300 | 57,500 | 80,100 | 84,700 | 120,800 | 11,310 | 10,560 | 4,740 | 31,500 | 28,130 | 11,310 | 88,300 |
| 21 | 13,300 | 46,200 | 66,600 | 86,500 | 96,700 | 11,310 | 10,560 | 4,500 | 26,330 | 23,480 | 10,560 | 68,400 |
| 22 | 13,300 | 39,900 | 61,700 | 138,400 | 86,500 | 10,200 | 9,520 | 4,070 | 21,770 | 17,960 | 10,200 | 66,600 |
| 23 | 13,300 | 29,430 | 62,500 | 154,400 | 72,800 | 10,200 | 8,850 | 3,680 | 17,960 | 17,960 | 10,200 | 42,200 |
| 24 | 13,300 | 23,480 | 83,800 | 147,200 | 61,700 | 11,310 | 8,540 | 3,680 | 16,460 | 16,460 | 10,560 | 35,000 |
| 25 | 13,300 | 23,480 | 90,800 | 119,000 | 58,400 | 11,310 | 7,940 | 3,500 | 16,460 | 15,510 | 10,560 | 34,300 |
| 26 | 13,300 | 23,480 | 99,200 | 97,600 | 50,200 | 13,300 | 7,370 | 3,680 | 14,600 | 15,510 | 10,200 | 34,300 |
| 27 | 13,300 | 22,340 | 127,800 | 83,800 | 43,800 | 15,510 | 7,090 | 4,070 | 13,300 | 15,510 | 10,200 | 49,400 |
| 28 | 13,300 | 20,650 | 114,600 | 71,000 | 41,400 | 17,960 | 7,090 | 4,070 | 13,300 | 13,300 | 11,310 | 66,600 |
| 29 | 13,300 | ----- | 101,000 | 62,500 | 38,500 | 20,650 | 12,100 | 6,550 | 13,300 | 13,300 | 21,770 | 65,800 |
| 30 | 16,460 | ----- | 101,000 | 54,300 | 35,000 | 17,960 | 6,020 | 23,480 | 13,300 | 13,300 | 31,500 | 54,300 |
| 31 | 17,960 | ----- | 77,300 | ----- | 31,500 | ----- | 6,020 | 24,620 | ----- | 14,600 | ----- | 46,200 |
| 1894. | | | | | | | | | | | | |
| 1 | 43,800 | 16,950 | 25,190 | 34,300 | 45,400 | 129,600 | 19,010 | 7,090 | 3,500 | 12,500 | 53,500 | 16,950 |
| 2 | 43,800 | 16,460 | 27,510 | 31,500 | 43,800 | 132,300 | 16,950 | 7,090 | 3,500 | 12,100 | 55,900 | 16,460 |
| 3 | 36,400 | 15,510 | 29,430 | 29,430 | 38,500 | 123,400 | 16,460 | 8,540 | 3,500 | 10,200 | 58,400 | 17,960 |
| 4 | 31,500 | 14,600 | 32,900 | 26,330 | 34,300 | 113,800 | 15,510 | 9,520 | 3,500 | 10,200 | 95,100 | 22,340 |
| 5 | 29,430 | 14,160 | 37,800 | 25,190 | 29,430 | 110,300 | 13,300 | 10,560 | 3,160 | 8,850 | 97,600 | 29,430 |
| 6 | 27,510 | 13,300 | 62,500 | 23,480 | 25,190 | 101,800 | 13,300 | 10,200 | 3,160 | 8,850 | 96,700 | 50,800 |
| 7 | 28,130 | 13,300 | 97,600 | 22,340 | 26,330 | 82,000 | 12,100 | 9,520 | 3,500 | 8,540 | 89,200 | 30,800 |
| 8 | 54,300 | 13,000 | 162,600 | 21,770 | 27,510 | 68,400 | 12,100 | 9,520 | 3,500 | 8,540 | 86,500 | 27,510 |
| 9 | 55,900 | 14,160 | 177,100 | 20,650 | 29,430 | 60,000 | 11,310 | 7,090 | 3,680 | 7,940 | 77,300 | 23,480 |
| 10 | 45,400 | 29,430 | 153,500 | 20,650 | 29,430 | 51,900 | 10,560 | 7,090 | 6,550 | 8,540 | 68,400 | 23,480 |
| 11 | 32,900 | 51,900 | 112,000 | 21,770 | 29,430 | 46,200 | 10,200 | 7,090 | 12,500 | 14,160 | 60,000 | 27,510 |
| 12 | 27,510 | 68,400 | 135,800 | 23,480 | 24,620 | 36,400 | 9,520 | 6,550 | 9,520 | 50,200 | 57,500 | 35,400 |
| 13 | 17,960 | 62,500 | 89,200 | 26,330 | 22,340 | 32,900 | 8,850 | 6,550 | 8,540 | 61,700 | 46,200 | 41,400 |
| 14 | 25,190 | 45,400 | 86,500 | 31,500 | 20,650 | 31,500 | 8,850 | 6,550 | 7,940 | 53,500 | 43,800 | 64,100 |
| 15 | 25,190 | 41,400 | 75,500 | 74,600 | 17,960 | 31,500 | 8,540 | 6,550 | 7,940 | 46,200 | 36,400 | 71,000 |
| 16 | 21,770 | 31,500 | 65,800 | 96,700 | 17,960 | 30,800 | 8,540 | 6,550 | 7,370 | 38,500 | 35,000 | 74,600 |
| 17 | 19,550 | 27,510 | 60,000 | 122,500 | 16,460 | 28,130 | 7,940 | 6,550 | 7,090 | 34,300 | 31,500 | 64,100 |
| 18 | 21,770 | 27,510 | 53,500 | 122,500 | 16,460 | 25,190 | 7,370 | 6,550 | 7,090 | 31,500 | 29,430 | 54,300 |
| 19 | 21,770 | 27,510 | 49,400 | 112,000 | 16,460 | 23,480 | 7,090 | 6,020 | 14,600 | 28,200 | 26,330 | 46,200 |
| 20 | 23,480 | 38,500 | 45,400 | 95,100 | 57,500 | 29,430 | 7,090 | 6,020 | 37,800 | 23,400 | 25,190 | 41,400 |
| 21 | 21,770 | 62,500 | 43,800 | 82,000 | 263,600 | 28,130 | 7,090 | 5,760 | 51,900 | 20,610 | 24,620 | 37,800 |
| 22 | 21,770 | 57,500 | 41,400 | 112,000 | 543,500 | 24,620 | 7,090 | 5,760 | 60,000 | 17,780 | 26,330 | 34,300 |
| 23 | 19,010 | 54,300 | 43,800 | 127,800 | 405,100 | 21,770 | 6,550 | 5,240 | 62,500 | 16,460 | 25,190 | 30,800 |
| 24 | 16,950 | 41,400 | 46,200 | 131,400 | 236,600 | 17,960 | 7,090 | 5,240 | 49,400 | 14,600 | 23,480 | 29,430 |
| 25 | 16,950 | 27,510 | 60,000 | 136,600 | 171,700 | 17,960 | 7,940 | 5,240 | 36,400 | 16,460 | 23,480 | 27,510 |
| 26 | 16,950 | 22,340 | 86,500 | 120,800 | 162,600 | 19,550 | 8,850 | 5,240 | 28,130 | 30,800 | 21,770 | 24,620 |
| 27 | 16,950 | 16,460 | 74,600 | 90,800 | 168,000 | 19,010 | 9,520 | 4,740 | 23,480 | 47,800 | 19,550 | 23,480 |
| 28 | 17,960 | 17,960 | 60,000 | 68,400 | 129,600 | 19,550 | 9,520 | 4,740 | 19,010 | 49,400 | 19,010 | 23,420 |
| 29 | 19,010 | ----- | 50,200 | 58,400 | 101,800 | 16,950 | 8,850 | 4,500 | 15,510 | 41,400 | 19,010 | 36,400 |
| 30 | 19,010 | ----- | 41,400 | 51,900 | 86,500 | 20,650 | 7,370 | 4,070 | 14,160 | 36,400 | 17,960 | 31,500 |
| 31 | 17,960 | ----- | 36,400 | ----- | 95,100 | ----- | 7,090 | 3,680 | ----- | 32,900 | ----- | 31,500 |

Mean daily discharge, in second-feet, of Susquehanna River at Harrisburg, Pa., 1891-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|---------|---------|---------|---------|--------|--------|--------|--------|--------|---------|---------|--------|
| 1895. | | | | | | | | | | | | |
| 1 | 35,000 | 22,340 | 68,400 | 64,100 | 28,130 | 19,550 | 21,770 | 4,500 | 5,240 | 3,680 | 3,000 | 24,620 |
| 2 | 36,400 | 21,770 | 113,800 | 62,500 | 27,510 | 19,010 | 19,550 | 4,740 | 5,240 | 3,680 | 3,000 | 24,620 |
| 3 | 39,900 | 23,480 | 105,200 | 71,000 | 26,330 | 17,960 | 22,340 | 4,740 | 4,740 | 3,500 | 3,160 | 20,650 |
| 4 | 41,400 | 23,480 | 147,200 | 83,800 | 23,480 | 15,510 | 17,960 | 4,740 | 4,740 | 3,500 | 3,160 | 17,960 |
| 5 | 41,400 | 86,500 | 101,000 | 80,100 | 20,650 | 14,160 | 15,510 | 4,500 | 4,500 | 3,500 | 3,500 | 15,510 |
| 6 | 41,400 | 62,500 | 97,600 | 71,000 | 19,550 | 12,500 | 13,300 | 4,070 | 4,500 | 3,500 | 3,680 | 13,300 |
| 7 | 41,400 | 64,100 | 80,100 | 68,400 | 17,960 | 12,100 | 12,500 | 4,070 | 5,240 | 3,500 | 3,680 | 12,500 |
| 8 | 43,800 | 62,500 | 72,800 | 64,100 | 16,950 | 11,310 | 11,310 | 5,760 | 5,240 | 3,160 | 3,680 | 12,500 |
| 9 | 47,800 | 60,000 | 65,800 | 105,200 | 15,510 | 11,310 | 10,200 | 5,240 | 4,740 | 3,160 | 3,680 | 12,500 |
| 10 | 71,000 | 60,000 | 71,000 | 174,500 | 20,650 | 10,200 | 9,520 | 6,550 | 4,070 | 3,000 | 3,680 | 12,100 |
| 11 | 93,400 | 61,700 | 71,000 | 205,400 | 23,480 | 8,540 | 9,520 | 7,090 | 6,550 | 3,000 | 3,680 | 9,520 |
| 12 | 101,000 | 66,600 | 74,600 | 183,600 | 27,510 | 8,850 | 8,850 | 7,090 | 9,520 | 3,000 | 3,870 | 9,520 |
| 13 | 112,000 | 65,800 | 71,000 | 154,400 | 31,500 | 8,540 | 8,540 | 7,090 | 10,200 | 3,500 | 4,070 | 6,280 |
| 14 | 101,000 | 65,800 | 68,400 | 129,600 | 41,400 | 7,940 | 8,540 | 6,020 | 8,850 | 3,330 | 4,500 | 5,240 |
| 15 | 82,000 | 62,500 | 77,300 | 138,400 | 41,400 | 7,940 | 7,940 | 8,540 | 6,550 | 3,330 | 4,500 | 6,550 |
| 16 | 72,800 | 61,700 | 82,000 | 134,000 | 38,500 | 7,940 | 7,940 | 8,540 | 5,760 | 3,160 | 4,500 | 6,550 |
| 17 | 64,100 | 60,000 | 80,100 | 116,400 | 37,800 | 7,940 | 7,940 | 7,090 | 4,740 | 3,160 | 4,740 | 5,840 |
| 18 | 58,400 | 60,000 | 74,600 | 96,700 | 31,500 | 7,940 | 6,550 | 6,550 | 4,500 | 3,680 | 5,760 | 8,540 |
| 19 | 51,900 | 57,500 | 62,500 | 80,100 | 29,430 | 7,940 | 6,020 | 6,550 | 4,740 | 4,500 | 6,550 | 8,540 |
| 20 | 43,800 | 55,900 | 60,000 | 68,400 | 27,510 | 7,940 | 6,020 | 6,020 | 4,740 | 4,070 | 6,550 | 8,540 |
| 21 | 42,200 | 54,300 | 57,500 | 60,000 | 25,190 | 7,370 | 5,760 | 5,760 | 4,740 | 3,680 | 6,020 | 9,520 |
| 22 | 41,400 | 53,500 | 54,300 | 51,900 | 24,620 | 6,550 | 5,760 | 4,500 | 4,500 | 3,680 | 5,500 | 12,100 |
| 23 | 36,400 | 51,900 | 51,900 | 45,400 | 22,340 | 5,240 | 5,760 | 4,070 | 4,500 | 3,500 | 4,740 | 13,300 |
| 24 | 36,400 | 50,200 | 51,900 | 41,400 | 20,650 | 5,240 | 5,760 | 4,070 | 4,500 | 3,160 | 5,240 | 19,550 |
| 25 | 27,510 | 47,800 | 51,900 | 36,400 | 19,010 | 5,240 | 5,760 | 3,680 | 4,500 | 3,160 | 5,240 | 20,650 |
| 26 | 26,330 | 45,400 | 65,800 | 32,900 | 17,960 | 9,520 | 5,760 | 3,500 | 4,070 | 3,000 | 5,240 | 21,770 |
| 27 | 24,620 | 43,800 | 103,500 | 30,800 | 17,960 | 9,520 | 5,760 | 3,500 | 4,070 | 2,850 | 5,240 | 27,510 |
| 28 | 24,620 | 47,800 | 120,800 | 32,900 | 16,950 | 9,520 | 5,760 | 3,500 | 3,680 | 2,710 | 19,550 | 29,430 |
| 29 | 24,620 | ----- | 103,500 | 32,900 | 16,950 | 13,300 | 5,240 | 3,500 | 3,680 | 2,710 | 21,770 | 53,500 |
| 30 | 26,330 | ----- | 89,200 | 29,430 | 24,620 | 29,430 | 4,500 | 3,500 | 3,680 | 2,570 | 21,770 | 62,500 |
| 31 | 23,480 | ----- | 74,600 | ----- | 23,480 | ----- | 3,680 | 4,070 | ----- | 2,570 | ----- | 62,500 |
| 1896. | | | | | | | | | | | | |
| 1 | 136,600 | 43,800 | 89,200 | 223,200 | 23,480 | 9,520 | 19,550 | 46,200 | 3,500 | 58,400 | 14,160 | 35,000 |
| 2 | 123,400 | 32,900 | 123,400 | 223,200 | 23,480 | 9,520 | 16,950 | 41,400 | 3,500 | 39,900 | 12,500 | 35,000 |
| 3 | 110,300 | 30,800 | 134,000 | 207,200 | 21,770 | 11,310 | 14,160 | 34,900 | 3,500 | 36,400 | 12,100 | 34,900 |
| 4 | 77,300 | 30,800 | 110,300 | 180,800 | 21,770 | 12,100 | 12,100 | 32,900 | 3,500 | 25,190 | 12,100 | 27,510 |
| 5 | 53,500 | 29,430 | 89,200 | 147,200 | 19,550 | 10,560 | 11,310 | 31,500 | 3,160 | 19,550 | 12,100 | 23,480 |
| 6 | 36,400 | 36,400 | 60,000 | 118,200 | 17,960 | 10,560 | 10,560 | 30,800 | 3,160 | 14,160 | 90,800 | 20,650 |
| 7 | 34,300 | 165,300 | 51,900 | 90,800 | 16,950 | 10,560 | 14,600 | 17,960 | 3,160 | 12,100 | 140,100 | 19,550 |
| 8 | 23,480 | 153,600 | 47,800 | 77,300 | 14,600 | 10,200 | 13,300 | 16,460 | 3,160 | 10,560 | 99,200 | 17,960 |
| 9 | 46,200 | 144,500 | 43,800 | 71,000 | 14,160 | 8,850 | 12,500 | 16,460 | 3,160 | 9,520 | 77,300 | 17,960 |
| 10 | 41,400 | 112,000 | 49,400 | 65,800 | 13,300 | 11,310 | 16,460 | 15,510 | 3,160 | 9,520 | 62,500 | 19,550 |
| 11 | 37,800 | 83,800 | 53,500 | 60,000 | 13,300 | 17,960 | 20,650 | 15,510 | 3,160 | 9,520 | 47,800 | 28,130 |
| 12 | 36,400 | 57,500 | 46,200 | 60,000 | 12,500 | 19,010 | 20,650 | 13,300 | 3,160 | 9,520 | 42,200 | 32,900 |
| 13 | 35,000 | 50,200 | 36,400 | 68,400 | 11,310 | 28,130 | 17,960 | 12,100 | 3,160 | 12,500 | 38,500 | 36,400 |
| 14 | 36,400 | 39,900 | 29,430 | 75,500 | 10,560 | 26,330 | 14,600 | 10,560 | 3,500 | 92,600 | 36,400 | 39,900 |
| 15 | 34,300 | 32,900 | 19,550 | 103,500 | 10,560 | 22,340 | 13,300 | 10,560 | 3,500 | 86,500 | 34,300 | 34,300 |
| 16 | 34,300 | 32,900 | 19,550 | 110,300 | 11,310 | 19,010 | 12,100 | 10,200 | 3,500 | 129,600 | 31,500 | 31,500 |
| 17 | 32,900 | 34,300 | 16,460 | 106,000 | 10,200 | 19,010 | 10,560 | 10,200 | 4,070 | 97,600 | 29,430 | 28,130 |
| 18 | 30,800 | 30,800 | 17,960 | 92,600 | 9,520 | 21,770 | 10,200 | 10,200 | 4,070 | 61,700 | 27,510 | 24,620 |
| 19 | 31,500 | 22,340 | 25,190 | 83,800 | 9,520 | 19,550 | 10,560 | 8,540 | 4,500 | 49,400 | 25,190 | 22,340 |
| 20 | 36,400 | 23,480 | 36,400 | 74,600 | 9,520 | 23,480 | 10,560 | 7,940 | 4,500 | 37,800 | 23,480 | 19,010 |
| 21 | 31,500 | 16,460 | 68,400 | 64,100 | 9,520 | 25,190 | 12,500 | 6,550 | 4,740 | 30,800 | 21,770 | 16,460 |
| 22 | 29,430 | 31,500 | 64,100 | 55,900 | 8,850 | 23,480 | 10,560 | 5,760 | 5,760 | 28,130 | 19,550 | 13,300 |
| 23 | 29,430 | 58,400 | 64,100 | 49,400 | 8,850 | 16,950 | 10,200 | 5,760 | 7,370 | 26,330 | 19,010 | 13,300 |
| 24 | 29,430 | 58,400 | 72,800 | 45,400 | 8,850 | 16,460 | 10,560 | 5,760 | 7,370 | 23,480 | 17,960 | 9,520 |
| 25 | 33,400 | 28,130 | 61,700 | 41,400 | 8,540 | 15,510 | 10,560 | 5,760 | 6,020 | 23,480 | 17,960 | 9,520 |
| 26 | 90,800 | 29,430 | 51,900 | 37,800 | 7,940 | 19,550 | 11,310 | 5,240 | 5,240 | 23,480 | 16,460 | 9,520 |
| 27 | 92,600 | 31,500 | 55,900 | 36,400 | 7,370 | 47,800 | 12,500 | 5,240 | 4,500 | 20,650 | 16,460 | 9,520 |
| 28 | 71,000 | 25,190 | 70,100 | 30,800 | 7,940 | 36,400 | 17,960 | 4,740 | 4,070 | 19,550 | 16,950 | 9,520 |
| 29 | 68,400 | 25,190 | 77,300 | 28,130 | 9,520 | 29,430 | 17,960 | 4,500 | 3,680 | 17,960 | 19,550 | 8,540 |
| 30 | 64,100 | ----- | 125,200 | 26,330 | 9,520 | 24,620 | 32,900 | 4,070 | 6,760 | 16,950 | 29,430 | 10,200 |
| 31 | 58,400 | ----- | 183,600 | ----- | 9,520 | ----- | 41,400 | 3,500 | ----- | 15,510 | ----- | 11,310 |

Mean daily discharge, in second-feet, of Susquehanna River at Harrisburg, Pa.,
1891-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|---------|---------|---------|---------|---------|--------|--------|--------|--------|---------|---------|---------|
| 1897. | | | | | | | | | | | | |
| 1. | 12,100 | 27,510 | 39,900 | 51,900 | 24,620 | 22,340 | 8,850 | 36,400 | 7,940 | 11,310 | 4,740 | 51,900 |
| 2. | 13,300 | 25,190 | 31,500 | 46,200 | 24,620 | 21,770 | 8,540 | 41,400 | 7,090 | 9,520 | 4,370 | 43,800 |
| 3. | 13,300 | 25,190 | 26,330 | 41,400 | 60,000 | 19,550 | 7,940 | 34,300 | 6,550 | 8,540 | 24,620 | 36,400 |
| 4. | 14,160 | 25,190 | 34,300 | 38,500 | 77,300 | 19,010 | 7,940 | 26,330 | 6,550 | 7,370 | 37,800 | 32,900 |
| 5. | 17,960 | 24,620 | 50,200 | 36,400 | 95,100 | 19,550 | 7,940 | 21,770 | 6,550 | 7,090 | 29,430 | 27,510 |
| 6. | 23,480 | 23,480 | 66,600 | 34,300 | 88,300 | 23,480 | 7,940 | 19,550 | 6,020 | 6,550 | 24,620 | 47,800 |
| 7. | 31,500 | 39,900 | 97,600 | 32,900 | 86,500 | 19,550 | 8,850 | 16,950 | 5,760 | 6,550 | 23,480 | 54,300 |
| 8. | 31,500 | 95,100 | 113,800 | 32,900 | 74,600 | 17,960 | 8,850 | 19,550 | 5,760 | 6,020 | 20,650 | 53,500 |
| 9. | 31,500 | 79,200 | 103,500 | 32,900 | 60,000 | 19,550 | 7,940 | 17,960 | 5,760 | 5,760 | 17,960 | 58,400 |
| 10. | 27,510 | 58,400 | 84,700 | 66,600 | 49,400 | 19,550 | 7,940 | 14,160 | 4,740 | 4,740 | 16,950 | 50,200 |
| 11. | 24,620 | 49,400 | 77,300 | 120,800 | 43,800 | 19,550 | 7,370 | 14,160 | 4,500 | 4,740 | 19,550 | 41,400 |
| 12. | 21,770 | 43,800 | 90,800 | 129,600 | 36,400 | 19,550 | 7,090 | 13,300 | 4,740 | 4,500 | 19,550 | 38,500 |
| 13. | 16,950 | 35,000 | 114,600 | 103,500 | 36,400 | 24,620 | 6,550 | 12,100 | 4,740 | 5,240 | 17,960 | 38,500 |
| 14. | 13,300 | 34,300 | 110,300 | 83,800 | 68,400 | 29,430 | 7,090 | 11,310 | 4,740 | 5,240 | 17,960 | 41,400 |
| 15. | 13,300 | 34,300 | 99,200 | 68,400 | 99,200 | 26,330 | 6,550 | 10,200 | 4,070 | 5,240 | 17,960 | 45,400 |
| 16. | 13,300 | 29,430 | 86,500 | 68,400 | 101,800 | 22,340 | 6,550 | 10,200 | 4,500 | 5,240 | 17,960 | 79,200 |
| 17. | 13,300 | 29,430 | 84,700 | 79,200 | 92,600 | 19,550 | 7,370 | 9,520 | 4,740 | 4,740 | 17,960 | 97,600 |
| 18. | 14,600 | 27,510 | 60,000 | 86,500 | 77,300 | 17,960 | 7,370 | 9,520 | 5,240 | 4,740 | 19,550 | 106,000 |
| 19. | 16,460 | 30,800 | 51,900 | 79,200 | 64,100 | 15,510 | 7,090 | 8,850 | 5,240 | 4,500 | 22,340 | 92,500 |
| 20. | 13,300 | 37,800 | 50,500 | 68,400 | 51,900 | 14,600 | 7,090 | 8,850 | 4,740 | 4,500 | 23,130 | 74,600 |
| 21. | 12,100 | 36,400 | 93,400 | 60,000 | 39,900 | 14,600 | 9,520 | 8,540 | 4,500 | 4,070 | 26,330 | 61,700 |
| 22. | 12,100 | 39,900 | 107,800 | 50,200 | 39,900 | 14,600 | 9,520 | 7,370 | 4,500 | 5,240 | 25,190 | 51,900 |
| 23. | 12,500 | 66,600 | 134,000 | 43,800 | 30,800 | 13,300 | 8,540 | 7,370 | 4,500 | 5,240 | 21,770 | 37,800 |
| 24. | 10,560 | 101,800 | 129,600 | 38,500 | 29,430 | 12,100 | 8,850 | 7,940 | 6,550 | 5,240 | 17,960 | 34,300 |
| 25. | 10,560 | 95,100 | 141,000 | 34,300 | 32,900 | 11,310 | 10,200 | 10,560 | 9,520 | 6,550 | 17,960 | 28,130 |
| 26. | 9,520 | 77,300 | 165,300 | 31,500 | 32,900 | 11,310 | 11,310 | 19,550 | 9,520 | 6,550 | 17,960 | 21,770 |
| 27. | 27,510 | 60,000 | 149,900 | 30,800 | 29,430 | 10,560 | 11,310 | 14,160 | 12,100 | 6,550 | 16,460 | 20,650 |
| 28. | 27,510 | 43,800 | 103,500 | 29,430 | 30,800 | 10,200 | 14,600 | 11,310 | 12,500 | 6,020 | 17,960 | 19,550 |
| 29. | 23,480 | ----- | 93,400 | 27,510 | 35,000 | 10,200 | 34,300 | 10,200 | 15,510 | 5,760 | 29,430 | 19,550 |
| 30. | 26,330 | ----- | 74,600 | 25,190 | 29,430 | 9,520 | 43,800 | 9,520 | 13,300 | 5,240 | 50,200 | 19,010 |
| 31. | 27,510 | ----- | 61,700 | ----- | 26,330 | ----- | 37,800 | 8,540 | ----- | 5,240 | ----- | 17,960 |
| 1898. | | | | | | | | | | | | |
| 1. | 19,550 | 35,000 | 46,200 | 114,600 | 68,400 | 41,400 | 13,300 | 8,850 | 19,550 | 5,240 | 46,200 | 24,620 |
| 2. | 16,460 | 28,130 | 41,400 | 93,400 | 58,400 | 38,500 | 14,600 | 9,520 | 16,460 | 5,240 | 36,400 | 25,190 |
| 3. | 14,600 | 23,480 | 38,500 | 75,500 | 49,400 | 35,000 | 13,300 | 8,850 | 23,480 | 4,740 | 31,500 | 24,620 |
| 4. | 19,550 | 19,550 | 35,000 | 64,100 | 46,200 | 30,800 | 11,310 | 16,460 | 17,960 | 4,740 | 29,430 | 23,480 |
| 5. | 12,500 | 19,550 | 31,500 | 58,400 | 42,200 | 27,510 | 10,560 | 45,400 | 14,160 | 4,740 | 25,190 | 31,500 |
| 6. | 12,500 | 19,550 | 30,800 | 50,200 | 43,000 | 23,480 | 10,200 | 57,500 | 12,500 | 4,740 | 23,480 | 51,900 |
| 7. | 15,510 | 19,550 | 29,430 | 43,800 | 46,200 | 21,770 | 9,520 | 36,400 | 10,560 | 4,740 | 22,340 | 43,800 |
| 8. | 17,960 | 24,620 | 29,430 | 42,200 | 60,000 | 19,550 | 8,850 | 29,430 | 10,560 | 6,550 | 17,960 | 37,800 |
| 9. | 19,550 | 28,130 | 27,510 | 38,500 | 72,800 | 17,960 | 8,540 | 24,620 | 10,560 | 8,540 | 17,960 | 34,300 |
| 10. | 20,650 | 29,430 | 27,510 | 34,300 | 61,700 | 17,960 | 7,940 | 31,500 | 13,300 | 8,850 | 19,960 | 30,800 |
| 11. | 23,480 | 28,130 | 34,300 | 31,500 | 54,300 | 16,460 | 7,370 | 39,900 | 21,770 | 15,510 | 19,010 | 24,620 |
| 12. | 23,480 | 32,900 | 50,200 | 29,430 | 47,800 | 16,460 | 7,090 | 32,900 | 20,650 | 16,950 | 36,400 | 17,960 |
| 13. | 27,510 | 42,200 | 77,300 | 27,510 | 43,800 | 15,510 | 6,550 | 27,510 | 19,010 | 16,460 | 116,400 | 15,510 |
| 14. | 36,400 | 97,600 | 114,600 | 26,330 | 36,400 | 15,510 | 6,020 | 19,550 | 14,160 | 13,300 | 103,500 | 15,510 |
| 15. | 85,600 | 106,000 | 135,800 | 25,190 | 36,400 | 16,950 | 5,720 | 17,960 | 12,500 | 13,300 | 79,200 | 14,160 |
| 16. | 105,200 | 95,100 | 126,900 | 31,500 | 39,900 | 20,650 | 5,760 | 15,510 | 11,310 | 14,160 | 60,000 | 13,300 |
| 17. | 101,000 | 77,300 | 105,200 | 37,800 | 54,300 | 26,330 | 5,240 | 13,300 | 8,850 | 14,600 | 49,400 | 13,300 |
| 18. | 96,700 | 65,800 | 89,200 | 35,000 | 70,100 | 23,480 | 4,740 | 12,500 | 8,540 | 26,330 | 41,400 | 12,500 |
| 19. | 79,200 | 51,900 | 74,600 | 31,500 | 57,500 | 19,550 | 4,740 | 16,460 | 7,370 | 32,900 | 38,500 | 13,300 |
| 20. | 65,800 | 41,400 | 65,800 | 29,430 | 60,000 | 16,950 | 5,240 | 23,480 | 6,550 | 36,400 | 38,500 | 17,960 |
| 21. | 64,100 | 46,200 | 92,600 | 28,130 | 80,100 | 16,460 | 6,020 | 42,200 | 6,020 | 41,400 | 39,900 | 22,340 |
| 22. | 71,000 | 83,800 | 125,200 | 27,510 | 80,100 | 16,460 | 5,240 | 41,400 | 6,020 | 39,900 | 45,400 | 24,620 |
| 23. | 93,400 | 84,700 | 154,400 | 25,190 | 77,300 | 14,160 | 6,020 | 32,900 | 6,020 | 92,600 | 49,400 | 29,430 |
| 24. | 125,200 | 99,200 | 245,900 | 23,480 | 68,400 | 13,300 | 5,760 | 28,130 | 5,760 | 109,400 | 46,200 | 58,400 |
| 25. | 147,200 | 80,100 | 236,600 | 29,430 | 86,500 | 14,600 | 5,760 | 23,480 | 5,760 | 93,400 | 41,400 | 101,000 |
| 26. | 129,600 | 72,800 | 168,000 | 80,100 | 77,300 | 14,160 | 5,760 | 19,550 | 5,240 | 71,000 | 36,400 | 97,600 |
| 27. | 103,500 | 62,500 | 125,200 | 144,500 | 77,300 | 13,300 | 8,540 | 17,960 | 6,020 | 62,500 | 35,000 | 74,600 |
| 28. | 86,500 | 51,900 | 99,200 | 129,600 | 71,000 | 12,500 | 7,370 | 16,950 | 6,020 | 61,700 | 31,500 | 57,500 |
| 29. | 70,100 | ----- | 80,100 | 106,000 | 64,100 | 12,100 | 12,100 | 38,500 | 5,240 | 62,500 | 29,430 | 49,400 |
| 30. | 60,000 | ----- | 86,500 | 80,100 | 57,500 | 10,560 | 10,200 | 34,300 | 5,240 | 70,100 | 27,510 | 41,400 |
| 31. | 49,400 | ----- | 120,800 | ----- | 50,200 | ----- | 8,540 | 23,480 | ----- | 57,500 | ----- | 34,300 |

Mean daily discharge, in second-feet, of Susquehanna River at Harrisburg, Pa., 1891-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|---------|---------|---------|---------|--------|--------|--------|--------|--------|-------|---------|--------|
| 1899. | | | | | | | | | | | | |
| 1 | 26,330 | 17,960 | 110,300 | 90,800 | 28,130 | 17,960 | 11,310 | 5,240 | 12,100 | 7,090 | 4,070 | 11,310 |
| 2 | 25,190 | 13,300 | 106,000 | 75,500 | 24,620 | 19,010 | 10,560 | 5,240 | 9,520 | 5,760 | 10,560 | 10,200 |
| 3 | 20,650 | 12,500 | 101,000 | 65,800 | 24,620 | 17,960 | 10,560 | 5,240 | 7,940 | 5,760 | 17,960 | 9,520 |
| 4 | 26,330 | 15,510 | 93,400 | 57,500 | 28,130 | 17,960 | 9,520 | 5,240 | 7,090 | 5,240 | 26,330 | 9,520 |
| 5 | 29,430 | 19,010 | 103,500 | 50,200 | 25,190 | 17,960 | 8,540 | 5,240 | 7,090 | 4,740 | 43,800 | 9,520 |
| 6 | 51,900 | 19,550 | 183,600 | 42,200 | 25,190 | 16,460 | 7,940 | 6,020 | 6,550 | 4,740 | 35,000 | 9,520 |
| 7 | 103,500 | 21,770 | 193,000 | 39,900 | 23,480 | 14,160 | 7,940 | 5,240 | 6,020 | 4,500 | 32,900 | 9,520 |
| 8 | 83,800 | 16,950 | 163,500 | 47,800 | 20,650 | 12,500 | 7,370 | 5,240 | 6,020 | 4,500 | 25,190 | 9,520 |
| 9 | 70,100 | 17,960 | 125,200 | 83,800 | 21,770 | 12,500 | 7,370 | 5,760 | 5,760 | 4,500 | 21,770 | 9,520 |
| 10 | 58,400 | 16,950 | 97,600 | 116,400 | 19,550 | 12,500 | 7,370 | 5,240 | 6,550 | 4,740 | 17,960 | 9,520 |
| 11 | 45,400 | 16,950 | 77,300 | 110,300 | 20,650 | 11,310 | 8,850 | 4,740 | 6,550 | 4,500 | 15,510 | 9,520 |
| 12 | 36,400 | 42,200 | 64,100 | 99,200 | 20,650 | 10,560 | 7,940 | 4,740 | 5,240 | 4,500 | 14,600 | 9,520 |
| 13 | 27,510 | 42,200 | 64,100 | 82,000 | 22,340 | 10,560 | 7,370 | 7,090 | 5,760 | 4,070 | 14,160 | 20,650 |
| 14 | 25,190 | 43,400 | 93,400 | 82,000 | 21,770 | 10,200 | 7,370 | 7,090 | 8,850 | 4,070 | 13,300 | 60,000 |
| 15 | 27,510 | 43,400 | 110,300 | 103,500 | 19,010 | 9,520 | 7,370 | 7,940 | 7,940 | 4,070 | 15,510 | 74,600 |
| 16 | 31,500 | 46,200 | 103,500 | 103,500 | 17,960 | 9,520 | 7,090 | 6,020 | 5,760 | 3,680 | 16,950 | 68,400 |
| 17 | 49,400 | 49,400 | 93,400 | 101,000 | 17,960 | 8,850 | 6,550 | 4,740 | 5,240 | 3,680 | 16,950 | 57,500 |
| 18 | 86,500 | 49,400 | 75,500 | 92,600 | 19,010 | 7,940 | 7,940 | 4,740 | 5,240 | 3,680 | 16,950 | 45,400 |
| 19 | 74,600 | 50,200 | 41,400 | 83,800 | 32,900 | 7,940 | 7,940 | 4,070 | 4,500 | 3,680 | 21,770 | 37,800 |
| 20 | 62,500 | 47,800 | 89,200 | 68,400 | 47,800 | 7,940 | 7,940 | 4,070 | 4,740 | 3,500 | 23,480 | 32,900 |
| 21 | 50,200 | 50,200 | 112,000 | 58,400 | 54,300 | 7,370 | 7,940 | 4,070 | 5,240 | 3,500 | 22,340 | 32,900 |
| 22 | 41,400 | 57,500 | 106,000 | 53,500 | 39,900 | 7,090 | 8,540 | 4,070 | 4,740 | 3,500 | 19,010 | 34,300 |
| 23 | 39,900 | 95,100 | 95,100 | 50,200 | 35,000 | 6,550 | 8,540 | 4,070 | 4,740 | 3,500 | 17,960 | 43,800 |
| 24 | 37,800 | 95,100 | 89,200 | 43,800 | 30,800 | 8,850 | 8,540 | 4,070 | 4,740 | 2,850 | 15,510 | 39,900 |
| 25 | 38,500 | 89,200 | 93,400 | 42,200 | 25,190 | 13,300 | 7,370 | 4,070 | 4,740 | 2,850 | 15,510 | 65,800 |
| 26 | 55,900 | 83,800 | 93,400 | 36,400 | 23,480 | 10,560 | 6,550 | 3,680 | 4,740 | 3,160 | 15,510 | 82,000 |
| 27 | 43,800 | 92,600 | 83,800 | 35,000 | 22,340 | 9,520 | 6,550 | 4,740 | 6,550 | 3,500 | 14,600 | 55,900 |
| 28 | 34,300 | 120,800 | 92,600 | 32,900 | 19,550 | 9,520 | 6,550 | 36,400 | 8,540 | 3,500 | 13,300 | 45,400 |
| 29 | 26,330 | ----- | ----- | 31,500 | 17,960 | 11,310 | 6,020 | 19,550 | 7,370 | 3,680 | 13,300 | 34,300 |
| 30 | 23,480 | ----- | 120,800 | 29,430 | 17,960 | ----- | 5,760 | 17,960 | 7,090 | 3,500 | 12,100 | 33,480 |
| 31 | 23,480 | ----- | ----- | ----- | 17,960 | ----- | 5,240 | 14,600 | ----- | 3,500 | ----- | 15,510 |
| 1900. | | | | | | | | | | | | |
| 1 | 12,100 | 22,340 | 36,400 | 38,500 | 36,400 | 19,010 | 7,370 | 7,940 | 6,550 | 2,570 | 5,760 | 86,500 |
| 2 | 10,560 | 12,100 | 194,900 | 36,400 | 32,900 | 17,960 | 7,090 | 6,550 | 6,550 | 2,570 | 5,760 | 65,800 |
| 3 | 43,800 | 35,000 | 180,800 | 38,500 | 29,430 | 16,460 | 6,550 | 6,550 | 5,760 | 2,570 | 5,240 | 55,900 |
| 4 | 50,200 | 36,400 | 129,600 | 42,200 | 27,510 | 14,600 | 7,090 | 6,020 | 7,370 | 2,570 | 5,240 | 43,800 |
| 5 | 49,400 | 46,200 | 101,800 | 57,500 | 24,620 | 17,960 | 8,540 | 5,240 | 6,020 | 2,570 | 5,240 | 51,900 |
| 6 | 55,900 | 41,400 | 84,700 | 68,400 | 21,770 | 19,550 | 7,370 | 4,740 | 5,760 | 2,570 | 4,740 | 90,800 |
| 7 | 60,000 | 60,000 | 68,400 | 58,400 | 21,770 | 17,960 | 8,540 | 4,740 | 4,500 | 2,570 | 4,740 | 93,400 |
| 8 | 57,500 | 51,900 | 71,000 | 53,500 | 20,650 | 14,600 | 7,370 | 4,500 | 4,500 | 2,710 | 4,740 | 88,300 |
| 9 | 50,200 | 36,400 | 77,300 | 71,000 | 17,960 | 14,600 | 8,850 | 4,070 | 4,500 | 2,570 | 5,240 | 68,400 |
| 10 | 45,400 | 49,400 | 65,800 | 82,000 | 17,960 | 14,160 | 8,850 | 4,500 | 4,070 | 2,570 | 4,500 | 55,900 |
| 11 | 43,800 | 64,100 | 62,500 | 77,300 | 16,950 | 13,300 | 8,540 | 4,070 | 3,680 | 2,570 | 4,740 | 47,800 |
| 12 | 60,000 | 60,000 | 72,800 | 61,700 | 16,460 | 13,300 | 7,370 | 3,500 | 3,500 | 2,570 | 4,070 | 37,800 |
| 13 | 50,200 | 62,500 | 64,100 | 51,900 | 16,950 | 12,500 | 7,090 | 3,500 | 2,850 | 3,160 | 4,500 | 34,300 |
| 14 | 55,900 | 97,600 | 46,200 | 43,800 | 16,950 | 12,500 | 7,090 | 3,160 | 3,160 | 5,760 | 5,240 | 30,800 |
| 15 | 55,900 | 103,500 | 43,800 | 41,400 | 17,960 | 13,300 | 6,550 | 2,850 | 3,160 | 5,760 | 4,740 | 22,340 |
| 16 | 55,900 | 107,800 | 36,400 | 43,800 | 16,950 | 14,600 | 6,550 | 2,850 | 3,160 | 5,240 | 4,740 | 21,770 |
| 17 | 46,200 | 93,400 | 31,500 | 42,200 | 16,460 | 14,600 | 6,550 | 3,160 | 3,160 | 4,500 | 5,760 | 15,510 |
| 18 | 51,900 | 68,400 | 25,190 | 41,400 | 16,460 | 13,300 | 7,090 | 2,850 | 2,850 | 4,740 | 6,020 | 14,160 |
| 19 | 49,400 | 47,800 | 23,480 | 53,500 | 15,510 | 12,100 | 6,020 | 2,850 | 2,710 | 4,740 | 5,240 | 14,160 |
| 20 | 36,400 | 35,000 | 23,480 | 88,300 | 17,960 | 12,100 | 6,020 | 2,850 | 2,710 | 4,500 | 6,020 | 14,160 |
| 21 | 39,900 | 14,600 | 35,000 | 92,600 | 22,340 | 11,700 | 5,760 | 3,500 | 2,710 | 4,070 | 6,020 | 13,300 |
| 22 | 149,900 | 30,800 | 83,800 | 83,800 | 14,600 | 11,310 | 5,240 | 3,680 | 2,570 | 4,070 | 6,020 | 14,600 |
| 23 | 174,500 | 129,600 | 83,800 | 70,100 | 21,770 | 11,310 | 5,240 | 5,760 | 2,570 | 4,070 | 5,760 | 16,950 |
| 24 | 123,400 | 159,000 | 68,400 | 65,800 | 19,010 | 10,200 | 5,240 | 4,070 | 2,570 | 4,070 | 6,550 | 14,600 |
| 25 | 90,800 | 134,000 | 64,100 | 68,400 | 16,950 | 8,850 | 5,240 | 7,940 | 2,570 | 6,550 | 7,090 | 16,460 |
| 26 | 70,100 | 83,800 | 65,800 | 72,800 | 15,510 | 8,540 | 5,760 | 6,550 | 2,440 | 7,090 | 10,560 | 16,950 |
| 27 | 51,900 | 60,000 | 60,000 | 64,100 | 14,600 | 8,540 | 5,520 | 7,370 | 2,440 | 6,550 | 66,600 | 13,300 |
| 28 | 43,800 | 43,800 | 55,900 | 53,500 | 13,300 | 8,540 | 7,940 | 9,520 | 2,330 | 7,940 | 194,000 | 19,550 |
| 29 | 37,800 | ----- | 49,400 | 45,400 | 13,300 | 8,540 | 7,940 | 8,540 | 2,330 | 7,370 | 180,800 | 22,340 |
| 30 | 27,510 | ----- | 43,800 | 38,500 | 13,300 | 7,370 | 8,850 | 6,550 | 2,570 | 6,550 | 119,000 | 19,010 |
| 31 | 17,960 | ----- | 42,200 | ----- | 12,500 | ----- | 7,940 | 7,090 | ----- | 6,020 | ----- | 17,960 |

*Mean daily discharge, in second-feet, of Susquehanna River at Harrisburg, Pa.,
1891-1904—Continued.*

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|---------|---------|---------|---------|---------|---------|---------|---------|--------|--------|--------|---------|
| 1901. | | | | | | | | | | | | |
| 1 | 15,510 | 19,000 | 11,310 | 89,200 | 54,300 | 185,500 | 24,620 | 10,560 | 29,430 | 14,160 | 8,850 | 24,620 |
| 2 | 14,160 | 36,400 | 10,560 | 68,400 | 45,400 | 145,400 | 21,770 | 12,100 | 32,900 | 16,950 | 8,850 | 23,480 |
| 3 | 10,560 | 27,580 | 11,310 | 62,500 | 43,800 | 119,000 | 19,010 | 11,310 | 47,800 | 16,460 | 8,540 | 20,650 |
| 4 | 10,560 | 26,360 | 12,100 | 72,800 | 42,200 | 101,000 | 16,460 | 10,200 | 54,300 | 16,460 | 8,540 | 20,650 |
| 5 | 11,310 | 26,360 | 16,460 | 95,100 | 54,300 | 89,200 | 15,510 | 9,520 | 49,400 | 16,460 | 7,940 | 24,620 |
| 6 | 10,560 | 24,570 | 17,960 | 101,000 | 51,900 | 74,600 | 14,600 | 7,940 | 38,500 | 16,950 | 7,940 | 19,550 |
| 7 | 8,850 | 25,160 | 19,010 | 114,600 | 45,400 | 60,000 | 16,460 | 10,560 | 30,800 | 14,600 | 7,940 | 20,650 |
| 8 | 7,370 | 25,160 | 17,960 | 163,500 | 37,800 | 60,000 | 14,600 | 19,010 | 25,190 | 12,100 | 7,370 | 15,510 |
| 9 | 9,520 | 25,160 | 23,480 | 188,400 | 32,900 | 68,400 | 14,160 | 20,650 | 21,770 | 11,310 | 7,370 | 14,600 |
| 10 | 9,520 | 23,400 | 26,330 | 165,300 | 31,500 | 64,100 | 14,160 | 17,960 | 17,960 | 11,310 | 7,370 | 19,010 |
| 11 | 10,560 | 21,700 | 75,500 | 138,400 | 28,130 | 60,000 | 13,300 | 16,460 | 17,960 | 10,560 | 7,370 | 43,800 |
| 12 | 13,300 | 22,250 | 169,800 | 114,600 | 34,300 | 51,900 | 12,500 | 20,650 | 16,460 | 10,560 | 6,550 | 86,500 |
| 13 | 13,300 | 21,700 | 171,700 | 95,100 | 38,500 | 46,200 | 12,500 | 16,950 | 16,950 | 10,560 | 7,090 | 86,500 |
| 14 | 17,960 | 20,610 | 126,900 | 84,700 | 43,800 | 39,900 | 12,100 | 13,300 | 16,460 | 12,100 | 7,940 | 71,000 |
| 15 | 29,430 | 20,610 | 95,100 | 71,000 | 54,300 | 35,000 | 12,500 | 11,310 | 16,460 | 16,950 | 8,540 | 125,200 |
| 16 | 27,510 | 19,000 | 80,100 | 66,600 | 53,500 | 29,430 | 11,310 | 10,560 | 15,510 | 19,550 | 10,200 | 405,100 |
| 17 | 28,130 | 20,610 | 72,800 | 64,100 | 46,200 | 32,900 | 10,560 | 10,560 | 16,950 | 17,960 | 10,560 | 322,700 |
| 18 | 22,340 | 19,000 | 64,100 | 57,500 | 38,500 | 30,800 | 14,160 | 11,310 | 16,950 | 14,160 | 12,500 | 214,800 |
| 19 | 19,010 | 17,780 | 55,900 | 51,900 | 36,400 | 29,430 | 16,950 | 60,000 | 17,960 | 14,160 | 12,500 | 135,800 |
| 20 | 11,310 | 17,780 | 51,900 | 47,800 | 39,900 | 26,330 | 15,510 | 65,800 | 19,550 | 13,300 | 12,500 | 93,400 |
| 21 | 11,310 | 14,160 | 66,600 | 60,000 | 37,800 | 24,620 | 13,300 | 51,900 | 19,010 | 13,300 | 11,310 | 71,000 |
| 22 | 12,100 | 13,300 | 112,000 | 156,300 | 36,400 | 26,330 | 12,100 | 37,800 | 19,010 | 12,500 | 11,310 | 49,400 |
| 23 | 13,300 | 13,300 | 129,600 | 204,400 | 60,000 | 32,900 | 11,310 | 38,500 | 16,950 | 12,500 | 10,200 | 34,300 |
| 24 | 11,310 | 12,500 | 122,500 | 177,100 | 110,300 | 34,300 | 10,560 | 47,800 | 16,460 | 12,100 | 12,100 | 30,800 |
| 25 | 13,300 | 12,500 | 103,500 | 141,000 | 95,100 | 36,400 | 10,200 | 99,200 | 14,160 | 12,100 | 17,960 | 32,900 |
| 26 | 11,310 | 12,500 | 97,600 | 123,400 | 103,500 | 35,000 | 9,520 | 120,800 | 13,300 | 10,560 | 24,620 | 32,900 |
| 27 | 13,300 | 11,310 | 109,400 | 112,000 | 95,100 | 32,900 | 10,200 | 90,800 | 12,100 | 10,200 | 58,400 | 35,000 |
| 28 | 13,300 | 11,310 | 169,800 | 90,800 | 86,500 | 29,430 | 10,560 | 64,100 | 11,310 | 10,560 | 55,900 | 35,000 |
| 29 | 13,300 | ----- | 191,100 | 77,300 | 116,400 | 26,330 | 9,520 | 47,800 | 10,560 | 9,520 | 36,400 | 35,000 |
| 30 | 11,310 | ----- | 159,000 | 64,100 | 178,900 | 25,190 | 9,520 | 36,400 | 10,560 | 8,850 | 30,800 | 61,700 |
| 31 | 10,560 | ----- | 120,800 | ----- | 210,100 | ----- | 9,520 | 29,430 | ----- | 8,850 | ----- | 72,800 |
| 1902. | | | | | | | | | | | | |
| 1 | 55,900 | 30,800 | 372,800 | 72,800 | 20,650 | 11,310 | 30,800 | 65,800 | 7,940 | 49,400 | 60,000 | 16,950 |
| 2 | 47,800 | 31,500 | 484,100 | 61,700 | 21,770 | 11,310 | 71,000 | 57,500 | 7,940 | 68,400 | 47,800 | 16,950 |
| 3 | 39,900 | 29,430 | 465,300 | 57,500 | 21,770 | 10,560 | 92,000 | 60,000 | 7,940 | 66,600 | 43,800 | 19,010 |
| 4 | 34,300 | 26,330 | 405,100 | 51,900 | 19,550 | 10,560 | 80,100 | 72,800 | 7,940 | 62,500 | 36,400 | 27,510 |
| 5 | 23,480 | 16,950 | 263,600 | 47,800 | 19,550 | 10,560 | 101,000 | 60,000 | 7,370 | 46,200 | 29,430 | 32,900 |
| 6 | 23,480 | 13,300 | 178,900 | 43,800 | 21,770 | 10,560 | 95,100 | 49,400 | 7,090 | 46,200 | 29,430 | 26,330 |
| 7 | 23,480 | 70,100 | 129,600 | 43,800 | 20,650 | 9,520 | 83,800 | 43,800 | 6,550 | 46,200 | 26,330 | 29,430 |
| 8 | 21,770 | 55,900 | 86,500 | 43,800 | 19,550 | 7,940 | 92,600 | 36,400 | 6,020 | 42,200 | 24,620 | 28,130 |
| 9 | 20,650 | 51,900 | 55,900 | 120,800 | 19,550 | 9,520 | 112,000 | 30,800 | 6,020 | 34,300 | 22,340 | 28,130 |
| 10 | 23,480 | 53,500 | 51,900 | 224,200 | 19,550 | 10,200 | 89,200 | 26,330 | 6,020 | 34,300 | 20,650 | 25,190 |
| 11 | 22,340 | 57,500 | 80,100 | 214,800 | 19,550 | 9,520 | 71,000 | 29,430 | 6,020 | 29,430 | 19,550 | 23,480 |
| 12 | 19,550 | 54,300 | 109,400 | 167,100 | 17,960 | 9,520 | 71,000 | 30,800 | 7,940 | 30,800 | 16,950 | 23,480 |
| 13 | 19,010 | 49,400 | 154,400 | 154,400 | 16,950 | 9,520 | 72,800 | 26,330 | 7,940 | 47,800 | 16,950 | 34,300 |
| 14 | 15,510 | 42,200 | 200,600 | 106,000 | 16,460 | 9,520 | 60,000 | 24,620 | 7,090 | 49,400 | 16,460 | 31,500 |
| 15 | 15,510 | 42,200 | 204,400 | 88,200 | 15,510 | 11,310 | 45,400 | 21,770 | 7,370 | 32,900 | 16,460 | 36,400 |
| 16 | 15,510 | 39,900 | 174,500 | 75,500 | 14,600 | 11,310 | 36,400 | 20,650 | 7,090 | 35,000 | 15,510 | 36,400 |
| 17 | 14,600 | 37,800 | 177,100 | 62,500 | 14,600 | 15,510 | 29,430 | 17,960 | 7,090 | 32,900 | 14,600 | 57,500 |
| 18 | 13,300 | 34,300 | 231,000 | 53,500 | 13,300 | 16,950 | 36,330 | 17,960 | 6,550 | 25,190 | 14,600 | 113,800 |
| 19 | 13,300 | 32,900 | 205,400 | 47,800 | 12,100 | 16,950 | 26,330 | 14,000 | 6,550 | 27,510 | 14,600 | 109,400 |
| 20 | 14,600 | 32,900 | 162,600 | 42,200 | 12,100 | 16,460 | 25,190 | 13,900 | 6,550 | 23,480 | 12,500 | 97,600 |
| 21 | 14,600 | 32,900 | 129,600 | 37,800 | 11,310 | 14,600 | 27,510 | 13,900 | 6,550 | 22,340 | 12,100 | 89,200 |
| 22 | 54,300 | 36,400 | 68,400 | 34,300 | 11,310 | 14,600 | 41,400 | 12,500 | 6,020 | 19,550 | 11,310 | 112,000 |
| 23 | 138,400 | 36,400 | 60,000 | 29,430 | 12,100 | 14,600 | 105,200 | 12,500 | 5,760 | 19,010 | 11,310 | 183,600 |
| 24 | 82,000 | 37,800 | 57,500 | 28,130 | 10,560 | 13,300 | 103,500 | 11,310 | 5,760 | 16,950 | 10,560 | 186,400 |
| 25 | 77,300 | 38,500 | 57,500 | 26,330 | 10,560 | 13,300 | 90,800 | 11,310 | 5,760 | 15,510 | 10,560 | 165,300 |
| 26 | 58,400 | 75,500 | 46,200 | 23,480 | 10,560 | 13,300 | 99,200 | 10,200 | 10,560 | 16,950 | 10,560 | 107,800 |
| 27 | 53,500 | 127,800 | 31,500 | 22,340 | 10,560 | 14,600 | 105,200 | 10,200 | 32,900 | 16,460 | 12,500 | 90,800 |
| 28 | 57,500 | 132,300 | 31,500 | 20,650 | 10,560 | 16,950 | 83,800 | 9,520 | 54,300 | 16,460 | 13,300 | 71,000 |
| 29 | 57,500 | ----- | 42,200 | 20,650 | 10,560 | 16,950 | 65,800 | 8,850 | 41,400 | 31,500 | 15,510 | 61,700 |
| 30 | 41,400 | ----- | 42,200 | 20,650 | 10,560 | 23,480 | 71,000 | 7,940 | 41,400 | 31,500 | 16,460 | 49,400 |
| 31 | 35,000 | ----- | 57,500 | ----- | 11,310 | ----- | 71,000 | 7,940 | ----- | 68,400 | 16,950 | 45,400 |

Mean daily discharge, in second-feet, of Susquehanna River at Harrisburg, Pa., 1891-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|---------|---------|---------|---------|--------|--------|--------|---------|---------|---------|--------|---------|
| 1903. | | | | | | | | | | | | |
| 1 | 38,500 | 165,300 | 200,600 | 77,300 | 28,130 | 8,190 | 79,640 | 25,310 | 123,500 | 9,730 | 21,660 | 15,450 |
| 2 | 31,500 | 147,200 | 276,500 | 90,800 | 26,330 | 8,190 | 58,820 | 23,660 | 94,080 | 9,730 | 21,170 | 14,580 |
| 3 | 34,300 | 116,400 | 221,300 | 95,100 | 23,480 | 8,190 | 46,700 | 19,210 | 72,070 | 9,730 | 20,190 | 14,160 |
| 4 | 49,400 | 119,000 | 156,300 | 82,000 | 19,010 | 8,190 | 39,730 | 16,810 | 53,750 | 8,770 | 18,720 | 12,530 |
| 5 | 61,700 | 209,200 | 120,800 | 77,300 | 17,960 | 8,190 | 32,510 | 14,580 | 46,700 | 8,770 | 18,720 | 12,180 |
| 6 | 66,600 | 223,200 | 116,400 | 64,100 | 16,460 | 8,190 | 36,290 | 15,450 | 39,040 | 8,190 | 16,810 | 11,440 |
| 7 | 74,600 | 178,900 | 97,600 | 64,100 | 16,460 | 8,190 | 39,730 | 19,210 | 31,300 | 7,610 | 16,350 | 11,440 |
| 8 | 65,800 | 126,900 | 106,000 | 64,100 | 15,510 | 8,190 | 49,450 | 41,110 | 23,660 | 10,410 | 15,450 | 11,440 |
| 9 | 51,900 | 107,800 | 103,500 | 64,100 | 14,600 | 9,080 | 49,450 | 39,730 | 27,090 | 16,810 | 15,450 | 14,160 |
| 10 | 41,400 | 86,500 | 149,000 | 83,800 | 14,600 | 13,340 | 35,600 | 32,510 | 29,500 | 44,630 | 14,580 | 12,560 |
| 11 | 28,130 | 68,400 | 183,600 | 86,500 | 14,600 | 13,340 | 29,500 | 27,090 | 25,310 | 128,900 | 14,580 | 10,750 |
| 12 | 22,340 | 71,000 | 163,500 | 83,800 | 14,600 | 13,340 | 21,660 | 25,310 | 25,310 | 138,300 | 14,580 | 10,750 |
| 13 | 19,550 | 77,300 | 172,600 | 77,300 | 14,160 | 21,660 | 22,640 | 25,310 | 25,310 | 136,000 | 14,580 | 10,750 |
| 14 | 15,510 | 80,100 | 153,500 | 77,300 | 14,160 | 27,090 | 22,640 | 25,310 | 23,660 | 107,700 | 14,160 | 11,440 |
| 15 | 15,510 | 95,100 | 134,000 | 118,200 | 14,160 | 32,510 | 17,760 | 20,190 | 25,310 | 79,640 | 14,160 | 5,630 |
| 16 | 19,550 | 97,600 | 109,400 | 186,400 | 14,160 | 35,600 | 17,760 | 21,660 | 21,660 | 57,280 | 14,160 | 5,630 |
| 17 | 23,480 | 97,600 | 101,000 | 188,400 | 14,160 | 36,290 | 16,350 | 25,310 | 18,720 | 46,700 | 14,160 | 5,630 |
| 18 | 25,190 | 86,500 | 89,200 | 149,900 | 12,100 | 34,310 | 14,160 | 23,660 | 18,720 | 42,480 | 15,450 | 7,340 |
| 19 | 25,190 | 68,400 | 77,300 | 126,900 | 12,100 | 29,500 | 21,170 | 21,660 | 21,660 | 49,450 | 98,560 | 21,660 |
| 20 | 25,190 | 55,900 | 77,300 | 103,500 | 11,310 | 24,190 | 37,670 | 18,720 | 23,660 | 66,480 | 92,710 | 31,900 |
| 21 | 25,190 | 37,800 | 60,000 | 77,300 | 11,310 | 23,660 | 53,750 | 16,350 | 20,190 | 68,110 | 66,480 | 53,750 |
| 22 | 26,330 | 43,800 | 62,500 | 74,600 | 10,560 | 23,660 | 50,220 | 15,450 | 18,720 | 61,060 | 61,060 | 53,060 |
| 23 | 38,500 | 43,800 | 68,400 | 65,800 | 10,560 | 27,090 | 35,600 | 14,160 | 16,810 | 51,600 | 39,730 | 53,060 |
| 24 | 36,400 | 41,400 | 127,800 | 62,500 | 10,560 | 35,600 | 30,100 | 14,580 | 15,450 | 42,480 | 35,600 | 39,040 |
| 25 | 35,000 | 38,500 | 234,300 | 55,900 | 10,560 | 53,060 | 26,490 | 14,160 | 14,580 | 36,290 | 31,300 | 36,290 |
| 26 | 29,430 | 37,800 | 214,800 | 45,400 | 10,560 | 66,480 | 21,660 | 12,560 | 14,160 | 27,090 | 28,290 | 31,300 |
| 27 | 29,430 | 45,400 | 156,300 | 43,800 | 10,560 | 76,710 | 20,190 | 12,560 | 12,560 | 28,290 | 25,660 | 25,310 |
| 28 | 30,800 | 43,800 | 131,400 | 36,400 | 10,560 | 66,480 | 20,190 | 13,340 | 12,180 | 27,090 | 15,450 | 21,170 |
| 29 | 32,900 | | 106,000 | 29,430 | 10,200 | 58,820 | 18,720 | 33,110 | 10,410 | 25,310 | 15,450 | 19,210 |
| 30 | 46,200 | | 83,800 | 29,430 | 10,200 | 51,600 | 20,190 | 57,280 | 10,110 | 23,660 | 15,450 | 16,810 |
| 31 | 105,200 | | 83,800 | | 9,520 | | 23,660 | 107,670 | | 21,660 | | 12,180 |
| 1904. | | | | | | | | | | | | |
| 1 | (a) | (a) | (a) | 75,500 | 97,600 | 31,500 | 12,500 | 10,060 | 9,048 | 11,540 | 13,980 | 11,620 |
| 2 | (a) | (a) | (a) | 141,000 | 80,100 | 35,000 | 11,160 | 10,780 | 8,120 | 10,780 | 13,140 | 9,792 |
| 3 | (a) | (a) | (a) | 194,200 | 75,500 | 39,600 | 13,140 | 12,740 | 7,824 | 9,724 | 12,340 | 9,114 |
| 4 | (a) | (a) | (a) | 159,000 | 62,500 | 39,600 | 12,500 | 12,740 | 7,824 | 11,540 | 11,540 | 7,882 |
| 5 | (a) | (a) | (a) | 127,800 | 50,200 | 36,120 | 10,560 | 12,340 | 7,538 | 12,740 | 10,780 | 8,180 |
| 6 | (a) | (a) | (a) | 98,900 | 37,200 | 50,200 | 11,160 | 11,540 | 7,258 | 11,160 | 10,490 | 6,228 |
| 7 | (a) | (a) | (a) | 81,600 | 36,120 | 55,600 | 11,160 | 13,980 | 6,982 | 10,060 | 10,200 | 8,180 |
| 8 | (a) | (a) | (a) | 71,000 | 33,740 | 47,500 | 15,330 | 13,550 | 6,442 | 9,384 | 9,792 | 7,036 |
| 9 | (a) | (a) | (a) | 69,400 | 29,170 | 36,120 | 18,590 | 11,540 | 6,442 | 8,726 | 9,792 | 7,882 |
| 10 | (a) | (a) | (a) | 75,500 | 28,130 | 30,250 | 18,590 | 10,780 | 7,538 | 7,824 | 9,452 | 7,594 |
| 11 | (a) | (a) | (a) | 111,600 | 25,190 | 40,800 | 43,480 | 12,340 | 7,538 | 7,538 | 10,130 | 5,708 |
| 12 | (a) | (a) | (a) | 123,400 | 23,250 | 58,400 | 52,900 | 10,420 | 7,538 | 7,824 | 9,792 | 6,228 |
| 13 | (a) | (a) | (a) | 103,200 | 22,340 | 46,200 | 42,200 | 10,060 | 7,258 | 7,824 | 10,130 | 10,860 |
| 14 | (a) | (a) | (a) | 89,200 | 18,590 | 35,000 | 32,620 | 9,384 | 6,982 | 7,824 | 10,860 | 9,114 |
| 15 | (a) | (a) | (a) | 73,900 | 21,320 | 26,100 | 26,100 | 8,420 | 8,420 | 8,726 | 10,490 | 9,452 |
| 16 | (a) | (a) | (a) | 55,900 | 25,190 | 22,340 | 22,340 | 8,420 | 10,060 | 22,680 | 10,130 | 8,788 |
| 17 | (a) | (a) | (a) | 54,300 | 28,130 | 19,550 | 18,590 | 8,120 | 13,140 | 20,440 | 9,792 | 8,240 |
| 18 | (a) | (a) | (a) | 52,900 | 31,500 | 21,320 | 15,790 | 7,824 | 14,870 | 16,750 | 9,452 | 9,520 |
| 19 | (a) | (a) | (a) | 44,800 | 36,120 | 21,320 | 13,980 | 7,258 | 11,540 | 14,420 | 10,130 | 9,520 |
| 20 | (a) | (a) | (a) | 43,500 | 51,540 | 18,590 | 13,140 | 7,538 | 11,540 | 12,340 | 10,130 | 9,520 |
| 21 | (a) | (a) | (a) | 35,000 | 69,400 | 18,590 | 13,550 | 8,120 | 10,420 | 11,160 | 9,452 | 8,550 |
| 22 | (a) | (a) | (a) | 27,090 | 78,400 | 19,550 | 12,340 | 7,538 | 9,048 | 12,340 | 9,792 | 8,550 |
| 23 | (a) | (a) | (a) | 32,620 | 56,900 | 18,590 | 12,740 | 8,120 | 8,420 | 22,680 | 10,130 | 9,520 |
| 24 | (a) | (a) | (a) | 30,250 | 44,800 | 18,590 | 23,250 | 8,120 | 7,538 | 33,040 | 10,860 | 10,200 |
| 25 | (a) | (a) | (a) | 28,130 | 39,600 | 20,440 | 14,420 | 8,120 | 7,538 | 37,240 | 10,860 | 10,200 |
| 26 | (a) | (a) | (a) | 29,170 | 33,740 | 17,760 | 11,940 | 10,780 | 6,982 | 30,520 | 11,620 | 10,200 |
| 27 | (a) | (a) | (a) | 29,170 | 36,120 | 16,080 | 11,160 | 16,270 | 6,712 | 25,820 | 12,420 | 11,700 |
| 28 | (a) | (a) | (a) | 32,620 | 35,000 | 13,820 | 10,780 | 13,980 | 7,258 | 19,880 | 12,020 | 12,500 |
| 29 | (a) | (a) | (a) | 50,200 | 31,500 | 13,140 | 11,540 | 11,940 | 10,420 | 18,270 | 11,230 | 14,160 |
| 30 | (a) | (a) | (a) | 86,100 | 27,090 | 11,780 | 10,780 | 10,420 | 11,160 | 17,760 | 12,020 | 651,120 |
| 31 | (a) | (a) | (a) | | 28,130 | | | 9,724 | | 15,790 | | 644,120 |

^aThe ice gorges during January, February, and March make it impossible to estimate daily flow.

^bDischarge for December 30 and 31 reduced to 40 per cent on account of ice gorge.

Estimated monthly discharge of Susquehanna River at Harrisburg, Pa., 1891-1904.

[Drainage area, 24,080 square miles.]

| Month. | Discharge in second-feet. | | | Run-off. | |
|-----------------|---------------------------|----------|---------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1891. | | | | | |
| January | 135,800 | 21,770 | 72,224 | 3.006 | 3.466 |
| February | 334,500 | 61,700 | 140,746 | 5.857 | 6.099 |
| March | 156,300 | 46,200 | 97,361 | 4.052 | 4.672 |
| April | 120,800 | 34,300 | 79,830 | 3.322 | 3.706 |
| May | 30,800 | 13,300 | 19,193 | .799 | .921 |
| June | 71,000 | 12,500 | 25,397 | 1.057 | 1.179 |
| July | 41,400 | 12,100 | 21,708 | .903 | 1.041 |
| August | 79,200 | 13,300 | 30,568 | 1.272 | 1.467 |
| September | 46,200 | 11,310 | 23,711 | .987 | 1.101 |
| October | 46,200 | 10,200 | 18,596 | .774 | .892 |
| November | 75,500 | 13,300 | 34,115 | 1.419 | 1.583 |
| December | 129,600 | 29,430 | 62,988 | 2.621 | 3.022 |
| The year | 334,500 | 10,200 | 52,201 | 2.172 | 29.149 |
| 1892. | | | | | |
| January | 195,800 | 14,160 | 78,944 | 3.285 | 3.787 |
| February | 49,400 | 10,560 | 22,350 | .930 | 1.003 |
| March | 193,000 | 17,960 | 51,301 | 2.135 | 2.461 |
| April | 224,200 | 25,190 | 79,705 | 3.317 | 3.701 |
| May | 118,200 | 21,770 | 67,255 | 2.799 | 3.227 |
| June | 183,600 | 26,330 | 65,242 | 2.715 | 3.029 |
| July | 46,200 | 8,850 | 19,324 | .804 | .927 |
| August | 38,500 | 12,100 | 18,664 | .777 | .896 |
| September | 22,340 | 7,090 | 11,219 | .467 | .521 |
| October | 8,850 | 4,070 | 5,999 | .250 | .288 |
| November | 30,800 | 4,070 | 10,896 | .453 | .505 |
| December | 39,900 | 6,020 | 16,153 | .672 | .775 |
| The year | 224,200 | 4,070 | 37,254 | 1.550 | 21.120 |

Estimated monthly discharge of Susquehanna River at Harrisburg, Pa., 1891-1904—Continued.

| Month. | Discharge in second-feet. | | | Run-off. | |
|-----------------|---------------------------|----------|---------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1893. | | | | | |
| January | 21,770 | 13,300 | 15,515 | 0.646 | 0.745 |
| February | 167,100 | 19,550 | 55,585 | 2.313 | 2.409 |
| March | 223,200 | 17,960 | 93,257 | 3.881 | 4.474 |
| April | 154,400 | 54,300 | 103,387 | 4.302 | 4.800 |
| May | 267,400 | 31,500 | 91,090 | 3.791 | 4.371 |
| June | 31,500 | 10,200 | 18,627 | .775 | .865 |
| July | 16,460 | 6,020 | 10,224 | .425 | .490 |
| August | 24,620 | 3,500 | 5,680 | .236 | .272 |
| September | 42,200 | 9,520 | 18,785 | .782 | .872 |
| October | 57,500 | 7,940 | 18,638 | .776 | .895 |
| November | 31,500 | 10,200 | 15,425 | .642 | .716 |
| December | 118,200 | 13,300 | 40,382 | 1.681 | 1.938 |
| The year | 267,400 | 3,500 | 40,549 | 1.688 | 22.847 |
| 1894. | | | | | |
| January | 55,900 | 16,950 | 27,018 | 1.124 | 1.296 |
| February | 68,400 | 13,300 | 31,545 | 1.313 | 1.367 |
| March | 177,100 | 25,190 | 69,791 | 2.904 | 3.348 |
| April | 136,600 | 20,650 | 65,407 | 2.722 | 3.037 |
| May | 543,500 | 16,460 | 94,621 | 3.938 | 4.540 |
| June | 132,300 | 16,950 | 49,839 | 2.074 | 2.314 |
| July | 19,010 | 6,550 | 10,050 | .418 | .482 |
| August | 10,560 | 3,680 | 6,626 | .276 | .318 |
| September | 62,500 | 3,500 | 17,281 | .719 | .802 |
| October | 61,700 | 7,940 | 25,888 | 1.077 | 1.242 |
| November | 97,600 | 17,960 | 46,345 | 1.929 | 2.152 |
| December | 74,600 | 16,460 | 35,195 | 1.465 | 1.689 |
| The year | 543,500 | 3,500 | 39,967 | 1.663 | 22.587 |

Estimated monthly discharge of Susquehanna River at Harrisburg, Pa., 1891-1904—Continued.

| Month. | Discharge in second-feet. | | | Run-off. | |
|-----------------|---------------------------|----------|--------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1895. | | | | | |
| January | 112,000 | 23,480 | 50,123 | 2.086 | 2.405 |
| February | 86,500 | 21,770 | 53,531 | 2.228 | 2.320 |
| March | 147,200 | 51,900 | 79,655 | 3.315 | 3.822 |
| April | 205,400 | 29,430 | 84,858 | 3.531 | 3.940 |
| May | 41,400 | 15,510 | 25,048 | 1.042 | 1.201 |
| June | 29,430 | 5,240 | 10,868 | .452 | .504 |
| July | 22,340 | 3,680 | 9,370 | .390 | .450 |
| August | 8,540 | 3,500 | 5,263 | .219 | .252 |
| September | 10,200 | 3,680 | 5,211 | .217 | .242 |
| October | 4,500 | 2,570 | 3,306 | .138 | .159 |
| November | 21,770 | 3,000 | 6,108 | .254 | .283 |
| December | 62,500 | 5,240 | 18,594 | .774 | .892 |
| The year | 205,400 | 2,570 | 29,328 | 1.220 | 16.470 |
| 1896. | | | | | |
| January | 136,600 | 23,480 | 52,586 | 2.188 | 2.523 |
| February | 183,600 | 16,460 | 52,478 | 2.184 | 2.355 |
| March | 183,600 | 16,460 | 64,346 | 2.678 | 3.087 |
| April | 223,200 | 26,330 | 88,502 | 3.683 | 4.109 |
| May | 23,480 | 7,370 | 12,637 | .526 | .606 |
| June | 47,800 | 8,850 | 19,216 | .800 | .893 |
| July | 41,400 | 10,200 | 15,195 | .632 | .729 |
| August | 46,200 | 3,500 | 14,499 | .603 | .695 |
| September | 7,370 | 3,160 | 4,153 | .173 | .193 |
| October | 129,600 | 9,520 | 34,463 | 1.434 | 1.653 |
| November | 140,100 | 12,100 | 35,476 | 1.476 | 1.647 |
| December | 39,900 | 8,540 | 21,577 | .898 | 1.035 |
| The year | 223,200 | 3,160 | 34,594 | 1.439 | 19.525 |

Estimated monthly discharge of Susquehanna River at Harrisburg, Pa., 1891-1904—Continued.

| Month. | Discharge in second-feet. | | | Run-off. | |
|-----------------|---------------------------|----------|--------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1897. | | | | | |
| January | 31,500 | 9,520 | 18,609 | 0.774 | 0.892 |
| February | 101,800 | 23,480 | 46,802 | 1.927 | 2.007 |
| March | 165,300 | 26,330 | 88,240 | 3.672 | 4.233 |
| April | 129,600 | 25,190 | 55,768 | 2.321 | 2.590 |
| May | 101,800 | 24,620 | 53,844 | 2.241 | 2.584 |
| June | 29,430 | 9,520 | 17,648 | .734 | .819 |
| July | 43,800 | 6,550 | 11,374 | .473 | .545 |
| August | 41,400 | 7,370 | 15,208 | .633 | .730 |
| September | 15,510 | 4,070 | 6,749 | .281 | .314 |
| October | 11,310 | 4,070 | 5,906 | .246 | .284 |
| November | 50,200 | 4,740 | 21,592 | .899 | 1.003 |
| December | 106,000 | 17,960 | 46,585 | 1.939 | 2.235 |
| The year | 165,300 | 4,070 | 32,319 | 1.345 | 18.246 |
| 1898. | | | | | |
| January | 147,200 | 12,500 | 58,490 | 2.434 | 2.806 |
| February | 106,000 | 19,550 | 52,376 | 2.199 | 2.290 |
| March | 245,900 | 27,510 | 88,570 | 3.686 | 4.250 |
| April | 144,500 | 23,480 | 53,141 | 2.211 | 2.467 |
| May | 86,500 | 36,400 | 59,310 | 2.468 | 2.845 |
| June | 41,400 | 10,560 | 19,979 | .831 | .927 |
| July | 14,600 | 4,740 | 7,998 | .333 | .384 |
| August | 57,500 | 8,850 | 26,014 | 1.083 | 1.249 |
| September | 23,480 | 5,240 | 11,238 | .468 | .522 |
| October | 109,400 | 4,740 | 32,904 | 1.369 | 1.578 |
| November | 116,400 | 17,960 | 41,096 | 1.710 | 1.908 |
| December | 101,000 | 12,500 | 34,733 | 1.445 | 1.666 |
| The year | 245,900 | 4,740 | 40,487 | 1.686 | 22.892 |

Estimated monthly discharge of Susquehanna River at Harrisburg, Pa., 1891-1904—Continued.

| Month. | Discharge in second-feet. | | | Run-off. | |
|-----------------|---------------------------|----------|---------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1899. | | | | | |
| January | 103,500 | 20,650 | 44,427 | 1.849 | 2.132 |
| February | 120,800 | 12,500 | 46,106 | 1.919 | 1.998 |
| March | 193,000 | 41,400 | 100,920 | 4.200 | 4.842 |
| April | 116,400 | 29,430 | 66,984 | 2.788 | 3.111 |
| May | 54,300 | 17,960 | 25,349 | 1.055 | 1.216 |
| June | 19,010 | 6,550 | 11,511 | .479 | .534 |
| July | 11,310 | 5,240 | 7,820 | .325 | .375 |
| August | 36,400 | 3,680 | 7,297 | .304 | .350 |
| September | 12,100 | 4,500 | 6,432 | .268 | .299 |
| October | 7,090 | 2,850 | 4,130 | .172 | .198 |
| November | 43,800 | 4,070 | 18,795 | .782 | .872 |
| December | 82,000 | 9,520 | 32,169 | 1.340 | 1.545 |
| The year | 193,000 | 2,850 | 30,995 | 1.290 | 17.472 |
| 1900. | | | | | |
| January | 174,500 | 10,560 | 57,040 | 2.374 | 2.737 |
| February | 159,000 | 12,100 | 63,816 | 2.656 | 2.766 |
| March | 194,900 | 23,480 | 67,494 | 2.809 | 3.238 |
| April | 92,600 | 36,400 | 58,223 | 2.423 | 2.703 |
| May | 36,400 | 12,500 | 19,250 | .801 | .923 |
| June | 19,550 | 7,370 | 13,112 | .546 | .609 |
| July | 9,520 | 5,240 | 7,134 | .297 | .342 |
| August | 9,520 | 2,850 | 5,066 | .211 | .243 |
| September | 7,370 | 2,330 | 3,721 | .155 | .173 |
| October | 7,940 | 2,570 | 4,314 | .180 | .208 |
| November | 194,000 | 4,070 | 23,489 | .977 | 1.091 |
| December | 93,400 | 13,300 | 36,726 | 1.528 | 1.762 |
| The year | 194,900 | 2,330 | 29,949 | 1.246 | 16.595 |

Estimated monthly discharge of Susquehanna River at Harrisburg, Pa., 1891-1904—Continued.

| Month. | Discharge in second-feet. | | | Run-off. | |
|-----------------|---------------------------|----------|---------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1901. | | | | | |
| January | 29,430 | 7,370 | 14,038 | 0.584 | 0.673 |
| February | 36,400 | 11,310 | 20,038 | .834 | .868 |
| March | 191,100 | 10,560 | 81,035 | 3.372 | 3.888 |
| April | 204,400 | 47,800 | 103,963 | 4.326 | 4.827 |
| May | 210,100 | 28,130 | 63,972 | 2.662 | 3.069 |
| June | 185,500 | 25,190 | 55,083 | 2.292 | 2.557 |
| July | 24,620 | 9,520 | 13,518 | .563 | .649 |
| August | 120,800 | 7,940 | 33,266 | 1.384 | 1.596 |
| September | 54,300 | 10,560 | 22,089 | .919 | 1.025 |
| October | 19,550 | 8,850 | 13,150 | .547 | .631 |
| November | 58,400 | 6,550 | 14,849 | .618 | .689 |
| December | 405,100 | 14,600 | 73,514 | 3.059 | 3.527 |
| The year | 405,100 | 6,550 | 42,376 | 1.738 | 23.999 |
| 1902. | | | | | |
| January | 138,400 | 13,300 | 37,012 | 1.540 | 1.775 |
| February | 132,300 | 13,300 | 47,168 | 1.963 | 2.044 |
| March | 484,100 | 31,500 | 155,396 | 6.467 | 7.456 |
| April | 224,200 | 20,650 | 68,132 | 2.835 | 3.163 |
| May | 21,770 | 10,560 | 15,401 | .641 | .739 |
| June | 23,480 | 7,940 | 12,810 | .533 | .595 |
| July | 112,000 | 25,190 | 70,209 | 2.922 | 3.369 |
| August | 72,800 | 7,940 | 26,962 | 1.122 | 1.294 |
| September | 54,300 | 5,760 | 11,714 | .488 | .544 |
| October | 68,400 | 15,510 | 35,656 | 1.484 | 1.711 |
| November | 60,000 | 10,560 | 20,985 | .873 | .974 |
| December | 186,400 | 16,950 | 63,774 | 2.654 | 3.060 |
| The year | 484,100 | 5,760 | 47,102 | 1.960 | 26.724 |

Estimated monthly discharge of Susquehanna River at Harrisburg, Pa., 1891-1904—Continued.

| Month. | Discharge in second-feet. | | | Run-off. | |
|-----------------------------|---------------------------|----------|---------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1903. | | | | | |
| January | 105,200 | 15,510 | 37,765 | 1.572 | 1.812 |
| February | 223,200 | 37,800 | 93,236 | 3.880 | 4.040 |
| March | 276,500 | 60,000 | 133,500 | 5.556 | 6.405 |
| April | 188,400 | 29,430 | 82,715 | 3.442 | 3.840 |
| May | 28,130 | 9,520 | 14,297 | .595 | .686 |
| June | 76,710 | 8,190 | 27,964 | 1.163 | 1.298 |
| July | 79,640 | 14,160 | 32,581 | 1.355 | 1.560 |
| August | 107,670 | 12,560 | 25,581 | 1.064 | 1.227 |
| September | 123,500 | 10,410 | 30,511 | 1.270 | 1.417 |
| October | 138,300 | 7,610 | 45,160 | 1.880 | 2.167 |
| November | 98,560 | 14,160 | 27,289 | 1.135 | 1.266 |
| December | 53,750 | 5,630 | 19,743 | .822 | .948 |
| The year | 276,500 | 5,630 | 47,528 | 1.978 | 26.666 |
| 1904. | | | | | |
| January ^a | | | 30,410 | 1.27 | 1.47 |
| February ^a | | | 38,590 | 1.61 | 1.74 |
| March ^a | | | 102,000 | 4.24 | 4.89 |
| April | 194,200 | 27,030 | 74,230 | 3.09 | 3.45 |
| May | 97,600 | 18,590 | 41,740 | 1.74 | 2.01 |
| June | 58,400 | 11,780 | 29,320 | 1.22 | 1.36 |
| July | 52,900 | 10,420 | 18,020 | .750 | .865 |
| August | 16,270 | 7,258 | 10,420 | .434 | .500 |
| September | 14,870 | 6,442 | 8,657 | .360 | .402 |
| October | 37,240 | 7,538 | 15,240 | .634 | .731 |
| November | 13,980 | 9,452 | 10,760 | .448 | .500 |
| December | 51,120 | 5,708 | 8,448 | .352 | .405 |
| The year | | | 32,320 | 1.35 | 18.32 |

^aOwing to an ice gorge below Harrisburg the monthly mean for January, February, and March has been estimated by taking 89 per cent of means for McCall's Ferry. Practically open conditions existed at the latter station (see p. 183).

SUSQUEHANNA RIVER AT McCALLS FERRY, PA.

The McCalls Ferry gaging station is located, as shown in Pl. VIII, at a narrow and rocky part of Susquehanna River, about 20 miles above its mouth and 1 mile above the village of that name. It was established on May 17, 1902, by Boyd Ehle while investigating a power development there. For a considerable distance along this portion of the river the bank on the York County shore is the retaining wall of an abandoned canal which can be overtopped only in the greatest floods. The Lancaster shore, on the opposite side, is made up of almost vertical rock, and the railroad which skirts it has never yet been flooded at this point.

The gaging section first selected for the station is located at Duncan's Run (A-A, Pl. VIII), where two islands, Hartman and Streepers, divide the river into three channels, ranging in width from 100 to 500 feet. At ordinary low water, however, two of these run dry, thus confining the discharge to the main or westernmost channel. The river bed at the section is composed of schistose rock, with some projecting bowlders and large irregularities. The flow, however, is comparatively free from the boils so common in a river of this character.

The discharge measurements are made from a boat held in place by a rope stretched between the towpath and Streepers Island, the gaging points, 10 feet apart, being indicated by a tagged wire, which is also used for keeping the boat parallel to the current.

In order to provide for measuring the large floods which occur in the winter and spring months a cable station was established by Mr. Ehle in the fall of 1902, about 1,000 feet downstream from the Duncan's Run section (B-B, Pl. VIII). The banks of the river and the condition of the river bed are very similar to those at the upper section, though the latter is somewhat more irregular, as shown by Pl. I, B. During the low-water period of the fall of 1902 a careful survey was made of the section at the cable station, and a contour map with 1-foot intervals was prepared from which the effective areas could be accurately determined, thus eliminating the error in discharge due to possible inaccuracies in soundings made at the time of the measurements. The width of the stream at this point is about 1,300 feet, and the maximum depth during a gaging was 46 feet.

The car cable, a $\frac{3}{4}$ -inch 37-wire strand, with a span of 1,450 feet, is anchored to 3-inch eyebolts set in cement in the solid rock on either side of the river. A 2-inch turn-buckle is provided at the York County end to regulate its height above the water. A high cliff on one shore and a large red oak on the other give the cable a 10-foot clearance over the highest floods on record. The car which runs on the cable, as shown in Pl. IX, B, accommodates two people, and is propelled by a crank turning one of the sheaves.



VIEW OF SUSQUEHANNA RIVER ABOVE McCALLS FERRY.

A A, Duncans Run gaging station; B B, cable gaging station.

Eighty feet upstream from the main cable is suspended a $\frac{5}{8}$ -inch secondary cable, along which runs a trolley carrying a guy rope to hold the meter against the current (Pl. IX, A). Measuring points for this section are 50 feet apart and are indicated by red and white bands painted on the main cable, the intermediate distances being readily estimated by counting the revolutions of the sheave.

The measurements at both of the above stations are referred to two permanent gages, designated Nos. 2 and 5. These are painted on the rock and give elevations directly above sea level. Gage No. 2 is located about three-fourths of a mile below the village of McCalls Ferry in the tailrace of the proposed power house and has been read daily since June, 1902. The records in the following tables have been referred to this gage. Gage No. 5 is placed about 2 miles below McCalls Ferry, at the foot of Cullys Falls, and was thus located in order to be entirely out of the influence of the proposed dam. One of the purposes of the extensive investigations carried on at McCalls Ferry was to obtain data for determining the coefficient of discharge over ogee-faced weirs under high heads, and it is for use in these investigations that gage No. 5 was established.


The methods used in carrying on the work at the McCalls Ferry station were practically the same as those employed by the United States Geological Survey. Every effort was made to eliminate any source of error, and vertical velocity determinations were taken whenever possible. At Duncans Run, in order to get satisfactory vertical velocity curves, an 80-pound weight, with pulley and rope attached, was dropped to the bottom, so that the meter could be pulled down without being washed too far from the section. When the surface velocity or 0.6 method was used the results were reduced by coefficients determined from these vertical velocity curves. At the cable station the secondary cable with the aid of the guy rope made it possible to get vertical velocity measurements at exceptionally great velocities and depths. A No. 12 telegraph wire was found to be more satisfactory at such times for holding the meter than the insulated cable ordinarily used, as it offered less resistance to the current, would allow the meter to sink deeper, and being less bowed by the water would show more accurately its depth below the surface. In this way curves were obtained to depths of 20 feet and in currents of 10 feet per second.

During the highest stages, when the velocity sometimes reaches 17 feet per second, readings could only be taken at the surface. These results were, however, reduced by coefficients determined from the vertical velocity curves for each measuring point.

Discharge measurements of Susquehanna River at Duncans Run station above McCalls Ferry, Pa., 1902-1904.

| Date. | Hydrographer. | Gage height. ^a | Area of section. | Mean velocity. | Discharge. |
|----------|----------------------|---------------------------|---------------------|-------------------------|---------------------|
| 1902. | | <i>Feet.</i> | <i>Square feet.</i> | <i>Feet per second.</i> | <i>Second-feet.</i> |
| May 17 | Boyd Ehle ----- | 116.62 | 4,570 | 3.70 | 16,880 |
| 24 | do ----- | 115.83 | 4,340 | 2.93 | 12,710 |
| June 9 | do ----- | 115.30 | 3,990 | 2.59 | 10,330 |
| 23 | do ----- | 116.32 | 4,564 | 3.17 | 14,440 |
| July 14 | do ----- | 121.90 | 9,180 | 6.00 | 55,100 |
| 16 | do ----- | 120.12 | 7,400 | 5.15 | 38,100 |
| 21 | do ----- | 117.90 | 6,020 | 4.02 | 24,200 |
| 24 | do ----- | 125.10 | 11,900 | 8.01 | 95,300 |
| 26 | do ----- | 123.82 | 11,000 | 7.41 | 81,500 |
| Sept. 3 | do ----- | 114.82 | 3,800 | 2.14 | 8,130 |
| 25 | do ----- | 114.34 | 3,500 | 1.82 | 6,370 |
| 1903. | | | | | |
| June 5 | R. H. Anderson ----- | 115.17 | 3,850 | 2.60 | 10,000 |
| 1904. | | | | | |
| Sept. 29 | W. G. Steward ----- | 114.75 | 3,717 | 216 | 7,940 |

^a At gage No. 2.



A



B

GAGING CAR AT McCALLS FERRY CABLE STATION.

A, Gaging car in operation; B, gaging car.

Discharge measurements of Susquehanna River at cable station above McCall's Ferry, Pa., 1903-1904.

| Date. | Hydrographer. | Gage height. ^a | Area of section. | Mean velocity. | Discharge. |
|---------|----------------------|---------------------------|---------------------|-------------------------|---------------------|
| | | <i>Feet.</i> | <i>Square feet.</i> | <i>Feet per second.</i> | <i>Second-feet.</i> |
| 1903. | | | | | |
| Feb. 10 | R. H. Anderson | 123.90 | 14,300 | 5.97 | <i>b</i> 85,400 |
| Mar. 2 | do | 135.90 | 33,800 | 8.59 | <i>b</i> 290,550 |
| 3 | do | 133.60 | 30,365 | 8.23 | <i>b</i> 250,000 |
| 4 | do | 130.00 | 23,050 | 7.55 | <i>b</i> 174,060 |
| 5 | do | 127.20 | 19,000 | 6.80 | <i>b</i> 129,300 |
| 6 | do | 125.20 | 16,175 | 6.41 | <i>c</i> 104,600 |
| 7 | do | 124.20 | 14,780 | 5.77 | <i>c</i> 85,300 |
| 12 | do | 129.40 | 22,460 | 7.16 | <i>c</i> 160,600 |
| 18 | do | 123.40 | 13,220 | 5.84 | <i>c</i> 77,240 |
| 25 | do | 134.30 | 31,220 | 8.75 | <i>b</i> 273,300 |
| 27 | do | 130.10 | 23,720 | 7.38 | <i>b</i> 175,210 |
| 28 | do | 127.60 | 19,780 | 6.90 | <i>b</i> 136,400 |
| Apr. 3 | do | 123.80 | 14,060 | 5.72 | <i>b</i> 80,400 |
| 9 | do | 123.30 | 13,310 | 5.75 | <i>c</i> 76,600 |
| 16 | do | 131.50 | 26,445 | 7.91 | <i>b</i> 209,200 |
| 18 | do | 128.80 | 21,350 | 7.15 | <i>b</i> 152,500 |
| 22 | do | 122.60 | 11,840 | 5.62 | <i>b</i> 66,600 |
| 25 | do | 120.70 | 9,400 | 4.96 | <i>c</i> 46,660 |
| May 4 | do | 117.85 | 5,870 | 4.16 | <i>c</i> 24,400 |
| 14 | do | 116.50 | 4,410 | 3.63 | <i>c</i> 16,000 |
| 23 | do | 115.72 | 4,120 | 3.19 | <i>c</i> 13,140 |
| June 5 | do | 115.17 | 2,885 | 3.40 | <i>c</i> 9,810 |
| 17 | do | 120.00 | 8,180 | 4.67 | <i>c</i> 38,200 |
| 1904. | | | | | |
| Mar. 8 | R. H. Anderson | 146.6 | 54,500 | 11.6 | <i>d</i> 631,000 |
| May 11 | do | 119.00 | 7,035 | 4.7 | <i>b</i> 34,400 |

^a At gage No. 2.
^b Surface velocities.

^c Multiple points.
^d See page 177.

Mean daily gage height, in feet, of Susquehanna River at McCall's Ferry, Pa., for 1902-1904.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|
| 1902. | | | | | | | | | | | | |
| 1 | | | | | | 116.15 | 117.50 | 122.10 | 114.90 | 120.50 | 122.10 | 117.15 |
| 2 | | | | | | 116.15 | 121.70 | 121.70 | 114.90 | 122.60 | 121.30 | 117.40 |
| 3 | | | | | | 115.80 | 123.70 | 121.60 | 114.80 | 122.70 | 120.10 | 118.45 |
| 4 | | | | | | 115.80 | 123.10 | 122.20 | 114.85 | 122.10 | 119.60 | 119.25 |
| 5 | | | | | | 115.80 | 123.15 | 122.00 | 114.80 | 121.50 | 119.00 | 119.60 |
| 6 | | | | | | 115.35 | 124.50 | 121.20 | 114.60 | 121.40 | 118.50 | 119.40 |
| 7 | | | | | | 115.25 | 123.55 | 120.60 | 114.55 | 121.30 | 118.20 | 119.40 |
| 8 | | | | | | 115.20 | 123.55 | 119.40 | 114.50 | 120.90 | 118.00 | 119.10 |
| 9 | | | | | | 115.20 | 125.50 | 118.85 | 114.60 | 120.00 | 117.80 | 119.10 |
| 10 | | | | | | 115.50 | 124.50 | 118.50 | 114.65 | 119.50 | 117.55 | ----- |
| 11 | | | | | | 115.65 | 122.90 | 118.90 | 114.55 | 118.80 | 117.40 | ----- |
| 12 | | | | | | 115.60 | 122.10 | 119.00 | 114.65 | 119.20 | 117.10 | 118.10 |
| 13 | | | | | | 115.60 | 122.50 | 118.70 | 114.80 | 121.40 | 117.00 | 119.50 |
| 14 | | | | | | 115.70 | 121.85 | 118.10 | 114.75 | 121.00 | 116.90 | 120.10 |
| 15 | | | | | | 116.20 | 120.80 | 117.75 | 114.75 | 120.50 | 116.70 | 119.30 |
| 16 | | | | | | 116.20 | 120.20 | 117.50 | 114.70 | 119.60 | 116.60 | 119.40 |
| 17 | | | | | | 116.35 | 119.30 | 117.20 | 114.65 | 119.00 | 116.50 | 123.00 |
| 18 | | | | | | 116.80 | 118.65 | 116.95 | 114.65 | ----- | 116.40 | 126.35 |
| 19 | | | | | | 116.45 | 118.20 | 116.70 | 114.55 | 118.70 | 116.35 | 125.85 |
| 20 | | | | | | 116.65 | 117.80 | 116.30 | 114.50 | 118.20 | 116.30 | 125.00 |
| 21 | | | | | | 116.60 | 117.90 | 116.20 | 114.40 | 117.80 | 116.20 | 124.50 |
| 22 | | | | | | 116.35 | 117.30 | 116.00 | 114.50 | 117.50 | 116.10 | 127.65 |
| 23 | | | | | | 116.30 | 122.85 | 115.80 | 114.40 | 117.20 | 116.00 | 131.50 |
| 24 | | | | | | 116.15 | ----- | 115.75 | 114.30 | 116.90 | 115.95 | 131.50 |
| 25 | | | | | | 115.95 | 124.05 | 115.75 | 114.35 | 117.00 | 116.00 | 129.95 |
| 26 | | | | | | 116.15 | 123.85 | 115.70 | 114.60 | 117.00 | 116.20 | 126.55 |
| 27 | | | | | | 116.40 | 124.70 | 115.55 | 118.55 | 116.90 | 116.85 | 124.30 |
| 28 | | | | | | 116.65 | 123.85 | 115.40 | 121.00 | 117.10 | ----- | 122.90 |
| 29 | | | | | | 116.75 | 122.20 | 115.30 | 120.00 | 118.70 | 117.15 | 122.30 |
| 30 | | | | | | 116.95 | 121.90 | 115.20 | 119.85 | 122.00 | 117.15 | 121.00 |
| 31 | | | | | | ----- | 122.60 | 115.00 | ----- | ----- | ----- | 120.60 |
| 1903. | | | | | | | | | | | | |
| 1 | 120.10 | 131.00 | 132.80 | 123.10 | 118.60 | 115.55 | 123.00 | 118.00 | 127.00 | 115.75 | 117.80 | 117.00 |
| 2 | 119.50 | 129.20 | 136.00 | 123.40 | 118.20 | 115.50 | 122.30 | 117.70 | 124.80 | 115.75 | 117.75 | 116.80 |
| 3 | 121.30 | 126.80 | 133.60 | 123.80 | 118.00 | 115.40 | 119.90 | 117.50 | 123.20 | 115.50 | 117.60 | 116.60 |
| 4 | 122.10 | 126.50 | 129.90 | 123.40 | 117.80 | 115.30 | 119.40 | 117.20 | 122.00 | 115.40 | 117.50 | 116.30 |
| 5 | 122.70 | 131.50 | 127.00 | 122.60 | 117.75 | 115.20 | 120.10 | 117.10 | 121.00 | 115.40 | 117.40 | 116.80 |
| 6 | 122.90 | 133.10 | 125.20 | 122.10 | 117.60 | 115.10 | 120.00 | 117.10 | 120.00 | 115.40 | 117.25 | 116.80 |
| 7 | 123.10 | 131.20 | 124.20 | 122.10 | 117.50 | 115.10 | 119.80 | 118.00 | 119.50 | 115.50 | 117.10 | 116.80 |
| 8 | 122.30 | 128.70 | 124.30 | 122.30 | 117.30 | 115.50 | 121.60 | 119.70 | 119.00 | 116.10 | 116.95 | 116.60 |
| 9 | 121.10 | 125.60 | 124.70 | 123.10 | 117.10 | 115.65 | 120.80 | 119.90 | 118.70 | 116.70 | 117.00 | 116.50 |
| 10 | (a) | 124.00 | 127.10 | 123.80 | 117.00 | 116.20 | 120.00 | 119.60 | 118.75 | 120.80 | 117.00 | 116.60 |
| 11 | | 122.90 | 131.00 | 124.00 | 116.90 | 116.90 | 119.00 | 119.00 | 118.75 | 127.80 | 117.05 | 116.80 |
| 12 | | 122.80 | 129.70 | 123.50 | 116.60 | 117.45 | 118.70 | 118.60 | 118.50 | 129.20 | 117.00 | 116.00 |
| 13 | | 123.00 | ----- | 123.00 | 116.55 | 117.50 | 118.85 | 118.10 | 118.75 | 128.50 | 116.85 | 116.60 |
| 14 | (b) | 123.30 | 129.40 | 123.00 | 116.50 | 118.30 | 118.50 | 118.00 | 118.60 | 126.40 | 116.50 | 115.50 |
| 15 | | 123.60 | 127.50 | ----- | 116.25 | 119.60 | 118.00 | 117.65 | 118.55 | 123.80 | 116.40 | 115.80 |
| 16 | | 124.50 | 125.30 | ----- | 116.20 | 119.50 | 117.50 | 117.90 | 118.00 | 122.00 | 116.40 | 115.00 |
| 17 | 118.40 | 124.90 | 124.20 | 131.70 | 116.15 | 120.00 | 117.20 | 117.90 | 117.95 | 120.90 | 116.70 | 115.00 |
| 18 | 118.70 | 124.50 | 123.30 | 129.50 | 116.05 | 119.70 | 117.15 | 118.00 | 118.00 | 120.80 | 116.80 | 114.70 |
| 19 | 119.00 | ----- | 122.70 | 126.60 | 115.95 | 119.15 | 119.50 | 117.70 | 118.05 | 121.10 | 125.60 | 115.00 |
| 20 | | 120.30 | 122.00 | 124.80 | 115.95 | 118.75 | 120.60 | 117.40 | 118.50 | 122.50 | 125.00 | 116.00 |
| 21 | 119.50 | 119.30 | 121.70 | 123.60 | 115.95 | 118.65 | 121.80 | 117.10 | 118.00 | 123.10 | 123.10 | 118.50 |
| 22 | 119.80 | 119.10 | 121.80 | 122.60 | 115.85 | 118.40 | 120.60 | 116.80 | 117.60 | 122.30 | 121.60 | 118.60 |
| 23 | 120.00 | 118.70 | 122.60 | 121.80 | 115.75 | 118.10 | 120.00 | 116.60 | 117.40 | 121.30 | 120.40 | 119.70 |
| 24 | 120.10 | 119.50 | 126.80 | 121.10 | 115.85 | 118.50 | 119.50 | 117.00 | 117.10 | 120.50 | 119.70 | 120.50 |
| 25 | 119.60 | 120.60 | 134.10 | 120.50 | 115.85 | ----- | 118.95 | 117.30 | 116.90 | 119.80 | 119.20 | 119.70 |
| 26 | 119.30 | 120.40 | 132.80 | 120.10 | 115.85 | 121.80 | 118.10 | 116.95 | 116.60 | 119.60 | 118.80 | 119.40 |
| 27 | 119.20 | 120.50 | 129.80 | 119.80 | 115.80 | 123.60 | 117.85 | 116.70 | 116.30 | 119.00 | 118.50 | 118.40 |
| 28 | 119.50 | 122.30 | 127.00 | 119.50 | 115.80 | 123.00 | 118.20 | 117.80 | 116.20 | 118.70 | 118.20 | 117.70 |
| 29 | 120.40 | ----- | 125.20 | 119.10 | ----- | 122.30 | 117.80 | 121.30 | 116.00 | 118.40 | 117.70 | 117.50 |
| 30 | 121.10 | ----- | 123.90 | ----- | 115.70 | 122.40 | 117.50 | 122.40 | 115.90 | 118.10 | 117.30 | 117.40 |
| 31 | 122.70 | ----- | 123.50 | ----- | 115.60 | ----- | 118.00 | 124.20 | ----- | 118.00 | ----- | 116.90 |

α Slush ice filled in above gage.

β River frozen over at neck and foot of Gullys Falls.

Mean daily gage height, in feet, of Susquehanna River at McCall's Ferry, Pa., for 1902-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|---------|--------------------|-------|--------------------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| 1904. | | | | | | | | | | | | |
| 1..... | 116.6 | 120.0 | 120.0 | 123.9 | 125.2 | 119.4 | 116.8 | 115.8 | 115.5 | 116.2 | 117.1 | 116.0 |
| 2..... | 116.3 | 119.0 | 121.0 | 129.2 | 124.4 | 119.3 | 116.5 | 115.7 | 115.3 | 116.1 | 116.9 | 115.9 |
| 3..... | 115.9 | 118.5 | 122.0 | 132.6 | 123.3 | 119.9 | 116.3 | 116.0 | 115.1 | 116.0 | 116.8 | 115.8 |
| 4..... | ^a 115.8 | 117.9 | 122.9 | 130.0 | 122.5 | 120.4 | 116.0 | 116.6 | 115.5 | 115.8 | 116.5 | 115.5 |
| 5..... | 116.0 | 117.3 | 128.0 | 127.0 | 121.5 | 120.2 | 116.0 | 116.6 | 115.3 | 115.9 | 116.3 | 115.3 |
| 6..... | 116.5 | 117.0 | 128.0 | 125.0 | 120.9 | 120.8 | 116.0 | 116.4 | 115.1 | 115.6 | 116.2 | 115.3 |
| 7..... | 116.9 | 118.5 | 126.4 | 123.9 | 120.0 | 122.3 | 116.2 | 116.6 | 115.0 | 115.8 | 115.9 | 115.1 |
| 8..... | 115.8 | 119.4 | ^b 146.6 | 123.1 | 119.8 | 121.4 | 116.5 | 116.7 | 114.9 | 115.7 | 115.7 | 115.0 |
| 9..... | 115.5 | 121.5 | 130.2 | 123.2 | 119.5 | 120.1 | 117.0 | 116.7 | 114.8 | 115.6 | 115.5 | 114.8 |
| 10..... | 115.5 | 125.0 | 130.4 | 123.4 | 119.3 | 119.9 | 117.5 | 117.0 | 114.7 | 115.4 | 115.7 | 114.7 |
| 11..... | 116.0 | 125.7 | 130.9 | 124.6 | 119.0 | 119.6 | 119.9 | 117.5 | 114.7 | 115.3 | 115.5 | 114.5 |
| 12..... | 116.8 | 124.3 | 126.6 | 127.3 | 118.6 | 121.7 | 121.0 | 117.0 | 114.8 | 115.4 | 115.5 | 114.4 |
| 13..... | 117.1 | 122.7 | 124.9 | 125.9 | 118.3 | 121.0 | 121.1 | 116.4 | 115.0 | 115.4 | 115.6 | 114.2 |
| 14..... | 117.3 | 121.9 | 123.6 | 124.4 | 118.3 | 119.9 | 119.9 | 116.0 | 115.3 | 115.4 | 115.9 | 114.2 |
| 15..... | 117.3 | 121.0 | 122.3 | 123.6 | 118.2 | 119.3 | 119.0 | 115.7 | 115.8 | 115.4 | 116.0 | 114.4 |
| 16..... | 117.4 | 120.4 | 121.5 | 122.6 | 119.0 | 118.5 | 118.5 | 115.5 | 116.1 | 115.4 | 116.0 | 115.3 |
| 17..... | 117.0 | 119.5 | 121.1 | 121.9 | 119.5 | 118.3 | 118.7 | 115.3 | 116.4 | 118.2 | 115.9 | 114.6 |
| 18..... | 116.6 | 118.6 | 120.7 | 121.6 | 119.7 | 118.0 | 117.4 | 115.2 | 117.0 | 118.0 | 115.8 | 114.6 |
| 19..... | 116.4 | 118.0 | 120.9 | 121.0 | 120.3 | 118.0 | 117.0 | 115.2 | 116.8 | 117.5 | 115.7 | 114.6 |
| 20..... | 116.0 | 117.8 | 121.0 | 120.6 | 121.3 | 117.9 | 116.8 | 115.3 | 116.5 | 116.8 | 115.7 | 114.5 |
| 21..... | 116.0 | 118.0 | 121.6 | 120.2 | 122.7 | 117.8 | 116.6 | 115.7 | 116.3 | 117.0 | 115.7 | 114.6 |
| 22..... | 117.4 | 120.0 | 122.6 | 120.1 | 123.8 | 117.2 | 116.5 | 115.6 | 116.0 | 117.3 | 115.6 | 114.5 |
| 23..... | 122.3 | 120.9 | 123.0 | 119.9 | 122.8 | 118.0 | 116.4 | 115.5 | 115.8 | 117.5 | 115.5 | 114.5 |
| 24..... | ^c 120.7 | 120.1 | 123.9 | 119.5 | 121.0 | 117.9 | 116.4 | 115.4 | 115.6 | 118.7 | 115.7 | 114.8 |
| 25..... | 129.3 | 120.7 | 128.3 | 119.3 | 120.6 | 118.0 | 117.8 | 115.3 | 115.2 | 119.7 | 115.7 | 115.0 |
| 26..... | 126.8 | 120.7 | 130.0 | 119.2 | 119.9 | 117.8 | 117.4 | 115.4 | 114.9 | 120.0 | 115.8 | 114.9 |
| 27..... | 124.0 | 120.3 | 131.6 | 119.3 | 120.2 | 117.3 | 116.5 | 115.7 | 114.8 | 119.3 | 116.0 | 115.0 |
| 28..... | 123.0 | 119.8 | 132.9 | 119.7 | 119.9 | 116.9 | 116.3 | 116.9 | 114.6 | 118.5 | 116.3 | 115.1 |
| 29..... | 122.3 | 119.0 | 130.7 | 121.0 | 119.6 | 116.8 | 116.0 | 116.6 | 114.8 | 117.9 | 115.7 | 115.5 |
| 30..... | 121.4 | ----- | 128.9 | 122.1 | 119.0 | 116.7 | 116.0 | 116.1 | 115.8 | 117.8 | 116.1 | 116.2 |
| 31..... | 120.5 | ----- | 125.3 | ----- | 119.6 | ----- | 115.9 | 115.8 | ----- | 117.5 | ----- | 123.0 |

^a Entire river covered with 14 to 18 inch ice.

^b Ice moved 2 p.m.

^c Ice broke and went out of deeps at 5.30 p. m.; 133.8 maximum reading during night, 24th and 25th.


Rating table for Susquehanna River at McCalls Ferry, Pa., for 1902 to 1904.

| Gage height. | Discharge. | Gage height. | Discharge. | Gage height. | Discharge. | Gage height. | Discharge. |
|--------------|---------------------|--------------|---------------------|--------------|---------------------|--------------|---------------------|
| <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> |
| 114.0 | 5,160 | 116.4 | 15,610 | 120.6 | 44,200 | 126.0 | 112,900 |
| 114.1 | 5,500 | 116.5 | 16,150 | 120.8 | 46,100 | 126.5 | 119,900 |
| 114.2 | 5,840 | 116.6 | 16,690 | 121.0 | 48,000 | 127.0 | 127,000 |
| 114.3 | 6,200 | 116.7 | 17,240 | 121.2 | 50,000 | 127.5 | 134,100 |
| 114.4 | 6,560 | 116.8 | 17,800 | 121.4 | 52,100 | 128.0 | 141,100 |
| 114.5 | 6,930 | 116.9 | 18,360 | 121.6 | 54,300 | 128.5 | 148,300 |
| 114.6 | 7,310 | 117.0 | 18,930 | 121.8 | 56,600 | 129.0 | 155,300 |
| 114.7 | 7,700 | 117.2 | 20,120 | 122.0 | 59,000 | 129.5 | 163,400 |
| 114.8 | 8,100 | 117.4 | 21,320 | 122.2 | 61,500 | 130.0 | 172,500 |
| 114.9 | 8,500 | 117.6 | 22,560 | 122.4 | 64,000 | 130.5 | 182,800 |
| 115.0 | 8,920 | 117.8 | 23,820 | 122.6 | 66,500 | 131.0 | 194,100 |
| 115.1 | 9,340 | 118.0 | 25,110 | 122.8 | 69,000 | 131.5 | 205,800 |
| 115.2 | 9,770 | 118.2 | 26,430 | 123.0 | 71,500 | 132.0 | 217,300 |
| 115.3 | 10,210 | 118.4 | 27,780 | 123.2 | 74,000 | 132.5 | 228,600 |
| 115.4 | 10,660 | 118.6 | 29,140 | 123.4 | 76,400 | 133.0 | 240,000 |
| 115.5 | 11,120 | 118.8 | 30,500 | 123.6 | 78,900 | 133.5 | 251,200 |
| 115.6 | 11,580 | 119.0 | 31,900 | 123.8 | 81,500 | 134.0 | 262,000 |
| 115.7 | 12,060 | 119.2 | 33,300 | 124.0 | 84,200 | 134.5 | 273,600 |
| 115.8 | 12,540 | 119.4 | 34,700 | 124.2 | 87,000 | 135.0 | 285,300 |
| 115.9 | 13,040 | 119.6 | 36,100 | 124.4 | 89,900 | 135.5 | 297,200 |
| 116.0 | 13,540 | 119.8 | 37,500 | 124.6 | 92,800 | 136.0 | 309,300 |
| 116.1 | 14,040 | 120.0 | 39,100 | 124.8 | 95,700 | | |
| 116.2 | 14,560 | 120.2 | 40,700 | 125.0 | 98,600 | | |
| 116.3 | 15,080 | 120.4 | 42,400 | 125.5 | 105,900 | | |


Gage height at gage No. 2 = Elev. of W.S. above mean sea level

at York Furnace
" Duncan Run
its at cable
small Price meter
large " "
" " "

show G.H. $120 = (y - 111)^2 = (1.032 + .051'y) x$
on of whole curve $(y - 111)^2 = 2.020 x$
1000 sec.-ft.



RIVER AT McCALLS FERRY, PA.



RATING CURVE FOR SUSQUEHANNA RIVER AT McCALLS FERRY, PA.

*Mean daily discharge, in second-feet, of Susquehanna River at McCall's Ferry,
Pa., for 1902-1904.*

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|--------|---------|---------|---------|--------|--------|---------|--------|---------|---------|---------|---------|
| 1902. | | | | | | | | | | | | |
| 1. | | | | | | 14,300 | 21,940 | 60,200 | 8,510 | 43,300 | 60,200 | 19,830 |
| 2. | | | | | | 14,300 | 50,000 | 55,400 | 8,510 | 66,500 | 51,100 | 21,320 |
| 3. | | | | | | 12,550 | 80,200 | 53,200 | 8,100 | 67,700 | 39,900 | 28,120 |
| 4. | | | | | | 12,550 | 72,700 | 61,500 | 8,300 | 60,200 | 36,000 | 33,500 |
| 5. | | | | | | 12,550 | 73,550 | 59,000 | 8,100 | 53,200 | 31,900 | 36,000 |
| 6. | | | | | | 10,450 | 88,500 | 50,000 | 7,300 | 52,100 | 28,460 | 34,600 |
| 7. | | | | | | 9,990 | 78,250 | 44,200 | 7,120 | 51,100 | 26,430 | 34,600 |
| 8. | | | | | | 9,770 | 78,250 | 34,600 | 6,930 | 47,050 | 25,110 | 32,500 |
| 9. | | | | | | 9,770 | 105,900 | 30,870 | 7,300 | 39,100 | 23,820 | 32,500 |
| 10. | | | | | | 11,120 | 91,300 | 28,460 | 7,500 | 35,300 | 22,250 | 30,000 |
| 11. | | | | | | 11,820 | 70,200 | 31,210 | 7,120 | 30,530 | 21,320 | 28,000 |
| 12. | | | | | | 11,580 | 60,200 | 31,900 | 7,500 | 33,200 | 19,530 | 25,770 |
| 13. | | | | | | 11,580 | 65,300 | 29,840 | 8,100 | 52,100 | 18,940 | 35,300 |
| 14. | | | | | | 12,060 | 57,200 | 25,770 | 7,900 | 48,000 | 18,360 | 39,900 |
| 15. | | | | | | 14,560 | 46,100 | 23,500 | 7,900 | 43,300 | 17,250 | 33,900 |
| 16. | | | | | | 14,560 | 40,700 | 21,940 | 7,700 | 36,000 | 16,630 | 34,600 |
| 17. | | | | | | 15,340 | 33,900 | 20,120 | 7,500 | 31,900 | 16,150 | 71,500 |
| 18. | | | | | | 17,800 | 29,500 | 18,640 | 7,500 | 31,000 | 15,610 | 117,800 |
| 19. | | | | | | 15,880 | 26,430 | 17,250 | 7,120 | 29,840 | 15,340 | 110,800 |
| 20. | | | | | | 16,970 | 23,820 | 15,080 | 6,930 | 26,430 | 15,080 | 98,600 |
| 21. | | | | | | 16,690 | 24,460 | 14,560 | 6,560 | 23,820 | 14,560 | 91,300 |
| 22. | | | | | | 15,340 | 20,720 | 13,540 | 6,930 | 21,940 | 14,050 | 136,200 |
| 23. | | | | | | 15,080 | 69,600 | 12,550 | 6,590 | 20,120 | 13,540 | 205,800 |
| 24. | | | | | | 14,300 | 77,000 | 12,300 | 6,200 | 18,360 | 13,290 | 205,800 |
| 25. | | | | | | 13,290 | 84,900 | 12,300 | 6,380 | 18,940 | 13,540 | 170,600 |
| 26. | | | | | | 14,300 | 82,150 | 12,060 | 7,300 | 18,940 | 14,560 | 119,900 |
| 27. | | | | | | 15,610 | 94,300 | 11,350 | 28,800 | 18,360 | 18,080 | 88,500 |
| 28. | | | | | | 16,970 | 82,150 | 10,660 | 48,000 | 19,530 | 19,000 | 70,200 |
| 29. | | | | | | 17,530 | 61,500 | 10,210 | 39,100 | 29,840 | 19,830 | 62,800 |
| 30. | | | | | | 18,640 | 57,800 | 9,770 | 37,900 | 59,000 | 19,830 | 48,000 |
| 31. | | | | | | | 66,500 | 8,920 | | 59,000 | | 44,200 |
| 1903. | | | | | | | | | | | | |
| 1. | 39,900 | 194,100 | 235,400 | 72,700 | 29,150 | 11,350 | 71,500 | 25,110 | 127,000 | 12,300 | 23,820 | 18,940 |
| 2. | 35,300 | 158,400 | 309,300 | 76,400 | 20,430 | 11,120 | 62,800 | 23,180 | 95,700 | 12,300 | 23,500 | 17,800 |
| 3. | 51,000 | 124,100 | 253,400 | 81,500 | 25,110 | 10,660 | 38,300 | 21,940 | 74,000 | 11,120 | 22,560 | 16,690 |
| 4. | 60,200 | 119,900 | 170,600 | 76,400 | 23,820 | 10,210 | 34,600 | 20,120 | 59,000 | 10,660 | 21,940 | 15,080 |
| 5. | 67,700 | 205,800 | 127,000 | 66,500 | 23,500 | 9,770 | 39,900 | 19,530 | 48,000 | 10,660 | 21,320 | 17,800 |
| 6. | 70,200 | 242,300 | 101,500 | 60,200 | 22,560 | 9,350 | 39,100 | 19,530 | 39,100 | 10,660 | 20,420 | 17,800 |
| 7. | 72,700 | 198,800 | 87,000 | 60,200 | 21,940 | 9,350 | 37,500 | 25,110 | 35,300 | 11,120 | 19,530 | 17,800 |
| 8. | 62,800 | 151,100 | 88,500 | 62,800 | 20,720 | 11,120 | 54,300 | 36,750 | 31,900 | 14,050 | 18,640 | 16,690 |
| 9. | 49,000 | 107,300 | 94,300 | 72,700 | 19,530 | 11,820 | 46,100 | 38,300 | 29,840 | 17,250 | 18,940 | 16,150 |
| 10. | 46,200 | 84,200 | 128,500 | 81,500 | 18,940 | 14,560 | 39,100 | 36,000 | 30,180 | 46,100 | 18,940 | 16,690 |
| 11. | 43,600 | 70,200 | 194,100 | 84,200 | 18,360 | 18,360 | 31,900 | 31,900 | 30,180 | 138,300 | 19,230 | 15,080 |
| 12. | 41,000 | 69,000 | 167,000 | 77,600 | 16,690 | 21,630 | 29,840 | 29,150 | 28,460 | 158,400 | 18,940 | 13,540 |
| 13. | 38,400 | 71,500 | 164,000 | 71,500 | 16,420 | 21,940 | 30,870 | 25,770 | 30,180 | 148,300 | 18,080 | 16,690 |
| 14. | 35,800 | 75,200 | 161,700 | 71,500 | 16,150 | 27,100 | 28,460 | 25,110 | 29,150 | 118,500 | 16,690 | 13,540 |
| 15. | 33,200 | 78,900 | 134,100 | 120,000 | 14,820 | 36,000 | 25,110 | 22,870 | 28,800 | 81,500 | 16,150 | 11,120 |
| 16. | 30,600 | 91,300 | 103,000 | 200,000 | 14,560 | 35,300 | 21,940 | 24,460 | 25,110 | 59,000 | 15,610 | 10,210 |
| 17. | 27,780 | 97,100 | 87,000 | 210,400 | 14,300 | 39,100 | 20,120 | 24,460 | 24,780 | 47,050 | 17,250 | 8,920 |
| 18. | 29,840 | 91,300 | 75,200 | 163,400 | 13,800 | 36,750 | 19,830 | 25,110 | 25,110 | 46,100 | 17,800 | 7,700 |
| 19. | 31,900 | 66,000 | 67,700 | 121,300 | 13,290 | 32,800 | 35,300 | 23,180 | 25,440 | 49,000 | 107,300 | 8,920 |
| 20. | 33,000 | 41,550 | 59,000 | 95,700 | 13,290 | 30,180 | 44,200 | 21,320 | 28,460 | 65,300 | 98,600 | 13,540 |
| 21. | 35,300 | 33,900 | 55,400 | 78,900 | 13,290 | 29,500 | 56,600 | 19,530 | 25,110 | 72,700 | 72,700 | 28,460 |
| 22. | 37,500 | 32,500 | 56,600 | 66,500 | 12,800 | 27,780 | 44,200 | 17,800 | 22,560 | 62,800 | 54,300 | 29,150 |
| 23. | 39,100 | 29,840 | 66,500 | 56,600 | 12,300 | 25,770 | 39,100 | 16,690 | 21,320 | 51,100 | 42,400 | 36,750 |
| 24. | 39,900 | 35,300 | 124,100 | 49,000 | 12,800 | 28,460 | 35,300 | 18,940 | 19,530 | 43,300 | 36,750 | 43,300 |
| 25. | 36,000 | 44,200 | 264,300 | 43,300 | 12,800 | 42,000 | 31,550 | 20,720 | 18,360 | 37,500 | 33,200 | 36,750 |
| 26. | 33,900 | 42,400 | 235,400 | 39,900 | 12,800 | 56,600 | 25,770 | 18,640 | 16,690 | 36,000 | 30,530 | 34,600 |
| 27. | 33,200 | 43,300 | 168,800 | 37,500 | 12,550 | 78,900 | 24,140 | 17,250 | 15,080 | 31,900 | 28,460 | 27,780 |
| 28. | 35,300 | 62,800 | 127,000 | 35,300 | 12,550 | 71,500 | 26,430 | 23,820 | 14,560 | 29,840 | 26,430 | 23,180 |
| 29. | 42,400 | | 101,500 | 32,500 | 12,300 | 62,800 | 23,820 | 51,100 | 13,540 | 27,780 | 23,180 | 21,940 |
| 30. | 49,000 | | 82,800 | 31,000 | 12,060 | 64,000 | 21,940 | 64,000 | 13,040 | 25,770 | 20,720 | 21,320 |
| 31. | 67,700 | | 77,600 | | 11,580 | | 25,110 | 87,000 | | 25,110 | | 18,360 |

a Estimated.

Mean daily discharge, in second-feet, of Susquehanna River at McCalls Ferry, Pa., for 1902-1904—Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|---------|---------|---------|---------|---------|--------|--------|--------|--------|--------|--------|--------|
| 1904. | | | | | | | | | | | | |
| 1 | 16,690 | 39,100 | 39,100 | 82,800 | 101,500 | 34,700 | 17,800 | 12,540 | 11,120 | 14,560 | 19,520 | 13,540 |
| 2 | 15,080 | 31,900 | 48,000 | 158,400 | 89,900 | 34,000 | 16,150 | 12,060 | 10,210 | 14,040 | 18,360 | 13,040 |
| 3 | 13,040 | 28,460 | 59,000 | 230,900 | 75,200 | 38,300 | 15,080 | 13,540 | 9,340 | 13,540 | 17,800 | 12,540 |
| 4 | 12,540 | 24,460 | 70,200 | 172,500 | 65,300 | 42,400 | 13,540 | 16,690 | 11,120 | 12,540 | 16,150 | 11,120 |
| 5 | 13,540 | 20,720 | 141,100 | 127,000 | 53,200 | 40,700 | 13,540 | 16,690 | 10,210 | 13,040 | 15,080 | 10,210 |
| 6 | 16,150 | 18,930 | 141,100 | 98,600 | 47,050 | 46,100 | 13,540 | 15,610 | 9,340 | 11,120 | 14,560 | 10,210 |
| 7 | 18,360 | 28,460 | 118,500 | 82,800 | 39,100 | 62,800 | 14,560 | 16,690 | 8,920 | 12,540 | 13,040 | 9,340 |
| 8 | 12,540 | 34,700 | 300,000 | 72,700 | 37,500 | 52,100 | 16,150 | 17,240 | 8,500 | 12,060 | 12,060 | 8,920 |
| 9 | 11,120 | 53,200 | 176,500 | 74,000 | 35,400 | 39,900 | 18,930 | 17,240 | 8,100 | 11,120 | 11,120 | 8,100 |
| 10 | 11,120 | 98,600 | 180,700 | 76,400 | 34,000 | 38,300 | 21,940 | 18,930 | 7,700 | 10,660 | 12,060 | 7,700 |
| 11 | 13,540 | 108,700 | 192,000 | 92,800 | 31,900 | 36,100 | 38,300 | 21,940 | 7,700 | 10,210 | 11,120 | 6,930 |
| 12 | 17,800 | 88,500 | 121,300 | 131,300 | 29,140 | 55,400 | 48,000 | 18,930 | 8,100 | 10,660 | 11,120 | 6,560 |
| 13 | 19,520 | 67,700 | 97,100 | 111,500 | 27,100 | 48,000 | 49,000 | 15,610 | 8,920 | 10,660 | 11,580 | 5,840 |
| 14 | 20,720 | 57,800 | 78,900 | 89,900 | 27,100 | 38,300 | 38,300 | 13,540 | 10,210 | 10,660 | 13,040 | 5,840 |
| 15 | 20,720 | 48,000 | 62,800 | 78,900 | 26,430 | 34,000 | 31,900 | 12,060 | 12,540 | 10,210 | 13,540 | 6,560 |
| 16 | 21,320 | 42,400 | 53,200 | 66,500 | 31,900 | 28,460 | 28,460 | 11,120 | 14,040 | 10,660 | 13,540 | 10,210 |
| 17 | 18,930 | 35,400 | 49,000 | 57,800 | 35,400 | 27,100 | 29,820 | 10,210 | 15,610 | 26,430 | 13,040 | 7,310 |
| 18 | 16,690 | 29,140 | 45,100 | 54,300 | 36,800 | 25,110 | 21,320 | 9,770 | 18,930 | 25,100 | 12,540 | 7,310 |
| 19 | 15,610 | 25,110 | 47,050 | 48,000 | 41,550 | 25,110 | 18,930 | 9,770 | 17,800 | 21,940 | 12,660 | 7,310 |
| 20 | 13,540 | 23,820 | 48,000 | 44,200 | 51,100 | 24,460 | 17,800 | 10,210 | 16,150 | 17,800 | 12,060 | 6,930 |
| 21 | 13,540 | 25,110 | 54,300 | 40,700 | 67,700 | 23,820 | 16,690 | 12,060 | 15,080 | 18,930 | 12,060 | 7,310 |
| 22 | 21,320 | 39,100 | 66,500 | 39,900 | 81,500 | 20,120 | 16,150 | 11,580 | 13,540 | 20,720 | 11,580 | 6,930 |
| 23 | 62,800 | 47,050 | 71,500 | 38,300 | 69,000 | 25,110 | 15,610 | 11,120 | 12,540 | 21,940 | 11,120 | 6,930 |
| 24 | 45,100 | 39,900 | 82,800 | 35,400 | 48,000 | 24,460 | 15,610 | 10,660 | 11,580 | 29,820 | 12,060 | 8,100 |
| 25 | 160,000 | 45,100 | 145,500 | 34,000 | 44,200 | 25,110 | 23,820 | 10,210 | 9,770 | 36,800 | 12,060 | 8,920 |
| 26 | 124,100 | 45,100 | 172,500 | 33,300 | 38,300 | 23,820 | 21,320 | 10,660 | 8,500 | 39,100 | 12,540 | 8,500 |
| 27 | 84,200 | 41,550 | 208,100 | 34,000 | 40,700 | 20,720 | 16,150 | 12,060 | 8,100 | 34,000 | 13,540 | 8,920 |
| 28 | 71,500 | 37,500 | 237,700 | 36,800 | 38,300 | 18,360 | 15,080 | 18,360 | 7,310 | 28,460 | 15,080 | 9,340 |
| 29 | 62,800 | 31,900 | 187,200 | 48,000 | 36,100 | 17,800 | 13,540 | 16,690 | 8,100 | 24,460 | 12,060 | 11,120 |
| 30 | 52,100 | ----- | 153,900 | 60,200 | 31,900 | 17,240 | 13,540 | 14,040 | 12,540 | 23,820 | 14,040 | 14,560 |
| 31 | 43,300 | ----- | 103,000 | ----- | 36,100 | ----- | 13,040 | 12,540 | ----- | 21,940 | ----- | 71,500 |

α Maximum discharge, 631,000. Mean daily discharge estimated.

Estimated monthly discharge of Susquehanna River at McCalls Ferry, Pa., 1902-1904.

[Drainage area 26,766 square miles.]

| Month. | Discharge in second-feet. | | | Run-off. | |
|-----------|---------------------------|----------|--------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1902. | | | | | |
| June | 18,640 | 9,770 | 13,908 | 0.519 | 0.580 |
| July | 105,900 | 20,720 | 61,768 | 2.307 | 2.658 |
| August | 61,500 | 8,920 | 27,126 | 1.013 | 1.168 |
| September | 48,000 | 6,200 | 11,556 | .431 | .481 |
| October | 67,700 | 18,360 | 38,248 | 1.429 | 1.649 |
| November | 60,200 | 13,290 | 22,657 | .846 | .944 |
| December | 205,800 | 19,830 | 69,111 | 2.582 | 2.977 |

*Estimated monthly discharge of Susquehanna River at McCall's Ferry, Pa.,
1902-1904—Continued.*

| Month. | Discharge in second-feet. | | | Run off. | |
|-----------------|---------------------------|----------|---------|------------------------------------|---------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1903. | | | | | |
| January | 72,700 | 27,780 | 43,533 | 1.626 | 1.877 |
| February | 242,300 | 29,840 | 95,082 | 3.552 | 3.698 |
| March | 309,300 | 55,400 | 134,461 | 5.023 | 5.791 |
| April | 210,400 | 31,000 | 79,900 | 2.910 | 3.247 |
| May | 29,150 | 11,580 | 16,826 | .628 | .724 |
| June | 78,900 | 9,350 | 29,859 | 1.115 | 1.244 |
| July | 71,500 | 19,830 | 35,636 | 1.331 | 1.535 |
| August | 87,000 | 16,690 | 28,206 | 1.053 | 1.214 |
| September | 127,000 | 13,040 | 34,183 | 1.277 | 1.426 |
| October | 158,400 | 10,660 | 48,757 | 1.822 | 2.102 |
| November | 107,300 | 15,610 | 30,797 | 1.151 | 1.284 |
| December | 43,300 | 7,700 | 19,751 | .737 | .848 |
| The year | 309,300 | 7,700 | 49,638 | 1.854 | 25.019 |
| 1904. | | | | | |
| January | 160,000 | 11,120 | 34,170 | 1.280 | 1.480 |
| February | 108,700 | 18,930 | 43,360 | 1.620 | 1.750 |
| March | 300,000 | 39,100 | 114,600 | 4.280 | 4.930 |
| April | 230,900 | 33,300 | 78,400 | 2.930 | 3.270 |
| May | 101,500 | 26,430 | 46,720 | 1.750 | 2.020 |
| June | 62,800 | 17,240 | 34,580 | 1.290 | 1.440 |
| July | 49,000 | 13,040 | 21,410 | .800 | .922 |
| August | 21,940 | 9,770 | 13,880 | .519 | .598 |
| September | 18,930 | 7,310 | 11,050 | .413 | .461 |
| October | 39,100 | 10,210 | 18,700 | .698 | .805 |
| November | 19,520 | 11,120 | 13,320 | .498 | .556 |
| December | 71,500 | 5,840 | 10,890 | .407 | .469 |
| The year | 300,000 | 5,840 | 36,760 | 1.370 | 18.700 |

CHEMUNG RIVER AT CHEMUNG, N. Y.^a

A gaging station was established at the suspension bridge across Chemung River near Chemung station, September 7, 1903. Gage heights are taken each morning and night, by Daniel L. Orcutt, by a chain gage attached to the bridge. Current-meter measurements which have been made, and the mean daily stage of the stream, are shown in the accompanying tables. The gaging station is located 1 mile upstream from the New York-Pennsylvania line, and is shown on the Waverly sheet of the United States Geological Survey's topographic map of the country.

Chemung River is formed at Painted Post, N. Y., by the union of Tioga and Cohocton rivers. The Cohocton branch lies entirely in the State of New York. Tioga River receives, just above its mouth, Canisteo River, a large tributary, which also has its drainage basin in New York to the south of the Cohocton. The drainage of Tioga River above the Canisteo is mainly in Pennsylvania. The concentration, just above Corning, of the storm waters of these three main branches favors the formation of excessive floods.

Chemung River flows southeasterly through Corning, Elmira, and Chemung, crosses the State line, flows for a short distance in Pennsylvania, then returns to New York and again crosses to Pennsylvania near Waverly, finally emptying into Susquehanna River near Athens, Bradford County, Pa. The total length of the stream is about 40 miles, about 30 miles of which is in New York State. Chemung River is a sluggish stream with low banks and a broad valley or flood plain, which is often overflowed. It was formerly paralleled by a canal taking its supply from dams across the stream. This has been abandoned and at present the largest water-power development on the main river is at Elmira.

The topographic features of the drainage basin are, as a rule, bold and broad. The hills rise within a short distance of the stream several hundred feet on either side, and the upland plateau is to a large extent wooded, with impervious soil, no lake storage, and few marsh areas. Tributaries are ramifying and uniformly distributed, though not numerous, and dry gulleys or flood channels are common. Dikes have been erected in the cities of Elmira and Corning for protection against floods. One of the highest recorded freshets in the stream occurred June 1, 1889. It was preceded by phenomenal rainfall, on the night of May 31 and June 1, aggregating several inches in the course of a few hours. The discharge has been estimated at 67 second-feet per square mile from 2,055 square miles, or 138,000 cubic feet per second.^b

^a Data on pages 140-153, inclusive, from Supplement of 1903 Report of New York State Engineer.

^b Report of Francis Collingwood, C. E., on The Protection of the City of Elmira, N. Y., against Floods.

Discharge measurements of Chemung River at Chemung, N. Y.

| Date. | Hydrographer. | Gage height. | Discharge. |
|-------------------|--------------------|-----------------|---------------------|
| 1903. | | <i>Feet.</i> | <i>Second-feet.</i> |
| August 27 ----- | C. C. Covert ----- | 2.89 | 809 |
| September 7 ----- | R. E. Horton ----- | 3.29 | 1,354 |
| October 2 ----- | H. H. Halsey ----- | 2.47 | 611 |
| October 12 ----- | C. C. Covert ----- | 6.72 | 8,766 |
| 1904. | | | |
| March 11 ----- | C. C. Covert ----- | 5.75 | 6,170 |
| April 9 ----- | R. E. Horton ----- | 5.64 | 5,717 |
| July 15 ----- | C. C. Covert ----- | 3.05 | 1,042 |
| September 9 ----- | do ----- | 1.90 | 220 |

Mean daily gage height, in feet, of Chemung River at Chemung, N. Y.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|---------|---------|---------|------|------|-------|-------|------|-------|------|------|------|
| 1903. | | | | | | | | | | | | |
| 1 | | | | | | | | | | 2.24 | 2.98 | 2.90 |
| 2 | | | | | | | | | | 2.40 | 2.88 | 2.88 |
| 3 | | | | | | | | | | 2.52 | 2.88 | 2.88 |
| 4 | | | | | | | | | | 2.57 | 2.83 | 2.88 |
| 5 | | | | | | | | | | 2.74 | 2.86 | 2.82 |
| 6 | | | | | | | | | | 3.30 | 2.90 | 2.59 |
| 7 | | | | | | | | | 3.29 | 3.37 | 3.08 | 3.69 |
| 8 | | | | | | | | | 2.24 | 4.62 | 2.98 | 2.79 |
| 9 | | | | | | | | | 3.19 | 9.97 | 4.93 | 2.69 |
| 10 | | | | | | | | | 3.16 | 7.78 | 2.90 | 2.64 |
| 11 | | | | | | | | | 4.84 | 8.80 | 2.88 | 2.49 |
| 12 | | | | | | | | | 4.56 | 6.74 | 2.86 | 2.49 |
| 13 | | | | | | | | | 3.84 | 6.12 | 2.80 | 2.69 |
| 14 | | | | | | | | | 3.46 | 4.97 | 2.73 | 2.69 |
| 15 | | | | | | | | | 3.22 | 4.47 | 2.68 | 2.69 |
| 16 | | | | | | | | | 3.06 | 4.20 | 2.76 | 2.74 |
| 17 | | | | | | | | | 2.96 | 3.92 | 7.06 | 2.74 |
| 18 | | | | | | | | | 3.44 | 7.04 | 8.13 | 2.64 |
| 19 | | | | | | | | | 3.46 | 6.24 | 5.88 | 2.64 |
| 20 | | | | | | | | | 3.29 | 4.90 | 4.88 | 2.64 |
| 21 | | | | | | | | | 2.99 | 4.42 | 4.26 | 2.69 |
| 22 | | | | | | | | | 2.84 | 4.12 | 3.98 | 2.74 |
| 23 | | | | | | | | | 2.54 | 3.87 | 3.88 | 2.79 |
| 24 | | | | | | | | | 2.34 | 4.72 | 3.83 | 2.79 |
| 25 | | | | | | | | | 2.34 | 3.54 | 3.78 | 2.79 |
| 26 | | | | | | | | | 2.29 | 3.44 | 3.88 | 2.74 |
| 27 | | | | | | | | | 2.24 | 3.32 | 3.23 | 2.69 |
| 28 | | | | | | | | | 2.24 | 3.30 | 3.10 | 2.54 |
| 29 | | | | | | | | | 2.22 | 3.24 | 3.10 | 2.44 |
| 30 | | | | | | | | | 2.26 | 3.22 | 3.10 | 2.54 |
| 31 | | | | | | | | | | 3.13 | | 2.64 |
| 1904. | | | | | | | | | | | | |
| 1 | 3.00 | a 3.85 | 3.57 | 6.50 | 7.20 | 7.05 | 2.60 | 2.50 | 2.00 | 2.35 | 2.40 | 2.05 |
| 2 | 2.95 | 3.50 | 3.37 | 9.00 | 6.25 | 5.85 | 2.88 | 2.42 | 2.02 | 2.42 | 2.50 | 2.00 |
| 3 | 2.90 | 3.45 | 3.67 | 7.05 | 5.45 | 5.35 | 2.70 | 2.98 | 2.00 | 2.22 | 2.22 | 1.90 |
| 4 | 2.90 | 3.35 | 8.57 | 5.75 | 5.02 | 4.85 | 2.62 | 2.82 | 1.95 | 2.10 | 2.20 | 1.90 |
| 5 | 2.90 | 4.00 | 5.72 | 5.38 | 4.62 | 7.70 | 2.60 | 2.70 | 2.00 | 2.15 | 2.25 | 1.90 |
| 6 | 2.90 | 4.20 | 4.72 | 5.15 | 4.40 | 5.95 | 2.58 | 2.60 | 1.98 | 2.18 | 2.20 | 1.90 |
| 7 | 2.85 | 5.90 | 7.69 | 5.20 | 4.18 | 5.10 | 2.35 | 2.45 | 1.92 | 1.88 | 2.20 | 1.85 |
| 8 | 2.90 | a 16.70 | b 15.97 | 5.25 | 4.00 | 4.62 | 2.85 | 2.35 | 1.95 | 1.95 | 2.22 | 1.65 |
| 9 | 3.00 | 8.70 | 9.68 | 5.75 | 3.80 | 5.35 | 2.72 | 2.20 | 1.90 | 1.90 | 2.12 | 2.25 |
| 10 | 3.00 | 6.85 | 6.48 | 9.55 | 3.70 | 6.15 | 2.75 | 2.15 | 1.90 | 1.95 | 2.18 | 2.10 |
| 11 | 3.00 | 5.85 | 5.02 | 7.40 | 3.58 | 4.90 | 3.90 | 2.20 | 1.95 | 1.95 | 2.20 | 2.10 |
| 12 | 3.00 | 5.40 | 4.90 | 6.55 | 3.40 | 4.42 | 3.68 | 2.18 | 1.95 | 2.10 | 2.20 | 2.10 |
| 13 | 3.00 | 4.75 | 4.50 | 5.75 | 3.38 | 4.00 | 3.45 | 2.10 | 1.95 | 2.62 | 2.12 | 2.00 |
| 14 | 3.00 | 4.22 | 4.30 | 5.15 | 3.30 | 3.70 | 3.45 | 2.08 | 1.90 | 3.65 | 2.08 | 2.00 |
| 15 | 3.00 | 3.95 | 4.05 | 4.80 | 5.15 | 3.48 | 3.02 | 2.00 | 1.90 | 3.15 | 2.05 | 2.00 |
| 16 | c 3.15 | 3.65 | 3.88 | 4.80 | 6.75 | 4.05 | 2.82 | 2.00 | 1.90 | 2.82 | 2.25 | 2.00 |
| 17 | 3.20 | d 4.85 | 3.62 | 4.80 | 5.65 | 3.80 | 2.70 | 2.00 | 1.90 | 2.70 | 2.15 | 1.90 |
| 18 | 3.20 | 4.55 | 3.78 | 5.10 | 5.00 | 3.42 | 2.62 | 1.95 | 1.90 | 2.60 | 2.20 | 1.90 |
| 19 | 3.20 | e 4.30 | 3.92 | 5.10 | 9.45 | 3.22 | 2.50 | 1.95 | 1.90 | 2.50 | 2.05 | 1.95 |
| 20 | 3.20 | 4.15 | 5.98 | 4.85 | 8.40 | 3.12 | 2.40 | 2.05 | 1.88 | 2.45 | 2.00 | 2.00 |
| 21 | 3.35 | 4.00 | 6.78 | 4.42 | 6.60 | 3.02 | 2.30 | 2.05 | 1.80 | 2.52 | 2.00 | 2.10 |
| 22 | 3.50 | f 4.12 | 5.20 | 4.55 | 5.40 | 3.10 | 2.35 | 2.30 | 1.75 | 3.40 | 2.00 | 2.05 |
| 23 | g 11.35 | 4.05 | h 10.90 | 4.60 | 4.95 | 3.05 | 2.25 | 2.75 | 1.80 | 3.40 | 2.00 | 2.18 |
| 24 | a 9.55 | 4.32 | 11.40 | 4.50 | 5.35 | 3.05 | 2.72 | 2.88 | 1.82 | 3.18 | 2.02 | 2.10 |
| 25 | 6.65 | 4.12 | 10.25 | 4.55 | 5.25 | 2.88 | 2.78 | 2.70 | 2.00 | 3.05 | 2.20 | 2.10 |
| 26 | 5.30 | 4.05 | h 13.20 | 4.82 | 4.75 | 2.55 | 2.55 | 2.45 | 2.15 | 2.85 | 2.15 | 2.15 |
| 27 | 4.90 | 3.90 | 11.05 | 4.65 | 4.82 | 2.70 | 2.60 | 2.30 | 2.38 | 2.75 | 2.00 | 2.60 |
| 28 | 4.20 | 3.37 | 7.28 | 9.10 | 5.40 | 2.65 | 2.50 | 2.12 | 2.35 | 2.65 | 1.95 | 6.40 |
| 29 | 4.22 | 3.57 | 5.95 | 8.50 | 4.25 | 2.60 | 2.70 | 2.10 | 2.35 | 2.60 | 2.10 | 5.15 |
| 30 | 4.25 | | 5.60 | 7.42 | 4.00 | 2.60 | 2.80 | 2.08 | 2.35 | 2.45 | 1.95 | 3.90 |
| 31 | 4.05 | | 5.70 | | 5.85 | | 2.62 | 2.00 | | 2.30 | | 3.80 |

a No ice.

b Water over flats highest point 17 feet.

c River freezing over below gage.

d River frozen over.

e Thickness of ice 5 inches.

f Thickness of ice 12 inches.

g Ice running.

h River over the flats.

*Rating table for Chemung River at Chemung, N. Y., from August 27, 1903, to
December 31, 1904.*

| Gage height. | Discharge. | Gage height. | Discharge. | Gage height. | Discharge. | Gage height. | Discharge. |
|--------------|---------------------|--------------|---------------------|--------------|---------------------|--------------|---------------------|
| <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> | <i>Feet.</i> | <i>Second-feet.</i> |
| 1.75 | 146 | 4.00 | 2,255 | 6.30 | 7,575 | 8.60 | 14,260 |
| 1.80 | 170 | 4.10 | 2,420 | 6.40 | 7,855 | 8.70 | 14,560 |
| 1.90 | 220 | 4.20 | 2,590 | 6.50 | 8,135 | 8.80 | 14,860 |
| 2.00 | 273 | 4.30 | 2,765 | 6.60 | 8,415 | 8.90 | 15,160 |
| 2.10 | 328 | 4.40 | 2,950 | 6.70 | 8,700 | 9.00 | 15,460 |
| 2.20 | 385 | 4.50 | 3,140 | 6.80 | 8,985 | 9.10 | 15,760 |
| 2.30 | 445 | 4.60 | 3,340 | 6.90 | 9,270 | 9.20 | 16,060 |
| 2.40 | 510 | 4.70 | 3,550 | 7.00 | 9,560 | 9.30 | 16,360 |
| 2.50 | 575 | 4.80 | 3,765 | 7.10 | 9,850 | 9.40 | 16,660 |
| 2.60 | 645 | 4.90 | 3,990 | 7.20 | 10,140 | 9.50 | 16,960 |
| 2.70 | 720 | 5.00 | 4,220 | 7.30 | 10,430 | 9.60 | 17,260 |
| 2.80 | 800 | 5.10 | 4,455 | 7.40 | 10,720 | 9.70 | 17,560 |
| 2.90 | 890 | 5.20 | 4,695 | 7.50 | 11,010 | 9.80 | 17,860 |
| 3.00 | 985 | 5.30 | 4,940 | 7.60 | 11,300 | 9.90 | 18,160 |
| 3.10 | 1,085 | 5.40 | 5,190 | 7.70 | 11,590 | 10.00 | 18,460 |
| 3.20 | 1,190 | 5.50 | 5,445 | 7.80 | 11,880 | 11.00 | 2,146 |
| 3.30 | 1,300 | 5.60 | 5,700 | 7.90 | 12,170 | 12.00 | 24,460 |
| 3.40 | 1,415 | 5.70 | 5,960 | 8.00 | 12,460 | 13.00 | 27,460 |
| 3.50 | 1,540 | 5.80 | 6,220 | 8.10 | 12,760 | 14.00 | 30,460 |
| 3.60 | 1,670 | 5.90 | 6,485 | 8.20 | 13,060 | 15.00 | 33,460 |
| 3.70 | 1,805 | 6.00 | 6,750 | 8.30 | 13,360 | 16.00 | 36,460 |
| 3.80 | 1,945 | 6.10 | 7,020 | 8.40 | 13,660 | | |
| 3.90 | 2,095 | 6.20 | 7,295 | 8.50 | 13,960 | | |

The above table is applicable only for open-channel conditions. It is based upon 8 discharge measurements made during 1903 and 1904. It is fairly well defined between gage heights 1.90 and 3.30 feet. The table has been extended above gage height 6.70 feet. Above gage height 8.0 feet the rating curve is a tangent, the difference being 300 per tenth. The rating table has been applied to the nearest hundredth of a foot to gage height 6.00, to the nearest half-tenth of a foot to gage height 9.00, to the nearest tenth of a foot above gage height 9.00 feet.

Mean daily discharge, in second-feet, of Chemung River at Chemung, N. Y.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|------|------|--------|--------|--------|--------|-------|------|-------|--------|--------|-------|
| 1903. | | | | | | | | | | | | |
| 1 | | | | | | | | | | 409 | 966 | 890 |
| 2 | | | | | | | | | | 510 | 872 | 872 |
| 3 | | | | | | | | | | 589 | 2,065 | 872 |
| 4 | | | | | | | | | | 624 | 827 | 872 |
| 5 | | | | | | | | | | 752 | 854 | 818 |
| 6 | | | | | | | | | | 1,300 | 890 | 638 |
| 7 | | | | | | | | | 1,289 | 1,380 | 1,065 | 1,791 |
| 8 | | | | | | | | | 409 | 3,382 | 966 | 792 |
| 9 | | | | | | | | | 1,180 | 18,460 | 4,059 | 712 |
| 10 | | | | | | | | | 1,148 | 11,880 | 890 | 675 |
| 11 | | | | | | | | | 3,855 | 14,860 | 872 | 568 |
| 12 | | | | | | | | | 3,260 | 8,840 | 854 | 569 |
| 13 | | | | | | | | | 2,005 | 7,020 | 800 | 712 |
| 14 | | | | | | | | | 1,490 | 4,157 | 748 | 712 |
| 15 | | | | | | | | | 1,212 | 3,083 | 705 | 712 |
| 16 | | | | | | | | | 1,045 | 2,590 | 768 | 752 |
| 17 | | | | | | | | | 947 | 2,127 | 9,705 | 752 |
| 18 | | | | | | | | | 1,465 | 9,705 | 12,910 | 675 |
| 19 | | | | | | | | | 1,490 | 7,435 | 6,432 | 675 |
| 20 | | | | | | | | | 1,289 | 3,990 | 3,945 | 675 |
| 21 | | | | | | | | | 975 | 2,988 | 2,695 | 712 |
| 22 | | | | | | | | | 836 | 2,454 | 2,223 | 752 |
| 23 | | | | | | | | | 603 | 2,050 | 2,065 | 792 |
| 24 | | | | | | | | | 471 | 3,593 | 1,990 | 792 |
| 25 | | | | | | | | | 471 | 1,592 | 1,917 | 792 |
| 26 | | | | | | | | | 439 | 1,465 | 1,332 | 752 |
| 27 | | | | | | | | | 409 | 1,323 | 1,223 | 712 |
| 28 | | | | | | | | | 409 | 1,300 | 1,085 | 603 |
| 29 | | | | | | | | | 397 | 1,234 | 1,085 | 536 |
| 30 | | | | | | | | | 421 | 1,212 | 1,085 | 603 |
| 31 | | | | | | | | | | 1,116 | | 675 |
| 1904. | | | | | | | | | | | | |
| 1 | | | | 8,135 | 10,140 | 9,705 | 645 | 575 | 273 | 478 | 510 | 300 |
| 2 | | | | 15,460 | 7,435 | 35,860 | 872 | 523 | 284 | 523 | 445 | 273 |
| 3 | | | | 9,705 | 5,318 | 5,065 | 720 | 966 | 273 | 397 | 397 | 220 |
| 4 | | | | 6,090 | 4,267 | 3,877 | 660 | 818 | 246 | 328 | 385 | 220 |
| 5 | | | | 5,140 | 3,382 | 11,590 | 645 | 720 | 273 | 356 | 415 | 220 |
| 6 | | | | 4,575 | 2,950 | 6,617 | 631 | 645 | 262 | 374 | 385 | 220 |
| 7 | | | | 4,695 | 2,556 | 4,455 | 938 | 542 | 231 | 210 | 385 | 195 |
| 8 | | | 36,460 | 4,817 | 2,255 | 3,382 | 845 | 477 | 246 | 246 | 397 | 100 |
| 9 | | | 17,560 | 6,090 | 1,945 | 5,065 | 736 | 385 | 220 | 220 | 339 | 415 |
| 10 | | | 8,135 | 17,260 | 1,805 | 7,158 | 760 | 356 | 220 | 246 | 374 | 328 |
| 11 | | | 4,267 | 10,720 | 1,644 | 3,990 | 2,095 | 385 | 246 | 246 | 385 | 328 |
| 12 | | | 3,990 | 8,275 | 1,415 | 2,988 | 1,778 | 374 | 246 | 328 | 385 | 328 |
| 13 | | | 3,140 | 6,090 | 1,392 | 2,255 | 1,477 | 328 | 246 | 660 | 339 | 273 |
| 14 | | | 2,765 | 4,575 | 1,300 | 1,805 | 1,477 | 317 | 220 | 1,732 | 317 | 273 |
| 15 | | | 2,337 | 3,765 | 4,575 | 1,515 | 1,005 | 273 | 220 | 1,138 | 300 | 273 |
| 16 | | | 2,065 | 3,765 | 8,842 | 2,337 | 818 | 273 | 220 | 818 | 415 | 273 |
| 17 | | | 1,697 | 3,765 | 5,830 | 1,945 | 720 | 273 | 220 | 720 | 356 | 220 |
| 18 | | | 1,917 | 4,455 | 4,220 | 1,440 | 660 | 246 | 220 | 645 | 385 | 220 |
| 19 | | | 2,127 | 4,455 | 16,660 | 1,212 | 575 | 246 | 220 | 575 | 300 | 246 |
| 20 | | | 6,697 | 3,877 | 13,660 | 1,106 | 510 | 300 | 210 | 542 | 273 | 273 |
| 21 | | | 8,985 | 2,988 | 8,415 | 1,005 | 445 | 300 | 170 | 589 | 273 | 328 |
| 22 | | | 4,695 | 3,240 | 5,190 | 1,085 | 477 | 445 | 146 | 1,415 | 273 | 300 |
| 23 | | | 21,160 | 3,540 | 4,105 | 1,035 | 415 | 760 | 170 | 1,415 | 273 | 374 |
| 24 | | | 22,660 | 3,140 | 5,065 | 1,035 | 736 | 872 | 180 | 1,169 | 284 | 328 |
| 25 | | | 19,060 | 3,240 | 4,817 | 872 | 784 | 720 | 273 | 1,035 | 385 | 328 |
| 26 | | | 28,060 | 3,810 | 3,658 | 800 | 610 | 542 | 356 | 845 | 356 | 356 |
| 27 | | | 21,460 | 3,445 | 3,810 | 720 | 645 | 445 | 497 | 760 | 273 | 645 |
| 28 | | | 10,430 | 15,760 | 5,190 | 683 | 575 | 339 | 477 | 682 | 246 | 7,855 |
| 29 | | | 6,617 | 13,960 | 2,678 | 645 | 720 | 328 | 477 | 645 | 328 | 4,575 |
| 30 | | | 5,700 | 10,720 | 2,255 | 645 | 800 | 317 | 477 | 542 | 246 | 2,095 |
| 31 | | | 5,960 | | 6,352 | | 660 | 273 | | 445 | | 1,945 |

Estimated monthly discharge of Chemung River near Chemung, N. Y., for 1903-4.

[Drainage area, 2,440 square miles.]

| Month. | Discharge in second-feet. | | | Run-off. | |
|---------------------|---------------------------|----------|--------|------------------------------|------------------|
| | Maximum. | Minimum. | Mean. | Second-feet per square mile. | Depth in inches. |
| 1903. | | | | | |
| September 7-30..... | 3,855 | 397 | 1,146 | 0.47 | 0.42 |
| October..... | 18,460 | 409 | 3,981 | 1.63 | 1.88 |
| November..... | 12,910 | 705 | 2,265 | .93 | 1.04 |
| December..... | 1,791 | 536 | 757 | .31 | .36 |
| 1904. | | | | | |
| March 8-31..... | 36,460 | 1,697 | 10,331 | 4.23 | 3.90 |
| April..... | 17,260 | 2,988 | 6,645 | 2.72 | 3.03 |
| May..... | 16,660 | 1,300 | 4,940 | 2.02 | 2.33 |
| June..... | 35,860 | 645 | 4,063 | 1.67 | 1.86 |
| July..... | 2,095 | 415 | 820 | .336 | .387 |
| August..... | 966 | 246 | 463 | .190 | .219 |
| September..... | 497 | 146 | 267 | .109 | .122 |
| October..... | 1,732 | 210 | 656 | .269 | .310 |
| November..... | 510 | 246 | 347 | .142 | .158 |
| December..... | 7,855 | 100 | 785 | .322 | .371 |
| The period..... | 36,460 | 100 | 2,932 | 1.20 | 12.69 |

TIOUGHNIOGA RIVER AT CHENANGO FORKS, N. Y.

During the fall of 1903 the gaging station was established at this point in order to determine the low-water flow. Owing to the heavy rains which occurred that fall, as shown by the following table, the stage of the river did not fall as low as was expected.

Rainfall at Deruyter, N. Y., 1903.

| Inches. | Inches. |
|------------------------------|----------------------------|
| September 1 to 10..... 0.00 | October 8 to 11..... 8.00 |
| September 11..... .96 | October 16 to 19..... 1.38 |
| September 17 and 18..... .71 | October 23 to 28..... .39 |
| September 27..... .40 | November 5..... .34 |
| October 1 and 2..... .71 | November 6 to 15..... .12 |
| October 5..... .99 | |

The measurements were made at the highway bridge across the river at Chenango Forks. This bridge is located straight across the section of the channel and affords an excellent opportunity for

gagings, except at extreme high waters. Gage readings were taken during October and part of November from a staff gage fastened to the right-hand face of the center pier of the bridge. The drainage area of Tioughnioga River above the mouth at Chenango Forks, including the areas naturally tributary to the Tioughnioga, but now diverted to supply Erie Canal through the Erieville and Deruyter reservoirs is 735 square miles.

The following measurements were made at the station:

| Date. | Hydrographer. | Gage height. | Discharge. |
|--------------------|--------------------|--------------|------------|
| 1903. | | | |
| September 11.----- | C. C. Covert ----- | 2.0 | 992 |
| September 30.----- | H. H. Halsey ----- | 1.2 | 358 |

Mean daily gage height, in feet, of Tioughnioga River at Chenango Forks, N. Y.

| Day. | Oct. | Nov. | Day. | Oct. | Nov. | Day. | Oct. | Nov. | Day. | Oct. | Nov. |
|---------|------|------|----------|------|-------|----------|------|-------|----------|------|-------|
| 1903. | | | 1903. | | | 1903. | | | 1903. | | |
| 1 ----- | 1.12 | 2.15 | 9 ----- | 4.00 | 1.90 | 17 ----- | 3.40 | ----- | 25 ----- | 2.32 | ----- |
| 2 ----- | 1.20 | 1.95 | 10 ----- | (a) | 1.90 | 18 ----- | 4.50 | ----- | 26 ----- | 2.30 | ----- |
| 3 ----- | 1.45 | 2.00 | 11 ----- | (a) | ----- | 19 ----- | 3.65 | ----- | 27 ----- | 2.20 | ----- |
| 4 ----- | 1.22 | 1.95 | 12 ----- | 4.30 | ----- | 20 ----- | 3.10 | ----- | 28 ----- | 2.15 | ----- |
| 5 ----- | 1.50 | 1.90 | 13 ----- | 3.15 | ----- | 21 ----- | 2.70 | ----- | 29 ----- | 2.25 | ----- |
| 6 ----- | 2.45 | 2.05 | 14 ----- | 2.80 | ----- | 22 ----- | 2.45 | ----- | 30 ----- | 2.25 | ----- |
| 7 ----- | 1.90 | 2.00 | 15 ----- | 3.38 | ----- | 23 ----- | 2.45 | ----- | 31 ----- | 2.20 | ----- |
| 8 ----- | 2.10 | 1.95 | 16 ----- | 3.35 | ----- | 24 ----- | 2.45 | ----- | | | |

^a Above gage.

CAYUTA CREEK AT WAVERLY, N. Y.

A record of the daily stage of Cayuta Creek at the Ithaca Street Bridge, a short distance below the milldam in Waverly, was kept by T. P. Yates, covering the period March 1, 1898, to March 31, 1902. The accompanying tables show the observed distance from the reference point on bridge to water surface, the mean of the several readings being used where more than one daily observation was taken.^a Discharge measurements by means of floats were also made by Mr. Yates.

Cayuta Creek drains a long, narrow valley extending from eastern Schuyler County in a direction somewhat east of southerly a distance of 30 miles, the stream crossing the New York State line at Waverly and emptying into Susquehanna River at Sayre, Pa. In cross section the valley consists of a plain about one-half mile wide, through which the stream flows, bordered on both sides by abrupt slopes rising 500 feet within a distance of 1 or 2 miles from the foot on each side,

^aReference point is top iron hand rail at left-hand side second iron post from left-hand end of bridge on upstream side.

beyond which lies a plateau, cut by the numerous short lateral tributaries and their branches.

Cayuta Lake drains an area of 16.5 square miles at the head of the stream. The area of the lake is 0.78 square mile, and this constitutes the only storage in the drainage basin. The average width of the valley is about 6 miles. The conditions favor rapid concentration of the run-off in the main stream, there being no large branches. Maximum floods result, however, only from rapid inflow of sufficient duration to enable the waters from the whole length of the valley to reach the lower stretches of the stream at the same time. Cayuta Lake is at elevation 1,272 feet. The stream descends to elevation 800 feet at Waverly in a distance of 18 miles from Cayuta Lake, following the general trend of the valley, a limited amount of water power being developed at small dams.

Drainage areas of Cayuta Creek.^a

| | Area. | Total. |
|---|-------------------|-------------------|
| | <i>Sq. miles.</i> | <i>Sq. miles.</i> |
| Above outlet, Cayuta Lake | 16 | 16 |
| Above Van Etten | 92 | 108 |
| Above Ithaca Street Bridge, Waverly | 41 | 149 |

^aFrom Watkins, Ithaca, and Waverly sheets, U. S. G. S. topographic map.

Discharge measurements of Cayuta Creek at Waverly, N. Y.

| Date. | Hydrographer. | Gage height. ^a | Discharge. |
|------------------|--------------------|---------------------------|---------------------|
| 1903. | | <i>Feet.</i> | <i>Second-feet.</i> |
| June 13 | R. E. Horton | 17.11 | 24.9 |
| August 27 | C. C. Covert | 17.25 | 46.3 |
| October 2 | H. H. Halsey | 17.00 | 25.4 |
| October 12 | H. H. Halsey | 14.45 | 698 |

^aGage inverted.

Mean daily gage height, in feet, of Cayuta Creek at Waverly, N. Y., 1898-1902.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| 1898. | | | | | | | | | | | | |
| 1. | | | 16.90 | 16.00 | 16.30 | 16.80 | 17.50 | 17.70 | 17.20 | 17.80 | 16.70 | 16.70 |
| 2. | | | | 16.20 | 16.40 | | 17.60 | | 17.30 | | 16.80 | 16.80 |
| 3. | | | 16.80 | 16.40 | | 16.90 | | 17.80 | 17.40 | | 16.90 | |
| 4. | | | | 16.50 | 16.30 | | | 17.30 | 17.50 | | | |
| 5. | | | 16.90 | 16.60 | 16.50 | 17.00 | | 17.05 | | | 17.00 | 16.70 |
| 6. | | | | | 15.60 | 17.10 | | 17.10 | 17.60 | | | |
| 7. | | | 16.80 | 16.70 | 16.20 | 17.30 | | 17.40 | 16.87 | | 17.10 | |
| 8. | | | 16.50 | 16.80 | 16.40 | 17.00 | | 17.70 | 16.70 | 17.30 | | 16.80 |
| 9. | | | | 16.90 | 16.50 | 17.10 | | | 17.00 | 17.40 | 17.20 | 16.90 |
| 10. | | | 16.30 | | 16.60 | 17.20 | | | 17.30 | 17.60 | 14.87 | 17.00 |
| 11. | | | 14.60 | | 16.70 | 16.63 | | | 17.40 | 17.70 | 13.30 | 17.10 |
| 12. | | | 13.00 | | 16.60 | 16.90 | | | | 17.80 | 15.25 | |
| 13. | | | 15.00 | | 16.40 | 17.00 | | 17.60 | 17.50 | 17.70 | 15.70 | 17.20 |
| 14. | | | 15.30 | 17.00 | 16.60 | 17.00 | 17.70 | 17.50 | 17.50 | 16.54 | 16.00 | |
| 15. | | | 15.50 | | 16.70 | 17.10 | | 17.60 | 17.60 | 16.30 | 16.30 | |
| 16. | | | 15.80 | | 16.23 | 17.20 | | | | 16.85 | 16.60 | |
| 17. | | | 16.00 | 17.10 | 16.20 | 17.20 | | 17.50 | | 17.00 | 16.70 | |
| 18. | | | 16.20 | 17.20 | 16.40 | 17.40 | | | | 17.10 | 16.70 | |
| 19. | | | 16.30 | | 15.37 | | | 17.25 | 17.70 | 17.00 | 16.40 | |
| 20. | | | 16.00 | 17.30 | 14.50 | 17.30 | | 17.40 | | 16.63 | 15.73 | 17.00 |
| 21. | | | 16.40 | | 15.20 | | | 17.50 | | 16.60 | 16.10 | 16.35 |
| 22. | | | 15.40 | | 15.70 | 17.40 | 17.50 | | | 14.52 | 16.30 | 16.15 |
| 23. | | | 14.30 | 17.30 | 16.20 | | 17.60 | 17.60 | | 15.05 | 16.40 | 13.80 |
| 24. | | | 15.00 | 12.05 | 15.33 | | 17.70 | 17.70 | | 16.00 | 16.50 | 14.70 |
| 25. | | | 15.40 | 12.25 | | 17.50 | 17.80 | 17.35 | | 16.30 | 16.60 | 15.80 |
| 26. | | | 15.80 | 13.40 | 15.95 | | 17.50 | 17.30 | 17.80 | 16.36 | | 16.00 |
| 27. | | | 16.00 | 14.90 | 16.00 | 17.40 | 17.60 | | | 15.20 | 16.70 | 16.50 |
| 28. | | | 16.10 | 15.50 | 16.30 | | 17.70 | 17.50 | | 16.10 | 16.60 | 16.60 |
| 29. | | | 15.40 | 15.80 | 16.50 | | 17.60 | 17.60 | | 16.40 | | 16.70 |
| 30. | | | | 16.00 | 16.60 | | 17.70 | 16.57 | | 16.60 | 16.70 | 16.80 |
| 31. | | | 15.80 | | 16.70 | | | 17.00 | | | | 16.90 |
| 1899. | | | | | | | | | | | | |
| 1. | 15.80 | 17.80 | 15.50 | 15.80 | 17.00 | 17.30 | 17.80 | 17.90 | 17.90 | 17.90 | 15.08 | 17.70 |
| 2. | 16.20 | | 16.00 | 15.90 | 17.10 | 16.45 | | | | | 15.40 | |
| 3. | 16.30 | 17.60 | 16.20 | 16.00 | | 17.00 | | | | | 15.90 | |
| 4. | | | 14.40 | 16.30 | | 17.20 | | | | | | |
| 5. | 14.03 | 17.20 | 13.20 | 16.50 | | 17.30 | | | | | 16.50 | 17.80 |
| 6. | 15.55 | | 14.00 | 16.60 | | 17.40 | | 18.00 | | 18.00 | 16.60 | |
| 7. | 15.80 | | 14.60 | 16.70 | 17.30 | | | | | | 16.70 | |
| 8. | 16.00 | | 16.00 | 14.60 | | 17.30 | 17.90 | | | | 16.80 | |
| 9. | 16.10 | | 16.30 | 15.00 | | 17.40 | 15.60 | | | | 16.90 | |
| 10. | 16.40 | | | 15.80 | | 17.50 | 17.20 | 18.10 | 18.60 | | 17.00 | |
| 11. | | | 16.40 | 16.20 | | | 17.30 | | | | 17.10 | |
| 12. | 16.50 | 17.10 | 15.20 | 15.35 | 17.20 | 17.60 | | | | | 16.50 | 16.02 |
| 13. | 16.70 | | 14.46 | 14.40 | 17.30 | | | 18.00 | | | 16.90 | 16.40 |
| 14. | | | 15.70 | 14.90 | 17.40 | | | | | | | |
| 15. | 14.90 | 17.20 | 16.00 | 15.40 | | | 17.80 | | | | | 66.50 |
| 16. | 15.60 | | 16.00 | | | 17.70 | 17.50 | 18.00 | | 18.10 | 17.00 | |
| 17. | 15.80 | 17.30 | 16.30 | 15.90 | 17.30 | | 17.30 | | | | | 16.70 |
| 18. | 15.90 | | 16.60 | 16.30 | 17.26 | 17.80 | 16.80 | | | | | 16.70 |
| 19. | | | 15.90 | 16.40 | 17.20 | | | | | | | |
| 20. | 16.00 | 17.20 | 16.10 | | | | 17.40 | | | | | |
| 21. | 16.30 | 16.70 | 16.60 | | | | | | | | 17.20 | 16.80 |
| 22. | 16.50 | 16.00 | 16.30 | | 17.30 | | | | | | | |
| 23. | 16.80 | 14.80 | 15.40 | 16.60 | | | 17.60 | | | | | |
| 24. | 17.20 | 15.40 | 15.90 | 16.60 | | | | | | | | 16.90 |
| 25. | 17.40 | | 16.20 | 16.70 | | 17.55 | | | | | 17.40 | 15.00 |
| 26. | 17.60 | 16.30 | 16.50 | 16.60 | 17.40 | | | 18.10 | | | | 15.70 |
| 27. | 17.70 | 15.60 | 16.00 | 16.70 | | | | | 17.90 | | | 15.90 |
| 28. | 17.80 | | 15.70 | 16.80 | | 17.70 | | 17.77 | | | | 16.00 |
| 29. | | | 15.50 | | 17.50 | | | | | | 17.60 | 16.30 |
| 30. | | | 15.90 | 16.80 | 17.20 | 17.80 | 17.90 | 17.90 | | | 17.70 | 16.60 |
| 31. | | | 15.80 | | 17.20 | | | | | | | 16.90 |

Mean daily gage height, in feet, of Cayuta Creek at Waverly, N. Y., 1898-1902—
Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| 1900. | | | | | | | | | | | | |
| 1 | 16.90 | 16.90 | 14.08 | 16.10 | 14.30 | 17.30 | 17.90 | 18.10 | 18.20 | 18.30 | 18.30 | 15.00 |
| 2 | | | 14.00 | 15.20 | | | | | | | | 15.50 |
| 3 | | 17.00 | 15.40 | 14.30 | 16.40 | 17.10 | | | | | | 15.70 |
| 4 | | 17.10 | 15.80 | 14.70 | | 17.20 | | | | | | 15.50 |
| 5 | | 16.50 | 16.10 | 15.60 | 16.50 | | | | | | | 14.06 |
| 6 | | | 16.40 | 15.05 | | 17.30 | 17.60 | | | | | 14.60 |
| 7 | | 16.80 | 16.70 | 13.76 | 16.60 | 17.50 | 17.50 | | | | | 15.00 |
| 8 | | | 16.60 | 13.80 | | 17.50 | 17.70 | | | | | 15.20 |
| 9 | 17.00 | 16.50 | 16.40 | 15.50 | 16.70 | 17.40 | | | | | | 15.60 |
| 10 | | 14.00 | 15.40 | 16.00 | | 17.50 | | | | | | 15.80 |
| 11 | | 15.40 | 15.90 | | | | 17.80 | | | | | 16.00 |
| 12 | | 16.40 | 16.00 | 16.10 | | | | | | | | 16.20 |
| 13 | | 15.50 | 16.20 | | 16.80 | | | | | | | 16.30 |
| 14 | | 15.60 | 16.40 | | | 17.60 | | | | | | 16.40 |
| 15 | | 16.00 | 16.70 | | | | | | | | 18.20 | 16.50 |
| 16 | | 16.40 | 16.90 | | | | | | | | | |
| 17 | | 16.60 | | 15.90 | 16.90 | 17.70 | | | | | | 16.60 |
| 18 | | 16.80 | | 14.45 | | | 17.90 | | | | | |
| 19 | 17.00 | 17.00 | 16.60 | 14.90 | | 17.80 | | | | | | 16.70 |
| 20 | 13.50 | | 13.70 | 15.50 | | 17.60 | | | | | | |
| 21 | 12.55 | 17.20 | 15.40 | 16.20 | 12.00 | | | | | | | 16.80 |
| 22 | 15.10 | 12.13 | 16.40 | 16.00 | | | | | | | | |
| 23 | 15.70 | 12.20 | 15.20 | 15.50 | | | 18.00 | | | | 18.10 | 16.80 |
| 24 | 16.10 | 15.40 | 15.05 | 16.00 | | 17.70 | | | | | | 15.35 |
| 25 | 16.70 | 15.00 | | | 17.10 | | | | | 18.20 | 18.00 | 15.60 |
| 26 | 14.70 | 15.80 | | 16.10 | | 17.80 | | | | 18.25 | 10.30 | 15.90 |
| 27 | 15.90 | 16.20 | 16.20 | | | | 18.10 | | | 18.30 | 11.75 | 16.20 |
| 28 | 16.40 | 16.70 | 16.10 | 16.20 | 17.20 | | | | | | 14.40 | 16.40 |
| 29 | 16.80 | | 16.20 | | | | | | | | 14.50 | 16.50 |
| 30 | | | | 16.30 | | 17.90 | | | | | 14.70 | |
| 31 | 16.90 | | 16.30 | | 17.30 | | | | | | | |
| 1901. | | | | | | | | | | | | |
| 1 | 16.5 | 17.3 | 17.5 | 15.7 | 16.1 | 14.8 | 17.3 | 17.6 | 17.1 | 17.4 | 17.8 | 17.3 |
| 2 | 16.7 | | | 15.95 | 16.2 | 15.06 | | 17.6 | 16.9 | 17.5 | | |
| 3 | 16.8 | 17.4 | | 15.45 | 15.85 | 15.2 | | | 17.1 | 17.4 | | 16.8 |
| 4 | 16.9 | | 17.45 | 15.1 | 16.2 | 15.5 | 17.4 | | 17.2 | | | |
| 5 | | | 17.4 | 15.2 | 16.3 | 15.9 | 17.4 | 17.7 | 17.3 | | | |
| 6 | | | 17.5 | 14.05 | 16.5 | 16.1 | 17.0 | 17.8 | 17.4 | 17.5 | | 16.9 |
| 7 | 17.0 | | | 12.35 | 16.6 | 15.86 | 17.1 | 17.7 | 17.5 | 17.6 | | |
| 8 | | | | 12.90 | 16.7 | 15.3 | 17.3 | 17.4 | 17.6 | | | 17.0 |
| 9 | | | 17.3 | 13.90 | | 16.0 | | | 17.7 | | | 17.05 |
| 10 | 16.95 | 17.5 | 16.9 | 14.1 | | 16.3 | | 17.6 | | | | 14.86 |
| 11 | 16.4 | | 13.25 | 14.7 | 16.6 | 16.5 | | | | | | 15.0 |
| 12 | 15.63 | | 14.0 | 14.9 | 16.5 | 16.8 | 17.5 | 17.7 | | | | 16.2 |
| 13 | 16.1 | | 15.2 | 15.0 | 16.4 | | | | | | | 16.3 |
| 14 | 16.5 | | 15.65 | 15.3 | 16.5 | | | | 17.5 | 17.5 | 17.7 | 13.48 |
| 15 | 16.5 | | 15.15 | 15.6 | 16.7 | | | 17.7 | 17.4 | | | 9.80 |
| 16 | 16.0 | | 15.35 | 15.8 | 16.8 | | | 17.0 | | | | 13.35 |
| 17 | 16.1 | 17.5 | 15.6 | 15.9 | 16.9 | 17.0 | | 17.3 | 17.3 | | | 14.4 |
| 18 | 16.5 | | 15.36 | 16.0 | 16.9 | | | | | | | 15.0 |
| 19 | | | 14.2 | 16.1 | 16.7 | | 17.4 | 17.4 | 17.4 | | | 15.4 |
| 20 | 16.6 | | 15.4 | 14.75 | 16.9 | 16.9 | 17.5 | 17.4 | | | 17.8 | 15.6 |
| 21 | 16.7 | | 12.52 | 11.75 | | | | 17.0 | | | | 15.7 |
| 22 | 16.8 | | 14.26 | 11.83 | 16.85 | 17.0 | | 17.3 | 17.5 | | | 15.8 |
| 23 | 16.9 | | 15.1 | 13.4 | 16.80 | | | 17.4 | | 17.6 | | 16.0 |
| 24 | 17.1 | 17.5 | 14.2 | 13.75 | 16.50 | | 17.6 | | | | 15.16 | 16.2 |
| 25 | | | 13.3 | 14.1 | 16.40 | 17.1 | 17.7 | | 17.6 | | | |
| 26 | | | 12.26 | 14.6 | 16.5 | 17.2 | | | 17.7 | | 15.0 | 16.3 |
| 27 | | | 11.73 | 15.1 | 16.5 | | 17.5 | | 17.4 | 17.7 | | 16.2 |
| 28 | | | 13.5 | 15.5 | 15.58 | 17.3 | | | | | 16.6 | |
| 29 | | | 14.8 | 15.8 | 13.3 | | 17.6 | | | | 17.1 | 16.4 |
| 30 | 17.2 | | 15.2 | 16.0 | 13.85 | | 17.4 | 17.5 | | 17.8 | 17.2 | 16.0 |
| 31 | | | 15.5 | | 14.6 | | | 17.5 | | | | 16.1 |

Mean daily gage height, in feet, of Cayuta Creek at Waverly, N. Y., 1898-1902—
Continued.

| Day. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. |
|-------|-------|-------|------|------|------|-------|-------|------|-------|------|------|------|
| 1902. | | | | | | | | | | | | |
| 1 | 16.2 | 15.6 | 9.5 | | | | | | | | | |
| 2 | 16.4 | | 11.2 | | | | | | | | | |
| 3 | 16.3 | | 11.5 | | | | | | | | | |
| 4 | 16.4 | | 13.5 | | | | | | | | | |
| 5 | | | 14.8 | | | | | | | | | |
| 6 | | | 15.4 | | | | | | | | | |
| 7 | 16.5 | 16.0 | 15.0 | | | | | | | | | |
| 8 | | | 15.0 | | | | | | | | | |
| 9 | | | 14.8 | | | | | | | | | |
| 10 | 16.7 | | 14.3 | | | | | | | | | |
| 11 | | | 14.0 | | | | | | | | | |
| 12 | 16.9 | | 13.9 | | | | | | | | | |
| 13 | | | 12.7 | | | | | | | | | |
| 14 | 17.0 | | 13.5 | | | | | | | | | |
| 15 | | 16.4 | 14.3 | | | | | | | | | |
| 16 | 17.1 | | 14.2 | | | | | | | | | |
| 17 | 17.2 | | 11.5 | | | | | | | | | |
| 18 | 17.3 | | 14.0 | | | | | | | | | |
| 19 | 17.4 | | 14.8 | | | | | | | | | |
| 20 | 17.5 | 16.5 | 15.0 | | | | | | | | | |
| 21 | | | 15.2 | | | | | | | | | |
| 22 | | 15.5 | 15.4 | | | | | | | | | |
| 23 | 13.15 | | 15.4 | | | | | | | | | |
| 24 | 14.0 | | 15.6 | | | | | | | | | |
| 25 | 15.0 | 16.8 | 15.8 | | | | | | | | | |
| 26 | 15.4 | | 16.0 | | | | | | | | | |
| 27 | 15.4 | 16.65 | 16.2 | | | | | | | | | |
| 28 | 15.0 | 12.4 | 16.4 | | | | | | | | | |
| 29 | 15.4 | | 16.4 | | | | | | | | | |
| 30 | 15.8 | | | | | | | | | | | |
| 31 | | | 16.4 | | | | | | | | | |

CHENANGO RIVER AT OXFORD, N. Y.

A temporary board gage was attached to the upstream side of the left-hand abutment of the highway bridge across Chenango River at South Oxford, N. Y., September 29, 1903, and observations of the stream stage were taken twice daily from that date until November 7, 1903. The desired data relative to low-water flow could not be obtained on account of heavy rains. The precipitation during the period of observation, as recorded at Oxford, is given below:

Precipitation at Oxford, N. Y.

| | Depth. |
|-----------------|---------|
| | Inches. |
| 1903. | T. |
| September 1-10 | 0.64 |
| September 11 | .72 |
| September 17 | .16 |
| September 27-28 | 1.14 |
| October 5 | 3.71 |
| October 8-12 | 1.72 |
| October 16-19 | .49 |
| October 23-27 | .34 |
| November 5 | .12 |
| November 6-15 | |

South Oxford is located on Chenango River 18 miles above the inflow of Tioughnioga River. The drainage area is 453 square miles gross, or 423 square miles net, excluding 30 square miles tributary to the reservoirs which supply Erie Canal summit level during the navigation period.

Mean daily gage height, in feet, of Chenango River at South Oxford, N. Y.

| Day. | Sept. | Oct. | Nov. | Day. | Sept. | Oct. | Nov. | Day. | Sept. | Oct. | Nov. |
|----------|-------|------|------|----------|-------|------|------|----------|-------|------|------|
| 1903. | | | | 1903. | | | | 1903. | | | |
| 1.----- | | 0.85 | 1.80 | 12.----- | | 4.55 | | 22.----- | | 2.55 | |
| 2.----- | | .85 | 1.70 | 13.----- | | 3.65 | | 23.----- | | 2.40 | |
| 3.----- | | 1.00 | 1.70 | 14.----- | | 2.90 | | 24.----- | | 2.20 | |
| 4.----- | | .90 | 1.60 | 15.----- | | 2.55 | | 25.----- | | 2.15 | |
| 5.----- | | 1.35 | 1.65 | 16.----- | | 2.30 | | 26.----- | | 2.00 | |
| 6.----- | | 1.80 | 1.75 | 17.----- | | 2.35 | | 27.----- | | 1.90 | |
| 7.----- | | 1.45 | 1.65 | 18.----- | | 4.90 | | 28.----- | | 1.95 | |
| 8.----- | | 1.65 | | 19.----- | | 4.30 | | 29.----- | 0.90 | 1.95 | |
| 9.----- | | 4.35 | | 20.----- | | 3.40 | | 30.----- | .85 | 1.90 | |
| 10.----- | | 7.40 | | 21.----- | | 2.90 | | 31.----- | | 1.85 | |
| 11.----- | | 6.50 | | | | | | | | | |

EATON AND MADISON BROOKS, MADISON COUNTY, N. Y.

Records of the flow of Eaton and Madison brooks, two small streams near the headwaters of Chenango River, are among the earliest, if not the first, systematic stream gagings in the United States. The flow of these streams was determined by John B. Jervis in 1835 in an investigation of water supply for the summit level of Chenango Canal, extending from Utica to Binghamton, and now abandoned.

The headwaters of Chenango River, including Eaton and Madison brooks and the storage reservoirs which have been constructed to supply the summit level of Erie Canal through Oriskany Creek, are shown on the Morrisville, Cazenovia, Norwich, and Pitcher sheets of the United States Geological Survey topographic map.

Eaton Brook drainage basin is from $1\frac{1}{2}$ to 3 miles in width and 7 miles in length. It contains near its head Eaton reservoir, at an elevation of about 1,430 feet. The slopes are steep; the soil is close textured, with shale near the surface. Tributaries are few, and the fall is rapid.

The soil and topography of Madison Brook are similar, the area consisting of rounded hill slopes with a somewhat more porous soil, greater breadth, and more tributaries than in the Eaton Brook area.

It is stated that the Eaton Brook and Madison Brook gagings show only the volume of water passed downstream from the reservoirs.

Estimated monthly discharge of Eaton Brook, Madison County, N. Y.

[Drainage area, 10.62 square miles.]

| Month. | Mean discharge in second-feet. | Run-off. | | Rainfall, inches. |
|------------------------|--------------------------------|------------------------------|------------------|-------------------|
| | | Second-feet per square mile. | Depth in inches. | |
| 1835. | | | | |
| January | | | | |
| February | | | | |
| March | | | | |
| April | | | | |
| May | | | | |
| June | 22.15 | 2.08 | 2.32 | 6.72 |
| July | 10.46 | .98 | 1.13 | 2.74 |
| August | 5.06 | .48 | .55 | 2.86 |
| September | 3.70 | .35 | .39 | 1.34 |
| October | 7.73 | .73 | .84 | 3.00 |
| November | 9.17 | .86 | .96 | 2.20 |
| December | 12.89 | 1.21 | 1.39 | .96 |
| The period | | | 7.58 | 19.82 |
| Per cent run-off | | | | 38 |

Estimated monthly discharge of Madison Brook, Madison County, N. Y.

[Drainage area, 9.37 square miles.]

| Month. | Mean discharge in second-feet. | Run-off. | | Rainfall, inches. ^a |
|------------------------|--------------------------------|------------------------------|------------------|--------------------------------|
| | | Second-feet per square mile. | Depth in inches. | |
| 1835. | | | | |
| January ----- | 8.66 | 0.93 | 1.07 | 2.17 |
| February ----- | 10.49 | 1.12 | 1.16 | 2.50 |
| March ----- | 16.16 | 1.73 | 1.99 | 1.03 |
| April ----- | 31.16 | 3.33 | 3.71 | 5.00 |
| May ----- | 21.66 | 2.32 | 2.67 | 1.98 |
| June ----- | 7.77 | .83 | .93 | 8.05 |
| July ----- | 8.64 | .92 | 1.06 | 3.87 |
| August ----- | 8.86 | .95 | 1.10 | 3.06 |
| September ----- | 7.39 | .79 | .88 | .88 |
| October ----- | 7.30 | .78 | .90 | 3.86 |
| November ----- | 7.03 | .75 | .84 | 2.10 |
| December ----- | 7.24 | .77 | .89 | .76 |
| The year ----- | | | 17.20 | 39.26 |
| Per cent run-off ----- | | | | 44 |

DIVERSIONS FROM CHENANGO RIVER DRAINAGE BASIN.

An examination was made of the diversion from Chenango River drainage basin to supply Erie Canal during September, 1903.

Proceeding upstream from along the feeder which enters Oriskany Creek at Solsville, the draft from the storage reservoirs was observed as follows:

Leland Ponds, well drawn down, September 11, 1903, outflow about 9 second-feet.

Chenango Feeder above inflow from Leland Ponds, September 11, 1903, about 30 second-feet.

Approximate total diversion, 39 second-feet.

The outflow from the several reservoirs proceeding upstream was approximately as follows:

Madison reservoir, September 11, 1903, 10 second-feet.

Flow in Chenango feeder at first bridge above Hamilton, also above Madison reservoir outlet, about 23 second-feet.

The outflow from the remaining reservoirs in the Chenango River area, Kingsley, Bradley Brook, and Eaton reservoirs, respectively, was slight. Their combined outflow passes a diverting dam above Randalsville, the waste from which, together with waste and seepage from the feeder, enters the natural channel of Chenango River. The flow in this river channel at the bridge above Earlville September 12, 1903, was approximately 44 second-feet.

PRECIPITATION.

During the last few years the United States Weather Bureau has maintained about 47 precipitation stations in the Susquehanna River drainage area (see list on p. 160). The locations of these stations and of the gaging stations are indicated in fig. 1 (p. 11).

In order to compare the relation of rainfall to run-off in the Susquehanna basin, the run-off at Harrisburg has been taken as representative of the whole basin, and that at Wilkesbarre and Williamsport as representative of the main stream above Sunbury and the West Branch, respectively.

The rainfall stations are so distributed as to represent fairly well the conditions over each of these areas. Therefore, it is assumed that for any one month the mean rainfall over the whole of any of these areas is the mean of the monthly rainfall at the various stations in that area. Based upon this assumption, the monthly and yearly rainfall for each of the years when the run-off records are available has been determined, as shown in tables on pages 161-171.

An examination of the tables on pages 156 and 157, which give a comparison of the rainfall and run-off above Harrisburg, shows that the mean annual rainfall over the drainage area varies from 31.4 to

^a Snow of November and December, 1904, on ground.

44.3 inches, with a mean for the fourteen years of 39.4. This yields a run-off of from 16.6 to 29.1 inches, with a mean of 21.6. The amount of rainfall which runs off varies from 49 to 71 per cent of the total, with a mean of 54 per cent. The run-off is a minimum in August, September, and October, during which months it ranges from 5 to 30 per cent of the rainfall, and averages about 15 per cent.

As complete snowfall data are not available, it has been impossible to allow for the snow storage, which accounts for the high percentages in the late winter and early spring. To fully account for this storage a cube of snow should be melted at the end of each month in order to determine the amount of water stored during that time. The quantity available for run-off during the following month would be the amount so determined plus the precipitation during the following month minus the amount left in snow storage at the end of that month. Unfortunately sufficient data of this kind are not available, and therefore no attempt has been made to account for this disturbing feature.

The tables on pages 158 and 159 show that the conditions on the main stream above Wilkesbarre and the West Branch taken separately are practically the same as when taken together in connection with the entire river as referred to above.

Rainfall stations in the portion of the Susquehanna River drainage basin above Harrisburg.

NEW YORK.

- | | |
|---------------------|----------------------|
| a2. Cooperstown. | 10. Perry City. |
| 4. New Lisbon. | 11. Wedgwood. |
| 6. South Kortright. | 14. South Canesteeo. |
| 7. Oxford. | 15. Addison. |
| 9. Binghamton. | 16. Elmira. |

PENNSYLVANIA.

- | | |
|------------------|--------------------|
| 20. Wellsboro. | 35. Selinsgrove. |
| 21. Leroy. | 38. State College. |
| 24. South Eaton. | 40. Altoona. |
| 26. Wilkesbarre. | 41. Huntingdon. |
| 29. Emporium. | 42. Harrisburg. |
| 31. Lock Haven. | 43. Lebanon. |
| 32. Lewisburg. | 46. York. |

In the following table are shown the rainfall and run-off in the Susquehanna drainage basin above Harrisburg. The computations are based on the flow at the Harrisburg gaging station and the rainfall at the 24 stations listed above.

^aThe number refers to the accompanying map (fig. 1, p. 11), on which the locations of the stations are shown.

Rainfall and run-off in the portion of the Susquehanna River drainage basin above Harrisburg, Pa.

| Month. | 1891. | | | 1892. | | | 1893. | | |
|-----------------|-----------------------|----------|---------------------------|-----------------------|----------|---------------------------|-----------------------|----------|---------------------------|
| | Rain-fall, inches. | Run-off. | | Rain-fall, inches. | Run-off. | | Rain-fall, inches. | Run-off. | |
| | | Inches. | Per cent of rain-fall. | | Inches. | Per cent of rain-fall. | | Inches. | Per cent of rain-fall. |
| January | 3.98 | 3.466 | 87 | 4.40 | 3.787 | 86 | 2.30 | 0.745 | 32 |
| February | 3.77 | 6.099 | 162 | 1.72 | 1.003 | 58 | 4.55 | 2.409 | 53 |
| March | 3.89 | 4.672 | 120 | 4.11 | 2.461 | 60 | 2.68 | 4.474 | 167 |
| April | 1.97 | 3.706 | 188 | 1.49 | 3.701 | 25 | 4.06 | 4.800 | 118 |
| May | 1.56 | .921 | 59 | 5.97 | 3.227 | 54 | 6.05 | 4.371 | 72 |
| June | 3.93 | 1.178 | 30 | 5.71 | 3.029 | 53 | 3.15 | .865 | 27 |
| July | 5.07 | 1.041 | 21 | 4.62 | .777 | 17 | 3.26 | .490 | 15 |
| August | 4.84 | 1.467 | 30 | 4.60 | .896 | 19 | 4.84 | .272 | 6 |
| September | 1.91 | 1.101 | 58 | 2.30 | .521 | 23 | 3.00 | .872 | 29 |
| October | 3.49 | .892 | 26 | .95 | .288 | 30 | 2.76 | .895 | 32 |
| November | 2.63 | 1.583 | 60 | 3.45 | .505 | 15 | 2.03 | .716 | 35 |
| December | 4.13 | 3.022 | 73 | 1.23 | .775 | 61 | 2.69 | 1.939 | 72 |
| The year | 41.17 | 29.148 | 71 | 40.60 | 20.970 | 52 | 41.37 | 22.848 | 55 |

| Month. | 1894. | | | 1895. | | | 1896. | | |
|-----------------|-------|--------|-----|-------|--------|-----|-------|--------|-----|
| January | 2.25 | 1.296 | 58 | 3.32 | 2.405 | 72 | 1.90 | 2.523 | 133 |
| February | 2.93 | 1.367 | 47 | 1.11 | 2.320 | 209 | 4.49 | 2.355 | 52 |
| March | 1.21 | 3.348 | 277 | 1.78 | 3.822 | 214 | 3.98 | 3.087 | 78 |
| April | 4.41 | 3.037 | 69 | 2.50 | 3.940 | 158 | 1.27 | 4.109 | 324 |
| May | 7.70 | 4.540 | 59 | 2.84 | 1.201 | 42 | 2.89 | .606 | 21 |
| June | 2.81 | 2.514 | 82 | 3.47 | .504 | 14 | 4.34 | .893 | 21 |
| July | 2.42 | .482 | 20 | 2.66 | .450 | 17 | 5.14 | .729 | 14 |
| August | 2.19 | .318 | 15 | 3.93 | .252 | 6 | 1.92 | .695 | 36 |
| September | 5.61 | .802 | 14 | 2.17 | .242 | 11 | 4.01 | .193 | 5 |
| October | 4.64 | 1.242 | 27 | 1.46 | .159 | 11 | 3.88 | 1.653 | 43 |
| November | 2.04 | 2.152 | 105 | 2.52 | .283 | 11 | 2.89 | 1.647 | 57 |
| December | 3.28 | 1.689 | 51 | 3.65 | .892 | 24 | 1.04 | 1.035 | 100 |
| The year | 41.49 | 22.587 | 54 | 51.41 | 16.470 | 52 | 37.75 | 19.525 | 52 |

Rainfall and run-off in the portion of the Susquehanna River drainage basin above Harrisburg, Pa.—Continued.

| Month. | 1897. | | | 1898. | | | 1899. | | | 1900. | | |
|-----------------|----------------------|----------|------------------------|----------------------|----------|------------------------|----------------------|----------|------------------------|----------------------|----------|------------------------|
| | Rain-fall, inches | Run-off. | | Rain-fall, inches | Run-off. | | Rain-fall, inches | Run-off. | | Rain-fall, inches | Run-off. | |
| | | Inches | Per cent of rain-fall. | | Inches | Per cent of rain-fall. | | Inches | Per cent of rain-fall. | | Inches | Per cent of rain-fall. |
| January | 1.77 | 0.892 | 50 | 3.65 | 2.806 | 77 | 2.29 | 2.132 | 93 | 2.28 | 2.737 | 120 |
| February | 2.33 | 2.007 | 86 | 1.79 | 2.290 | 128 | 3.22 | 1.998 | 62 | 3.69 | 2.766 | 75 |
| March | 3.22 | 4.233 | 131 | 3.46 | 4.250 | 123 | 3.94 | 4.842 | 123 | 3.52 | 3.238 | 92 |
| April | 3.03 | 2.590 | 85 | 2.97 | 2.467 | 83 | 1.63 | 3.111 | 191 | 1.52 | 2.703 | 178 |
| May | 4.72 | 2.584 | 55 | 4.74 | 2.845 | 60 | 3.48 | 1.216 | 35 | 2.20 | .923 | 42 |
| June | 3.24 | .819 | 25 | 2.77 | .927 | 33 | 3.25 | .534 | 16 | 2.95 | .609 | 21 |
| July | 4.53 | .545 | 12 | 3.12 | .384 | 12 | 2.76 | .375 | 14 | 3.63 | .342 | 9 |
| August | 3.11 | .730 | 23 | 6.35 | 1.249 | 20 | 4.08 | .350 | 9 | 3.04 | .243 | 8 |
| September | 2.90 | .314 | 11 | 2.04 | .522 | 26 | 3.70 | .299 | 8 | 1.41 | .173 | 12 |
| October | 1.19 | .284 | 24 | 5.74 | 1.578 | 28 | 1.68 | .198 | 12 | 3.35 | .208 | 6 |
| November | 4.42 | 1.003 | 23 | 3.23 | 1.908 | 59 | 2.70 | .872 | 32 | 4.43 | 1.091 | 25 |
| December | 3.27 | 2.235 | 68 | 2.43 | 1.666 | 69 | 2.95 | 1.545 | 52 | 2.12 | 1.762 | 83 |
| The year. | 37.73 | 18.246 | 48 | 42.29 | 22.892 | 54 | 35.68 | 17.472 | 49 | 34.19 | 16.595 | 49 |

| Month. | 1901. | | | 1902. | | | 1903. | | | 1904. | | |
|-----------------|-------|--------|-----|-------|--------|-----|-------|--------|-----|-------|--------|-----|
| January | 1.81 | 0.673 | 37 | 2.31 | 1.775 | 77 | 3.23 | 1.812 | 56 | 3.31 | 1.470 | 44 |
| February | .93 | .868 | 93 | 3.41 | 2.044 | 60 | 3.71 | 4.040 | 109 | 2.16 | 1.740 | 81 |
| March | 3.52 | 3.888 | 110 | 3.88 | 7.456 | 192 | 4.58 | 6.405 | 140 | 3.43 | 4.890 | 142 |
| April | 4.46 | 4.827 | 108 | 2.87 | 3.163 | 110 | 2.76 | 3.840 | 139 | 3.28 | 3.450 | 105 |
| May | 5.68 | 3.069 | 54 | 1.63 | .739 | 45 | 1.27 | .686 | 54 | 3.82 | 2.010 | 53 |
| June | 2.96 | 2.557 | 86 | 6.17 | .595 | 10 | 6.44 | 1.298 | 20 | 3.37 | 1.360 | 40 |
| July | 3.96 | .649 | 16 | 7.24 | 3.252 | 47 | 4.52 | 1.560 | 35 | 4.95 | .865 | 17 |
| August | 6.24 | 1.596 | 26 | 2.76 | 1.294 | 47 | 6.48 | 1.227 | 19 | 3.94 | .500 | 13 |
| September | 3.01 | 1.025 | 34 | 4.12 | .544 | 13 | 1.95 | 1.417 | 73 | 3.20 | .402 | 13 |
| October | 1.43 | .631 | 44 | 4.13 | 1.711 | 41 | 4.94 | 2.167 | 44 | 2.71 | .731 | 27 |
| November | 2.30 | .689 | 30 | 1.24 | .974 | 79 | 2.02 | 1.266 | 63 | .92 | .500 | 54 |
| December | 5.63 | 3.527 | 63 | 4.56 | 3.060 | 67 | 2.42 | .948 | 39 | 2.13 | .405 | 19 |
| The year. | 41.93 | 23.999 | 57 | 44.32 | 26.724 | 60 | 44.32 | 26.666 | 60 | 37.22 | 18.320 | 49 |

Rainfall stations in the portion of the Susquehanna River drainage basin above Wilkesbarre.

NEW YORK.

- | | |
|---------------------|---------------------|
| 1. Richmondville. | 10. Perry City. |
| 2. Cooperstown. | 11. Wedgwood. |
| 3. Bouckville. | 12. Atlanta. |
| 4. New Lisbon. | 13. Angelica. |
| 5. Oneonta. | 14. South Canisteo. |
| 6. South Kortright. | 15. Addison. |
| 7. Oxford. | 16. Elmira. |
| 8. Cortland. | 17. Waverly. |
| 9. Binghamton. | |

PENNSYLVANIA.

- | | |
|--------------------|------------------|
| 18. Athens. | 23. Dushore. |
| 19. Lawrenceville. | 24. South Eaton. |
| 20. Wellsboro. | 25. Scranton. |
| 21. Leroy. | 26. Wilkesbarre. |
| 22. Towanda. | 34. Girardville. |

In the following table are shown the rainfall and run-off in the portion of the Susquehanna basin above Wilkesbarre. The computations are based on the flow at the Wilkesbarre gaging station and the rainfall at the 27 stations listed above.

Rainfall and run-off in the portion of the Susquehanna River drainage basin above Wilkesbarre, Pa.

| Month. | 1899. | | | 1900. | | | 1901. | | |
|-----------------|-----------------------|----------|------------------------|-----------------------|----------|------------------------|-----------------------|----------|------------------------|
| | Rain-fall, inches. | Run-off. | | Rain-fall, inches. | Run-off. | | Rain-fall, inches. | Run-off. | |
| | | Inches. | Per cent of rain-fall. | | Inches. | Per cent of rain-fall. | | Inches. | Per cent of rain-fall. |
| January | 2.14 | ----- | ----- | 2.43 | 2.078 | 85 | 1.69 | 3.402 | 201 |
| February | 2.67 | ----- | ----- | 3.46 | 2.987 | 86 | 1.17 | 1.696 | 145 |
| March | 3.60 | ----- | ----- | 3.59 | 2.773 | 77 | 3.36 | 4.044 | 120 |
| April | 1.63 | 3.262 | 200 | 1.50 | 2.988 | 199 | 4.67 | 4.465 | 96 |
| May | 2.78 | .876 | 32 | 1.97 | .660 | 33 | 5.39 | 2.490 | 46 |
| June | 3.11 | .354 | 11 | 2.94 | .364 | 12 | 3.11 | 1.712 | 55 |
| July | 3.13 | .235 | 8 | 4.13 | .269 | 7 | 4.03 | .357 | 8 |
| August | 3.76 | .197 | 5 | 2.73 | .201 | 7 | 5.96 | .831 | 14 |
| September | 3.14 | .138 | 4 | 1.40 | .148 | 11 | 2.94 | .434 | 15 |
| October | 1.85 | .136 | 7 | 3.58 | .141 | 4 | 1.69 | .382 | 23 |
| November | 2.58 | .724 | 28 | 4.70 | 1.226 | 26 | 2.68 | .563 | 21 |
| December | 3.19 | 1.470 | 46 | 2.29 | 3.206 | 140 | 5.58 | 4.902 | 88 |
| The year | 33.53 | 7.571 | ----- | 34.73 | 16.977 | 49 | 42.27 | 25.258 | 60 |

| Month. | 1902. | | | 1903. | | | 1904. | | |
|-----------------|-----------------------|---------|------------------------|-----------------------|---------|------------------------|-----------------------|---------|------------------------|
| | Rain-fall, inches. | Inches. | Per cent of rain-fall. | Rain-fall, inches. | Inches. | Per cent of rain-fall. | Rain-fall, inches. | Inches. | Per cent of rain-fall. |
| January | 2.00 | 3.144 | 157 | 2.64 | 3.441 | 130 | 3.40 | 2.570 | 76 |
| February | 3.03 | 2.432 | 80 | 2.93 | 3.715 | 127 | 1.99 | 3.920 | 197 |
| March | 3.51 | 7.898 | 223 | 4.77 | 6.289 | 132 | 3.17 | 6.160 | 195 |
| April | 2.54 | 2.441 | 96 | 2.90 | 2.654 | 115 | 2.79 | 3.560 | 128 |
| May | 2.17 | .495 | 23 | 1.11 | .366 | 33 | 3.69 | 1.860 | 50 |
| June | 5.87 | .489 | 8 | 6.98 | 1.134 | 18 | 3.27 | 1.270 | 39 |
| July | 7.86 | 3.401 | 43 | 4.39 | .842 | 19 | 4.96 | .428 | 9 |
| August | 2.88 | 1.115 | 39 | 6.51 | 1.446 | 22 | 4.26 | .529 | 14 |
| September | 4.32 | .543 | 13 | 1.67 | 1.157 | 69 | 3.69 | .469 | 13 |
| October | 3.83 | 1.674 | 44 | 6.04 | 3.183 | 53 | 3.00 | 1.330 | 44 |
| November | 1.13 | .861 | 76 | 2.21 | 1.382 | 62 | 1.18 | .679 | 58 |
| December | 4.04 | 2.999 | 74 | 2.44 | 1.543 | 63 | 2.24 | .900 | 40 |
| The year | 43.18 | 27.317 | 63 | 43.32 | 27.153 | 63 | 37.64 | 23.760 | 63 |

Rainfall stations in the portion of the West Branch of the Susquehanna River drainage basin above Williamsport.

20. Wellsboro.
21. Leroy.
27. Williamsport.
29. Emporium.

31. Lock Haven.
36. Center Hall.
38. State College.
39. Grampian.

In the following table are given the rainfall and run-off in the portion of the West Branch of Susquehanna River drainage basin above Williamsport. The computations are based on the flow at the Williamsport gaging station and the rainfall at the eight stations listed above.

Rainfall and run-off in the portion of the West Branch of the Susquehanna River drainage basin above Williamsport.

| Month. | 1895. | | | 1896. | | | 1897. | | |
|-----------------|-----------------------|----------|------------------------|-----------------------|----------|------------------------|-----------------------|----------|------------------------|
| | Rain-fall, inches. | Run-off. | | Rain-fall, inches. | Run-off. | | Rain-fall, inches. | Run-off. | |
| | | Inches. | Per cent of rain-fall. | | Inches. | Per cent of rain-fall. | | Inches. | Per cent of rain-fall. |
| January | 3.74 | ----- | ----- | 1.51 | 1.167 | 77 | 2.04 | 1.012 | 50 |
| February | 1.04 | ----- | ----- | 4.00 | 2.077 | 52 | 2.95 | 1.754 | 59 |
| March | 2.02 | 4.241 | 210 | 3.84 | 2.822 | 74 | 3.77 | 5.231 | 139 |
| April | 2.53 | 5.990 | 171 | 1.44 | 3.980 | 276 | 3.21 | 2.744 | 85 |
| May | 3.33 | 1.128 | 34 | 2.06 | .787 | 38 | 4.47 | 2.921 | 65 |
| June | 4.66 | .688 | 15 | 4.48 | 1.475 | 33 | 3.18 | .602 | 19 |
| July | 3.00 | .602 | 20 | 5.75 | 1.283 | 22 | 5.28 | .696 | 13 |
| August | 3.57 | .387 | 11 | 2.26 | 1.505 | 58 | 3.30 | .759 | 23 |
| September | 2.31 | .204 | 9 | 4.70 | .809 | 7 | 3.37 | .357 | 10 |
| October | 1.26 | .152 | 12 | 4.22 | 2.685 | 64 | 1.16 | .263 | 23 |
| November | 2.42 | .289 | 12 | 2.75 | 1.734 | 63 | 4.91 | 1.329 | 27 |
| December | 3.74 | .924 | 25 | 1.25 | 1.276 | 102 | 3.54 | 2.345 | 66 |
| The year | 33.43 | ----- | ----- | 38.26 | 20.899 | 55 | 41.18 | 19.993 | 49 |

| Month. | 1898. | | | 1899. | | | 1900. | | |
|-----------------|-----------------------|---------------------|------------------------|-----------------------|---------------------|------------------------|-----------------------|---------------------|------------------------|
| | Rain-fall, inches. | Run-off, Inches. | Per cent of rain-fall. | Rain-fall, inches. | Run-off, Inches. | Per cent of rain-fall. | Rain-fall, inches. | Run-off, Inches. | Per cent of rain-fall. |
| January | 3.69 | 3.230 | 87 | 2.49 | 2.453 | 99 | 2.46 | 2.848 | 116 |
| February | 1.54 | 2.254 | 146 | 3.46 | 1.717 | 50 | 3.71 | 2.602 | 70 |
| March | 5.20 | 6.410 | 123 | 3.89 | 5.622 | 144 | 3.87 | 3.197 | 83 |
| April | 2.98 | 2.552 | 86 | 1.85 | 3.104 | 168 | 1.33 | 2.768 | 208 |
| May | 4.26 | 2.154 | 50 | 3.70 | 1.530 | 41 | 2.22 | 1.006 | 45 |
| June | 3.37 | .848 | 25 | 3.60 | .539 | 15 | 2.94 | .800 | 27 |
| July | 2.92 | .420 | 14 | 2.77 | .357 | 13 | 3.63 | .418 | 12 |
| August | 5.47 | .914 | 17 | 4.18 | .273 | 7 | 3.24 | .267 | 82 |
| September | 1.23 | .302 | 25 | 3.50 | .365 | 10 | 1.05 | .184 | 17 |
| October | 6.22 | 1.507 | 24 | 1.87 | .206 | 11 | 3.71 | .372 | 10 |
| November | 2.68 | 1.684 | 63 | 2.77 | 1.136 | 41 | 4.43 | 1.845 | 42 |
| December | 2.81 | 1.552 | 55 | 3.95 | 1.892 | 48 | 2.05 | 1.750 | 85 |
| The year | 42.38 | 23.827 | 56 | 38.02 | 19.194 | 50 | 34.64 | 18.057 | 52 |

| Month. | 1901. | | | 1902. | | | 1903. | | |
|-----------------|-----------------------|---------------------|------------------------|-----------------------|---------------------|------------------------|-----------------------|---------------------|------------------------|
| | Rain-fall, inches. | Run-off, Inches. | Per cent of rain-fall. | Rain-fall, inches. | Run-off, Inches. | Per cent of rain-fall. | Rain-fall, inches. | Run-off, Inches. | Per cent of rain-fall. |
| January | 1.83 | 1.060 | 58 | 2.46 | 1.449 | 59 | 3.09 | 2.032 | 66 |
| February | 1.28 | .556 | 43 | 3.19 | 1.572 | 49 | 3.68 | 4.516 | 123 |
| March | 3.42 | 4.280 | 126 | 4.04 | 8.092 | 200 | 4.41 | 7.200 | 163 |
| April | 4.69 | 5.447 | 116 | 3.24 | 3.975 | 123 | 3.23 | 3.526 | 109 |
| May | 5.41 | 3.148 | 58 | 1.90 | .963 | 51 | 1.74 | .601 | 34 |
| June | 3.69 | 2.436 | 66 | 5.72 | .667 | 12 | 6.03 | 1.569 | 26 |
| July | 3.79 | .595 | 16 | 7.58 | 4.108 | 54 | 5.30 | 1.992 | 38 |
| August | 6.62 | 1.441 | 22 | 2.72 | .995 | 37 | 5.44 | 1.230 | 23 |
| September | 3.19 | 1.245 | 39 | 3.68 | .340 | 9 | 2.08 | 1.165 | 56 |
| October | .89 | .493 | 49 | 3.18 | .725 | 23 | 4.32 | 1.699 | 39 |
| November | 2.89 | .844 | 29 | 1.43 | .486 | 34 | 2.55 | 1.735 | 68 |
| December | 5.48 | 4.145 | 76 | 4.12 | 2.556 | 62 | 2.36 | .719 | 30 |
| The year | 43.18 | 25.630 | 59 | 43.26 | 25.928 | 60 | 44.23 | 27.984 | 63 |

| Month. | 1904. | | |
|-----------------|-----------------------|---------------------|------------------------|
| | Rain-fall, inches. | Run-off, Inches. | Per cent of rain-fall. |
| January | 3.44 | 1.940 | 56 |
| February | 2.30 | 1.970 | 86 |
| March | 5.03 | 7.380 | 147 |
| April | 4.44 | 4.700 | 106 |
| May | 3.69 | 2.470 | 69 |
| June | 3.73 | 1.420 | 38 |
| July | 4.70 | 1.270 | 27 |
| August | 3.32 | .315 | 9 |
| September | 2.63 | .231 | 9 |
| October | 2.20 | .472 | 21 |
| November | .54 | .326 | 60 |
| December | 2.18 | .334 | 15 |
| The year | 38.20 | 22.830 | 60 |

Rainfall stations in Susquehanna drainage basin.

| No. ^a | Station. | County. | Elevation above sea level. |
|------------------|-----------------------|------------------|----------------------------------|
| NEW YORK. | | | <i>Feet.</i> |
| 1 | Richmondville | Schoharie | 500 |
| 2 | Cooperstown | Otsego | 1,250 |
| 3 | Bonckville | Madison | 1,350 |
| 4 | New Lisbon | Otsego | 1,234 |
| 5 | Oneonta | do | 1,100 |
| 6 | South Kortright | Delaware | 1,700 |
| 7 | Oxford | Chenango | 550 |
| 8 | Cortland | Cortland | 1,130 |
| 9 | Binghamton | Broome | 854 |
| 10 | Perry City | Schuyler | 1,038 |
| 11 | Wedgwood | do | 1,350 |
| 12 | Atlanta | Steuben | 1,200 |
| 13 | Angelica | Allegany | 1,340 |
| 14 | South Canisteo | Steuben | 1,480 |
| 15 | Addison | do | 993 |
| 16 | Elmira | Chemung | 856 |
| 17 | Waverly | Tioga | 824 |
| PENNSYLVANIA. | | | |
| 18 | Athens | Bradford | 768 |
| 19 | Lawrenceville | Tioga | 1,006 |
| 20 | Wellsboro | do | 1,327 |
| 21 | Leroy | Bradford | 1,400 |
| 22 | Towanda | do | 754 |
| 23 | Dushore | Sullivan | 1,590 |
| 24 | South Eaton | Wyoming | 660 |
| 25 | Scranton | Lackawanna | 805 |
| 26 | Wilkesbarre | Luzerne | 541 |
| 27 | Williamsport | Lycoming | 530 |
| 28 ^b | Renovo | Clinton | 672 |
| 29 | Emporium | Cameron | 1,029 |
| 30 ^b | St. Marys | Elk | 1,740 |
| 31 | Lock Haven | Clinton | 560 |
| 32 | Lewisburg | Union | 450 |
| 33 ^b | Drifton | Luzerne | 1,633 |
| 34 | Girardville | Schmylkill | 1,018 |
| 35 | Selinsgrove | Snyder | 455 |
| 36 | Center Hall | Center | 1,272 |
| 37 ^b | Bellefonte | do | 744 |

^aThe numbers indicate locations on map, fig. 1, p. 11.^bData incomplete, not used.

Rainfall stations in Susquehanna drainage basin—Continued.

| No. | Station. | County. | Elevation above sea level. |
|-----------------|-------------------------|------------|----------------------------------|
| | PENNSYLVANIA—continued. | | <i>Feet.</i> |
| 38 | State College | Center | 1,191 |
| 39 | Grampion | Clearfield | 1,570 |
| 40 | Altoona | Blair | 1,179 |
| 41 | Huntingdon | Huntingdon | 650 |
| 42 | Harrisburg | Dauphin | 317 |
| 43 | Lebanon | Lebanon | 458 |
| 44 ^a | Ephrata | Lancaster | 381 |
| 45 ^a | Lancaster | do | 413 |
| 46 | York | York | 381 |
| 47 ^a | Everett | Bedford | 1,060 |

^a Data incomplete, not used.*Monthly and annual precipitation at stations in Susquehanna drainage basin.*1.^a RICHMONDVILLE, N. Y.

| Year. | Jan. | Feb. | Mar. | Apr. | May. | June | July. | Aug. | Sept. | Oct. | Nov. | Dec. | Annual. |
|-------|--------|--------|------|------|------|------|--------|------|-------|------|------|------|---------|
| 1899 | [2.02] | [2.48] | 6.24 | 1.62 | 2.75 | 2.32 | [5.74] | 1.20 | 3.22 | 1.15 | 1.58 | 2.85 | 33.17 |
| 1900 | 3.21 | 3.61 | 4.06 | 2.35 | 2.23 | 2.37 | 5.63 | 3.39 | 1.34 | 2.61 | 3.74 | 1.96 | 36.50 |
| 1901 | 1.69 | .66 | 2.09 | 6.82 | 5.22 | 2.54 | 7.24 | 5.38 | 3.24 | 2.19 | 1.62 | 3.83 | 42.52 |
| 1902 | 1.58 | 3.11 | 5.54 | 3.99 | 2.39 | 4.81 | 6.95 | 5.05 | 4.49 | 3.81 | 1.05 | 4.45 | 43.50 |
| 1903 | 1.78 | 2.54 | 5.16 | 1.03 | .22 | 8.84 | 3.12 | 5.66 | 1.23 | 6.78 | 1.63 | 2.42 | 40.46 |
| 1904 | 3.21 | 2.18 | 5.27 | 2.47 | 1.10 | 3.61 | 3.27 | 4.20 | 3.86 | 4.16 | 1.26 | 2.62 | 35.21 |
| Mean | 2.22 | 2.43 | 4.06 | 3.05 | 2.32 | 4.08 | 5.32 | 3.81 | 2.90 | 3.45 | 1.82 | 3.02 | 38.48 |

2. COOPERSTOWN, N. Y.

| Year. | Jan. | Feb. | Mar. | Apr. | May. | June | July. | Aug. | Sept. | Oct. | Nov. | Dec. | Annual. |
|-------|------|------|------|------|------|------|-------|------|-------|------|------|------|---------|
| 1891 | 5.54 | 4.76 | 2.60 | 2.22 | 2.16 | 1.98 | 5.02 | 4.26 | 1.41 | 3.01 | 3.15 | 4.96 | 41.07 |
| 1892 | 4.99 | 2.23 | 3.43 | 1.38 | 7.82 | 4.86 | 7.80 | 7.96 | 3.57 | 1.79 | 3.19 | 1.53 | 50.55 |
| 1893 | 1.89 | 4.99 | 2.13 | 2.96 | 6.74 | 2.20 | 4.85 | 7.59 | 4.03 | 1.27 | 2.20 | 4.02 | 44.87 |
| 1894 | 2.84 | 2.09 | 1.92 | 2.54 | 5.29 | 2.62 | 3.41 | 1.88 | 5.55 | 4.73 | 2.72 | 2.33 | 37.92 |
| 1895 | 2.34 | 1.43 | 1.93 | 2.89 | 2.44 | 2.18 | 3.80 | 7.15 | 2.86 | 2.17 | 3.65 | 3.89 | 36.73 |
| 1896 | 1.48 | 5.36 | 4.74 | 1.25 | 2.33 | 4.70 | 4.60 | 3.49 | 4.33 | 2.23 | 3.56 | 1.21 | 39.28 |
| 1897 | 1.72 | 2.06 | 3.31 | 3.65 | 5.21 | 5.22 | 4.86 | 6.60 | 3.40 | .64 | 5.21 | 4.64 | 46.52 |
| 1898 | 4.90 | 2.93 | 2.14 | 4.00 | 4.70 | 3.80 | 3.02 | 9.75 | 4.20 | 5.36 | 4.64 | 2.44 | 51.88 |
| 1899 | 2.22 | 2.31 | 6.04 | 1.87 | 4.52 | 2.85 | 3.92 | 2.72 | 3.17 | 2.25 | 1.93 | 4.10 | 37.90 |
| 1900 | 3.08 | 5.59 | 2.91 | 1.94 | 1.98 | 3.03 | 6.61 | 4.62 | 1.92 | 2.57 | 4.62 | 2.59 | 41.46 |
| 1901 | 2.47 | 1.12 | 3.00 | 4.73 | 4.94 | 3.65 | 6.79 | 5.96 | 3.08 | 2.48 | 2.74 | 4.85 | 45.81 |
| 1902 | 1.04 | 2.89 | 3.70 | 3.10 | 2.76 | 5.43 | 9.17 | 3.05 | 4.89 | 4.00 | 1.48 | 4.30 | 45.31 |
| 1903 | 3.30 | 3.61 | 5.84 | 1.57 | .17 | 7.35 | 5.52 | 7.26 | 1.64 | 8.32 | 2.21 | 2.66 | 49.45 |
| 1904 | 4.29 | 3.00 | 3.06 | 2.84 | 2.40 | 4.00 | 4.74 | 4.55 | 4.08 | 3.49 | 1.18 | 2.49 | 40.12 |
| Mean | 3.01 | 3.17 | 3.34 | 2.64 | 3.82 | 3.85 | 5.29 | 5.49 | 3.40 | 3.16 | 3.03 | 3.29 | 43.49 |

3. BOUCKVILLE, N. Y.

| Year. | Jan. | Feb. | Mar. | Apr. | May. | June | July. | Aug. | Sept. | Oct. | Nov. | Dec. | Annual. |
|-------|------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|---------|
| 1899 | 2.43 | 2.19 | 4.80 | 2.20 | 3.35 | 3.08 | 2.86 | 1.97 | 2.28 | 2.53 | 2.85 | 3.25 | 33.79 |
| 1900 | 3.82 | 2.60 | 6.73 | 1.21 | 1.93 | 2.21 | 5.09 | 3.32 | 1.21 | 3.60 | 6.03 | 3.72 | 41.47 |
| 1901 | 3.85 | 3.30 | 3.18 | 3.87 | 5.79 | 4.14 | 3.54 | 3.44 | 2.30 | 2.38 | 3.74 | 4.50 | 44.03 |
| 1902 | 1.88 | [4.61] | [3.70] | [1.56] | [3.53] | [6.25] | [7.25] | [3.13] | [2.99] | [5.59] | [1.53] | [5.37] | [47.39] |
| 1903 | 3.60 | 3.03 | 4.70 | 1.80 | .00 | 10.25 | 2.49 | 5.91 | 1.66 | 8.09 | 2.32 | 4.72 | 48.57 |
| 1904 | 5.39 | 3.24 | 2.68 | 3.80 | 2.49 | 2.35 | 8.85 | 4.79 | 3.28 | 3.06 | 1.11 | 3.88 | 44.92 |
| Mean | 3.50 | 3.16 | 4.30 | 2.41 | 2.85 | 4.71 | 5.01 | 3.76 | 2.29 | 4.21 | 2.93 | 4.24 | 43.37 |

^a The numbers indicate locations on map, fig. 1, p. 11.

[] Interpolated.

Monthly and annual precipitation at stations in Susquehanna drainage basin—
Continued.

4. NEW LISBON, N. Y.

| Year. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. | Annual. |
|-----------|------|------|------|------|------|-------|-------|------|-------|------|------|------|---------|
| 1891..... | 4.11 | 3.56 | 2.09 | 1.89 | 2.50 | 3.72 | 4.63 | 5.59 | 1.39 | 3.26 | 2.25 | 4.78 | 39.77 |
| 1892..... | 4.40 | 1.52 | 3.44 | 1.25 | 7.27 | 3.86 | 6.23 | 8.70 | 2.76 | 1.61 | 3.63 | 1.00 | 45.67 |
| 1893..... | 1.65 | 4.86 | 2.12 | 3.30 | 4.90 | 1.97 | 5.13 | 8.38 | 4.05 | 1.25 | .95 | 2.38 | 40.94 |
| 1894..... | 2.13 | 1.75 | 1.40 | 1.50 | 4.82 | 3.88 | 2.13 | 2.04 | 5.74 | 4.67 | 2.00 | 1.92 | 33.98 |
| 1895..... | 2.03 | 1.98 | 1.41 | 3.21 | 2.50 | 2.00 | 2.53 | 5.76 | 2.16 | 1.45 | 2.98 | 4.04 | 32.05 |
| 1896..... | .86 | 4.31 | 3.96 | .80 | 2.42 | 3.77 | 5.12 | 2.45 | 5.07 | 2.09 | 2.96 | .95 | 34.76 |
| 1897..... | 1.14 | 1.53 | 2.90 | 2.63 | 4.40 | 4.10 | 5.58 | 3.17 | 3.19 | .73 | 4.04 | 4.20 | 37.61 |
| 1898..... | 4.37 | 2.13 | 1.63 | 2.77 | 3.92 | 3.04 | 6.50 | 7.38 | 4.95 | 7.19 | 3.64 | 1.48 | 49.05 |
| 1899..... | 1.46 | 1.96 | 4.49 | 2.04 | 3.44 | 3.67 | 3.19 | 3.49 | 3.25 | 1.70 | 1.93 | 3.17 | 33.79 |
| 1900..... | 2.04 | 3.29 | 3.82 | 1.30 | 1.63 | 2.98 | 7.27 | 3.50 | 2.33 | 2.87 | 3.89 | 2.54 | 37.46 |
| 1901..... | 1.27 | .83 | 2.78 | 3.38 | 5.51 | 4.21 | 3.68 | 5.60 | 3.60 | 1.54 | 2.08 | 4.53 | 39.01 |
| 1902..... | 1.00 | 2.81 | 4.13 | 1.72 | 2.94 | 4.61 | 10.08 | 3.93 | 3.05 | 4.11 | 1.12 | 5.55 | 45.05 |
| 1903..... | 2.88 | 3.19 | 5.77 | 1.26 | .25 | 7.04 | 5.24 | 6.54 | 1.57 | 7.36 | 2.04 | 3.35 | 46.49 |
| 1904..... | 3.73 | 1.75 | 2.98 | 2.59 | 2.62 | 4.60 | 5.92 | 4.41 | 4.51 | 3.09 | 1.86 | 2.08 | 40.14 |
| Mean..... | 2.36 | 2.53 | 3.07 | 2.12 | 3.51 | 3.82 | 5.23 | 5.07 | 3.40 | 3.07 | 2.53 | 3.00 | 39.71 |

5. ONEONTA, N. Y.

| | | | | | | | | | | | | | |
|-----------|------|--------|------|------|------|--------|------|------|------|------|------|------|-------|
| 1899..... | 2.33 | 2.60 | 5.51 | 0.81 | 2.79 | 4.82 | 4.05 | 2.72 | 4.96 | 1.77 | 1.70 | 3.53 | 37.59 |
| 1900..... | 2.63 | [2.44] | 2.23 | 1.35 | 1.26 | 3.41 | 5.14 | 6.24 | 2.44 | 3.07 | 2.65 | 2.06 | 34.92 |
| 1901..... | 1.80 | .92 | 2.41 | 3.93 | 4.54 | [5.00] | 3.85 | 4.45 | 3.34 | 2.64 | 2.15 | 4.36 | 39.59 |
| 1902..... | 1.09 | 2.97 | 3.45 | 1.30 | 2.82 | 4.96 | 7.71 | 2.54 | 2.59 | 4.91 | 1.11 | 4.61 | 40.06 |
| 1903..... | 2.46 | 3.29 | 5.90 | 1.05 | .36 | 6.83 | 4.81 | 7.70 | 1.44 | 7.97 | 2.31 | 2.36 | 46.48 |
| 1904..... | 3.57 | 2.80 | 5.28 | 3.59 | 2.82 | 2.71 | 5.20 | 7.13 | 4.66 | 4.45 | 2.07 | 2.64 | 46.92 |
| Mean..... | 2.31 | 2.50 | 4.13 | 2.00 | 2.43 | 4.62 | 5.13 | 5.13 | 3.24 | 4.14 | 2.00 | 3.26 | 40.89 |

6. SOUTH KORTRIGHT, N. Y.

| | | | | | | | | | | | | | |
|-----------|--------|------|------|------|------|--------|--------|------|------|--------|------|--------|---------|
| 1891..... | 4.67 | 3.31 | 2.37 | 1.65 | 3.57 | 3.04 | 3.67 | 4.21 | 1.45 | [2.70] | 2.63 | 4.57 | [37.84] |
| 1892..... | 3.30 | 1.20 | 2.32 | .77 | 6.35 | 2.80 | 5.14 | 6.55 | 2.98 | 1.13 | 2.61 | 1.11 | 36.26 |
| 1893..... | 1.27 | 4.22 | 2.82 | 3.35 | 5.81 | 5.76 | 3.50 | 7.26 | 3.76 | 2.05 | 1.10 | 1.99 | 42.89 |
| 1894..... | 2.28 | 1.19 | 1.25 | 2.25 | 6.67 | 4.16 | 4.10 | .84 | 3.08 | 4.04 | 2.30 | 3.08 | 35.24 |
| 1895..... | 1.76 | 1.40 | 1.69 | 3.31 | 2.10 | 1.53 | 3.11 | 4.68 | 2.69 | 2.71 | 3.70 | 3.23 | 31.91 |
| 1896..... | [2.19] | 4.81 | 3.76 | 1.48 | 2.94 | 2.75 | 5.50 | 2.12 | 3.68 | 2.85 | 2.83 | 1.37 | 35.78 |
| 1897..... | .94 | 1.53 | 2.59 | 2.91 | 5.33 | 5.00 | 5.56 | 6.03 | 4.67 | .98 | 4.35 | 4.02 | 43.91 |
| 1898..... | 2.84 | 2.38 | 1.82 | 2.54 | 4.06 | 3.70 | 2.56 | 8.21 | 2.98 | 5.23 | 3.88 | 1.87 | 42.07 |
| 1899..... | 1.35 | 2.35 | 3.53 | 1.79 | 2.81 | 4.24 | 4.31 | 2.19 | 4.89 | .90 | 1.43 | 2.44 | 32.23 |
| 1900..... | 1.91 | 3.55 | 2.31 | 1.71 | 1.66 | 4.74 | 2.84 | 3.18 | 2.50 | 2.09 | 2.37 | [3.07] | 31.93 |
| 1901..... | 1.84 | 1.23 | 3.64 | 3.06 | 4.97 | [4.37] | [4.17] | 3.87 | 4.25 | 3.87 | 2.57 | 5.75 | 43.59 |
| 1902..... | 1.61 | 3.56 | 3.28 | 3.30 | 2.48 | 8.41 | 6.39 | 3.55 | 5.24 | 5.11 | .81 | 4.11 | 47.85 |
| 1903..... | 2.55 | 3.31 | 4.74 | 1.71 | .25 | 6.21 | 3.39 | 5.44 | 1.64 | 8.30 | 2.23 | 3.25 | 43.02 |
| 1904..... | 2.87 | 1.67 | 2.75 | 1.99 | 2.19 | 1.73 | 4.54 | 6.33 | 4.34 | 4.61 | 1.98 | 1.87 | 36.37 |
| Mean..... | 2.21 | 2.55 | 2.78 | 2.27 | 3.66 | 4.17 | 4.20 | 4.60 | 3.44 | 3.29 | 2.48 | 2.98 | 38.63 |

7. OXFORD, N. Y.

| | | | | | | | | | | | | | |
|-----------|------|------|------|------|------|------|------|------|------|------|------|------|-------|
| 1891..... | 4.83 | 4.15 | 2.78 | 2.44 | 1.39 | 5.44 | 4.27 | 6.02 | 2.72 | 4.42 | 2.65 | 5.38 | 46.49 |
| 1892..... | 6.47 | 1.66 | 4.87 | 1.74 | 9.37 | 4.12 | 5.62 | 7.90 | 2.50 | 1.62 | 3.44 | 1.27 | 50.58 |
| 1893..... | 2.57 | 4.47 | 2.58 | 4.89 | 6.23 | 3.70 | 6.01 | 7.37 | 3.94 | 1.46 | 1.72 | 3.28 | 48.22 |
| 1894..... | 2.85 | 2.46 | 1.86 | 2.79 | 5.03 | 4.02 | 2.73 | 2.36 | 6.11 | 5.97 | 2.58 | 2.60 | 41.36 |
| 1895..... | 3.46 | 2.00 | 2.13 | 2.76 | 2.78 | 1.74 | 2.48 | 4.59 | 2.64 | 1.06 | 3.95 | 4.23 | 53.82 |
| 1896..... | 1.99 | 4.97 | 5.56 | .77 | 3.53 | 2.96 | 5.37 | 2.71 | 2.17 | 2.69 | 2.66 | 1.72 | 37.10 |
| 1897..... | 1.76 | 2.09 | 4.08 | 3.76 | 5.47 | 4.80 | 8.04 | 2.68 | 3.13 | .80 | 4.85 | 4.01 | 45.47 |
| 1898..... | 4.76 | 3.11 | 2.75 | 4.90 | 3.90 | 3.58 | 3.41 | 9.82 | 4.99 | 7.08 | 4.58 | 3.35 | 56.23 |
| 1899..... | 2.22 | 3.29 | 5.44 | 1.70 | 3.43 | 4.30 | 5.22 | 3.20 | 3.05 | 2.52 | 2.03 | 3.54 | 39.94 |
| 1900..... | 3.19 | 4.76 | 5.31 | 1.70 | 2.00 | 3.77 | 3.72 | 2.89 | 2.53 | 3.62 | 5.31 | 3.43 | 42.23 |
| 1901..... | 2.89 | 2.05 | 3.70 | 3.33 | 7.69 | 2.96 | 3.93 | 4.33 | 3.61 | 3.04 | 3.12 | 6.21 | 46.86 |
| 1902..... | 1.82 | 4.02 | 4.32 | 1.78 | 2.73 | 6.46 | 8.65 | 2.62 | 3.97 | 4.80 | 1.25 | 6.11 | 48.53 |
| 1903..... | 3.92 | 2.99 | 5.64 | 1.69 | .42 | 7.56 | 3.98 | 7.89 | 1.52 | 7.06 | 1.88 | 5.53 | 50.08 |
| 1904..... | 4.63 | 2.85 | 3.72 | 3.09 | 3.06 | 1.22 | 5.98 | 4.49 | 5.25 | 3.06 | 1.50 | 3.75 | 42.60 |
| Mean..... | 3.38 | 3.20 | 3.91 | 2.67 | 4.07 | 4.04 | 4.96 | 4.92 | 3.44 | 3.51 | 2.97 | 3.89 | 44.96 |

*Monthly and annual precipitation at stations in Susquehanna drainage basin—
Continued.*

8. CORTLAND, N. Y.

| Year. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. | An- nual. |
|-----------|------|------|------|--------|--------|-------|-------|------|-------|-------|------|------|--------------|
| 1899..... | 1.88 | 0.69 | 1.83 | 0.56 | 2.50 | 2.25 | 4.69 | 2.64 | 2.40 | 2.99 | 2.99 | 3.98 | 29.40 |
| 1900..... | 3.28 | 1.84 | 1.49 | 1.56 | 1.17 | 2.40 | 4.78 | 1.92 | 2.00 | 4.59 | 7.17 | 2.58 | 34.78 |
| 1901..... | 1.22 | 1.44 | 2.76 | 3.31 | 3.25 | 2.96 | 3.49 | 3.83 | 2.90 | 1.02 | 3.47 | 6.41 | 36.06 |
| 1902..... | 1.25 | 1.35 | 3.20 | 1.21 | 2.79 | 5.03 | 10.12 | 3.68 | 2.51 | 3.59 | 1.07 | 4.78 | 40.58 |
| 1903..... | 1.70 | 1.71 | 5.13 | 1.12 | [2.43] | 6.12 | 3.99 | 8.21 | 2.07 | 11.47 | 2.24 | 1.62 | 47.81 |
| 1904..... | 3.62 | 2.10 | 2.85 | [1.55] | 4.03 | 2.57 | 7.55 | 4.50 | 5.02 | 3.29 | .84 | 2.68 | 40.60 |
| Mean..... | 2.16 | 1.52 | 2.88 | 1.55 | 2.70 | 3.55 | 5.77 | 4.13 | 2.82 | 4.49 | 2.96 | 3.68 | 38.21 |

9. BINGHAMTON, N. Y.

| | | | | | | | | | | | | | |
|-----------|------|------|------|------|------|------|------|------|--------|------|------|------|-------|
| 1891..... | 3.30 | 3.27 | 4.46 | 2.16 | 1.16 | 3.55 | 3.30 | 6.59 | 1.54 | 4.24 | 2.65 | 3.24 | 39.46 |
| 1892..... | 4.21 | 1.90 | 3.98 | 1.13 | 6.08 | 5.43 | 2.92 | 6.04 | 1.33 | 1.54 | 2.65 | 1.27 | 38.48 |
| 1893..... | 2.42 | 4.16 | 2.80 | 3.36 | 5.16 | 2.58 | 4.10 | 4.88 | 4.50 | 1.68 | 1.38 | 2.91 | 39.93 |
| 1894..... | 2.18 | 2.98 | 1.51 | 3.53 | 5.34 | 1.97 | 2.88 | 1.47 | 4.98 | 5.62 | 1.98 | 3.31 | 37.75 |
| 1895..... | 3.18 | 1.60 | 1.58 | 2.29 | 2.92 | 2.05 | 4.06 | 3.39 | 2.11 | .82 | 2.94 | 3.63 | 30.57 |
| 1896..... | 2.25 | 4.28 | 4.68 | .63 | 3.11 | 2.64 | 3.85 | 1.42 | 4.62 | 3.68 | 2.66 | 1.20 | 35.02 |
| 1897..... | 1.12 | 1.37 | 2.66 | 1.98 | 4.01 | 2.98 | 2.30 | 1.37 | 3.03 | .66 | 2.43 | 3.23 | 27.14 |
| 1898..... | 2.86 | 2.51 | 2.31 | 2.79 | 4.02 | 2.16 | 2.05 | 6.48 | 2.70 | 5.79 | 3.15 | 1.45 | 38.27 |
| 1899..... | 1.79 | 2.63 | 2.84 | .96 | 2.43 | 2.15 | 1.84 | 2.44 | 1.45 | 1.12 | 1.83 | 2.02 | 23.50 |
| 1900..... | 1.59 | 2.65 | 3.17 | 1.35 | .53 | 1.54 | 2.29 | .67 | 2.10 | 2.05 | 3.08 | 1.40 | 22.42 |
| 1901..... | .76 | 1.09 | 2.95 | 4.20 | 5.49 | 1.77 | 3.47 | 3.76 | 3.10 | 1.46 | 2.31 | 5.41 | 35.77 |
| 1902..... | 1.13 | 2.31 | 3.54 | 1.49 | 1.93 | 6.84 | 5.51 | 2.13 | 4.75 | 3.08 | 1.07 | 2.92 | 36.70 |
| 1903..... | 2.41 | 2.24 | 3.84 | 1.57 | .42 | 5.79 | 2.67 | 6.85 | 1.21 | 5.74 | 2.26 | 2.12 | 37.12 |
| 1904..... | 2.11 | 1.16 | 2.11 | 2.51 | 2.66 | 2.76 | 4.73 | 3.12 | [2.88] | 3.31 | .49 | 1.12 | 28.96 |
| Mean..... | 2.24 | 2.44 | 3.03 | 2.14 | 3.23 | 3.16 | 3.28 | 3.62 | 2.88 | 2.91 | 2.21 | 2.52 | 33.66 |

10. PERRY CITY, N. Y.

| | | | | | | | | | | | | | |
|-----------|------|------|------|------|------|------|------|------|------|------|------|------|-------|
| 1891..... | 3.34 | 4.23 | 3.45 | 2.16 | 0.74 | 4.13 | 3.54 | 3.90 | 0.98 | 5.46 | 2.19 | 4.48 | 38.60 |
| 1892..... | 4.56 | 1.54 | 3.95 | 1.65 | 6.08 | 6.65 | 6.86 | 4.12 | .84 | 1.64 | 4.63 | .78 | 43.30 |
| 1893..... | 1.75 | 2.80 | 2.43 | 3.58 | 5.37 | 2.13 | 4.99 | 5.21 | 4.12 | 2.74 | .91 | 1.87 | 37.90 |
| 1894..... | 3.13 | 2.54 | .99 | 6.10 | 6.55 | 4.05 | 2.86 | 1.38 | 5.46 | 4.33 | 2.10 | 3.06 | 42.55 |
| 1895..... | 2.82 | 1.40 | 2.06 | 1.37 | 2.49 | 3.54 | 2.72 | 4.67 | 2.00 | .91 | 4.16 | 3.08 | 31.22 |
| 1896..... | 1.68 | 3.58 | 3.70 | 1.58 | 3.81 | 3.67 | 4.18 | 2.54 | 3.97 | 4.07 | 2.44 | 1.40 | 36.62 |
| 1897..... | 1.81 | 1.33 | 2.66 | 2.56 | 3.69 | 4.18 | 3.55 | 2.30 | 2.58 | .86 | 3.74 | 2.86 | 32.12 |
| 1898..... | 2.47 | 1.68 | 1.85 | 3.64 | 3.36 | 3.47 | 1.82 | 4.68 | 2.12 | 6.26 | 3.90 | 2.35 | 37.60 |
| 1899..... | 2.03 | 1.42 | 2.93 | 1.46 | 2.73 | 2.38 | 4.30 | .96 | 2.42 | 3.22 | 3.34 | 3.02 | 30.21 |
| 1900..... | 2.52 | 3.84 | 3.64 | 2.00 | 2.29 | 1.51 | 2.66 | 2.48 | 1.07 | 4.76 | 6.58 | 2.42 | 35.77 |
| 1901..... | 2.10 | 1.42 | 3.12 | 4.85 | 4.80 | 2.85 | 5.39 | 7.37 | 2.22 | .86 | 3.36 | 5.28 | 43.62 |
| 1902..... | 2.18 | 1.46 | 2.28 | 1.67 | 2.14 | 5.52 | 9.46 | 4.82 | 2.40 | 4.03 | 1.20 | 3.69 | 40.85 |
| 1903..... | 2.28 | 2.03 | 5.34 | 1.86 | .72 | 7.04 | 4.94 | 8.60 | .99 | 5.79 | 2.56 | 1.52 | 43.67 |
| 1904..... | 2.70 | 1.83 | 2.92 | 3.54 | 5.61 | 2.01 | 5.48 | 3.10 | 2.80 | 3.82 | 1.07 | 1.80 | 36.68 |
| Mean..... | 2.53 | 2.22 | 2.95 | 2.72 | 3.60 | 3.80 | 4.48 | 4.01 | 2.43 | 3.48 | 3.01 | 2.69 | 37.92 |

11. WEDGWOOD, N. Y.

| | | | | | | | | | | | | | |
|-----------|------|------|------|------|------|------|------|-------|------|------|------|------|-------|
| 1891..... | 2.48 | 3.88 | 3.11 | 2.46 | 0.89 | 2.43 | 2.45 | 4.58 | 0.66 | 4.19 | 1.77 | 3.85 | 32.75 |
| 1892..... | 3.50 | 2.50 | 3.81 | 1.08 | 5.17 | 4.35 | 7.24 | 4.02 | .75 | 2.20 | 3.25 | .71 | 38.58 |
| 1893..... | 2.23 | 2.49 | 2.93 | 3.55 | 5.37 | 5.51 | 3.55 | 5.61 | 2.83 | 2.57 | 1.60 | 1.71 | 39.95 |
| 1894..... | 3.10 | 3.09 | 1.00 | 6.67 | 8.01 | 2.59 | 2.49 | 1.41 | 5.91 | 4.22 | 1.86 | 3.15 | 43.50 |
| 1895..... | 2.30 | .85 | 1.00 | 1.55 | 2.71 | 4.03 | 2.31 | 8.27 | 1.32 | 1.02 | 3.37 | 3.51 | 32.24 |
| 1896..... | 1.72 | 5.02 | 3.43 | 2.52 | 2.98 | 6.23 | 5.02 | 1.54 | 5.02 | 4.42 | 2.03 | 1.42 | 41.35 |
| 1897..... | 1.85 | .87 | 2.54 | 2.72 | 3.72 | 2.74 | 3.43 | 3.04 | 2.66 | .74 | 3.20 | 1.93 | 29.44 |
| 1898..... | 2.73 | 1.88 | 2.62 | 2.91 | 3.40 | 2.72 | 3.48 | 4.73 | 1.86 | 5.95 | 2.73 | 1.98 | 36.99 |
| 1899..... | 1.72 | 2.07 | 2.80 | 1.03 | 2.04 | 2.11 | 3.77 | 2.55 | 2.48 | 2.62 | 3.50 | 2.90 | 29.59 |
| 1900..... | 2.56 | 2.57 | 3.74 | 1.80 | 2.72 | 1.91 | 3.19 | 1.71 | .90 | 5.33 | 6.79 | 2.53 | 35.75 |
| 1901..... | 2.05 | 1.37 | 3.32 | 5.44 | 4.82 | 4.09 | 2.84 | 9.42 | 2.46 | .81 | 2.90 | 5.29 | 44.81 |
| 1902..... | 2.04 | 2.02 | 2.87 | 2.96 | 2.33 | 6.25 | 9.23 | 3.70 | 2.73 | 3.41 | 1.24 | 3.25 | 42.03 |
| 1903..... | 3.29 | 2.25 | 5.42 | 2.06 | .87 | 5.53 | 3.26 | 10.34 | 1.51 | 5.05 | 1.81 | 1.93 | 43.32 |
| 1904..... | 3.68 | 1.77 | 3.12 | 3.87 | 5.31 | 3.39 | 4.79 | 4.85 | 2.13 | 2.02 | .62 | 1.87 | 37.42 |
| Mean..... | 2.52 | 2.33 | 2.98 | 2.90 | 3.60 | 3.85 | 4.08 | 4.70 | 2.37 | 3.18 | 2.62 | 2.57 | 37.70 |

Monthly and annual precipitation at stations in Susquehanna drainage basin—
Continued.

12. ATLANTA, N. Y.

| Year. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. | An- nual. |
|-----------|------|------|------|------|------|-------|-------|------|-------|------|------|------|--------------|
| 1899..... | 1.31 | 1.54 | 2.45 | 1.51 | 2.85 | 1.18 | 2.10 | 3.14 | 2.54 | 1.91 | 2.38 | 3.57 | 26.48 |
| 1900..... | 2.64 | 3.00 | 4.04 | 2.08 | 1.77 | 2.17 | 3.08 | 2.41 | 1.07 | 3.79 | 5.89 | 1.87 | 33.81 |
| 1901..... | 2.18 | 2.54 | 2.60 | 5.97 | 5.97 | 2.10 | 7.59 | 9.08 | 2.58 | 1.31 | 2.99 | 4.82 | 49.73 |
| 1902..... | 2.83 | 1.94 | 2.27 | 3.60 | 2.97 | 5.19 | 10.21 | 1.93 | 2.83 | 3.25 | 1.39 | 2.59 | 41.00 |
| 1903..... | 2.41 | 2.46 | 5.02 | 2.92 | 1.16 | 4.66 | 4.27 | 5.58 | 2.06 | 3.86 | 1.84 | 1.67 | 37.91 |
| 1904..... | 4.56 | 2.39 | 3.59 | 2.99 | 4.39 | 4.31 | 6.35 | 3.08 | 3.69 | 2.79 | .98 | 2.05 | 41.17 |
| Mean..... | 2.66 | 2.31 | 3.33 | 3.18 | 3.18 | 3.27 | 5.60 | 4.20 | 2.46 | 2.82 | 2.58 | 2.76 | 38.35 |

13. ANGELICA, N. Y.

| Year. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. | An- nual. |
|-----------|------|------|------|------|------|--------|-------|--------|--------|--------|--------|--------|--------------|
| 1899..... | 2.04 | 1.64 | 2.72 | 0.90 | 2.39 | 1.81 | 2.56 | 2.05 | 2.86 | 2.99 | 2.09 | 3.97 | 28.02 |
| 1900..... | 2.61 | 2.33 | 3.76 | 1.44 | 2.62 | 2.56 | 4.04 | 2.59 | 1.47 | 4.52 | 5.40 | 2.15 | 35.49 |
| 1901..... | 2.62 | 2.04 | 2.95 | 5.29 | 5.23 | 3.69 | 3.34 | 4.87 | 3.11 | 1.15 | 2.88 | 4.77 | 41.94 |
| 1902..... | 2.80 | 1.80 | 2.53 | 3.76 | 3.97 | 5.79 | 12.46 | 3.35 | 4.46 | 2.06 | .79 | 1.95 | 45.72 |
| 1903..... | 1.78 | 1.45 | 4.60 | 2.65 | 1.16 | 4.54 | 4.11 | 7.51 | 1.80 | [2.68] | 2.57 | .77 | 35.62 |
| 1904..... | 2.69 | 1.48 | 2.47 | 1.97 | 4.00 | [3.68] | 6.54 | [4.07] | [2.74] | [2.68] | [2.75] | [2.72] | [37.79] |
| Mean..... | 2.42 | 1.79 | 3.17 | 2.67 | 3.23 | 3.68 | 5.51 | 4.07 | 2.74 | 2.68 | 2.75 | 2.72 | 37.43 |

14. SOUTH CANISTEO, N. Y.

| Year. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. | An- nual. |
|-----------|------|------|------|------|-------|-------|-------|------|-------|------|------|------|--------------|
| 1891..... | 2.53 | 4.72 | 3.43 | 2.22 | 1.41 | 2.68 | 4.62 | 5.80 | 1.20 | 3.48 | 2.74 | 3.30 | 38.13 |
| 1892..... | 3.50 | 3.40 | 3.42 | 1.57 | 6.74 | 3.99 | 4.56 | 4.83 | 1.40 | 2.44 | 3.60 | 1.01 | 40.46 |
| 1893..... | 2.96 | 3.58 | 3.51 | 5.84 | 5.25 | 4.78 | 2.70 | 4.13 | 2.76 | 4.05 | 2.03 | 2.91 | 44.50 |
| 1894..... | 3.41 | 3.21 | 1.64 | 7.80 | 11.46 | 3.51 | 3.34 | 2.71 | 7.12 | 4.40 | 2.13 | 3.41 | 54.14 |
| 1895..... | 3.32 | .97 | 1.63 | 1.49 | 2.79 | 4.75 | 2.77 | 3.88 | 1.15 | 1.17 | 3.39 | 4.34 | 31.65 |
| 1896..... | 2.76 | 5.62 | 3.62 | 1.25 | 4.03 | 6.22 | 5.01 | 1.62 | 5.10 | 6.49 | 1.82 | 1.14 | 44.68 |
| 1897..... | 2.34 | 1.60 | 3.01 | 3.13 | 3.18 | 3.48 | 5.62 | 2.69 | 3.47 | 1.04 | 3.56 | 2.71 | 35.83 |
| 1898..... | 3.90 | 2.09 | 4.53 | 3.35 | 3.87 | 2.90 | 1.75 | 4.45 | 2.28 | 4.80 | 3.33 | 2.62 | 39.87 |
| 1899..... | 1.99 | 1.95 | 2.60 | 1.51 | 3.29 | 2.48 | 2.99 | 1.99 | 5.15 | 3.21 | 1.80 | 4.27 | 31.23 |
| 1900..... | 2.40 | 5.62 | 2.62 | 1.60 | 3.05 | 5.11 | 4.10 | 3.37 | 1.43 | 5.81 | 6.03 | 1.60 | 42.74 |
| 1901..... | 1.95 | 1.32 | 3.13 | 7.07 | 5.15 | 3.53 | 3.97 | 5.93 | 3.24 | .62 | 2.64 | 4.66 | 43.21 |
| 1902..... | 2.90 | 2.37 | 2.73 | 2.86 | 1.77 | 6.24 | 8.40 | 2.56 | 3.32 | 1.49 | 1.41 | 3.05 | 39.10 |
| 1903..... | 3.25 | 2.15 | 4.64 | 3.24 | 1.94 | 5.49 | 4.59 | 7.13 | 1.98 | 4.47 | 2.48 | 1.38 | 42.74 |
| 1904..... | 3.45 | 3.85 | 3.15 | 2.81 | 5.06 | 2.03 | 4.20 | 3.80 | 3.01 | 2.46 | 1.05 | 2.10 | 36.97 |
| Mean..... | 2.90 | 3.03 | 3.12 | 3.27 | 4.21 | 4.09 | 4.18 | 3.92 | 2.90 | 3.28 | 2.72 | 2.75 | 40.37 |

15. ADDISON, N. Y.

| Year. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. | An- nual. |
|-----------|------|------|------|------|------|-------|-------|------|-------|------|------|-------|--------------|
| 1891..... | 1.84 | 2.89 | 2.12 | 1.44 | 0.32 | 2.05 | 2.91 | 4.24 | 0.49 | 2.94 | 1.64 | 2.96 | 25.84 |
| 1892..... | 2.97 | 1.58 | 3.68 | .94 | 5.85 | 3.18 | 4.94 | 3.62 | .91 | 1.50 | 3.46 | .48 | 33.11 |
| 1893..... | 1.64 | 2.27 | 2.62 | 3.50 | 7.87 | 3.04 | 2.37 | 3.69 | 2.34 | 2.89 | 1.22 | 1.88 | 35.33 |
| 1894..... | 1.94 | 1.89 | 1.06 | 6.60 | 9.70 | 1.82 | 2.06 | 1.44 | 5.62 | 4.03 | 1.42 | 2.93 | 40.51 |
| 1895..... | 3.11 | 1.12 | .88 | 1.31 | 2.11 | 4.15 | 2.02 | 3.82 | 1.22 | .80 | 2.44 | 2.02 | 25.90 |
| 1896..... | 1.47 | 3.18 | 3.05 | 1.07 | 4.50 | 5.78 | 4.45 | .77 | 3.67 | 5.73 | .83 | .88 | 35.38 |
| 1897..... | 1.54 | .76 | 2.29 | 2.41 | 4.23 | 2.56 | 4.52 | 2.05 | 2.90 | .94 | 3.10 | 1.91 | 29.24 |
| 1898..... | 3.91 | 1.80 | 2.30 | 2.51 | 4.12 | 3.67 | 2.16 | 2.92 | 1.31 | 5.99 | 2.13 | 2.15 | 34.97 |
| 1899..... | 1.87 | 1.49 | 2.24 | 1.17 | 2.88 | 2.96 | 3.31 | 2.90 | 4.25 | 1.93 | 3.58 | 3.04 | 31.62 |
| 1900..... | 1.92 | 2.15 | 2.86 | 1.49 | 2.92 | 2.86 | 1.93 | 2.39 | 1.01 | 4.80 | 6.00 | 1.66 | 31.99 |
| 1901..... | 1.23 | .71 | 3.06 | 5.82 | 4.94 | 2.14 | 2.01 | 6.22 | 2.55 | .93 | 2.00 | 4.86 | 36.47 |
| 1902..... | 2.30 | 1.42 | 2.57 | 2.41 | 2.26 | 5.37 | 6.85 | 2.91 | 3.55 | .89 | 2.50 | 35.87 | 39.87 |
| 1903..... | 1.87 | 1.81 | 4.56 | 2.67 | 1.90 | 5.90 | 5.51 | 7.25 | 1.81 | 4.42 | 1.84 | .79 | 40.33 |
| 1904..... | 2.47 | 1.56 | 2.79 | 2.27 | 4.44 | 1.94 | 4.53 | 3.76 | 2.63 | 1.57 | .56 | 1.13 | 29.65 |
| Mean..... | 2.15 | 1.76 | 2.58 | 2.54 | 4.15 | 3.39 | 3.54 | 3.43 | 2.45 | 2.95 | 2.22 | 2.15 | 33.31 |

Monthly and annual precipitation at stations in Susquehanna drainage basin—
Continued.

16. ELMIRA, N. Y.

| Year. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. | An- nual. |
|-----------|--------|--------|------|------|------|-------|-------|------|-------|--------|--------|--------|--------------|
| 1891..... | 2.33 | 2.19 | 1.98 | 1.73 | 0.50 | 4.57 | 2.13 | 3.72 | 3.25 | [4.30] | [1.80] | [3.80] | 32.30 |
| 1892..... | 3.01 | [1.76] | 2.96 | 1.01 | 5.30 | 4.11 | 3.39 | 3.28 | 1.18 | 1.30 | [2.10] | [2.31] | 31.71 |
| 1893..... | .62 | 1.61 | 2.05 | 3.55 | 6.84 | 3.62 | 3.89 | 5.54 | 3.72 | 2.66 | [2.10] | [2.31] | 38.51 |
| 1894..... | 2.73 | 1.89 | 1.05 | 4.42 | 7.65 | 1.94 | 1.62 | 1.23 | 5.16 | 4.21 | 1.28 | 2.89 | 36.07 |
| 1895..... | 2.70 | 1.20 | 1.37 | 1.56 | 3.03 | 3.51 | 2.34 | 4.04 | 1.89 | .78 | 1.25 | 2.70 | 26.37 |
| 1896..... | 1.56 | 3.40 | 3.22 | .77 | 3.14 | 3.31 | 5.55 | .94 | 2.73 | 4.86 | 1.40 | .61 | 31.49 |
| 1897..... | 1.40 | .93 | 2.41 | 2.30 | 5.56 | 1.76 | 3.23 | 3.70 | 3.70 | .65 | 2.89 | 1.60 | 30.13 |
| 1898..... | 2.45 | 1.45 | 2.53 | 2.84 | 4.29 | 3.43 | 2.24 | 4.70 | 1.78 | 4.49 | 2.24 | 2.25 | 34.69 |
| 1899..... | 1.51 | 1.65 | 2.94 | 1.52 | 2.52 | 2.84 | 2.69 | 3.16 | 3.23 | 3.07 | 1.68 | 1.82 | 28.63 |
| 1900..... | [1.95] | 2.26 | 3.55 | 1.58 | 1.43 | 1.82 | 3.48 | 1.25 | 1.16 | 4.19 | 5.09 | 1.72 | 29.28 |
| 1901..... | 1.09 | .59 | 2.84 | 5.56 | 4.82 | 1.84 | 4.23 | 4.07 | 2.86 | 3.93 | 2.75 | 5.22 | 36.80 |
| 1902..... | 1.93 | 1.46 | 2.63 | 1.71 | 2.02 | 4.12 | 7.84 | 2.91 | 3.53 | 3.30 | .88 | 1.96 | 34.29 |
| 1903..... | 2.08 | 2.50 | 4.25 | 2.24 | 1.52 | 7.18 | 4.78 | 6.28 | 1.47 | 5.10 | 1.87 | .81 | 40.08 |
| 1904..... | 3.18 | 2.21 | 2.52 | 2.77 | 5.00 | 4.66 | 3.80 | 3.61 | 3.52 | 2.01 | .57 | 1.15 | 34.90 |
| Mean..... | 2.04 | 1.79 | 2.58 | 2.40 | 3.83 | 3.47 | 3.66 | 3.46 | 2.80 | 2.99 | 1.99 | 2.22 | 33.23 |

17. WAVERLY, N. Y.

| | | | | | | | | | | | | | |
|-----------|------|------|------|------|------|------|------|------|------|------|------|------|-------|
| 1899..... | 1.77 | 2.26 | 2.88 | 1.23 | 3.26 | 2.77 | 4.08 | 5.23 | 2.40 | 1.53 | 3.37 | 2.48 | 33.26 |
| 1900..... | 2.00 | 3.35 | 4.08 | 1.58 | 1.11 | 2.75 | 3.07 | 1.64 | 1.12 | 3.72 | 5.20 | 2.76 | 32.38 |
| 1901..... | 1.22 | .86 | 4.42 | 5.87 | 5.96 | 2.59 | 3.35 | 5.83 | 2.59 | 1.42 | 3.47 | 6.61 | 44.19 |
| 1902..... | 2.48 | 2.20 | 4.56 | 2.76 | 1.97 | 5.50 | 7.29 | 2.36 | 3.98 | 3.46 | 1.05 | 3.19 | 40.80 |
| 1903..... | 2.52 | 2.23 | 4.27 | 2.25 | .76 | 6.67 | 3.87 | 6.52 | 1.85 | 5.60 | 2.30 | 1.49 | 40.33 |
| 1904..... | 3.47 | 1.53 | 3.67 | 2.57 | 4.02 | 3.33 | 2.70 | 3.31 | 3.38 | 2.08 | .69 | 1.81 | 32.56 |
| Mean..... | 2.24 | 2.07 | 3.98 | 2.71 | 2.85 | 3.94 | 4.06 | 4.15 | 2.55 | 2.97 | 2.68 | 3.06 | 37.26 |

18. ATHENS, PA.

| | | | | | | | | | | | | | |
|-----------|------|------|------|--------|-------|-------|-------|-------|-------|-------|-------|-------|-------|
| 1899..... | 2.53 | 2.84 | 2.75 | 1.41 | 3.15 | 1.93 | 3.90 | 4.32 | 2.49 | 1.38 | 3.26 | 2.57 | 32.53 |
| 1900..... | 1.59 | 2.84 | 3.39 | 1.73 | 1.26 | 2.16 | 2.70 | 1.48 | 1.15 | 3.10 | 4.60 | 2.14 | 28.14 |
| 1901..... | .74 | .45 | 3.82 | 5.40 | 5.14 | 4.11 | 3.32 | 4.79 | 2.33 | 1.48 | 3.10 | 4.47 | 39.15 |
| 1902..... | 2.05 | 1.89 | 3.41 | 2.71 | 1.65 | 5.18 | 5.68 | 2.17 | 4.01 | 3.08 | 1.11 | 2.95 | 35.87 |
| 1903..... | 2.60 | 2.54 | 4.33 | [2.81] | 2.00 | 5.42 | 3.57 | 5.79 | 1.71 | 5.91 | 2.40 | 1.42 | 40.50 |
| 1904..... | 3.02 | 1.15 | (a) | ----- | ----- | ----- | ----- | ----- | ----- | ----- | ----- | ----- | ----- |
| Mean..... | 2.09 | 1.95 | 3.54 | 2.81 | 2.64 | 3.76 | 3.83 | 3.71 | 2.34 | 2.99 | 2.89 | 2.71 | 35.24 |

19. LAWRENCEVILLE, PA.

| | | | | | | | | | | | | | |
|-----------|------|------|--------|------|------|------|------|------|------|------|------|------|-------|
| 1899..... | 1.85 | 2.22 | 2.28 | 2.10 | 2.81 | 3.78 | 3.15 | 6.06 | 3.03 | 0.41 | 3.46 | 2.60 | 33.75 |
| 1900..... | 3.48 | 5.10 | [3.18] | 1.11 | 2.47 | 2.02 | 3.50 | 2.05 | .95 | 4.85 | 6.36 | 1.60 | 36.67 |
| 1901..... | 1.60 | .90 | 3.45 | 5.64 | 3.90 | 1.61 | 2.99 | 5.08 | 2.05 | 1.54 | 2.78 | 6.22 | 37.76 |
| 1902..... | 1.75 | 1.95 | 2.30 | 2.70 | 2.16 | 5.54 | 7.37 | 2.14 | 4.30 | 2.22 | 1.19 | 3.21 | 36.83 |
| 1903..... | 2.62 | 2.33 | 4.67 | 2.67 | 1.65 | 8.60 | 5.60 | 5.31 | 1.99 | 5.10 | 2.85 | 1.92 | 45.31 |
| 1904..... | 3.08 | 3.06 | 2.60 | 2.95 | 4.32 | 3.04 | 3.78 | 2.68 | 2.30 | 2.24 | .40 | 1.60 | 32.05 |
| Mean..... | 2.40 | 2.59 | 3.08 | 2.86 | 2.88 | 4.10 | 4.40 | 3.89 | 2.44 | 2.73 | 2.84 | 2.86 | 37.07 |

(a) No record.

Monthly and annual precipitation at stations in Susquehanna drainage basin—
Continued.

20. WELLSBORO, PA.

| Year. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. | An- nual. |
|-----------|------|------|------|------|-------|-------|-------|------|-------|------|------|------|--------------|
| 1891..... | 6.53 | 3.46 | 2.72 | 1.07 | 1.30 | 4.07 | 3.43 | 3.57 | 2.30 | 2.44 | 4.11 | 4.01 | 39.01 |
| 1892..... | 3.67 | 2.21 | 4.56 | .61 | 6.69 | 8.84 | 2.15 | 4.73 | 1.18 | .33 | 2.55 | .40 | 37.92 |
| 1893..... | 4.92 | 6.55 | 5.09 | 5.38 | 6.58 | 1.42 | 2.50 | 4.59 | 2.03 | 2.88 | 3.00 | 4.21 | 49.15 |
| 1894..... | 2.25 | 2.25 | .24 | 8.69 | 10.23 | 1.89 | 3.88 | 2.05 | 5.85 | 3.81 | 3.06 | 4.07 | 48.27 |
| 1895..... | 3.00 | .85 | 2.90 | 2.21 | 6.44 | 3.50 | 3.22 | 4.65 | 1.12 | 1.62 | 2.67 | 6.55 | 38.73 |
| 1896..... | 1.50 | 4.34 | 3.00 | .91 | 1.87 | 3.92 | 5.67 | .88 | 3.03 | 5.40 | .82 | .95 | 32.29 |
| 1897..... | 2.23 | 2.30 | 3.55 | 2.55 | 5.53 | 2.85 | 5.46 | 1.84 | 3.40 | .67 | 5.21 | 3.09 | 38.68 |
| 1898..... | 1.72 | 1.33 | 4.78 | 4.43 | 4.70 | 2.70 | 2.04 | 5.13 | 2.24 | 8.62 | 2.83 | 2.68 | 43.20 |
| 1899..... | 3.42 | 2.54 | 2.75 | 3.07 | 2.15 | 4.09 | 3.37 | 3.49 | 2.97 | 2.63 | 2.90 | 3.78 | 37.16 |
| 1900..... | 3.04 | 4.90 | 2.90 | 1.22 | 2.50 | 2.90 | 2.90 | 3.67 | .55 | 5.01 | 6.11 | .97 | 36.67 |
| 1901..... | 1.27 | .80 | 2.53 | 4.46 | 4.23 | 4.17 | 2.27 | 5.04 | 2.14 | .39 | 3.59 | 5.66 | 36.55 |
| 1902..... | 1.54 | 2.70 | 2.67 | 2.86 | 2.05 | 6.17 | 9.48 | 1.29 | 3.32 | 2.14 | .50 | 5.18 | 39.90 |
| 1903..... | 1.86 | 3.55 | 5.19 | 2.76 | 2.12 | 4.87 | 5.27 | 3.37 | 1.10 | 5.68 | 2.42 | 1.35 | 39.54 |
| 1904..... | 2.95 | (a) | | | | | | | | | | | |
| Mean..... | 2.85 | 2.91 | 3.30 | 3.09 | 4.34 | 3.95 | 3.97 | 3.41 | 2.40 | 3.20 | 3.06 | 3.30 | 39.77 |

21. LEROY, PA.

| | | | | | | | | | | | | | |
|-----------|------|------|------|------|------|------|------|------|------|------|------|------|-------|
| 1891..... | 4.63 | 3.13 | 3.15 | 2.01 | 1.18 | 4.75 | 3.05 | 4.33 | 2.00 | 4.25 | 3.24 | 4.34 | 40.06 |
| 1892..... | 4.60 | 1.09 | 4.25 | .96 | 5.14 | 7.97 | 2.39 | 4.04 | .91 | 3.22 | .93 | | 37.64 |
| 1893..... | 2.59 | 3.86 | 3.10 | 4.19 | 7.76 | 1.96 | 2.18 | 5.92 | 2.70 | 3.91 | 2.07 | 2.71 | 42.95 |
| 1894..... | 2.43 | 3.04 | 1.00 | 6.12 | 8.35 | 1.64 | 2.98 | 1.23 | 5.44 | 5.29 | 2.47 | 3.39 | 43.38 |
| 1895..... | 3.27 | .80 | 1.55 | 2.65 | 3.24 | 3.69 | 3.42 | 3.81 | 3.11 | .65 | 3.06 | 4.05 | 33.30 |
| 1896..... | 2.00 | 4.66 | 4.58 | 1.44 | 2.46 | 2.66 | 5.84 | 2.22 | 3.87 | 5.04 | 2.92 | .79 | 38.48 |
| 1897..... | 2.13 | 2.28 | 2.55 | 2.70 | 4.84 | 3.77 | 3.95 | 4.40 | 3.08 | 1.30 | 3.81 | 2.89 | 37.70 |
| 1898..... | 3.30 | 2.05 | 3.39 | 4.61 | 3.65 | 2.75 | 3.06 | 6.95 | .81 | 5.37 | 2.62 | 1.58 | 40.14 |
| 1899..... | 2.19 | 3.05 | 3.02 | 2.15 | 2.07 | 4.90 | 1.93 | 6.84 | 2.85 | 1.34 | 3.64 | 4.47 | 38.45 |
| 1900..... | 1.94 | 3.07 | 5.45 | 1.34 | 1.50 | 3.40 | 4.06 | 2.14 | .54 | 3.88 | 4.71 | 2.12 | 34.15 |
| 1901..... | .99 | .75 | 4.21 | 4.63 | 5.34 | 3.44 | 3.22 | 5.40 | 3.70 | 1.16 | 2.83 | 8.26 | 43.98 |
| 1902..... | 2.59 | 3.02 | 4.76 | 3.16 | 1.47 | 5.40 | 9.46 | 4.31 | 4.67 | 3.29 | .90 | 3.46 | 46.49 |
| 1903..... | 2.95 | 3.00 | 4.37 | 2.97 | 2.00 | 5.13 | 4.17 | 4.40 | 1.57 | 5.08 | 2.76 | 2.60 | 41.00 |
| 1904..... | 2.83 | 1.13 | 3.94 | 3.15 | 5.45 | 3.50 | 2.21 | 4.80 | 3.53 | 2.58 | .65 | 1.65 | 35.42 |
| Mean..... | 2.75 | 2.50 | 3.52 | 3.01 | 3.89 | 3.93 | 3.71 | 4.34 | 2.85 | 3.15 | 2.78 | 3.20 | 39.52 |

22. TOWANDA, PA.

| | | | | | | | | | | | | | |
|-----------|------|------|------|------|------|------|------|------|------|------|------|------|-------|
| 1899..... | 1.80 | 2.52 | 2.55 | 1.84 | 2.10 | 4.52 | 2.47 | 5.43 | 2.03 | 1.21 | 3.39 | 2.82 | 32.68 |
| 1900..... | 1.36 | 2.90 | 3.48 | 1.31 | 1.38 | 3.49 | 3.49 | 3.44 | .69 | 2.83 | 3.53 | 1.99 | 29.89 |
| 1901..... | .91 | .45 | 3.92 | 4.65 | 7.58 | 4.26 | 3.51 | 4.79 | 3.95 | 1.31 | 2.43 | 6.00 | 43.76 |
| 1902..... | 1.72 | 3.35 | 4.07 | 2.36 | 1.06 | 4.86 | 7.77 | 2.02 | 4.58 | 3.35 | 1.11 | 2.95 | 39.20 |
| 1903..... | 2.62 | 2.73 | 3.83 | 2.37 | .89 | 5.05 | 4.85 | 4.63 | 1.24 | 4.98 | 2.66 | 2.42 | 38.27 |
| 1904..... | 2.72 | 1.06 | 2.73 | 2.48 | 4.89 | 5.03 | 3.96 | 4.32 | 4.70 | 2.18 | .69 | 1.59 | 36.35 |
| Mean..... | 1.86 | 2.17 | 3.43 | 2.50 | 2.98 | 4.54 | 4.34 | 4.10 | 2.86 | 2.64 | 2.30 | 2.96 | 36.68 |

23. DUSHORE, PA.

| | | | | | | | | | | | | | |
|-----------|------|------|------|------|------|--------|------|-------|------|------|------|------|-------|
| 1899..... | 1.94 | 3.48 | 3.79 | 1.82 | 2.20 | 3.13 | 2.03 | 3.79 | 2.80 | 1.36 | 2.84 | 5.09 | 34.27 |
| 1900..... | 1.97 | 4.01 | 3.19 | 1.05 | 2.31 | 4.10 | 4.68 | 2.25 | 1.13 | 2.35 | 3.38 | 2.09 | 32.51 |
| 1901..... | 1.10 | .78 | 4.37 | 5.50 | 6.90 | 3.34 | 5.34 | 10.59 | 3.33 | 2.71 | 2.87 | 7.13 | 53.96 |
| 1902..... | 2.58 | 4.45 | 5.66 | 3.91 | 1.16 | 7.39 | 8.95 | 3.28 | 5.29 | 3.37 | 1.20 | 4.65 | 51.89 |
| 1903..... | 2.61 | 4.02 | 3.36 | 2.66 | 1.25 | 5.34 | 5.05 | 5.29 | 1.52 | 4.98 | 2.38 | 3.48 | 41.94 |
| 1904..... | 3.34 | .99 | 3.26 | 2.68 | 4.94 | [4.66] | 2.98 | 3.95 | 3.18 | 2.15 | .97 | 2.19 | 35.29 |
| Mean..... | 2.26 | 2.96 | 3.94 | 2.94 | 3.13 | 4.66 | 4.84 | 4.86 | 2.88 | 2.82 | 2.27 | 4.10 | 41.66 |

a No record.

Monthly and annual precipitation at stations in Susquehanna drainage basin—
Continued.

24. SOUTH EATON, PA.

| Year. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. | Annual. |
|-----------|-------|------|------|------|------|-------|-------|------|-------|------|------|------|---------|
| 1891..... | 5.47 | 3.48 | 4.54 | 2.85 | 1.06 | 2.17 | 4.88 | 4.15 | 1.35 | 3.71 | 2.84 | 3.88 | 40.38 |
| 1892..... | 5.38 | .91 | 4.53 | 1.20 | 5.49 | 4.50 | 3.14 | 2.85 | 2.97 | .77 | 2.88 | .86 | 35.48 |
| 1893..... | 2.69 | 5.49 | 3.03 | 3.53 | 5.12 | 2.98 | 3.83 | 5.41 | 2.21 | 1.88 | 1.94 | 2.46 | 40.57 |
| 1894..... | 1.65 | 2.79 | .80 | 2.76 | 7.26 | 1.09 | 1.98 | 2.22 | 3.69 | 6.50 | 2.27 | 3.41 | 36.42 |
| 1895..... | 2.35 | 1.53 | 1.62 | 3.60 | 3.40 | 4.50 | 2.81 | 2.07 | 1.68 | 2.26 | 2.44 | 4.26 | 32.32 |
| 1896..... | 10.52 | 4.11 | 4.45 | 1.13 | 2.86 | 2.62 | 4.66 | 3.06 | 2.45 | 4.94 | 4.16 | 1.11 | 46.07 |
| 1897..... | 1.89 | 2.49 | 2.40 | 3.11 | 5.29 | 3.92 | 3.38 | 3.23 | 2.24 | 1.12 | 3.96 | 4.13 | 37.16 |
| 1898..... | 3.93 | 1.43 | 3.16 | 2.73 | 3.67 | 1.63 | 1.64 | 6.30 | 1.90 | 4.49 | 3.27 | 2.02 | 36.17 |
| 1899..... | 1.98 | 3.58 | 3.96 | 2.30 | 2.24 | 2.58 | 2.39 | 3.58 | 2.16 | 1.16 | 2.71 | 2.81 | 31.25 |
| 1900..... | 2.10 | 3.47 | 3.75 | .97 | 1.97 | 3.52 | 4.09 | 1.93 | 1.84 | 1.98 | 3.21 | 2.17 | 31.00 |
| 1901..... | .92 | .81 | 3.73 | 4.21 | 6.70 | 3.01 | 5.32 | 5.76 | 2.66 | 1.94 | 1.69 | 6.16 | 42.91 |
| 1902..... | 1.42 | 5.26 | 4.06 | 2.22 | 1.34 | 6.61 | 5.41 | 2.27 | 8.15 | 7.05 | 1.00 | 6.09 | 50.88 |
| 1903..... | 2.78 | 4.53 | 4.83 | 3.29 | 1.31 | 6.74 | 3.86 | 6.19 | 1.93 | 5.23 | 2.09 | 3.85 | 46.63 |
| 1904..... | 2.97 | 1.67 | 2.56 | 3.21 | 3.00 | 3.74 | 5.94 | 3.40 | 3.71 | 3.54 | 1.06 | 1.90 | 36.70 |
| Mean..... | 3.29 | 2.95 | 3.39 | 2.65 | 3.62 | 3.54 | 3.81 | 3.73 | 2.78 | 3.33 | 2.54 | 3.22 | 38.85 |

25. SCRANTON, PA.

| | | | | | | | | | | | | | |
|-----------|------|------|------|------|------|------|------|------|------|------|------|------|-------|
| 1899..... | 3.03 | 6.30 | 4.46 | 1.96 | 2.73 | 2.66 | 4.73 | 3.62 | 3.47 | 0.63 | 2.11 | 2.10 | 37.80 |
| 1900..... | 2.13 | 2.75 | 2.98 | 1.81 | 2.81 | 3.54 | 4.63 | 1.27 | 1.72 | 2.66 | 2.37 | 2.61 | 31.28 |
| 1901..... | 1.17 | 1.34 | 3.23 | 3.44 | 5.58 | 1.82 | 4.12 | 6.88 | 2.35 | 1.11 | 2.58 | 5.64 | 39.26 |
| 1902..... | 2.14 | 4.73 | 3.14 | 2.27 | 1.61 | 6.69 | 4.60 | 3.28 | 6.23 | 4.94 | 1.06 | 4.36 | 45.05 |
| 1903..... | 2.73 | 3.54 | 4.40 | 2.55 | .96 | 7.73 | 4.89 | 6.03 | 1.27 | 6.42 | 1.86 | 2.59 | 44.97 |
| 1904..... | 3.23 | .92 | 2.10 | 2.32 | 2.17 | 3.46 | 5.94 | 4.69 | 3.33 | 3.80 | 1.51 | 3.71 | 37.18 |
| Mean..... | 2.40 | 3.26 | 3.38 | 2.39 | 2.64 | 4.32 | 4.82 | 4.30 | 3.06 | 3.26 | 1.92 | 3.50 | 39.25 |

26. WILKESBARRE, PA.

| | | | | | | | | | | | | | |
|-----------|------|------|------|------|------|-------|------|------|------|------|------|------|-------|
| 1891..... | 4.59 | 4.00 | 3.67 | 2.28 | 1.53 | 2.88 | 4.48 | 3.46 | 1.80 | 1.63 | 2.54 | 4.38 | 37.24 |
| 1892..... | 7.02 | 1.11 | 6.41 | 1.55 | 5.89 | 10.55 | 4.71 | 5.56 | 2.51 | .72 | 4.37 | 1.53 | 51.93 |
| 1893..... | 3.34 | 7.23 | 3.83 | 3.27 | 4.15 | 1.43 | 3.00 | 3.76 | 3.74 | 1.70 | 2.97 | 4.07 | 42.49 |
| 1894..... | 1.63 | 4.50 | 1.68 | 3.41 | 8.56 | 1.78 | .74 | 1.14 | 5.05 | 5.53 | 2.29 | 3.66 | 39.97 |
| 1895..... | 3.43 | 2.32 | 2.94 | 2.71 | 4.16 | 2.89 | 2.59 | 4.97 | 1.59 | 2.51 | 1.37 | 4.13 | 35.61 |
| 1896..... | 1.14 | 6.17 | 6.31 | 1.06 | 3.17 | 2.40 | 6.20 | 2.99 | 2.26 | 2.74 | 3.44 | 1.08 | 38.96 |
| 1897..... | 1.40 | 2.06 | 3.78 | 3.34 | 5.81 | 3.72 | 3.76 | 2.57 | 1.49 | 1.47 | 4.35 | 3.80 | 37.55 |
| 1898..... | 2.90 | .96 | 2.76 | 2.46 | 6.04 | 3.29 | 2.33 | 5.16 | 3.44 | 2.36 | 3.90 | 1.95 | 37.55 |
| 1899..... | 3.21 | 4.48 | 4.49 | 1.37 | 2.07 | 2.82 | 3.91 | 2.67 | 4.29 | 1.29 | 2.70 | 1.72 | 35.02 |
| 1900..... | 1.98 | 3.21 | 2.91 | 1.01 | 3.81 | 3.39 | 5.74 | 3.16 | .52 | 2.59 | 3.05 | 3.02 | 34.39 |
| 1901..... | 2.10 | .75 | 3.81 | 3.11 | 5.36 | 2.48 | 2.74 | 7.23 | 1.64 | 2.55 | 1.23 | 5.98 | 38.98 |
| 1902..... | 2.23 | 5.60 | 3.19 | 1.58 | .98 | 6.10 | 5.01 | 1.89 | 6.82 | 4.29 | 1.14 | 4.95 | 43.78 |
| 1903..... | 2.09 | 4.13 | 4.33 | 3.07 | 1.12 | 8.38 | 4.42 | 7.13 | 2.16 | 4.88 | 1.98 | 3.06 | 46.75 |
| 1904..... | 2.86 | 1.59 | 3.62 | 2.34 | 2.15 | 2.95 | 5.83 | 5.58 | 3.34 | 3.68 | 1.18 | 3.38 | 38.50 |
| Mean..... | 2.85 | 3.44 | 3.84 | 2.33 | 3.91 | 3.93 | 3.96 | 4.09 | 2.90 | 2.71 | 2.61 | 3.34 | 39.91 |

27 WILLIAMSPORT, PA.

| | | | | | | | | | | | | | |
|-----------|------|------|------|------|------|------|------|------|------|------|------|------|-------|
| 1899..... | 1.46 | 3.71 | 4.36 | 1.71 | 2.36 | 4.25 | 2.00 | 4.15 | 2.94 | 3.26 | 2.13 | 4.63 | 36.96 |
| 1900..... | 2.31 | 3.72 | 3.63 | .81 | 2.35 | 2.89 | 2.57 | 2.89 | 1.01 | 2.35 | 3.26 | 2.15 | 29.94 |
| 1901..... | 1.40 | .66 | 3.63 | 5.57 | 6.34 | 2.99 | 3.29 | 5.18 | 3.21 | 1.59 | 2.59 | 5.86 | 42.31 |
| 1902..... | 3.61 | 4.81 | 4.05 | 2.43 | 1.45 | 5.61 | 6.02 | 1.69 | 5.65 | 2.10 | 1.31 | 3.74 | 42.47 |
| 1903..... | 3.44 | 3.24 | 3.96 | 3.67 | 1.88 | 5.49 | 6.08 | 5.05 | 1.43 | 4.22 | 2.33 | 2.85 | 43.64 |
| 1904..... | 3.64 | 1.10 | 5.11 | 3.63 | 5.28 | 3.07 | 5.59 | 2.13 | 2.60 | 2.24 | .51 | 2.63 | 37.53 |
| Mean..... | 2.64 | 2.87 | 4.12 | 2.97 | 3.28 | 4.05 | 4.26 | 3.52 | 2.81 | 2.63 | 2.02 | 3.64 | 38.81 |

Monthly and annual precipitation at stations in Susquehanna drainage basin—
Continued.

29. EMPORIUM, PA.

| Year. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. | Annual. |
|-------|------|------|------|------|------|-------|-------|------|-------|------|------|------|---------|
| 1891 | 3.47 | 4.56 | 5.12 | 2.33 | 1.06 | 4.45 | 8.46 | 5.40 | 1.17 | 3.48 | 4.01 | 4.96 | 48.47 |
| 1892 | 3.29 | 3.77 | 3.87 | 1.64 | 7.38 | 6.13 | 2.67 | 3.02 | 2.78 | 1.35 | 3.24 | .94 | 40.08 |
| 1893 | 3.11 | 5.91 | 2.92 | 4.21 | 4.99 | 4.83 | 2.37 | 3.00 | 2.10 | 3.36 | 2.05 | 4.07 | 42.92 |
| 1894 | 3.85 | 3.08 | 1.24 | 3.89 | 9.45 | 3.06 | 2.09 | 1.37 | 5.26 | 3.94 | 1.81 | 2.93 | 41.97 |
| 1895 | 4.79 | .50 | 1.60 | 2.53 | 3.08 | 4.95 | 3.06 | 2.98 | 2.89 | 1.82 | 2.59 | 3.37 | 34.16 |
| 1896 | 1.17 | 3.68 | 4.36 | 1.88 | 3.36 | 6.75 | 5.11 | 1.62 | 5.69 | 3.31 | 3.60 | 1.82 | 42.35 |
| 1897 | 2.30 | 3.20 | 4.03 | 3.49 | 3.42 | 2.04 | 5.28 | 2.13 | 2.73 | .94 | 5.13 | 4.20 | 38.89 |
| 1898 | 4.54 | 1.47 | 5.80 | 2.59 | 4.21 | 3.90 | 4.13 | 5.87 | 1.89 | 6.24 | 3.37 | 2.66 | 46.67 |
| 1899 | 2.91 | 3.66 | 4.69 | 2.57 | 3.92 | 3.32 | 4.32 | 3.78 | 4.89 | 2.21 | 2.86 | 4.80 | 43.93 |
| 1900 | 3.16 | 2.85 | 4.50 | 1.29 | 3.46 | 2.43 | 4.48 | 3.50 | 1.36 | 3.84 | 5.05 | 2.08 | 38.00 |
| 1901 | 2.55 | 1.08 | 3.01 | 5.03 | 6.74 | 4.39 | 4.07 | 6.29 | 4.05 | 1.23 | 2.94 | 5.22 | 46.60 |
| 1902 | 2.27 | 3.25 | 3.78 | 3.52 | 2.29 | 7.15 | 12.35 | 2.49 | 2.93 | 2.06 | 1.72 | 5.00 | 48.59 |
| 1903 | 4.07 | 5.21 | 4.84 | 2.76 | 1.37 | 5.44 | 8.42 | 5.92 | 1.56 | 4.03 | 3.67 | 2.88 | 50.17 |
| 1904 | 3.04 | 3.09 | 6.18 | 4.74 | 3.28 | 5.11 | 5.46 | 4.13 | 4.59 | 2.08 | .64 | 2.89 | 45.23 |
| Mean | 3.18 | 3.24 | 4.00 | 3.02 | 4.14 | 4.57 | 5.16 | 3.68 | 3.14 | 2.85 | 3.05 | 3.42 | 43.45 |

31. LOCK HAVEN, PA.

| | | | | | | | | | | | | | |
|------|------|------|------|------|--------|------|------|------|------|------|------|------|-------|
| 1891 | 4.21 | 4.21 | 4.06 | 1.48 | 1.85 | 5.14 | 6.95 | 4.40 | 3.41 | 2.81 | 2.82 | 4.44 | 45.78 |
| 1892 | 4.86 | 1.37 | 4.73 | 1.21 | 4.91 | 9.66 | 3.92 | 3.72 | 1.34 | .38 | 3.34 | 1.35 | 40.79 |
| 1893 | 2.71 | 5.28 | 2.26 | 4.72 | 4.89 | 2.51 | 3.34 | 2.82 | 3.70 | 2.67 | 1.09 | 2.14 | 38.13 |
| 1894 | 1.77 | 3.67 | .84 | 5.81 | [3.19] | 3.52 | 2.96 | 5.51 | 6.46 | 5.73 | 1.99 | 3.73 | 45.18 |
| 1895 | 4.73 | 1.00 | 1.69 | .79 | 2.35 | 4.84 | 2.83 | 3.27 | 3.18 | 1.35 | 2.48 | 3.46 | 31.97 |
| 1896 | .85 | 4.44 | 4.05 | 1.02 | 1.49 | 3.67 | 5.16 | 3.59 | 5.46 | 4.44 | 2.64 | 1.02 | 37.83 |
| 1897 | 1.67 | 2.67 | 3.17 | 2.90 | 4.65 | 2.72 | 5.14 | 3.94 | 3.93 | .77 | 4.93 | 2.59 | 39.08 |
| 1898 | 4.11 | 1.51 | 5.02 | 2.24 | 4.10 | 3.45 | 3.76 | 4.90 | .36 | 5.19 | 2.24 | 2.14 | 39.02 |
| 1899 | 2.16 | 3.72 | 3.27 | 1.06 | 3.30 | 3.80 | 2.16 | 5.05 | 3.57 | .43 | 3.26 | 3.56 | 35.34 |
| 1900 | 2.40 | 4.04 | 3.42 | 1.20 | .94 | 1.53 | 3.03 | 4.45 | .65 | 4.92 | 4.95 | 1.70 | 33.23 |
| 1901 | 2.32 | .80 | 4.11 | 5.67 | 7.42 | 3.53 | 3.21 | 6.54 | 4.38 | 1.37 | 2.90 | 5.72 | 47.97 |
| 1902 | 2.70 | 3.59 | 4.93 | 5.61 | .70 | 6.12 | 8.34 | 1.86 | 4.52 | 3.93 | 1.06 | 4.27 | 47.03 |
| 1903 | 3.73 | 2.99 | 3.97 | 2.81 | 1.69 | 7.44 | 5.34 | 6.37 | 3.20 | 3.76 | 1.67 | 2.37 | 45.34 |
| 1904 | 3.66 | 2.33 | 4.99 | 4.52 | 3.66 | 2.73 | 2.92 | 4.09 | 1.95 | 1.92 | .48 | 2.83 | 36.08 |
| Mean | 2.99 | 2.97 | 3.61 | 2.89 | 3.22 | 4.33 | 4.22 | 4.32 | 3.29 | 2.83 | 2.56 | 2.95 | 40.18 |

32. LEWISBURG, PA.

| | | | | | | | | | | | | | |
|------|--------|--------|------|------|------|------|------|--------|------|------|------|--------|-------|
| 1891 | 3.33 | 3.75 | 6.40 | 2.39 | 0.67 | 5.21 | 5.09 | 9.42 | 2.90 | 3.75 | 2.40 | 4.40 | 49.71 |
| 1892 | [2.88] | [3.34] | 5.53 | 2.34 | 4.96 | 5.21 | 3.40 | 4.55 | 4.18 | .22 | 3.94 | .70 | 41.25 |
| 1893 | 2.40 | 4.57 | 3.07 | 4.62 | 6.42 | 4.36 | 2.35 | [5.11] | 1.74 | 3.20 | 1.61 | [3.43] | 42.88 |
| 1894 | 2.84 | 2.46 | 1.13 | 5.33 | 9.40 | 2.39 | 1.36 | 2.06 | 5.09 | 6.02 | 1.86 | 4.06 | 44.00 |
| 1895 | 3.10 | 1.35 | 1.38 | 2.41 | 3.66 | 4.13 | 2.54 | 4.22 | 4.11 | 1.29 | 2.96 | 4.09 | 35.24 |
| 1896 | 1.98 | 4.46 | 3.74 | 1.11 | 2.16 | 4.70 | 5.62 | 1.39 | 3.66 | 5.58 | 5.35 | 1.29 | 41.04 |
| 1897 | 3.26 | 2.54 | 4.74 | 3.21 | 4.30 | 2.31 | 4.72 | 2.52 | 2.01 | 2.08 | 4.76 | 3.94 | 40.39 |
| 1898 | 3.62 | 2.27 | 4.23 | 2.83 | 6.04 | 2.79 | 4.21 | 9.68 | .93 | 5.76 | 2.33 | 2.44 | 47.13 |
| 1899 | 2.55 | 4.57 | 4.36 | 1.89 | 4.32 | 3.83 | 1.53 | 5.49 | 4.36 | 1.36 | 2.88 | 3.98 | 41.12 |
| 1900 | 2.33 | 3.92 | 5.60 | 1.07 | 3.16 | 3.21 | 3.26 | 4.08 | .65 | 3.05 | 4.24 | 2.38 | 36.95 |
| 1901 | 1.67 | .74 | 4.49 | 4.39 | 7.95 | 2.09 | 5.02 | 10.60 | 3.85 | 1.16 | 1.75 | 6.90 | 50.61 |
| 1902 | 3.53 | 4.41 | 5.84 | 2.76 | .62 | 8.28 | 6.86 | 2.12 | 6.40 | 4.86 | 1.80 | 4.96 | 52.44 |
| 1903 | 3.95 | 4.85 | 3.32 | 4.34 | 2.40 | 8.02 | 5.73 | 5.21 | 2.21 | 3.47 | 1.69 | 2.00 | 47.19 |
| 1904 | 4.52 | 1.62 | 3.75 | 3.78 | 5.40 | 1.94 | 3.61 | 3.76 | 3.41 | 2.69 | .72 | 1.79 | 36.99 |
| Mean | 3.00 | 3.20 | 4.11 | 3.03 | 4.39 | 4.18 | 3.95 | 5.02 | 3.25 | 3.18 | 2.74 | 3.31 | 43.36 |

34. GIRARDVILLE, PA.

| | | | | | | | | | | | | | |
|------|------|------|------|------|------|------|------|-------|------|--------|------|--------|-------|
| 1899 | 2.76 | 6.69 | 4.85 | 2.02 | 3.53 | 5.40 | 4.99 | 7.40 | 6.65 | 1.02 | 2.63 | 4.19 | 52.13 |
| 1900 | 2.65 | 5.63 | 5.50 | .94 | 1.29 | 3.70 | 6.96 | 4.77 | 1.22 | 3.32 | 3.77 | 3.03 | 42.78 |
| 1901 | 2.48 | 1.03 | 5.68 | 2.52 | 5.59 | 1.39 | 3.21 | 12.05 | 4.20 | 2.81 | 2.51 | 7.87 | 51.34 |
| 1902 | 4.22 | 6.45 | 6.39 | 3.57 | 1.31 | 7.70 | 5.02 | 2.83 | 8.44 | 6.92 | 1.90 | 7.04 | 61.79 |
| 1903 | 4.28 | 5.86 | 4.72 | 4.25 | 2.28 | 7.95 | 6.19 | 5.15 | 6.05 | 6.75 | 1.87 | 4.83 | 57.16 |
| 1904 | 5.78 | 2.91 | 5.39 | 3.42 | 4.01 | 5.95 | 4.26 | 4.04 | 6.50 | [4.16] | 2.55 | [5.39] | 54.36 |
| Mean | 3.70 | 4.76 | 5.42 | 2.78 | 3.00 | 5.35 | 5.10 | 6.04 | 5.01 | 4.16 | 2.54 | 5.39 | 53.25 |

Monthly and annual precipitation at stations in Susquehanna drainage basin—
Continued.

35. SELINSGROVE, PA.

| Year. | Jan. | Feb. | Mar. | Apr. | May | June | July. | Aug. | Sept. | Oct. | Nov. | Dec. | An- nual. |
|-----------|--------|------|------|------|-------|------|-------|------|-------|------|------|------|--------------|
| 1891..... | 4.70 | 3.09 | 8.39 | 1.82 | 1.36 | 4.74 | 6.69 | 7.18 | 4.12 | 4.46 | 3.85 | 3.97 | 54.37 |
| 1892..... | 5.13 | 5.88 | 3.92 | 1.60 | 6.25 | 8.18 | 4.77 | 3.17 | 3.29 | 3.37 | 4.30 | 1.90 | 43.76 |
| 1893..... | 2.78 | 5.63 | 3.57 | 4.64 | 6.85 | 4.44 | 2.32 | 4.07 | 3.12 | 4.21 | 2.40 | 2.75 | 46.78 |
| 1894..... | 1.22 | 3.87 | 1.09 | 5.45 | 10.03 | 2.40 | 1.20 | 2.47 | 4.25 | 5.58 | 2.08 | 3.76 | 43.40 |
| 1895..... | [2.88] | 1.26 | 2.92 | 2.55 | 3.26 | 3.59 | 2.54 | 4.58 | 1.53 | 1.80 | 1.50 | 3.06 | 31.27 |
| 1896..... | .90 | 5.71 | 4.04 | 1.16 | 2.40 | 2.49 | 6.36 | 2.18 | 3.81 | 4.36 | 3.47 | .73 | 37.61 |
| 1897..... | 1.85 | 3.26 | 3.74 | 3.25 | 4.74 | 2.62 | 5.08 | 1.88 | 2.56 | 1.89 | 6.35 | 3.56 | 40.78 |
| 1898..... | 4.08 | 2.06 | 3.87 | 2.98 | 5.28 | 1.61 | 5.63 | 6.86 | .91 | 6.22 | 2.90 | 2.72 | 45.12 |
| 1899..... | 1.76 | 4.87 | 4.58 | 1.37 | 4.45 | 4.04 | 2.42 | 4.63 | 4.72 | 1.53 | 3.26 | 2.61 | 40.24 |
| 1900..... | 2.60 | 3.59 | 3.69 | 1.16 | .72 | 2.09 | 3.74 | 2.38 | 1.59 | 3.65 | 3.89 | 2.18 | 31.28 |
| 1901..... | 2.03 | .80 | 4.11 | 3.73 | 7.73 | 2.50 | 5.59 | 8.50 | 3.52 | 1.34 | 1.66 | 4.84 | 46.35 |
| 1902..... | 3.28 | 3.23 | 5.08 | 3.23 | .94 | 8.11 | 4.79 | 1.69 | 5.16 | 4.90 | 1.54 | 4.26 | 46.21 |
| 1903..... | 4.20 | 4.84 | 3.29 | 4.39 | 1.78 | 7.57 | 4.39 | 4.91 | 3.01 | 3.72 | 1.53 | 3.98 | 47.61 |
| 1904..... | 3.99 | 3.76 | 3.36 | 3.70 | 6.27 | 3.02 | 5.04 | 2.53 | 4.68 | 2.40 | .70 | 2.45 | 41.90 |
| Mean..... | 2.96 | 3.35 | 3.98 | 2.93 | 4.43 | 4.09 | 4.33 | 4.07 | 3.30 | 3.32 | 2.82 | 3.06 | 42.64 |

36. CENTERHALL, PA.

| | | | | | | | | | | | | | |
|-----------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|--------|---------|
| 1895..... | [2.30] | [3.43] | [4.32] | [2.27] | [3.56] | 5.70 | 3.60 | 4.70 | 2.10 | 1.20 | 2.33 | 3.94 | 39.45 |
| 1896..... | 2.18 | [3.43] | 3.77 | 1.41 | 2.00 | 4.06 | 5.66 | 1.26 | 6.23 | 3.92 | 3.11 | 1.63 | 38.66 |
| 1897..... | 2.20 | 4.17 | 5.08 | 3.84 | 5.79 | 4.03 | 4.96 | 2.43 | 4.06 | 1.78 | 5.43 | 4.19 | 47.96 |
| 1898..... | 3.89 | 1.16 | 5.16 | 2.60 | 4.87 | 2.89 | 2.86 | 7.37 | 1.26 | 6.70 | 2.60 | 3.90 | 45.26 |
| 1899..... | 2.07 | 4.54 | 4.42 | .88 | 5.66 | 3.05 | 2.36 | 3.79 | 3.90 | 2.12 | 1.96 | 3.87 | 38.62 |
| 1900..... | 1.95 | 4.09 | 3.58 | 1.52 | 1.92 | 3.70 | 3.48 | 2.56 | .88 | [3.17] | [2.57] | [3.23] | 32.65 |
| 1901..... | [2.30] | [3.43] | [4.32] | [2.27] | [3.56] | [4.43] | 5.45 | 11.30 | 2.73 | .71 | 2.46 | [3.23] | [46.19] |
| 1902..... | 1.50 | [3.43] | [4.32] | [2.27] | [3.56] | [4.43] | [4.04] | [5.00] | [3.04] | 5.20 | .80 | [3.23] | [40.82] |
| 1903..... | [2.30] | 3.21 | 3.90 | 3.35 | 1.10 | 7.59 | 3.91 | 6.61 | 3.19 | 3.75 | 1.89 | 1.84 | 42.64 |
| 1904..... | 2.90 | 2.07 | 4.91 | 5.18 | 2.38 | 3.79 | 5.72 | 3.01 | 1.26 | [3.17] | [2.57] | 1.32 | 38.28 |
| Mean..... | 2.36 | 3.30 | 4.38 | 2.56 | 3.44 | 4.37 | 4.20 | 4.80 | 2.86 | 3.17 | 2.57 | 3.04 | 41.05 |

38. STATE COLLEGE, PA.

| | | | | | | | | | | | | | |
|-----------|------|------|------|------|------|------|------|------|------|------|------|------|-------|
| 1891..... | 4.11 | 5.29 | 4.07 | 1.47 | 1.94 | 4.24 | 5.65 | 5.40 | 2.20 | 4.38 | 2.98 | 4.08 | 45.81 |
| 1892..... | 3.98 | 1.73 | 3.78 | 2.09 | 5.79 | 7.36 | 3.26 | 5.78 | 2.24 | .28 | 3.62 | 1.07 | 40.98 |
| 1893..... | 1.94 | 5.71 | 1.88 | 5.13 | 6.46 | 3.94 | 4.10 | 3.14 | 2.22 | 3.23 | 3.04 | 2.26 | 43.05 |
| 1894..... | 1.75 | 3.39 | 1.14 | 3.85 | 9.45 | 4.60 | 2.10 | 2.13 | 5.78 | 3.13 | 1.59 | 3.14 | 42.05 |
| 1895..... | 4.18 | .22 | 1.03 | 2.23 | 2.21 | 6.74 | 3.11 | 3.70 | 1.75 | 1.03 | 1.74 | 2.75 | 30.69 |
| 1896..... | 1.40 | 4.10 | 2.82 | 1.47 | 1.37 | 5.02 | 5.56 | 1.56 | 5.02 | 3.29 | 3.11 | 1.04 | 35.76 |
| 1897..... | 2.21 | 3.19 | 4.53 | 3.78 | 4.13 | 3.03 | 5.69 | 3.39 | 3.60 | 1.45 | 5.26 | 3.18 | 43.44 |
| 1898..... | 4.40 | 1.14 | 5.63 | 2.29 | 4.28 | 3.53 | 2.95 | 4.70 | .93 | 6.51 | 2.28 | 3.07 | 41.71 |
| 1899..... | 2.60 | 3.42 | 4.23 | 1.71 | 4.77 | 2.41 | 2.14 | 2.76 | 3.84 | 1.40 | 3.06 | 2.53 | 34.87 |
| 1900..... | 1.65 | 3.39 | 3.81 | 1.93 | 2.30 | 2.54 | 3.36 | 2.95 | .63 | 3.22 | 4.10 | 1.77 | 31.65 |
| 1901..... | 1.82 | .73 | 3.71 | 4.62 | 6.14 | 2.46 | 3.60 | 8.97 | 2.35 | .40 | 2.06 | 6.59 | 43.45 |
| 1902..... | 3.02 | 2.92 | 4.91 | 3.13 | .92 | 6.71 | 5.76 | 1.37 | 2.59 | 4.25 | 1.44 | 4.82 | 41.84 |
| 1903..... | 3.50 | 3.61 | 4.18 | 3.81 | 1.24 | 7.28 | 4.04 | 6.85 | 2.61 | 3.51 | 1.89 | 1.67 | 44.19 |
| 1904..... | 2.72 | 3.28 | 4.04 | 5.42 | 2.10 | 4.19 | 6.30 | 1.74 | 1.86 | 2.18 | .42 | 1.78 | 36.03 |
| Mean..... | 2.81 | 3.01 | 3.55 | 3.07 | 3.79 | 4.58 | 4.12 | 3.89 | 2.69 | 2.73 | 2.61 | 2.84 | 39.69 |

39. GRAMPIAN, PA.

| | | | | | | | | | | | | | |
|-----------|--------|------|------|------|-------|--------|--------|--------|--------|--------|--------|--------|---------|
| 1895..... | 5.19 | 0.96 | 1.90 | 3.81 | 2.38 | 2.87 | 2.85 | 3.08 | 2.20 | 1.26 | 2.57 | 3.48 | 32.55 |
| 1896..... | 1.22 | 3.57 | 4.02 | 2.40 | 2.20 | 5.76 | 8.83 | 3.98 | 4.45 | 2.62 | 3.26 | 1.82 | 44.13 |
| 1897..... | 2.15 | 2.78 | 4.25 | 4.14 | 4.55 | 3.14 | 7.02 | 2.46 | 3.16 | .68 | 6.04 | 4.57 | 44.94 |
| 1898..... | 3.81 | 2.06 | 8.40 | 2.30 | 3.30 | 5.03 | 3.41 | 4.12 | 1.54 | 5.21 | 3.55 | 3.56 | 46.29 |
| 1899..... | 3.12 | 3.03 | 4.42 | 1.67 | 5.34 | 3.00 | 3.84 | 3.54 | 3.00 | 1.56 | 2.31 | 3.96 | 38.79 |
| 1900..... | 3.21 | 3.63 | 3.64 | 1.36 | 2.77 | [4.13] | [5.18] | [3.76] | [2.75] | 3.32 | 4.71 | 2.40 | 40.86 |
| 1901..... | 2.03 | 1.98 | 1.88 | 5.22 | 3.51 | [4.13] | [5.18] | 4.22 | 2.95 | .26 | [3.74] | [3.30] | 38.40 |
| 1902..... | 2.42 | 1.84 | 2.87 | 3.71 | 2.81 | [4.13] | [5.18] | [3.76] | [2.75] | [2.43] | [3.74] | [3.30] | [38.94] |
| 1903..... | [2.89] | 4.64 | 4.89 | 3.72 | 2.51 | 4.98 | 5.15 | 4.94 | 1.98 | 4.55 | [3.74] | [3.30] | 47.29 |
| 1904..... | 5.75 | 3.09 | 6.06 | (a) | ----- | ----- | ----- | ----- | ----- | ----- | ----- | ----- | ----- |
| Mean..... | 3.18 | 2.76 | 4.23 | 3.15 | 3.26 | 4.13 | 5.18 | 3.76 | 2.75 | 2.43 | 3.74 | 3.30 | 41.36 |

a No record.

Monthly and annual precipitation at stations in Susquehanna drainage basin—
Continued.

40. ALTOONA, PA.

| Year. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. | An- nual. |
|-----------|------|------|------|------|------|-------|-------|------|-------|------|------|--------|--------------|
| 1891..... | 2.35 | 4.59 | 2.64 | 1.39 | 1.97 | 7.73 | 3.99 | 3.13 | 2.71 | 2.54 | 1.89 | 2.96 | 37.89 |
| 1892..... | 2.08 | 1.57 | 2.37 | 1.66 | 5.35 | 5.33 | 2.50 | 2.96 | 1.94 | .10 | 2.69 | [2.64] | 31.19 |
| 1893..... | 1.65 | 3.21 | 1.06 | 3.48 | 4.67 | 2.94 | 2.50 | 2.92 | 1.85 | 2.71 | 1.48 | 2.15 | 30.62 |
| 1894..... | .99 | 1.82 | .80 | 1.69 | 9.32 | 2.66 | 1.01 | 3.18 | 5.25 | 1.77 | .74 | 2.30 | 31.53 |
| 1895..... | 3.22 | .17 | 1.05 | 2.16 | .80 | 3.75 | 1.75 | 1.64 | 2.28 | .55 | 1.30 | 2.50 | 21.17 |
| 1896..... | .87 | 1.94 | 1.77 | 1.38 | 2.70 | 7.69 | 4.22 | 1.70 | 6.03 | 1.66 | 2.59 | .89 | 33.44 |
| 1897..... | .95 | 2.09 | 3.44 | 2.91 | 2.52 | 2.44 | 3.22 | 2.08 | 2.89 | .71 | 4.31 | 2.17 | 29.73 |
| 1898..... | 4.05 | 1.23 | 5.81 | 2.22 | 6.55 | 1.99 | 1.91 | 3.75 | .76 | 7.44 | 2.14 | 2.67 | 40.52 |
| 1899..... | 2.41 | 3.33 | 4.79 | 1.64 | 5.62 | 1.79 | 3.67 | 4.46 | 3.82 | 1.23 | 2.89 | 2.70 | 38.35 |
| 1900..... | 2.21 | 3.55 | 3.12 | 1.22 | 3.91 | 2.53 | 3.25 | 3.90 | 1.48 | 3.63 | 4.54 | 1.50 | 34.84 |
| 1901..... | 1.89 | .78 | 4.07 | 6.22 | 5.85 | 4.04 | 5.83 | 5.34 | 2.29 | .59 | 2.03 | 4.92 | 43.85 |
| 1902..... | 2.85 | 2.60 | 3.96 | 5.30 | 1.80 | 4.95 | 6.88 | 1.12 | 1.58 | 4.36 | 1.05 | 5.37 | 41.32 |
| 1903..... | 3.84 | 4.59 | 4.38 | 2.99 | 2.63 | 4.34 | 4.51 | 5.08 | 1.93 | 3.36 | 1.82 | 1.50 | 40.97 |
| 1904..... | 3.03 | 2.39 | 4.12 | 4.40 | 2.93 | 3.09 | 4.68 | 1.69 | 1.73 | 1.43 | .63 | 1.98 | 32.10 |
| Mean..... | 2.31 | 2.42 | 3.10 | 2.76 | 4.01 | 3.95 | 3.57 | 3.07 | 2.61 | 2.29 | 2.15 | 2.59 | 34.83 |

41. HUNTINGDON, PA.

| Year. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. | An- nual. |
|-----------|------|------|------|------|------|-------|-------|------|-------|------|------|------|--------------|
| 1891..... | 3.58 | 3.84 | 4.48 | 1.92 | 1.84 | 4.24 | 4.49 | 3.80 | 2.07 | 3.13 | 2.39 | 4.18 | 39.96 |
| 1892..... | 4.22 | 1.86 | 5.11 | 2.29 | 6.24 | 6.44 | 3.48 | 4.03 | 2.81 | .12 | 3.04 | 1.55 | 41.19 |
| 1893..... | 2.10 | 5.27 | 2.07 | 4.61 | 7.79 | 2.37 | 2.39 | 3.49 | 3.50 | 3.70 | 2.46 | 2.46 | 42.21 |
| 1894..... | 1.82 | 3.44 | 1.07 | 3.19 | 9.20 | 3.56 | 1.57 | 1.26 | 7.56 | 2.93 | 1.81 | 4.21 | 41.62 |
| 1895..... | 5.16 | .46 | 1.42 | 1.97 | 3.01 | 4.78 | 3.15 | 1.46 | 1.26 | 1.09 | 1.07 | 2.99 | 27.82 |
| 1896..... | 2.13 | 2.99 | 3.32 | 1.85 | 2.56 | 7.93 | 3.60 | 2.29 | 7.42 | 2.24 | 3.04 | .76 | 40.13 |
| 1897..... | 1.65 | 4.69 | 3.95 | 3.86 | 4.69 | 4.27 | 3.13 | 3.38 | 3.31 | 1.74 | 5.16 | 3.19 | 43.02 |
| 1898..... | 4.60 | 1.12 | 4.79 | 1.73 | 4.60 | 2.07 | 2.03 | 4.68 | .67 | 6.54 | 2.02 | 2.41 | 37.26 |
| 1899..... | 2.10 | 3.49 | 4.55 | 1.07 | 3.83 | 2.43 | 3.68 | 4.96 | 3.57 | .49 | 3.25 | 2.60 | 36.02 |
| 1900..... | 1.07 | 2.68 | 2.61 | 2.64 | 3.11 | 2.77 | 1.33 | 1.78 | .64 | 2.51 | 4.33 | 1.38 | 26.85 |
| 1901..... | 1.32 | .67 | 3.90 | 4.18 | 5.19 | 1.59 | 5.20 | 5.63 | 2.49 | 1.50 | .94 | 5.61 | 37.62 |
| 1902..... | 2.44 | 2.98 | 5.24 | 3.79 | 1.30 | 7.18 | 4.30 | 1.72 | 3.21 | 5.67 | .96 | 5.50 | 44.29 |
| 1903..... | 3.80 | 5.38 | 4.13 | 3.04 | 1.76 | 6.32 | 4.84 | 6.43 | 3.02 | 3.64 | 1.83 | 1.40 | 45.59 |
| 1904..... | 3.07 | 2.39 | 4.00 | 4.05 | 2.41 | 6.42 | 7.61 | 4.38 | .84 | 1.91 | .61 | 1.78 | 39.47 |
| Mean..... | 2.79 | 2.95 | 3.57 | 2.87 | 4.11 | 4.46 | 3.63 | 3.52 | 3.03 | 2.66 | 2.35 | 2.86 | 38.80 |

42. HARRISBURG, PA.

| Year. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. | An- nual. |
|-----------|------|------|------|------|------|-------|-------|------|-------|------|------|------|--------------|
| 1891..... | 4.73 | 3.31 | 4.25 | 1.70 | 1.77 | 3.76 | 8.40 | 5.20 | 1.75 | 2.87 | 1.95 | 3.71 | 43.40 |
| 1892..... | 5.14 | 1.02 | 4.81 | 2.15 | 3.95 | 4.93 | 6.48 | 2.39 | 3.31 | .15 | 4.15 | 1.17 | 39.65 |
| 1893..... | 2.05 | 4.66 | 1.97 | 3.67 | 5.32 | 2.46 | 1.92 | 3.69 | 1.74 | 3.25 | 2.54 | 1.91 | 35.18 |
| 1894..... | 1.77 | 4.56 | 1.30 | 2.27 | 6.07 | 3.25 | 1.89 | 4.08 | 5.53 | 4.60 | 1.90 | 3.34 | 40.56 |
| 1895..... | 3.80 | .54 | 1.94 | 3.67 | 1.98 | 1.66 | 1.16 | 2.36 | 2.18 | 1.63 | 1.72 | 3.38 | 26.02 |
| 1896..... | 1.00 | 5.48 | 3.85 | 1.19 | 2.99 | 3.82 | 6.32 | 1.45 | 1.81 | 3.45 | 3.30 | .40 | 35.06 |
| 1897..... | 1.60 | 2.77 | 2.87 | 2.53 | 5.30 | 1.83 | 3.68 | 3.13 | 1.30 | 1.35 | 4.09 | 3.21 | 35.66 |
| 1898..... | 3.23 | 1.60 | 3.04 | 1.95 | 6.13 | 1.98 | 5.07 | 8.44 | 2.08 | 5.26 | 3.15 | 3.16 | 45.09 |
| 1899..... | 2.27 | 3.71 | 3.69 | 1.15 | 4.49 | 2.93 | 1.90 | 4.85 | 4.25 | .78 | 2.13 | 1.83 | 33.98 |
| 1900..... | 2.07 | 3.40 | 3.00 | 1.43 | 1.83 | 2.88 | 3.14 | 4.72 | 1.41 | 1.25 | 2.69 | 1.62 | 28.94 |
| 1901..... | 1.83 | .53 | 3.60 | 2.88 | 5.98 | 1.13 | 1.52 | 2.99 | 2.16 | 1.15 | 1.29 | 4.75 | 29.81 |
| 1902..... | 3.28 | 5.49 | 2.98 | 2.73 | .29 | 4.76 | 3.68 | 2.26 | 4.01 | 5.81 | 1.49 | 4.57 | 39.35 |
| 1903..... | 3.67 | 4.19 | 3.76 | 3.24 | .46 | 5.63 | 1.76 | 5.82 | 1.95 | 2.62 | .88 | 1.92 | 35.90 |
| 1904..... | 3.11 | 1.54 | 2.72 | 2.07 | 3.45 | 3.99 | 4.76 | 2.95 | 1.69 | 2.78 | .54 | 2.39 | 31.99 |
| Mean..... | 2.82 | 3.06 | 3.13 | 2.33 | 3.54 | 3.22 | 3.69 | 3.88 | 2.51 | 2.50 | 2.27 | 2.67 | 35.62 |

Monthly and annual precipitation at stations in Susquehanna drainage basin—
Continued.

43. LEBANON, PA.

| Year. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. | An- nual. |
|-----------|--------|------|------|------|------|-------|-------|-------|-------|------|------|------|--------------|
| 1891..... | [5.30] | 3.33 | 5.30 | 2.19 | 3.00 | 3.40 | 8.70 | 5.06 | 1.07 | 3.14 | 2.44 | 4.34 | 47.27 |
| 1892..... | 6.27 | .95 | 4.91 | 2.22 | 5.14 | 4.75 | 4.75 | 3.80 | 3.63 | .29 | 4.55 | 1.96 | 43.22 |
| 1893..... | 2.10 | 5.67 | 2.63 | 3.67 | 8.05 | 2.21 | 2.67 | 5.30 | 3.79 | 3.95 | 3.42 | 2.35 | 45.81 |
| 1894..... | 2.17 | 4.23 | 1.48 | 4.77 | 9.45 | 1.91 | 4.42 | 4.17 | 5.47 | 6.14 | 2.57 | 4.17 | 50.95 |
| 1895..... | 4.70 | .87 | 2.49 | 5.10 | 1.85 | 1.88 | 2.10 | 1.97 | 1.32 | 2.31 | 1.95 | 4.14 | 30.68 |
| 1896..... | 1.11 | 6.31 | 5.29 | 1.29 | 4.54 | 4.51 | 6.38 | .56 | 2.92 | 4.70 | 4.76 | .68 | 43.05 |
| 1897..... | 2.26 | 3.75 | 3.46 | 3.51 | 6.52 | 3.00 | 3.89 | 2.51 | 1.57 | 2.36 | 5.76 | 4.05 | 44.64 |
| 1898..... | 4.27 | 1.59 | 3.20 | 3.18 | 7.90 | 1.30 | 3.58 | 10.43 | .99 | 5.38 | 5.54 | 3.41 | 50.77 |
| 1899..... | 3.67 | 5.16 | 5.21 | 1.51 | 4.53 | 5.54 | 1.91 | 3.18 | 6.20 | .95 | 2.59 | 1.75 | 42.20 |
| 1900..... | 2.81 | 5.50 | 2.94 | 2.08 | 2.13 | 3.64 | 5.43 | 4.26 | 1.84 | 1.35 | 2.85 | 2.39 | 37.22 |
| 1901..... | 2.46 | .84 | 4.36 | 4.02 | 6.05 | 3.24 | 3.61 | 8.66 | 3.65 | 1.40 | 1.39 | 6.35 | 46.03 |
| 1902..... | 3.62 | 5.67 | 4.79 | 3.38 | .43 | 6.18 | 4.21 | 5.49 | 4.43 | 5.93 | 1.45 | 7.46 | 53.04 |
| 1903..... | 4.68 | 5.95 | 4.65 | 3.67 | .94 | 6.08 | 3.94 | 7.28 | 2.55 | 4.48 | 1.28 | 3.15 | 48.65 |
| 1904..... | 3.58 | 2.22 | 3.50 | 2.48 | 5.60 | 5.22 | 5.89 | 5.56 | 3.81 | 3.06 | 1.63 | 2.71 | 45.26 |
| Mean..... | 3.50 | 3.72 | 3.87 | 3.08 | 4.72 | 3.78 | 4.53 | 4.87 | 3.09 | 3.25 | 3.01 | 3.49 | 44.91 |

46. YORK, PA.

| Year. | Jan. | Feb. | Mar. | Apr. | May. | June. | July. | Aug. | Sept. | Oct. | Nov. | Dec. | An- nual. |
|-----------|------|------|------|------|-------|-------|-------|-------|-------|-------|-------|-------|--------------|
| 1891..... | 3.65 | 3.37 | 6.07 | 2.01 | 2.39 | 3.98 | 10.77 | 3.29 | 1.88 | 3.20 | 2.13 | 4.20 | 46.94 |
| 1892..... | 6.08 | .10 | 3.94 | 1.70 | 4.10 | 3.81 | 8.59 | 2.81 | 2.66 | .14 | 4.44 | 2.13 | 40.50 |
| 1893..... | 1.76 | 4.76 | 1.76 | 4.37 | 6.53 | 2.50 | 1.58 | 3.40 | 1.57 | 3.03 | 3.55 | 2.22 | 37.03 |
| 1894..... | 1.34 | 4.20 | 1.58 | 4.48 | 4.40 | 3.06 | 2.22 | 2.93 | 9.16 | 4.24 | 2.09 | 3.90 | 43.60 |
| 1895..... | 4.63 | .98 | 2.50 | 3.74 | 2.73 | 3.10 | 1.41 | 2.41 | 4.01 | 2.36 | 1.80 | 3.33 | 32.40 |
| 1896..... | .94 | 4.88 | 4.20 | 1.45 | 2.53 | 3.92 | 4.00 | 1.05 | 2.54 | 3.44 | 3.00 | .45 | 32.40 |
| 1897..... | 1.55 | 4.59 | 2.51 | 3.42 | 6.61 | 2.42 | 3.69 | 4.04 | 2.73 | 2.60 | 5.69 | 3.37 | 43.22 |
| 1898..... | 3.67 | 1.15 | 3.00 | 2.71 | 6.86 | 1.08 | 3.47 | 6.44 | 1.82 | 4.31 | 4.75 | 3.58 | 42.84 |
| 1899..... | 3.61 | 6.64 | 5.16 | 1.28 | 5.71 | 3.54 | 5.32 | 6.76 | 6.07 | .92 | 3.59 | 1.18 | 49.78 |
| 1900..... | 2.12 | 4.62 | 3.08 | 1.35 | 1.85 | 4.81 | 2.36 | 4.09 | 3.18 | 1.51 | 2.81 | 2.52 | 34.30 |
| 1901..... | 2.72 | .53 | 3.94 | 2.51 | 2.55 | 1.55 | 3.33 | 6.27 | 2.96 | 1.59 | 2.50 | 6.17 | 36.02 |
| 1902..... | 2.73 | 6.74 | 4.80 | 3.41 | 1.24 | 5.15 | 5.74 | 4.22 | 4.12 | 6.40 | 2.39 | 6.15 | 53.09 |
| 1903..... | 4.67 | 6.13 | 4.72 | 3.21 | 1.18 | 6.21 | 4.01 | 6.96 | 2.72 | 3.51 | 1.89 | 2.90 | 48.11 |
| 1904..... | 4.39 | 1.08 | 2.93 | (a) | ----- | ----- | ----- | ----- | ----- | ----- | ----- | ----- | ----- |
| Mean..... | 3.09 | 3.56 | 3.58 | 2.74 | 3.74 | 3.47 | 4.35 | 4.21 | 3.45 | 2.87 | 3.13 | 3.24 | 41.56 |

(a) No record.

FLOODS.

During the last century there have been several great floods on Susquehanna River, the most notable of which are those of March, 1865; June, 1889 (the Johnstown flood); May, 1894, and March, 1904.


The flood of 1865 was the result of the rapid melting and passing away of a large quantity of ice and snow which had accumulated during an exceptionally severe winter. The amplitude of this flood was probably increased by ice gorges. No information in regard to the height of this flood has been obtained except that at the junction with the West Branch the river was 2 feet higher than during the June flood of 1889; and the old residents along other portions of the main river state that this flood was approximately the same as the June flood of 1889.

The flood of June, 1889, caused by the heavy rainfall of May 30 to June 1, probably exceeded any flood which has ever occurred on this stream. Being in the summer months, it was not augmented by ice gorges, and therefore illustrates the normal effect of high-water conditions. The table below, taken from the report of the Chief of Engineers, U. S. Army, shows the extent and duration of rainfall within the limits of the West Branch; it was upon the high table-lands of this portion of the basin that the heaviest precipitation took place.


Rainfall over drainage area of West Branch, May 30 to June 1, 1889.

| Station. | County. | Storm began— | Storm ended— | Dura- | Rain- |
|---------------------|------------------|---------------------|--------------------|-------|-------|
| | | | | tion. | fall. |
| | | | | Hrs. | Ins. |
| Siglerville | Mifflin | 3 p. m. May 30... | 1 a. m. June 1... | 34 | ----- |
| Holidaysburg | Blair |do | 3 a. m. June 1... | 36 | 6.10 |
| State College | Center | 3.30 p.m. May 30... |do | 37 | 5.04 |
| Lewistown | Mifflin | 4 p. m. May 30... | 2 a. m. June 1... | 34 | ----- |
| Huntingdon | Huntingdon |do |do | 34 | 7.50 |
| Philipsburg | Center |do | 3 a. m. June 1... | 35 | 6.09 |
| Grampian | Clearfield | 4.30 p.m. May 30... | 11.30 p.m. May 31 | 32 | 8.60 |
| Emporium | Cameron | 5 p. m. May 30... | 11 p. m. May 31... | 32 | 5.97 |
| Condersport | Potter | 6 p. m. May 30... | 12 p. m. May 31... | 30 | 5.40 |
| Selinsgrove | Snyder |do | 3 a. m. June 1... | 33 | 7.53 |
| Charlesville | Bedford | 8 p. m. May 30... | 3 p. m. May 31... | 36 | 7.60 |
| Williamsport | Lycoming | 9 p. m. May 30... | 5 a. m. June 1... | 32 | ----- |
| Ralston | do | 1 a. m. May 31... | 12 m. June 1 | 32 | ----- |
| Muncy | do | 3 a. m. May 31... | 1 p. m. June 1... | 34 | ----- |

From this table it is seen that the average duration of the rainfall was about thirty-four hours and that the average depth was about 6.6 inches. Under ordinary conditions about 50 per cent of the rainfall



CURVE OF MEAN VELOCITY FOR SUSQUEHANNA RIVER AT McCALLS FERRY, PA.,
CABLE STATION.



CURVE OF MEAN VELOCITY FOR SUSQUEHANNA RIVER AT HARRISBURG, PA.

in the Susquehanna drainage area reaches the outlet of the river. It is probable, however, that under extraordinary conditions, such as mentioned above, there was a run-off of at least 75 per cent of the rainfall.

Various methods of estimating the maximum discharge of the 1889 flood have been used, perhaps the most reliable indicating that about 593,000 second-feet flowed past Harrisburg, and 671,000 second-feet past McCalls Ferry. The basis of these estimates is shown in Pls. XI and XII, the other methods and results being given on pages 177 to 180.

Pls. XI and XII were prepared as follows: The mean velocities for the various discharge measurements taken at the respective stations were plotted with gage heights as ordinates and mean velocity in feet per second as abscissæ. Through these points a mean velocity curve was drawn and extended to reach the highest gage height of the flood. This curve shows the mean velocity for any stage of the river. The crest of the 1889 flood at Harrisburg was 27.1 feet above the low water of 1803 and at McCalls Ferry cable station about 162 feet above mean sea level. The curves show that the mean velocities for these heights are 7.24 feet per second and 11.90 feet per second, respectively. At each of these stations an accurate cross section was determined, and the product of the area below the flood line and the mean velocity for that gage height, as taken from the extended mean velocity curve, gives the flow of the river. In this method of estimating flood discharges the uncertainty due to the area of the cross section, as when the discharge curve is produced, is eliminated. A study of other mean velocity curves made in this manner shows that the liability to error in the mean velocity is comparatively small, and it is probable that this method gives a better estimate than either Kutter's formula or the discharge curve.

The result is a maximum flow at McCall Ferry about 13 per cent greater than at Harrisburg, which accords with the assumption that the discharge between two points on the same river where the drainage area is similar should increase in proportion to the drainage area. At McCalls Ferry the drainage area is 11.4 per cent greater than at Harrisburg.

The loss of life caused by the flood within the drainage area of the West Branch was 78, and the flood relief commission disbursed nearly \$300,000 to the sufferers within this district, but no attempt was made to secure even an approximate estimate of the damage. The flood of May, 1894, near McCalls Ferry was 2 or 3 feet lower than the 1889 flood.

The primary cause of the flood of March, 1904, was the breaking up of the ice in January without enough water behind it to force it down the river. Gorges were formed at various points along the river and

its branches, which were greatly solidified by the exceptionally cold weather in the following month. When the final break came these gorges were still further augmented and acted as dams, impounding the large quantity of water which was so destructive to property along the shores.

On March 6 and 7 there were heavy rains all over the drainage area, and on the morning of March 8 the floods so caused began to break through the various barriers. It finally forced the big gorges at Highspire and Bainbridge, wiping out islands and doing much damage in its course.


After the flood had subsided at York Haven, the gorge moved to Turkey Hill, where it stood for several hours and backed the water to within a few feet of the Columbia Bridge. Between 1 and 2 p. m. this gorge in turn gave way and moved to Shanks Ferry, where it gorged for the last time. Although it held here for only a few moments, it raised the water and ice 6 feet above the railroad track at Safe Harbor, completely destroying the stone-arch bridge there and leaving ice throughout the village to the height of the second-story windows.

The elevation of the crest of the flood, as shown for a portion of the river by the table on page 175, varied in height at various places along its course, as compared with the June flood of 1889. At York Furnace the height was about 3 feet greater; about a mile above McCalls Ferry it was practically the same; at McCalls Ferry station it was 3 feet lower, and at the head of Cullys Falls it was again about the same height.

There came down with the flood wave a large amount of ice, which varied from 3 to 10 feet in thickness, as shown by the blocks left on the shores. Owing to the cross currents in the river, the greater portion of the ice went down on the York County side, and it was on this side that most of it was left piled up on the shores. The channel on the Lancaster County shore soon cleared itself, and but little ice accumulated upon that bank.

The gorge at Turkey Hill broke about 2 o'clock in the afternoon, and at 3.30 p. m. the water reached a maximum height at McCalls Ferry. At the cable station it was 161.3 feet above sea level on the Lancaster County side and 159.8 feet on the York County side. Within half an hour from the time the maximum height was reached the water had fallen from 2 to 3 feet, and on the morning of March 9 it had fallen 15 feet.

Between Shanks Ferry and Port Deposit no more ice jams were formed, and the ice passed through the channel of the river very rapidly and caused but little damage. The history of nearly all floods has been that between "The Neck" and Port Deposit but little gorging takes place and that the river rapidly clears itself from any



ICE FLOOD OF 1875 AT WILKESBARRE, PA.



FLOOD OF MARCH 8, 1904, AT ITS HEIGHT AT YORK HAVEN, PA.

ice and seldom rises to such a height as to cause particular damage along the shores. At Port Deposit there is frequent trouble, for the shallow sand bars and tidal backwater often cause gorges which flood the tracks and lower part of the town.

Elevations of flood on lower portion of Susquehanna River, March 8, 1904.

| Locality. | Eleva- tion. | Remarks. |
|---------------------------------------|-----------------|--|
| | <i>Feet.</i> | |
| Fort Cullys Falls, gage No. 5 | 139.5 | Approximate. |
| Lock 13 (behind ice) | 136.2 | Ice gorged in channel above. |
| 600 feet above Lock 13 | 140.1 | Made of drift. |
| 500 feet above Lock 12 | 143.0 | Observed during flood. |
| Power house, gage 2 | 146.6 | Do. |
| Dam line, York side | 146.7 | Do. |
| High-water gage 10 | 147.7 | Do. |
| McCalls Ferry, York County | 150.7 | Observed during flood; in back- water behind ice. |
| McCalls Ferry, Lancaster County | 151.8 | Observed during flood. |
| At telegraph line on T. P | 156.3 | Do. |
| Station 71+80 on T. P | 158.8 | Do. |
| At cable, York County | 159.8 | Observed during flood; behind ice. |
| At cable, Lancaster County | 161.3 | Drift marks. |
| Tucquan culvert | 167.5 | Do. |
| Milepost 29 | 175.5 | Watermark on post. |
| York Furnace station | 179.5 | Watermark on station. |
| York Furnace Hotel | 178.6 | Observed during flood. |
| Pequea Bridge | 182.6 | Watermarks on house and post. |
| Milepost 31 | 182.7 | Watermarks on post. |
| Shanks Ferry Hotel | 185.7 | Observed during flood. |
| Milepost 32 | 186.3 | Watermarks on posts. |
| Safe Harbor | 204.0 | Watermarks on station. |

Above Shanks Ferry much damage was done, and the loss of property was great at many points. The facts are interesting to those who contemplate power development in the lower portion of Susquehanna River, as the possible damage from ice has been one of the great objections to such development.

The full effect of the flood on the main stream was not felt below Sunbury, being restrained by the big gorges at Kipps Run, Catawissa, and Nanticoke, which held several days longer. It was at its worst in Wyoming Valley on the 9th, doing much damage to Plymouth, Wilkesbarre, and Pittston, and then quietly passed away without noticeable effect on the lower river.

A rough estimate of damage due to flood, as given by press reports, is as follows:

Damage due to flood of March, 1904.

| | |
|--|-------------|
| Pittston to Sunbury ^a | \$6,500,000 |
| York County ^b | 200,000 |
| Lancaster County | 275,000 |
| Dauphin County ^c | 275,000 |
| Cumberland County | 200,000 |
| Perry County | 200,000 |
| Snyder County | 125,000 |
| Juniata County | 100,000 |
| Maryland | 100,000 |
| Total | 7,975,000 |

The loss and damage to State bridges was reported as \$800,000.

The table below gives a comparison of the heights during the flood period at various points along the river.

1904 flood heights, in feet, above low water of September, 1900.

| Date. | Main river at McCalls Ferry (4 p. m.). | Main river at Harris- burg (7 a. m.). | Main river at Wilkes- barre (8 a. m.). | West Branch at Williams- port (7.30 a. m.). | Juniata at Newport (12 m.). |
|--------------------------|---|--|---|---|-----------------------------------|
| 1904. | | | | | |
| March 3 | 9.0 | 11.9 | 9.0 | 7.4 | 4.4 |
| March 4 | 9.9 | 13.5 | 11.2 | 18.9 | 10.7 |
| March 5 | 15.0 | 22.0 | 16.0 | 16.4 | 6.1 |
| March 6 | 15.0 | 19.4 | 14.9 | 9.1 | 3.2 |
| March 7 | 13.4 | 16.3 | 15.4 | 7.3 | 2.7 |
| March 8 | 23.6 | 21.2 | 26.3 | 17.6 | 11.2 |
| March 9 | 17.2 | 15.9 | 28.5 | 13.4 | 7.2 |
| March 10 | 17.4 | 15.0 | 24.0 | 9.7 | 4.4 |
| March 11 | 17.9 | 12.0 | 21.9 | 7.5 | 3.2 |
| March 12 | 13.6 | 9.2 | 19.9 | 6.4 | 3.2 |
| Maximum height attained. | ^a 33.6 | ^b 23.3 | ^c 28.5 | ^d 18.9 | ----- |

^a March 8, 4 p. m.

^b March 4, 3 p. m.

^c March 9, 8 a. m.

^d March 4, 7 a. m.

NOTE.—Maximum heights other than at McCalls Ferry were caused by back-water from gorges.

^a Of which one to two millions were in Wyoming Valley.

^b Most damage at York Haven and vicinity.

^c Of which Middletown losses amounted to about \$109,000.



A



B

McCALLS FERRY IN FLOOD OF MARCH 8, 1904

A, At beginning of flood; *B*, after flood.



A



B

ICE LEFT BY FLOOD OF MARCH 8, 1904.

A, At York Haven, Pa.; *B*, below McCall's Ferry, Pa.

The cable gaging station about three-fourths mile above McCalls Ferry offered a good opportunity for determining the amount of water flowing at the maximum stage. At this point two cables are stretched across the river 80 feet apart, and at the time of the flood the sun was shining in line with these and bright enough to cast their shadows on the white ice, thus enabling the determination of the velocity at this point with considerable degree of accuracy. The velocity was determined in four different portions of the river, and several individual determinations were made in each portion. The result of this measurement is shown in the table below.

Flood discharge at cable station, McCalls Ferry, Pa., March 8, 1904, 4 p. m.

[Elevation water surface, Lancaster County side, 161.3 feet; York County side, 159.8 feet; mean 160.6 feet.^a]

| Stations. | Surface velocities. | Mean velocity 90 per cent of surface. | Area. | Discharge. | Remarks. |
|--------------------|---------------------|---------------------------------------|------------------|-------------------|---|
| | <i>Ft. per sec.</i> | <i>Ft. per sec.</i> | <i>Sq. feet.</i> | <i>Sec.-feet.</i> | |
| 50 to 125 | 0 | ----- | 4,710 | 0 | Ice piled along towpath. No apparent velocity. |
| 125 to 625 | 20 | 18 | 23,560 | 424,000 | Velocity obtained by timing ice cakes between cables 80 feet apart. |
| 625 to 725 | 13.3 | 12 | 4,600 | 55,200 | Do. |
| 725 to 825 | 0 | ----- | 4,370 | 0 | Backwater behind Streepers Island. |
| 825 to 975 | 13.3 | 12 | 6,960 | 83,500 | Velocity obtained by timing ice cakes between cables 80 feet apart. |
| 975 to 1180 | 11.4 | 10.2 | 6,700 | 68,300 | Do. |
| 1180 to 1320 | 0 | ----- | 3,600 | 0 | Ice and backwater. |
| Total | ----- | ----- | 54,500 | 631,000 | Mean velocity 11.6 feet per second. |

^aCorresponding gage height for 1889 flood was about 162 feet, with discharge of 671,000 second-feet.

The table on page 178 gives the estimated maximum, minimum, and mean discharge of Susquehanna River at Harrisburg for 1891 to 1904, inclusive.

Minimum, maximum, and mean discharge of Susquehanna River at Harrisburg, Pa., for 1891 to 1904, inclusive.


| Year. | Minimum. | | | Maximum. | | | Mean discharge. |
|------------------|---------------------------|--------------|-----------------|-----------------|--------------|-----------------|-----------------|
| | Date. | Gage height. | Discharge. | Date. | Gage height. | Discharge. | |
| | | <i>Feet.</i> | <i>Sec.-ft.</i> | | <i>Feet.</i> | <i>Sec.-ft.</i> | <i>Sec.-ft.</i> |
| 1891----- | Oct. 4-7, inclusive | 1.60 | 10,200 | Feb. 19 | 19.00 | 334,500 | 52,200 |
| 1892----- | Oct. 31-Nov. 8, inclusive | .50 | 4,070 | Apr. 6 | 14.65 | 224,200 | 37,250 |
| 1893----- | Aug. 16-19, inclusive, 25 | .35 | 3,500 | May 6 | 16.50 | 267,400 | 40,550 |
| 1894----- | Sept. 5-6 | .25 | 3,160 | May 22 | 25.60 | 543,500 | 39,970 |
| 1895----- | Oct. 30-31 | .05 | 2,570 | Apr. 11 | 13.65 | 205,400 | 29,330 |
| 1896----- | Sept. 5-13 | .25 | 3,160 | Apr. 1-2 | 14.60 | 223,200 | 34,600 |
| 1897----- | Sept. 15, Oct. 21 | .50 | 4,070 | Mar. 26 | 11.50 | 165,306 | 32,320 |
| 1898----- | Oct. 3-7 | .65 | 4,740 | Mar. 24 | 15.65 | 245,900 | 40,490 |
| 1899----- | Oct. 24 and 25 | .15 | 2,850 | Mar. 7 | 13.00 | 193,000 | 31,000 |
| 1900----- | Sept. 28 and 29 | -.04 | 2,360 | Mar. 2 | 13.10 | 194,900 | 29,950 |
| 1901----- | Nov. 12 | 1.00 | 6,550 | Dec. 16 | 21.40 | 405,100 | 42,380 |
| 1902----- | Sept. 23, 24, 25 | .85 | 5,760 | Mar. 2 | 23.90 | 484,100 | 47,100 |
| 1903----- | Oct. 7 | 1.40 | 8,850 | do | 16.85 | 276,500 | 54,510 |
| 1849----- | Dec. 11 | 0.84 | 5,708 | ----- | ----- | ----- | 32,318 |
| For the 14 years | Sept. 28-29, 1900 | -.04 | 2,360 | 1894. May 22 | 25.60 | 543,500 | 38,855 |

FLOOD DISCHARGES AND VALUES OF "N" BY KUTTER'S FORMULA.

Owing to the lack of high-water gagings on Susquehanna River, it became necessary to estimate the flood discharges by means of the slope formula, $v=c\sqrt{Rs}$, using Kutter's formula to fix the value of c . The 1889 flood is the highest on record, and as there remain many of its high-water marks made by eyewitnesses along the railroad and canal above McCall's Ferry, Pa., the mean slope along this part of the river could be closely approximated. These marks consist of notches on posts, rocks, hotels, bridge piers, and locks, and their elevations were accurately determined, as shown on the profile.

Ten sections, located as shown on Pl. XVIII, were then chosen from the contour map. These were selected so as to show as far as possible the average for the portions of the river represented, so that the mean slope between the nearest reliable high-water marks could be used in connection with them. The sections were carefully surveyed and sounded to determine their area and wetted perimeter.

In order to get a value for n in Kutter's formula the slopes were measured on the west channel of the Duncans Run section during



MIDDLETOWN, PA., DURING FLOOD OF MARCH 8, 1904.

several gagings. With these slopes and the data from the gagings made on July 24 and 26, 1902, June 5, 1903, and March 8, 1904, the coefficients c and n have been computed by the formulas—

$$Q = Av; v = c\sqrt{Rs}; c = \frac{41.6 + \frac{.00281}{s} + \frac{1.811}{n}}{1 + \frac{\left(41.6 + \frac{.00281}{s}\right)n}{\sqrt{R}}}$$

as shown in the table below.

Values of c and n , with data used in their determination.

| Date. | Discharge. | Area. | Wetted perim- eter. | (R) Hydraulic radius. | (V) Mean ve- locity. | Coefficient (c). | Observed slope (s). | Computed coefficient (n). | Remarks. |
|----------------------------|----------------|---------------|------------------------|--------------------------|------------------------------|------------------|------------------------|------------------------------|--|
| | <i>Sec.ft.</i> | <i>Sq.ft.</i> | <i>Feet.</i> | <i>Feet.</i> | <i>Feet per sec.</i> | | | | |
| July 24, 1902 ^a | 78,300 | 9,340 | 560 | 16.68 | 8.38 | 54.9 | 0.0014 | 0.0468 | { El. W. S. 150' above line=130.72' El. W. S. 150' below line=130.30' |
| July 26, 1902 ^a | 68,000 | 8,650 | 557 | 15.51 | 7.86 | 54.8 | .00133 | .0462 | Fall in 300' 0.42' |
| June 5, 1903 ^a | 10,000 | 3,846 | 380 | 10.12 | 2.60 | 52.3 | .000244 | .0460 | Fall in 300' as above = 0.40' |
| Mar. 8, 1904 ^b | 631,000 | 63,400 | 2,420 | 26.20 | 9.96 | 52.45 | .00138 | .0545 | Fall in 900' = 0.22' |
| | | | | | | | | | Slope taken between McCalls Ferry and Gage No. 2. |

^aAt Duncans Run.

^bAt section No. 10.

The three measurements at Duncans Run give a coefficient of about 0.046. The conditions there are exceptionally favorable for this part of the river, so that as the flood sections in many cases included brushy and wooded islands, the value of n as used in the computations was increased to 0.05.

The data and results showing the discharge at the respective sections during the 1889 flood are shown in table on page 180.

The mean of the discharges of these 10 sections gives a maximum for the 1889 flood of about 730,000 second-feet, or 9 per cent greater than the mean velocity curve estimate of 671,100 second-feet. (See pages 177 and 180.)

In this connection it is of interest to note that if a coefficient equaling 0.055, as determined by the single measurement at section 10, based upon the flood gaging of March 8, 1904, had been used, the mean discharge for the 1889 flood would have been about 685,000 second-feet, or only 2 per cent greater than the results obtained by using the mean velocity curve.

The general equation of the discharge curve shown on Pl. X is approximately that of the parabola $(y-111)^2=.00202 x$, which for a gage height of 149.5 gives the 1889 flood discharge as 733,800 second-feet.

From these estimates it may be assumed that the maximum discharge of the 1889 flood was between 670,000 and 735,000 second-feet.

In determining n at section 10 by means of the flood measurement of March 8, 1904, the slope used was between McCalls Ferry and gage No. 2, the same points as were taken for the 1889 flood slope, thus making the two comparable and indicating that the assumed value of $n=.05$ is on the safe side.

Discharge of Susquehanna River during 1889 flood as computed by Kutter's formula.


$$Q = A c \sqrt{R s}; \quad c = \frac{77.82 + \frac{.00281}{s}}{1 + \frac{2.08 + \frac{.00014}{s}}{\sqrt{R}}}$$

| No. of section. | Area. | Wetted perim-eter. | Hy-draulic radius. | Mean slope. | Co-effi-cient (N). | Mean veloc-ity. | Dis-charge. | Remarks. |
|-----------------|------------------|--------------------|--------------------|-------------|--------------------|---------------------|-----------------|--|
| | <i>Sq. feet.</i> | <i>Feet.</i> | <i>Feet.</i> | | | <i>Ft. per sec.</i> | <i>Sec. ft.</i> | |
| 1 | 89,300 | 4,750 | 18.80 | 0.0012 | 0.05 | 7.98 | 713,000 | One-fourth of section is brushy island. |
| 2 | 105,500 | 4,210 | 25.06 | .00060 | .05 | 6.91 | 730,000 | One-third of section is low, brushy, rocky island. |
| 3 | 110,400 | 4,300 | 25.66 | .00060 | .05 | 7.02 | 775,000 | Do. |
| 4 | 113,600 | 5,020 | 22.63 | .00064 | .05 | 6.67 | 758,000 | One-fourth of section covered with trees or brush. |
| 5 | 110,500 | 3,220 | 34.32 | .00035 | .05 | 6.61 | 730,000 | One-sixth of section covered with brush. |
| 6 | 63,700 | 2,800 | 22.75 | .00130 | .05 | 9.43 | 602,000 | One-fourth of section is covered with trees. |
| 7 | | | | | | | 739,000 | |
| 8 | 89,500 | 2,800 | 31.96 | .00070 | .05 | 8.72 | 780,000 | One-fourth of section is rocky island. |
| 9 | | | | | | | 720,000 | |
| 10 | 72,800 | 2,430 | 29.95 | .00110 | .05 | 10.38 | 756,000 | One-fourth of section covered with brush or trees. |
| Mean | | | | | | | 730,300 | |

LOW-WATER CONDITIONS.

At the time of the establishment of the gage at Harrisburg, in 1891, the lowest-known water on Susquehanna River was in 1803, and the zero of the gage was placed at the elevation of this low water.

The months of August and September, 1900, were periods of extreme drought, and beginning with the 1st of September the observations at Harrisburg showed a gradual falling of the river until September



MAP SHOWING SECTIONS USED IN KUTTER'S FORMULA DETERMINATIONS
NEAR MCCALLS FERRY, PA.

28-29, when the gage read 0.04 of a foot below the low-water mark of 1803. During this period of low water Mr. E. G. Paul, hydrographer, United States Geological Survey, spent considerable time in measuring the flow at the various stations in the Susquehanna drainage basin. On September 21 a measurement was made at Harrisburg at a gage height of 0.08 of a foot and a discharge of 2,655 second-feet. Mr. Paul returned to Harrisburg on September 28, at which date the river reached its extreme low point of -0.04 of a foot, and made a measurement giving a discharge of 2,357 second-feet.

The measurements made by Mr. Paul during the week of September 28, 1900, at Allenwood, Danville, and Newport, Pa., as shown by the table below, gave a very close check upon the Harrisburg work, and show that the measurements as made at the various points along the river are consistent among themselves and that no errors greater than would be expected in work of this kind exist.

Comparison of minimum discharges of Susquehanna River and its branches.

| Date. | Stream. | Station. | Dis-charge. | Remarks. |
|---|-------------|----------------|-------------------|--|
| | | | <i>Sec.-feet.</i> | |
| Sept. 24, 1900 | West Branch | Allenwood, Pa. | 511 | Gage same height as on Sept. 28. |
| Sept. 25, 1900 | Susquehanna | Danville, Pa. | 822 | Gage 0.1 of a foot lower than Sept. 26-28. |
| Sept. 22, 1900 | Juniata | Newport, Pa. | 418 | Gage same as Sept. 28. |
| Total discharge from gagings above Harrisburg | | | 1,751 | |
| Add 14 per cent for increase in drainage area | | | 258 | |
| Add for 0.1 lower gage height at Danville | | | 140 | |
| Total estimated discharge above Harrisburg | | | 2,149 | |
| Gaging at Harrisburg Sept. 28 | | | 2,357 | |
| Difference | | | 208 | |

From the best available authorities the elevation of lowest water, in September, 1900, at McCall's Ferry, gage No. 2, was about 112.6 feet. The measured minimum discharge at Harrisburg for that month was 2,357 second-feet, and by increasing this figure 11.4 per cent, to allow for the increase in drainage area, we find the corresponding maximum discharge at McCall's Ferry to be about 2,620 second-feet. In order to check this result, the mean velocities of the various discharge measurements made at Duncans Run have been plotted as abscissæ and their respective gage heights as ordinates, as shown in Pl. XIX. These points, it will be seen, seem to follow a general law, and a curve has been drawn through them

which has been extended through the gage height of the lowest water, which at Duncans Run was about 114.2 feet. The velocity from the curve for that gage height is 1.0 foot per second, and the area of the section is 2,940 square feet, the product of these two giving a discharge of 2,940 second-feet as a rough check on the above. The lowest water actually measured at McCalls Ferry was on September 25, 1902, at a gage height on gage No. 2 of 114.34 feet, giving a discharge of 6,370 second-feet. The mean discharge from the rating table at Harrisburg on that date was 5,760 second-feet, corresponding to a difference in drainage area of 10.6 per cent. The table on page 178 gives the minimum estimated discharge at Harrisburg for the years 1891 to 1904, inclusive.

ACCURACY OF STREAM MEASUREMENTS.


Considerable comment has been made upon the hydrographic work of the United States Geological Survey on Susquehanna River by engineers and others who are promoting power schemes in the lower portion of the river, and it was to obtain varying data that the late George S. Morison, engineer for the McCalls Ferry project, established a gaging station at that point.

As stated on page 130, the McCalls Ferry station was established in May, 1902, and during the following year 35 discharge measurements were made at stages which ranged between the highest and lowest gage heights during this period. These measurements were taken with great care, vertical velocity curves being used in most cases. From the measurements a rating curve and table was prepared, by which, in connection with the daily gage heights, both the daily and the monthly discharges of the river were computed, as shown on pages 137-139.

On comparing the monthly discharges at McCalls Ferry from June 1, 1902, to December 31, 1904, as obtained by Mr. Morison's engineers, with those obtained by the United States Geological Survey at Harrisburg, as shown in the table on page 183, it is found that the mean monthly discharge is approximately between 7 and 25 per cent greater at McCalls than at Harrisburg. This difference is what would be expected, as the drainage area at McCalls Ferry is 11.4 per cent greater than that at Harrisburg.

It is thus seen that the methods of stream measurement used by the Geological Survey give results which agree with those obtained by private engineers, whose work is generally carried on in greater detail and at much greater cost.

An inspection of the discharge curves shows that almost all of the individual measurements plot nearly on the curve, very few of them varying from it by more than 3 per cent. This fact, while it does not prove their accuracy, indicates that the measurements were carefully made and that the results are consistent.



CURVE OF MEAN VELOCITIES FOR SUSQUEHANNA RIVER AT DUNCANS RUN,
NEAR McCALLS FERRY, PA.

Comparison of the estimated monthly discharge of Susquehanna River at Harrisburg and McCall's Ferry, Pa.

| Month. | Mean discharge in second-feet. | | | |
|------------------|--------------------------------|-----------------|--------------|-----------|
| | Harrisburg. | McCall's Ferry. | Difference. | |
| | | | Second-feet. | Per cent. |
| 1902. | | | | |
| June | 12,810 | 13,908 | 1,098 | + 7.9 |
| July | 70,209 | 61,768 | -8,441 | -13.7 |
| August | 26,962 | 27,126 | 164 | + .6 |
| September | 11,714 | 11,556 | - 158 | - 1.4 |
| October | 35,656 | 38,248 | 2,592 | + 6.8 |
| November | 20,985 | 22,657 | 1,672 | + 7.4 |
| December | 63,774 | 69,111 | 5,337 | + 7.7 |
| The period | 34,587 | 34,911 | 324 | + .9 |
| 1903. | | | | |
| January | 37,765 | 43,533 | 5,768 | +13.2 |
| February | 93,236 | 95,082 | 1,846 | + 1.9 |
| March | 133,500 | 134,461 | 961 | + .7 |
| April | 82,715 | 79,900 | -2,815 | - 3.4 |
| May | 14,297 | 16,826 | 2,529 | +15.0 |
| June | 27,964 | 29,859 | 1,895 | + 6.4 |
| July | 32,581 | 35,636 | 3,055 | + 8.6 |
| August | 25,581 | 28,206 | 2,625 | + 9.3 |
| September | 30,511 | 34,183 | 3,672 | +10.7 |
| October | 45,160 | 48,757 | 3,597 | + 7.4 |
| November | 27,289 | 30,797 | 3,508 | +11.4 |
| December | 19,743 | 19,751 | - 8 | 0 |
| The year | 47,528 | 49,638 | 2,110 | +4.3 |
| 1904. | | | | |
| April | 74,230 | 78,400 | 4,170 | + 5.3 |
| May | 41,740 | 46,720 | 4,980 | +10.7 |
| June | 29,320 | 34,580 | 5,260 | +15.2 |
| July | 18,020 | 21,410 | 3,390 | +15.8 |
| August | 10,420 | 13,880 | 3,460 | +24.9 |
| September | 8,657 | 11,050 | 2,393 | +21.7 |
| October | 15,240 | 18,700 | 3,460 | +18.5 |
| November | 10,760 | 13,320 | 2,560 | +19.2 |
| December | 8,448 | 10,890 | 2,442 | +22.4 |
| The period | 24,090 | 27,660 | 3,570 | +12.9 |

NOTE.—Owing to an ice gorge below Harrisburg the monthly means for January, February, and March have been estimated by taking 89 per cent of means for McCall's Ferry.

VERTICAL VELOCITY MEASUREMENTS.

The standard with which all velocity determinations in stream-measurement work are compared is the mean velocity obtained by the vertical velocity method. This method consists in taking, in a vertical line, a series of velocity determinations, which when plotted with depths as ordinates and velocities as abscissæ give the basis for the construction of a velocity curve along the vertical in question. This curve shows the variation in velocity from the surface to the bottom of the stream, and from it the mean velocity for the vertical can be determined by dividing the area included within the curve by the depth. From these curves not only the depth at which the mean velocity occurs can be found, but also coefficients for reducing to the mean the velocities found at the top, bottom, or at other points.

In the work in the Susquehanna drainage area three series of vertical velocity measurements have been made, as follows: At McCall's Ferry, Pa.; at Binghamton, N. Y., and at Harrisburg, Pa.

The series at McCall's Ferry, Pa., was made during the years 1902 and 1903 by Messrs. Boyd Ehle and R. H. Anderson and consisted of 73 determinations at the Duncans Run section and 104 measurements at the cable section. The depths at the first section varied from 3 to 30 feet and the mean velocities from 1.2 to 5.8 feet per second. At the second section the depths ranged from 3 to 36 feet and the mean velocities from 1.2 to 9.7 feet per second. These great depths and the high velocities at which these measurements were made make them by far the most interesting series of the kind that have been made.

The bed of the stream at both of these points is very irregular and is made up mostly of solid rock, strewn with large bowlders, as shown in Pl. I, *B*, thus making the velocities near the bottom hard to determine.

The secondary guy cable with which the station is equipped, as noted on page 131 and shown on Pl. IX, *A*, enabled the observer to hold the meter at a depth which it is very difficult to reach under ordinary conditions.

The results of the measurements have been tabulated and are given in the tables on pages 185-187, and the platted curves are shown in Pls. XX to XXVI, inclusive.

A study of these tables shows that in order to draw any conclusions from the results the individual determinations must be grouped, in order to bring together those which were taken under the same conditions. The grouping for the Duncans Run series was made according to depth as follows: Group 1, 4 to 10 feet; group 2, 10 to 20 feet; group 3, 20 to 30 feet, and those for the cable station according to the distance from the initial point.

Rejecting disturbed and discordant observations, the averages from these groups give the results shown in the table on page 188.

Vertical velocity measurements at Duncans Run, above McCalls Ferry, Pa.

| Distance from initial point, in feet. | Depth, in feet. | Velocity, in feet, per second by following methods: | | | | Coefficient for reduc- ing to mean velocity. | | | Depth of thread of mean velocity.* | |
|---|-----------------------|--|----------------|-------------------------|------|---|-------------------------|------|--|-----------------------------|
| | | Verti- cal ve- locity. | 0.6 depth.* | Top and bot- tom. | Top. | 0.6 depth. | Top and bot- tom. | Top. | In feet. | In per cent of depth. |
| 9 | 15.5 | 2.52 | 2.73 | 1.77 | 3.00 | 0.92 | 1.42 | 0.84 | 10.5 | 68 |
| 10 <i>a</i> | 18.0 | 2.26 | 2.50 | 1.80 | 2.40 | .90 | 1.26 | .94 | 13.6 | 76 |
| 10 | 22.5 | 3.12 | 3.40 | 2.63 | 3.32 | .92 | 1.19 | .94 | 15.2 | 68 |
| 10 | 16.0 | 2.02 | 2.20 | 1.69 | 2.42 | .92 | 1.20 | .84 | 11.7 | 73 |
| 15 | 19.0 | 2.74 | 2.92 | 2.25 | 3.35 | .94 | 1.22 | .82 | 12.7 | 67 |
| 15 <i>a</i> | 18.0 | 2.58 | 2.63 | 2.40 | 2.73 | .98 | 1.08 | .94 | 12.7 | 71 |
| 20 | 16.0 | 1.79 | 2.10 | 1.88 | 1.20 | .86 | 1.30 | 1.49 | 13.7 | 86 |
| 20 <i>a</i> | 17.8 | 2.43 | 2.68 | 1.72 | 2.62 | .90 | 1.41 | .93 | 12.8 | 72 |
| 20 | 22.0 | 2.96 | 3.30 | 2.16 | 3.32 | .90 | 1.37 | .89 | 15.5 | 71 |
| 25 <i>a</i> | 20.5 | 2.62 | 2.72 | 2.14 | 2.85 | .96 | 1.22 | .92 | 15.4 | 75 |
| 28 <i>a</i> | 19.0 | 1.83 | 2.32 | 1.18 | 1.10 | .79 | 1.55 | 1.66 | 15.5 | 82 |
| 30 <i>a</i> | 18.0 | 1.68 | 2.10 | 1.28 | 1.13 | .80 | 1.31 | 1.48 | 16.2 | 90 |
| 30 <i>a</i> | 23.0 | 2.64 | 2.82 | 2.31 | 2.90 | .94 | 1.14 | .91 | 17.5 | 76 |
| 40 <i>b</i> | 4.0 | 2.68 | 2.88 | 2.58 | 3.05 | .93 | 1.04 | .88 | 2.5 | 63 |
| 50 <i>b</i> | 4.3 | 3.30 | 3.55 | 3.44 | 3.46 | .93 | .96 | .96 | 3.1 | 72 |
| 60 <i>b</i> | 3.3 | 3.10 | 3.64 | 2.52 | 4.36 | .85 | 1.23 | .71 | 2.2 | 67 |
| 70 <i>b</i> | 5.0 | 3.60 | 3.62 | 3.60 | 3.83 | 1.00 | 1.00 | .94 | 3.2 | 64 |
| 80 <i>b</i> | 9.0 | 3.55 | 3.45 | 3.51 | 4.50 | 1.03 | 1.01 | .79 | 4.8 | 53 |
| 90 <i>b</i> | 5.0 | 4.66 | 4.65 | 4.48 | 4.73 | 1.00 | 1.04 | .98 | 3.0 | 60 |
| 100 <i>b</i> | 4.5 | 5.80 | 6.05 | 4.43 | 5.30 | .96 | 1.31 | 1.10 | 3.0 | 67 |
| 110 <i>b</i> | 6.0 | 3.86 | 4.13 | 3.70 | 4.22 | .94 | 1.04 | .91 | 4.0 | 67 |
| 120 <i>b</i> | 7.5 | 2.42 | 2.48 | 2.53 | 2.72 | .98 | .96 | .89 | 5.3 | 71 |
| 122 <i>b</i> | 14.0 | 3.04 | 3.28 | 2.28 | 3.70 | .93 | 1.33 | .82 | 9.1 | 65 |
| 130 <i>a</i> | 12.0 | 2.12 | 2.30 | 1.95 | 2.06 | .92 | 1.09 | 1.03 | 9.5 | 79 |
| 130 | 14.0 | 2.38 | 2.42 | 2.15 | 3.10 | .98 | 1.11 | .77 | 8.8 | 63 |
| 132 <i>a</i> | 13.5 | 3.20 | 3.30 | 3.14 | 3.05 | .97 | 1.02 | 1.05 | 12.6 | 93 |
| 130 | 20.0 | 3.41 | 3.50 | 2.96 | 3.83 | .98 | 1.15 | .89 | 12.7 | 64 |
| 140 | 20.5 | 2.24 | 2.30 | 1.97 | 2.58 | .97 | 1.14 | .87 | 14.4 | 70 |
| 140 | 22.0 | 2.46 | 2.62 | 2.20 | 2.58 | .94 | 1.12 | .95 | 15.1 | 69 |
| 140 | 25.0 | 3.48 | 3.71 | 2.70 | 4.03 | .94 | 1.29 | .86 | 16.7 | 67 |
| 140 | 25.0 | 2.63 | 2.80 | 2.01 | 3.08 | .94 | 1.31 | .86 | 16.5 | 66 |
| 150 <i>a</i> | 20.0 | 2.20 | 2.27 | 2.06 | 2.34 | .97 | 1.07 | .94 | 14.7 | 73 |
| 150 | 21.5 | 2.93 | 3.05 | 2.83 | 2.96 | .96 | 1.04 | .99 | 15.7 | 73 |
| 150 | 22.5 | 2.65 | 2.75 | 2.59 | 2.76 | .96 | 1.02 | .96 | 16.4 | 73 |
| 150 | 27.5 | 3.38 | 3.58 | 2.55 | 3.83 | .94 | 1.32 | .88 | 20.3 | 74 |
| 160 <i>a</i> | 24.0 | 1.97 | 2.02 | 1.66 | 2.13 | .98 | 1.19 | .92 | 15.3 | 64 |
| 160 | 26.5 | 2.54 | 2.67 | 2.25 | 2.62 | .96 | 1.13 | .97 | 18.0 | 68 |
| 160 | 31.0 | 3.03 | 3.06 | 2.62 | 3.83 | .99 | 1.16 | .79 | 19.3 | 62 |
| 160 | 27.0 | 2.72 | 2.98 | 2.30 | 3.05 | .92 | 1.18 | .89 | 19.3 | 72 |
| 170 <i>b</i> | 24.5 | 2.02 | 2.22 | 1.73 | 2.10 | .91 | 1.17 | .96 | 18.0 | 73 |
| 170 | 25.5 | 2.35 | 2.54 | 2.06 | 2.48 | .92 | 1.14 | .96 | 17.8 | 70 |
| 170 | 28.0 | 3.22 | 3.18 | 2.75 | 3.79 | 1.01 | 1.17 | .85 | 16.0 | 57 |
| 170 | 24.0 | 2.80 | 3.00 | 2.37 | 2.84 | .94 | 1.18 | .99 | 19.7 | 82 |
| 180 <i>b</i> | 17.0 | 2.10 | 2.14 | 2.12 | 2.10 | .98 | .99 | 1.00 | 16.0 | 94 |
| 180 | 25.0 | 1.87 | 2.20 | 1.42 | 2.25 | .85 | 1.32 | .83 | 17.0 | 68 |
| 180 | 29.0 | 2.77 | 3.00 | 2.20 | 3.79 | .92 | 1.26 | .73 | 18.1 | 62 |
| 180 | 16.0 | 2.82 | 2.94 | 2.70 | 2.60 | .96 | 1.04 | 1.08 | 15.0 | 94 |
| 190 <i>b</i> | 25.0 | 1.84 | 1.92 | 1.67 | 1.92 | .96 | 1.10 | .96 | 16.7 | 67 |
| 190 | 27.0 | 2.16 | 2.33 | 1.88 | 2.34 | .93 | 1.15 | .92 | 20.4 | 75 |
| 190 | 30.0 | 2.98 | 2.87 | 2.46 | 3.70 | 1.04 | 1.21 | .80 | 17.4 | 58 |
| 190 | 25.6 | 2.75 | 2.75 | 2.69 | 2.81 | 1.00 | 1.02 | .98 | 15.0 | 60 |
| 200 <i>b</i> | 25.0 | 1.70 | 1.83 | 1.28 | 1.92 | .93 | 1.33 | .88 | 17.0 | 68 |
| 200 | 26.0 | 2.20 | 2.38 | 1.72 | 2.25 | .92 | 1.28 | .98 | 18.7 | 72 |
| 200 | 26.5 | 2.39 | 2.46 | 1.93 | 2.72 | .97 | 1.24 | .88 | 17.4 | 66 |
| 210 <i>a</i> | 21.0 | 1.69 | 1.78 | 1.50 | 1.79 | .95 | 1.13 | .94 | 16.5 | 78 |
| 210 | 22.5 | 2.17 | 2.30 | 1.88 | 2.20 | .94 | 1.15 | .98 | 17.7 | 79 |
| 210 | 21.5 | 2.78 | 2.78 | 2.77 | 3.11 | 1.00 | 1.00 | .90 | 12.9 | 60 |
| 220 <i>a</i> | 18.5 | 1.58 | 1.66 | 1.37 | 1.73 | .95 | 1.15 | .92 | 15.5 | 84 |
| 220 | 19.5 | 2.06 | 2.09 | 2.08 | 2.10 | .98 | .99 | .98 | 14.5 | 74 |
| 220 | 20.0 | 2.52 | 2.58 | 2.40 | 2.63 | .98 | 1.05 | .96 | 13.8 | 69 |
| 230 <i>a</i> | 16.3 | 1.45 | 1.57 | .94 | 1.56 | .92 | 1.54 | .93 | 11.0 | 68 |
| 230 | 16.0 | 2.40 | 2.50 | 2.25 | 2.54 | .96 | 1.07 | .94 | 11.0 | 69 |
| 230 | 17.0 | 1.75 | 1.85 | 1.62 | 2.02 | .95 | 1.08 | .87 | 11.5 | 68 |
| 240 <i>a</i> | 13.0 | 1.31 | 1.36 | 1.30 | 1.28 | .96 | 1.01 | 1.02 | 11.0 | 85 |
| 240 | 15.0 | 1.67 | 1.80 | 1.60 | 1.83 | .93 | 1.04 | .91 | 10.8 | 72 |
| 240 | 14.5 | 2.37 | 2.41 | 2.27 | 2.47 | .98 | 1.04 | .96 | 9.5 | 66 |
| 250 <i>a</i> | 10.0 | 1.21 | 1.35 | 1.11 | 1.09 | .90 | 1.09 | 1.11 | 8.6 | 86 |
| 250 | 12.5 | 1.55 | 1.73 | 1.44 | 1.56 | .90 | 1.08 | 1.00 | 9.7 | 78 |
| 250 | 13.5 | 1.90 | 2.00 | 1.62 | 2.10 | .95 | 1.17 | .90 | 9.0 | 67 |
| 260 <i>b</i> | 8.0 | 1.24 | 1.40 | 1.14 | 1.25 | .88 | 1.09 | .99 | 6.0 | 75 |
| 260 | 8.0 | 1.25 | 1.35 | 1.21 | 1.56 | .93 | 1.03 | .80 | 5.5 | 69 |
| 260 | 9.5 | 1.70 | 1.65 | 1.66 | 2.04 | 1.03 | 1.02 | .84 | 5.0 | 53 |

* From vertical velocity curve.

a Even rock bottom.*b* Uneven rock bottom.

Vertical velocity measurements at cable station above McCalls Ferry, Pa.

| Distance from initial point, in feet. | Depth, in feet. | Velocity, in feet per second, by following methods— | | | Coefficient for reducing to mean velocity. | | Depth of thread of mean velocity. ^a | |
|---------------------------------------|-----------------|---|-------------------------|-------|--|------|--|-----------------------|
| | | Vertical velocity. | 0.6 depth. ^a | Top. | 0.6 depth. | Top. | In feet. | In per cent of depth. |
| 150 <i>b</i> | 8.0 | 3.26 | 3.22 | 3.70 | 1.01 | 0.88 | 4.6 | 58 |
| | 10.0 | 4.30 | 4.40 | 4.82 | .98 | .89 | 6.5 | 65 |
| | 10.0 | 4.06 | 4.24 | 4.48 | .96 | .91 | 7.3 | 73 |
| | 12.0 | 4.15 | 4.68 | 4.45 | .89 | .93 | 9.3 | 77 |
| | 13.0 | 4.80 | 5.20 | 5.27 | .92 | .91 | 9.6 | 74 |
| | 19.0 | 5.76 | 6.40 | 5.75 | .90 | 1.00 | 15.0 | 79 |
| 200 <i>b</i> | 8.7 | 4.00 | 4.08 | 4.38 | .98 | .91 | 6.7 | 77 |
| | 10.0 | 5.20 | 5.45 | 5.75 | .95 | .90 | 7.3 | 73 |
| | 11.0 | 5.00 | 5.30 | 5.33 | .94 | .94 | 8.2 | 75 |
| | 14.0 | 6.75 | 7.06 | 7.07 | .96 | .96 | 11.0 | 78 |
| 250 <i>b</i> | 7.0 | 3.42 | 3.68 | 3.67 | .93 | .95 | 5.6 | 80 |
| | 9.0 | 4.90 | 5.00 | 5.45 | .98 | .90 | 6.3 | 70 |
| | 16.5 | 7.50 | 7.45 | 7.77 | 1.01 | .96 | 10.6 | 64 |
| 300 <i>c</i> | 7.0 | 4.64 | 5.05 | 5.30 | .92 | .88 | 5.3 | 76 |
| | 8.0 | 4.85 | 5.15 | 5.45 | .94 | .89 | 6.0 | 75 |
| | 16.5 | 7.60 | 6.63 | 9.60 | 1.14 | .79 | 12.6 | 76 |
| 350 <i>b</i> | 6.0 | 4.20 | 4.27 | 4.35 | .98 | .96 | 5.0 | 83 |
| | 8.0 | 4.76 | 4.88 | 5.27 | .98 | .90 | 6.5 | 81 |
| | 9.0 | 5.40 | 5.65 | 5.75 | .96 | .94 | 7.0 | 78 |
| | 16.0 | 8.12 | 8.70 | 9.60 | .93 | .85 | 12.7 | 79 |
| 385 <i>c</i> | 13.0 | 2.47 | 2.57 | 2.70 | .96 | .92 | 9.0 | 69 |
| 400 <i>c</i> | 10.0 | 1.22 | 1.01 | 1.73 | 1.21 | .71 | 3.5 | 35 |
| | 14.0 | 3.28 | 3.28 | 3.70 | 1.00 | .89 | 8.4 | 60 |
| | 15.0 | 2.96 | 3.00 | 3.63 | .99 | .82 | 9.2 | 61 |
| | 15.0 | 3.74 | 3.55 | 4.78 | 1.05 | .78 | 7.7 | 51 |
| | 15.0 | 5.20 | 5.72 | 5.30 | .91 | .98 | 11.6 | 77 |
| | 16.0 | 4.13 | 4.28 | 5.58 | .97 | .74 | 11.0 | 69 |
| | 18.0 | 5.13 | 4.93 | 6.83 | 1.04 | .75 | 8.2 | 46 |
| | 22.5 | 7.62 | 8.12 | 8.90 | .94 | .86 | 16.2 | 72 |
| 450 <i>c</i> | 8.0 | 3.18 | 3.30 | 3.38 | .96 | .94 | 6.0 | 75 |
| | 10.0 | 5.69 | 6.13 | 5.87 | .93 | .97 | 7.7 | 77 |
| | 15.5 | 5.75 | 6.10 | 6.20 | .94 | .93 | 10.7 | 69 |
| | 14.0 | 8.15 | 8.47 | 9.35 | .96 | .87 | 9.8 | 70 |
| 500 <i>b</i> | 16.0 | 9.16 | 9.60 | 10.90 | .95 | .84 | 11.3 | 70 |
| | 16.0 | 3.80 | 4.12 | 3.90 | .92 | .98 | 13.1 | 82 |
| | 16.5 | 3.74 | 3.83 | 3.93 | .98 | .95 | 15.3 | 93 |
| | 21.5 | 5.03 | 5.17 | 5.17 | .97 | .97 | 19.0 | 88 |
| | 24.5 | 6.02 | 6.00 | 6.88 | 1.00 | .88 | 14.4 | 59 |
| | 27.0 | 7.77 | 7.70 | 9.10 | 1.01 | .85 | 15.8 | 59 |
| | 28.0 | 7.50 | 7.80 | 8.75 | .96 | .86 | 18.7 | 67 |
| | 36.0 | 9.00 | 9.22 | 10.00 | .98 | .90 | 23.8 | 66 |
| 550 <i>b</i> | 16.0 | 4.30 | 4.30 | 5.17 | 1.00 | .83 | 9.6 | 60 |
| | 19.0 | 4.24 | 4.41 | 4.85 | .96 | .87 | 12.6 | 66 |
| | 21.0 | 4.33 | 4.42 | 5.00 | .98 | .87 | 13.1 | 62 |
| | 24.5 | 6.38 | 6.38 | 7.50 | 1.00 | .85 | 14.7 | 60 |
| | 28.0 | 7.20 | 7.22 | 8.15 | 1.00 | .88 | 17.0 | 61 |
| | 28.0 | 7.47 | 7.62 | 7.97 | .98 | .94 | 20.2 | 72 |
| | 35.0 | 9.70 | 9.80 | 10.65 | .99 | .91 | 22.2 | 63 |
| 600 <i>b</i> | 17.0 | 3.95 | 4.10 | 4.55 | .96 | .87 | 11.3 | 66 |
| | 20.0 | 4.30 | 4.50 | 4.90 | .96 | .88 | 13.3 | 66 |
| | 21.0 | 4.97 | 5.02 | 5.40 | .99 | .92 | 14.1 | 67 |
| | 25.0 | 6.30 | 6.43 | 6.63 | .98 | .95 | 17.8 | 71 |
| | 28.5 | 7.40 | 7.42 | 7.47 | 1.00 | .99 | 17.5 | 61 |
| | 29.0 | 7.54 | 7.64 | 8.05 | .99 | .94 | 22.0 | 76 |
| | 35.0 | 8.23 | 8.62 | 9.25 | .96 | .89 | 25.2 | 72 |
| 625 <i>c</i> | 15.0 | 3.27 | 3.00 | 4.20 | 1.09 | .78 | 7.9 | 53 |
| 650 <i>c</i> | 5.5 | 5.15 | 5.57 | 6.05 | .92 | .85 | 3.9 | 71 |
| | 11.0 | 5.80 | 5.65 | 6.53 | 1.03 | .89 | 6.0 | 55 |
| | 15.0 | 6.84 | 6.45 | 7.73 | 1.06 | .88 | 6.9 | 46 |
| | 17.0 | 6.83 | 6.50 | 7.73 | 1.05 | .88 | 8.5 | 50 |
| 650 | 18.0 | 6.70 | 6.60 | 8.17 | 1.01 | .82 | 10.5 | 58 |
| | 21.0 | 7.64 | 8.07 | 8.51 | .95 | .90 | 16.6 | 79 |
| | 26.0 | 7.44 | 7.70 | 8.92 | .97 | .83 | 17.6 | 68 |
| 700 <i>b</i> | 4.5 | 4.70 | 4.97 | 5.35 | .95 | .88 | 3.1 | 69 |
| | 8.0 | 5.28 | 5.60 | 6.08 | .94 | .87 | 5.8 | 73 |
| | 8.0 | 4.97 | 5.20 | 5.20 | .96 | .96 | 6.2 | 78 |
| | 13.7 | 6.24 | 6.45 | 7.25 | .97 | .86 | 9.2 | 67 |
| | 15.0 | 6.12 | 6.30 | 6.75 | .97 | .91 | 10.1 | 67 |
| | 15.5 | 6.00 | 6.12 | 6.85 | .98 | .88 | 10.4 | 67 |
| | 20.0 | 6.67 | 7.00 | 7.42 | .95 | .90 | 16.7 | 84 |
| | 24.5 | 7.00 | 7.37 | 7.87 | .95 | .89 | 19.3 | 79 |
| 750 <i>c</i> | 5.5 | 5.00 | 5.60 | 6.10 | .89 | .82 | 4.0 | 73 |
| | 12.0 | 5.56 | 5.70 | 6.20 | .98 | .90 | 7.9 | 66 |
| | 12.0 | 5.22 | 5.25 | 6.40 | .99 | .82 | 7.3 | 61 |
| | 13.5 | 5.30 | 5.47 | 6.33 | .97 | .84 | 8.8 | 65 |
| | 15.0 | 6.33 | 6.85 | 7.07 | .93 | .90 | 12.3 | 82 |
| | 20.0 | 5.50 | 5.50 | 6.65 | 1.00 | .83 | 12.0 | 60 |

^aFrom vertical velocity curve.^bRegular bottom.^cRough and irregular bottom.

Vertical velocity measurements at cable station above McCalls Ferry, Pa.—Continued.

| Distance from initial point, in feet. | Depth, in feet. | Velocity, in feet per second, by following methods— | | | Coefficient for reducing to mean velocity. | | Depth of thread of mean velocity. | |
|---------------------------------------|-----------------|---|------------|------|--|------|-----------------------------------|-----------------------|
| | | Vertical velocity. | 0.6 depth. | Top. | 0.6 depth. | Top. | In feet. | In per cent of depth. |
| 800 <i>a</i> ----- | 6.0 | 5.60 | 5.73 | 6.33 | 0.98 | 0.89 | 3.8 | 63 |
| | 11.0 | 5.80 | 6.20 | 6.80 | .94 | .85 | 7.9 | 72 |
| | 11.5 | 6.17 | 6.20 | 7.00 | 1.00 | .88 | 7.2 | 65 |
| | 15.0 | 5.73 | 6.12 | 6.20 | .94 | .93 | 12.1 | 81 |
| | 16.0 | 6.12 | 6.40 | 7.00 | .96 | .87 | 12.3 | 77 |
| | 21.5 | 5.36 | 5.55 | 5.60 | .97 | .96 | 16.6 | 77 |
| 850 <i>a</i> ----- | 6.0 | 3.83 | 3.95 | 4.13 | .97 | .93 | 4.2 | 70 |
| | 11.0 | 4.97 | 5.15 | 5.63 | .96 | .88 | 7.5 | 68 |
| | 13.0 | 4.87 | 5.15 | 5.05 | .95 | .96 | 9.7 | 75 |
| | 15.0 | 4.80 | 4.95 | 5.45 | .97 | .88 | 10.6 | 71 |
| | 15.0 | 4.66 | 4.82 | 5.63 | .97 | .83 | 10.6 | 71 |
| | 16.0 | 5.54 | 5.85 | 5.72 | .95 | .97 | 13.0 | 81 |
| 900 <i>a</i> ----- | 21.0 | 6.82 | 7.17 | 7.23 | .95 | .94 | 16.5 | 79 |
| | 7.0 | 1.88 | 1.45 | 1.62 | .95 | .85 | 4.8 | 69 |
| | 9.0 | 3.14 | 3.35 | 4.00 | .94 | .79 | 6.7 | 74 |
| | 13.0 | 3.38 | 3.56 | 3.77 | .95 | .90 | 9.7 | 75 |
| | 16.0 | 5.00 | 5.43 | 5.38 | .92 | .93 | 12.3 | 77 |
| | 16.0 | 4.94 | 5.20 | 5.32 | .95 | .93 | 11.2 | 70 |
| 950 <i>a</i> ----- | 18.0 | 5.30 | 5.35 | 5.87 | .99 | .90 | 12.0 | 67 |
| | 19.0 | 6.06 | 6.23 | 6.32 | .97 | .96 | 16.0 | 84 |
| | 25.0 | 7.20 | 7.35 | 8.05 | .98 | .90 | 19.7 | 79 |
| | 7.7 | 1.85 | 1.98 | 2.02 | .93 | .92 | 5.5 | 71 |
| | 10.0 | 2.67 | 2.75 | 3.14 | .97 | .85 | 6.3 | 63 |
| | 12.7 | 3.32 | 3.43 | 4.00 | .97 | .83 | 8.6 | 68 |
| | 16.0 | 4.90 | 5.07 | 5.50 | .97 | .89 | 11.3 | 71 |
| | 16.5 | 5.07 | 5.10 | 5.80 | .99 | .87 | 10.2 | 62 |
| | 17.7 | 6.40 | 6.66 | 7.07 | .96 | .91 | 14.0 | 79 |
| | 2.4 | 7.70 | 7.80 | 8.28 | .99 | .93 | 17.4 | 73 |

a Regular bottom.

Recapitulation and deductions from vertical velocity measurements at Duncans Run.

| Group. | No. of observations. | Depth. | Coefficients for reducing to mean velocity. | | | Depth of thread of mean velocity in per cent of total depth. |
|---------|----------------------|--------------|---|------------------|------------------|--|
| | | | Six-tenths depth. | Top and bottom. | Top. | |
| | | <i>Feet.</i> | <i>Per cent.</i> | <i>Per cent.</i> | <i>Per cent.</i> | |
| 1 ----- | 12 | 4 to 10 | 94.3 | 106.7 | 92.2 | 67.8 |
| 2 ----- | 23 | 10 to 20 | 94.8 | 115.5 | 92.2 | 71.7 |
| 3 ----- | 25 | 20 + | 94.8 | 118.4 | 91.7 | 70.1 |

From the above table we find, first, that the depth of the thread of mean velocity ranges from about 68 to 72 per cent of the total depth, and that holding the meter at 0.6 depth gives a result about 5 per cent too large; second, that the coefficient for reducing top velocity to mean velocity is practically 92 per cent; third, that the coefficient for reducing the mean of the top and bottom velocities to mean velocity ranges from 106 to 118 per cent. The discordance here is due to the roughness of bed, which reduces the bottom velocity to a minimum.

Recapitulation and deductions from vertical velocity measurements at cable station, McCalls Ferry, Pa.

| Distance from initial point, in feet. | Depths, in feet. | Velocities, in feet per second. | Number of observations. | Coefficients for reducing to mean velocity. | | Depth of thread of mean velocity in per cent of total depth. |
|---------------------------------------|------------------|---------------------------------|-------------------------|---|------|--|
| | | | | Six-tenths depth. | Top. | |
| 150..... | 8 to 19 | 3.3 to 5.8 | 6 | 0.94 | 0.92 | 71 |
| 200..... | 9 to 14 | 4.0 to 6.8 | 4 | .95 | .93 | 76 |
| 300..... | 7 to 16 | 5.0 to 6.6 | 3 | 1.00 | .85 | 76 |
| 350..... | 6 to 16 | 4.2 to 8.1 | 4 | .96 | .91 | 80 |
| 500..... | 16 to 36 | 3.8 to 9.2 | 7 | .97 | .91 | 73 |
| 550..... | 16 to 35 | 4.3 to 9.7 | 7 | .99 | .88 | 63 |
| 600..... | 17 to 29 | 4.0 to 7.5 | 7 | .98 | .92 | 68 |
| 700..... | 4 to 24 | 4.7 to 7.0 | 8 | .96 | .89 | 73 |
| 850..... | 6 to 21 | 3.8 to 6.8 | 7 | .96 | .91 | 74 |
| 900..... | 7 to 25 | 1.4 to 7.2 | 8 | .96 | .90 | 74 |
| 950..... | 8 to 24 | 1.9 to 7.7 | 7 | .97 | .89 | 70 |
| Mean | 5 to 36 | 1.4 to 9.7 | 68 | .97 | .90 | 72 |

An examination of the above table shows, first, that the thread of mean velocity varies between about 63 and 80 per cent of the total depth, and that holding the meter at 0.6 depth gives a result between 0 and 6 per cent too large, with an average of about 3 per cent. Second, that the coefficient for reducing top to mean velocity ranges from about 85 to 93 per cent, with a mean of 90 per cent.

From July 1, 1901, to August 15, 1902, Mr. E. C. Murphy made a special study of the accuracy of current-meter work and the laws of flowing water, on Chenango and Susquehanna rivers, at Binghamton, N. Y. A detailed account of these studies can be found in Water-Supply and Irrigation Paper No. 95, from which paper the data used in the following are taken.

Figs. 4 and 5 show contours of the bed and position of the piers and abutments at the two measuring stations. The Chenango River




FIG. 4.—Contour of bottom of Chenango River at Court Street Bridge, Binghamton, N. Y.

station is at Court Street Bridge, Binghamton, where the observations were taken. The channel there is straight for about 1,000 feet on each side of the station, has a width of about 300 feet at low water and 340 feet at high water, and is broken by three piers. The bed is gravel and cobbles, with large rough stones around the piers. The bed is seen to be irregular in shape, as well as rough, but is permanent. The station is about 2,500 feet from Susquehanna River, and is subject to backwater at certain stages. Although the channel is

broken by three piers, the bridge projects over the piers on each side, so that the section of measurement is continuous.




FIG. 5.—Contours of Susquehanna River bed at Exchange Street Bridge, Binghamton, N. Y.

At the Exchange Street Bridge, where the observations on Susquehanna River were made, the channel is straight for about 500 feet

above and below the station, has a width of about 300 feet at low water and about 450 feet at high water, broken by 3 piers. The bed is of gravel and cobbles, with large irregular-shaped-rock filling around the piers. The velocity is rather high, especially at the higher stages. About 900 feet above the station is a dam whose height is about 6 feet.

The methods of work and computations at each station were as follows: The vertical velocity curve observations consisted in measuring velocity at from three to five points in each of the verticals, the lowest point being one-half foot above the bed, and the highest 1 foot below the surface. Each observation covered four periods of 25 seconds each. The velocities computed from these observations were plotted on section paper, and a smooth curve was drawn among these called the velocity curve. These points gave, as a rule, a well-defined curve, except near the bottom, where the bed was rough.

The curves for each vertical were grouped according to gage height, so that the range for each group was not greater than 1 foot. A mean vertical velocity curve was then drawn for each group. In making these mean curves the means of the velocity at the surface and at each two-tenths depth of the original curves were used. The resulting mean curves are shown in figs. 6, 7, 8, and 9, and the deductions from these are given in the tables headed "Vertical Velocity Measurements on Susquehanna River at Binghamton, N. Y.," and "Vertical Velocity Curves on Chenango River at Binghamton, N. Y."

In the tables, top velocity means velocity one-half foot below the surface, and bottom velocity means velocity one-half foot above the bed. Columns 9, 10, and 11 give the mean velocities in each vertical, as obtained by three methods, and columns 12, 13, and 14 the coefficients for reducing velocities obtained by either of these methods to mean velocity as obtained from the vertical velocity curves.




FIG. 6.—Mean vertical velocity curves, Chenango River, Binghamton, N. Y.




FIG. 7.—Mean vertical velocity curves, Chenango River, Binghamton, N. Y.




FIG. 8.—Mean vertical velocity curves, Susquehanna River, Exchange Street Bridge, Binghamton, N. Y.




FIG. 9.—Mean vertical velocity curves, Susquehanna River, upper side of Exchange Street Bridge, Binghamton, N. Y.

Vertical velocity measurements on Chenango River, Binghamton, N. Y.

| No. of curve. | Gage height. | Distance from initial point. | Depth. | Velocity in feet per second from the mean curves by following method: | | | | | | Coefficient for reduction to mean velocity. | | | Position of thread of mean velocity. | Character of bed. | |
|---------------|--------------|------------------------------|--------|---|------------------|------------|---------|--------------|-----------------|---|------------|-----------------|--------------------------------------|-------------------|-----------------------|
| | | | | Top. | M i d l e depth. | 0.6 depth. | Bottom. | V. V. curve. | $\frac{T+B}{2}$ | $\frac{T+2M+B}{4}$ | 0.6 depth. | $\frac{T+B}{2}$ | $\frac{T+2M+B}{4}$ | | In per cent of depth. |
| 1 | 5.7 | 100 | 1.7 | 0.83 | 0.68 | 0.62 | 0.50 | 0.64 | 0.67 | 0.67 | 1.03 | 0.96 | 0.96 | 56 | G |
| 2 | 5.7 | 100 | 2.2 | 1.59 | 1.42 | 1.38 | 1.18 | 1.38 | 1.39 | 1.40 | 1.00 | .99 | .99 | 60 | G |
| 3 | 6.2 | 100 | 2.9 | 2.26 | 2.15 | 2.02 | 1.77 | 2.05 | 2.02 | 2.08 | 1.01 | 1.02 | .98 | 60 | G |
| 4 | 6.9 | 100 | 3.4 | 2.77 | 2.55 | 2.42 | 1.97 | 2.43 | 2.37 | 2.46 | 1.00 | 1.03 | .99 | 60 | G |
| 5 | 8.3 | 100 | 4.8 | 3.41 | 3.31 | 3.22 | 2.43 | 3.11 | 2.94 | 3.11 | .97 | 1.06 | 1.00 | 67 | G |
| 1 | 5.3 | 140 | 3.9 | 1.45 | 1.35 | 1.27 | .83 | 1.22 | 1.14 | 1.25 | .96 | 1.07 | .98 | 66 | G |
| 2 | 5.7 | 140 | 4.3 | 2.20 | 2.05 | 1.95 | 1.42 | 1.92 | 1.81 | 1.93 | .98 | 1.06 | .99 | 61 | G |
| 3 | 6.2 | 140 | 5.0 | 2.80 | 2.65 | 2.54 | 1.80 | 2.46 | 2.30 | 2.47 | .97 | 1.07 | 1.00 | 61 | G |
| 4 | 6.9 | 140 | 5.5 | 3.35 | 3.20 | 3.10 | 2.43 | 3.03 | 2.89 | 3.05 | .98 | 1.05 | .99 | 65 | G |
| 5 | 8.3 | 140 | 6.9 | 3.90 | 3.75 | 3.73 | 2.67 | 3.53 | 3.29 | 3.52 | .95 | 1.07 | 1.00 | 66 | G |
| 1 | 5.3 | 190 | 4.5 | 1.08 | 1.00 | .97 | .74 | .94 | .91 | .95 | .97 | 1.03 | .99 | 61 | G |
| 2 | 5.7 | 190 | 4.9 | 1.70 | 1.60 | 1.50 | 1.12 | 1.50 | 1.46 | 1.53 | 1.00 | 1.03 | .98 | 60 | G |
| 3 | 6.2 | 190 | 5.4 | 2.26 | 2.10 | 2.04 | 1.40 | 2.00 | 1.83 | 1.96 | .98 | 1.09 | 1.02 | 63 | G |
| 4 | 6.9 | 190 | 6.1 | 2.80 | 2.67 | 2.45 | 1.63 | 2.44 | 2.22 | 2.44 | 1.00 | 1.10 | 1.00 | 60 | G |
| 5 | 8.3 | 190 | 7.4 | 3.54 | 3.35 | 3.20 | 2.02 | 3.14 | 2.78 | 3.06 | .98 | 1.13 | 1.03 | 65 | G |
| 1 | 5.3 | 210 | 5.3 | 1.00 | .95 | .90 | .66 | .89 | .83 | .89 | .99 | 1.07 | 1.00 | 60 | G |
| 2 | 5.7 | 210 | 5.7 | 1.59 | 1.52 | 1.49 | 1.05 | 1.43 | 1.32 | 1.42 | .96 | 1.08 | 1.01 | 68 | G |
| 3 | 6.2 | 210 | 6.2 | 2.26 | 2.15 | 2.05 | 1.53 | 2.02 | 1.90 | 2.02 | .99 | 1.06 | 1.00 | 63 | G |
| 4 | 6.9 | 210 | 6.9 | 2.80 | 2.70 | 2.65 | 1.80 | 2.53 | 2.30 | 2.50 | .96 | 1.10 | 1.01 | 68 | G |
| 5 | 8.3 | 210 | 8.3 | 3.44 | 3.28 | 3.15 | 2.05 | 3.06 | 2.75 | 3.01 | .97 | 1.11 | 1.02 | 64 | G |
| 1 | 5.3 | 120 | 3.4 | 1.26 | 1.13 | 1.05 | .50 | .98 | .88 | 1.01 | .93 | 1.11 | .98 | 66 | G |
| 2 | 5.7 | 120 | 3.8 | 1.90 | 1.80 | 1.62 | .93 | 1.65 | 1.22 | 1.61 | 1.02 | 1.03 | 1.03 | 59 | G |
| 3 | 6.2 | 120 | 4.3 | 2.53 | 2.30 | 2.09 | 1.37 | 2.10 | 1.95 | 2.12 | 1.00 | 1.08 | .99 | 60 | G |
| 4 | 6.9 | 120 | 5.0 | 3.06 | 2.77 | 2.62 | 1.70 | 2.60 | 2.38 | 2.58 | .99 | 1.09 | 1.01 | 62 | G |
| 1 | 5.3 | 275 | 3.5 | .80 | .73 | .70 | .58 | .70 | .69 | .71 | 1.00 | 1.01 | .99 | 60 | B |
| 2 | 5.7 | 275 | 4.2 | 1.41 | 1.29 | 1.23 | .89 | 1.19 | 1.15 | 1.22 | .97 | 1.04 | .99 | 65 | B |
| 3 | 6.2 | 275 | 4.4 | 1.97 | 1.83 | 1.76 | 1.29 | 1.76 | 1.63 | 1.78 | 1.00 | 1.08 | .99 | 60 | B |
| 4 | 6.9 | 275 | 5.4 | 2.58 | 2.52 | 2.44 | 1.89 | 2.38 | 2.24 | 2.38 | .97 | 1.06 | 1.00 | 67 | B |
| 5 | 8.3 | 275 | 6.9 | 3.40 | 3.22 | 3.13 | 2.22 | 3.06 | 2.81 | 3.02 | .98 | 1.09 | 1.01 | 65 | B |
| 1 | 5.3 | 295 | 2.3 | .58 | .53 | .49 | .34 | .46 | .46 | .48 | .94 | 1.00 | .96 | 65 | G |
| 2 | 5.7 | 295 | 2.9 | .98 | .92 | .86 | .60 | .87 | .79 | .86 | 1.01 | 1.10 | 1.01 | 55 | G |
| 3 | 6.2 | 295 | 3.7 | 1.75 | 1.59 | 1.52 | 1.20 | 1.52 | 1.48 | 1.53 | 1.00 | 1.03 | .99 | 60 | G |
| 4 | 6.9 | 295 | 4.4 | 2.30 | 2.06 | 1.95 | 1.47 | 1.97 | 1.89 | 1.97 | 1.01 | 1.05 | 1.00 | 59 | G |
| 5 | 8.3 | 295 | 5.8 | 2.98 | 2.60 | 2.47 | 1.75 | 2.50 | 2.37 | 2.48 | 1.01 | 1.06 | 1.01 | 59 | G |
| Mean | | | | | | | | | | | .984 | 1.041 | .996 | 65.6 | |

NOTE.—“No. of curve” refers to figs. 6 and 7.

Vertical velocity measurements on Susquehanna River, Binghamton, N. Y.

| No. of curve. | Gage height. | Distance from initial point. | Velocity in feet per second from the mean curves by following method— | | | | | | Coefficient for reduction to mean velocity. | | | Position of thread of mean velocity. | Character of bed. | | |
|---------------|--------------|------------------------------|---|---------------|------------|---------|--------------|-------------------|---|------------|-------------------|--------------------------------------|-------------------|-----------------------|---|
| | | | Top. | Middle depth. | 0.6 depth. | Bottom. | V. V. curve. | $T + \frac{B}{2}$ | $T + \frac{2M + B}{4}$ | 0.6 depth. | $T + \frac{B}{2}$ | $T + \frac{2M + B}{4}$ | | In per cent of depth. | |
| 1 | -0.85 | 100 | 2.5 | 0.94 | 0.82 | 0.81 | 0.66 | 0.80 | 0.80 | 0.81 | 0.99 | 1.00 | 0.99 | 61 | G |
| 2 | +.10 | 100 | 3.5 | 1.85 | 1.65 | 1.52 | 1.27 | 1.58 | 1.56 | 1.60 | 1.04 | 1.01 | 1.03 | 57 | G |
| 4 | +.73 | 100 | 4.1 | 2.42 | 2.20 | 1.99 | 1.42 | 2.03 | 1.92 | 2.05 | 1.02 | 1.06 | .99 | 56 | G |
| 5 | +2.00 | 100 | 5.4 | 3.20 | 2.87 | 2.74 | 1.90 | 2.71 | 2.55 | 2.71 | .99 | 1.06 | .99 | 61 | G |
| 6 | +2.50 | 100 | 5.9 | 3.84 | 3.50 | 3.35 | 2.23 | 3.26 | 3.02 | 3.27 | .97 | 1.08 | 1.00 | 61 | G |
| 7 | +3.30 | 100 | 6.7 | 4.22 | 3.87 | 3.72 | 2.35 | 3.58 | 3.29 | 3.58 | .96 | 1.09 | 1.00 | 64 | G |
| 1 | -.30 | 125 | 4.0 | 1.42 | 1.32 | 1.26 | 1.05 | 1.27 | 1.24 | 1.28 | 1.01 | 1.03 | .99 | 56 | G |
| 2 | +.10 | 125 | 4.4 | 2.29 | 2.10 | 2.03 | 1.57 | 2.03 | 1.93 | 2.02 | 1.00 | 1.05 | 1.00 | 60 | G |
| 4 | 0.73 | 125 | 5.0 | 2.92 | 2.70 | 2.59 | 1.90 | 2.57 | 1.41 | 2.56 | .99 | 1.11 | 1.00 | 61 | G |
| 5 | 2.00 | 125 | 6.3 | 3.82 | 3.74 | 2.63 | 2.55 | 3.48 | 3.19 | 3.46 | .96 | 1.09 | 1.01 | 63 | G |
| 6 | 2.50 | 125 | 6.8 | 4.58 | 4.40 | 4.20 | 2.95 | 4.10 | 3.77 | 4.08 | .98 | 1.09 | 1.00 | 65 | G |
| 7 | 3.30 | 125 | 7.6 | 5.29 | 5.15 | 5.04 | 3.60 | 4.86 | 4.45 | 4.80 | .96 | 1.09 | 1.01 | 65 | G |
| 2 | -.10 | 310 | 4.7 | 2.80 | 2.06 | 1.95 | 1.48 | 1.98 | 1.89 | 1.97 | 1.01 | 1.05 | 1.00 | 60 | G |
| 4 | .73 | 310 | 5.5 | 2.85 | 2.62 | 2.53 | 2.00 | 2.53 | 2.42 | 2.52 | 1.00 | 1.05 | 1.00 | 60 | G |
| 5 | +2.00 | 310 | 6.8 | 3.52 | 3.32 | 3.15 | 2.51 | 3.18 | 3.02 | 3.17 | 1.01 | 1.05 | 1.00 | 60 | G |
| 6 | 2.50 | 310 | 7.3 | 3.63 | 3.57 | 3.43 | 2.65 | 3.37 | 3.14 | 3.35 | .98 | 1.07 | 1.01 | 66 | G |
| 7 | 3.30 | 310 | 8.1 | 4.30 | 4.05 | 3.97 | 3.13 | 3.93 | 3.72 | 3.88 | .99 | 1.06 | 1.02 | 63 | G |
| 1 | -.60 | 170 | 3.6 | 1.20 | 1.15 | 1.10 | .85 | 1.08 | 1.02 | 1.09 | .98 | 1.06 | .99 | 61 | B |
| 2 | +.10 | 170 | 4.6 | 1.65 | 1.40 | 1.30 | .90 | 1.34 | 1.27 | 1.34 | 1.03 | 1.06 | 1.00 | 56 | B |
| 4 | +.73 | 170 | 4.2 | 2.24 | 1.75 | 1.57 | .85 | 1.67 | 1.55 | 1.65 | 1.06 | 1.08 | 1.01 | 55 | B |
| 5 | 2.00 | 170 | 6.5 | 3.02 | 2.53 | 2.40 | 1.20 | 2.36 | 2.21 | 2.34 | .98 | 1.12 | 1.01 | 62 | B |
| 6 | 2.50 | 170 | 7.0 | 3.98 | 3.32 | 3.07 | 1.47 | 3.08 | 2.73 | 3.02 | .90 | 1.13 | 1.02 | 60 | B |
| 7 | 3.30 | 170 | 7.5 | 4.45 | 4.12 | 3.90 | 2.35 | 3.79 | 3.40 | 3.76 | .97 | 1.11 | 1.01 | 64 | B |
| 3 | +.10 | 245 | 5.6 | 2.30 | 2.23 | 2.20 | 1.80 | 2.16 | 2.05 | 2.14 | .98 | 1.05 | 1.01 | 66 | G |
| 4 | +.30 | 245 | 5.8 | 2.76 | 2.65 | 2.62 | 2.25 | 2.60 | 2.50 | 2.58 | 1.00 | 1.04 | 1.01 | 60 | G |
| 5 | +.70 | 245 | 6.0 | 2.94 | 2.80 | 2.75 | 2.45 | 2.78 | 2.70 | 2.75 | 1.01 | 1.03 | 1.01 | 58 | G |
| 6 | 2.00 | 245 | 7.5 | 3.96 | 3.95 | 3.78 | 2.20 | 3.59 | 3.08 | 3.51 | .95 | 1.17 | 1.02 | 68 | G |
| 7 | +0.10 | 285 | 5.1 | 2.45 | 2.26 | 2.19 | 1.69 | 2.16 | 2.07 | 2.16 | .99 | 1.04 | 1.00 | 61 | R |
| 4 | .73 | 285 | 5.7 | 3.30 | 3.05 | 3.00 | 2.32 | 2.95 | 2.81 | 2.93 | .98 | 1.05 | 1.01 | 63 | R |
| 5 | 2.00 | 285 | 7.0 | 3.93 | 3.65 | 3.55 | 2.88 | 3.55 | 3.40 | 3.53 | 1.00 | 1.04 | 1.01 | 60 | R |
| 6 | 2.50 | 285 | 6.8 | 4.25 | 4.05 | 3.95 | 2.92 | 3.86 | 3.59 | 3.82 | .98 | 1.08 | 1.01 | 63 | R |
| 2 | +.10 | 335 | 4.1 | 2.20 | 1.95 | 1.85 | 1.45 | 1.88 | 1.83 | 1.89 | 1.01 | 1.03 | 1.00 | 59 | G |
| 4 | .73 | 335 | 4.7 | 2.85 | 2.61 | 2.50 | 2.01 | 2.52 | 2.43 | 2.52 | 1.01 | 1.04 | 1.00 | 58 | G |
| 5 | 2.00 | 335 | 6.0 | 3.30 | 3.20 | 3.10 | 2.33 | 3.03 | 2.82 | 3.01 | .98 | 1.08 | 1.01 | 63 | G |
| 6 | 2.50 | 335 | 6.5 | 3.18 | 3.05 | 2.87 | 2.12 | 2.86 | 2.65 | 2.85 | 1.00 | 1.08 | 1.00 | 60 | G |
| 7 | 3.30 | 335 | 6.8 | 3.55 | 3.44 | 3.35 | 2.15 | 3.18 | 2.85 | 3.15 | .95 | 1.11 | 1.01 | 66 | G |
| Mean | ----- | ----- | ----- | ----- | ----- | ----- | ----- | ----- | ----- | ----- | .992 | 1.063 | 1.005 | 61.2 | |

NOTE.—"No. of curve" in column 1 refers to figs. 8 and 9.

From the curves and table for Chenango River it is seen that the value of the coefficient for reducing velocity obtained by the six-tenths-depth method varies from 0.93 to 1.03, the mean being 0.984. The coefficient for reducing velocity obtained by the top and bottom method to that obtained from the vertical velocity curve varies from 0.96 to 1.13, the mean being 1.041, the error of this method increasing as the depth increases. The coefficient for reducing velocity obtained by the third method to mean velocity obtained from the vertical velocity curve varies from 0.96 to 1.03, the mean being 0.996.

From the curves and table for Susquehanna River it is seen that the coefficient for reducing velocity at six-tenths depth to mean velocity obtained from vertical velocity curves varies from 0.95 to 1.06, the mean being 0.992. The coefficient for reducing velocity by the top and bottom method varies from 1 to 1.17, the mean being 1.068. The coefficient for reducing velocity obtained by the third method to mean velocity varies from 0.99 to 1.03, the mean being 1.005.

It is seen from the result in these tables: (1) That the third method of obtaining mean velocity by observing velocity one-half foot above the bed and one-half foot beneath the surface and at mid depth gives results agreeing very closely with that obtained from vertical velocity curves if the bed is smooth; (2) that results obtained by the top and bottom method agree quite closely with those obtained from vertical velocity curves if the depth is small and bed smooth, and that the error by this method increases as the depth increases; (3) that velocities obtained by the six-tenths-depth method are somewhat larger than those obtained from vertical velocity curves if the average depth is greater than about 4 feet.

The series of vertical velocity measurements made at Harrisburg were taken on November 2, 1903. They consisted of 20 measurements at depths ranging from 3 to 8 feet and mean velocity varying from 1.5 to 2.6 feet per second. The results of these measurements are shown in the following table and by the curves on Pl. XXVI.

*Vertical velocity measurements made on Susquehanna River at Harrisburg, Pa.,
November 2, 1903.*

| Distance from initial point, in feet. | Depth at measuring point, in feet. | Velocity in feet per second by fol- lowing methods. | | | | | Coefficients for reducing to mean velocity. | | | | Depth of thread of mean velocity. | |
|--|---------------------------------------|--|-------------|----------------------|--------------|-------|--|----------------------|--------------|-------|--|--------------------------|
| | | Vertical veloc- ity. | Six-tenths. | Top and bot- tom. | Integration. | Top. | Six-tenths. | Top and bot- tom. | Integration. | Top. | In feet. | In per cent of depth. |
| 140 | 3.2 | 2.00 | 1.96 | ----- | 1.92 | ----- | 1.02 | ----- | 1.04 | ----- | 2.0 | 62 |
| 120 | 4.3 | 1.52 | 1.79 | 1.83 | 1.74 | 1.96 | .85 | 0.83 | .87 | 0.78 | 2.8 | 65 |
| 220 | 4.3 | 1.95 | 1.98 | ----- | 2.08 | ----- | .99 | ----- | .94 | ----- | 2.6 | 60 |
| 200 | 4.7 | 1.85 | 1.67 | ----- | 1.93 | ----- | 1.11 | ----- | .96 | ----- | 2.6 | 55 |
| 160 | 4.8 | 1.82 | 1.87 | ----- | 1.74 | ----- | .97 | ----- | 1.05 | ----- | 3.3 | 69 |
| 180 | 5.0 | 1.67 | 1.70 | ----- | 1.74 | ----- | .98 | ----- | .96 | ----- | 2.9 | 58 |
| 260 | 5.2 | 2.02 | 2.05 | 1.68 | 2.01 | 2.37 | .99 | 1.21 | 1.00 | .85 | 3.6 | 69 |
| 320 | 5.4 | 2.55 | 2.88 | 2.34 | 2.64 | 2.92 | .89 | 1.09 | .97 | .87 | 3.9 | 72 |
| 280 | 5.8 | 2.15 | 1.73 | 2.00 | 2.06 | 2.67 | 1.24 | 1.07 | 1.04 | .81 | 3.6 | 62 |
| 340 | 5.9 | 2.57 | 2.62 | 2.72 | 2.80 | 2.83 | .98 | .95 | .92 | .91 | 3.5 | 59 |
| 380 | 6.0 | 2.63 | 2.35 | 2.81 | 2.62 | 3.02 | 1.12 | .94 | 1.00 | .87 | 3.9 | 65 |
| 300 | 6.0 | 2.44 | 2.48 | 2.57 | 2.37 | 2.79 | .98 | .95 | 1.03 | .87 | 3.7 | 62 |
| 360 | 6.1 | 2.71 | 2.85 | 2.75 | 2.72 | 2.99 | .95 | .99 | 1.00 | .91 | 3.7 | 61 |
| 560 | 7.6 | 2.16 | 2.28 | 2.14 | 2.31 | 2.63 | .95 | 1.01 | .94 | .82 | 4.6 | 61 |
| 590 | 7.7 | 2.40 | 2.40 | 2.34 | 2.41 | 2.92 | 1.00 | 1.02 | 1.00 | .82 | 4.3 | 56 |
| 540 | 7.9 | 2.18 | 2.09 | 2.23 | 2.29 | 2.87 | 1.04 | .98 | .95 | .76 | 4.4 | 56 |
| 520 | 8.0 | 2.57 | 2.73 | 2.66 | 2.52 | 3.08 | .94 | .97 | 1.02 | .83 | 5.2 | 65 |
| 585 | 8.0 | 2.48 | 2.28 | 2.42 | 2.62 | 2.85 | 1.09 | 1.02 | .95 | .87 | 4.6 | 58 |
| 580 | 8.0 | 2.48 | 2.33 | 2.32 | 2.46 | 2.80 | 1.06 | 1.07 | 1.01 | .89 | 4.1 | 51 |
| 580 | 8.0 | 2.49 | 2.49 | ----- | 2.48 | ----- | 1.00 | ----- | 1.00 | ----- | 5.5 | 60 |
| Mean ----- | | | | | | | 1.01 | 1.08 | .98 | .85 | ----- | 61 |

From these observations at Harrisburg we find, first, that the depth of the thread of mean velocity ranges from 51 to 72 per cent of the total depth and that the mean is 61 per cent. The error, therefore, introduced by holding the meter at 0.6 depth is only about 1 per cent. Second, the mean coefficient found for reducing top and bottom velocities to mean velocities is 1.08. Third, the coefficient for reducing velocities by the integration method to mean velocity is 0.98. Fourth, the coefficient for reducing top velocity to mean velocity is 0.85.

An interstudy of these various series of vertical velocity measurements shows that at these stations for depths up to about 10 feet and velocities not over 5 feet per second the depth of the thread of mean velocity is practically 60 per cent of the total depth, while for depths over 10 feet and velocities over 5 feet per second the depth of the thread of mean velocity becomes greater, averaging about 70 per cent of the total depth.

The coefficient for reducing top velocities to mean velocity for depths under 10 feet and velocities under 5 feet is about 0.85, while for greater depths and velocities it increases to a maximum of about 0.92.

The top and bottom velocities invariably give too small results, depending upon the roughness of the bed.


Furthermore, it is found that although the depth of the thread of mean velocity may vary between 50 and 80 per cent of the total depth, the error caused by holding the meter at 60 per cent of the depth does not exceed 5 or 6 per cent, which is within the limits of the accuracy one can expect in stream-measurement work.

The following table gives a summary of the results of the various series of vertical velocity measurements in the Susquehanna drainage:

Summary of results of vertical velocity measurements.

| Place. | Number of curves. | Range of depths. | Range of velocities. | Depth of thread of mean velocity in per cent of depth. | Coefficient for reducing to mean velocity. | | | | |
|--------------------------------------|-------------------|--------------------------|----------------------------------|--|--|-----------------|-------|--------------------|--------------|
| | | | | | Six-tenths. | Top and bottom. | Top. | $\frac{T+2M+B}{4}$ | Integration. |
| McCalls Ferry, Duncan Run | 73 | <i>Feet.</i> 3.3-30.0 | <i>Ft. per sec.</i> 1.21-5.80 | 68 | 0.94 | 1.07 | 0.92 | ----- | ----- |
| McCalls Ferry, cable station.... | 68 | 5.0-36.0 | 1.40-9.70 | 72 | .97 | ----- | .90 | ----- | ----- |
| Binghamton (Susquehanna River) | 36 | 2.5-8.1 | .80-4.86 | 61 | .99 | 1.07 | ----- | 1.00 | ----- |
| Binghamton (Chenango River) .. | 34 | 1.7-8.3 | .46-3.38 | 66 | .98 | 1.04 | ----- | 1.00 | ----- |
| Harrisburg (Susquehanna River) | 20 | 3.2-8.0 | 1.52-2.71 | 61 | 1.01 | 1.08 | .85 | ----- | 0.98 |


NOTE.—In the above table erratic observations were not used.




Station bottom

UF


at 1 inch=5 feet depth.






VERTICAL VELOCITY CURVES OF SUSQUEHANNA RIVER AT DUNCANS RUN, NEAR MCCALLS FERRY, PA.

Note: Curves are referred to the vertical lines nearest their tops. Station numbers are at the foot of the curves. Horizontal lines at the foot of the curves are at the river bottom. The curves terminate at their tops with the surface of the water. Horizontal scale, 1 inch=2 feet per second. Vertical scale, 1 inch=5 feet depth.




VERTICAL VELOCITY CURVES OF SUSQUEHANNA RIVER AT DUNCANS RUN, NEAR MCCALLS FERRY, PA.

Note: Curves are referred to the vertical lines nearest their tops. Station numbers are at the foot of the curves. Horizontal lines at the foot of the curves are at the river bottom. The curves terminate at their tops with the surface of the water. Horizontal scale, 1 inch = 2 feet per second. Vertical scale, 1 inch = 5 feet depth.




VERTICAL VELOCITY CURVES OF SUSQUEHANNA RIVER AT CABLE STATION NEAR McCALL'S FERRY, PA.

Note: Curves are referred to the vertical lines nearest their tops. Station numbers are at the foot of the curves. Horizontal lines at the foot of the curves are at the river bottom. The curves terminate at their tops with the surface of the water. Horizontal scale, 1 inch=2 feet per second. Vertical scale, 1 inch=5 feet depth.




VERTICAL VELOCITY CURVES OF SUSQUEHANNA RIVER AT CABLE STATION NEAR McCALL'S FERRY, PA.


Note: Curves are referred to the vertical lines nearest their tops. Station numbers are at the foot of the curves. Horizontal lines at the foot of the curves are at the river bottom. The curves terminate at their tops with the surface of the water. Horizontal scale, 1 inch=3 feet per second. Vertical scale, 1 inch=5 feet depth.



VERTICAL VELOCITY CURVES OF SUSQUEHANNA RIVER AT CABLE STATION NEAR McCALLS FERRY, PA.

Note: Curves are referred to the vertical lines nearest their tops. Station numbers are at the foot of the curves. Horizontal lines at the foot of the curves are at the river bottom. Vertical scale, 1 inch=5 feet depth. The curves terminate at their tops with the surface of the water. Horizontal scale, 1 inch=2 feet per second.





VERTICAL VELOCITY CURVES OF SUSQUEHANNA RIVER AT CABLE STATION NEAR MCCALLS FERRY, PA.

Note. Curves are referred to the vertical lines nearest their tops. Station numbers are at the foot of the curves. Horizontal lines at the foot of the curves are at the river bottom. The curves terminate at their tops with the surface of the water. Horizontal scale, 1 inch=2 feet per second. Vertical scale, 1 inch=5 feet depth.

WATER POWER.

GENERAL DISCUSSION.

In marked contrast to the New England streams, the power resources of the Susquehanna River basin, one of the largest draining into the Atlantic Ocean, are little developed.

As shown by the tables on pages 204, 205, taken from schedules furnished by the manufacturers' division of the Twelfth Census, 1900, a maximum of 10,375 horsepower is utilized in the portion of the drainage area in New York and 38,812 horsepower in Pennsylvania. This makes a total of less than 50,000 horsepower—an amount which, according to the estimates of various engineers, can be developed at any of several points on the lower river. By far the greater part of this is developed intermittently upon the smaller tributary streams by mills of from 20 to 50 horsepower. Pls. XXVIII and XXIX show the profile of Susquehanna River and its principal tributaries. These profiles are made up from data obtained from the army engineers, the report of the Tenth Census, Vol. XVI, and from levels furnished by private engineers, as shown in the tables on pages 207–210.

Over the greater portion of the river above Harrisburg the fall per mile is from 1 to 2 feet, while below Harrisburg the fall increases to between 5 and 8 feet, and it is here that the greatest opportunities for large power developments exist. The only point on the entire river at which this fall is now being utilized to any great extent is at York Haven, where a paper mill uses 2,000 horsepower, and a large electric-power plant in course of construction will soon use 10,000 or 20,000 more.

Mr. W. F. Bay Stewart, of York, Pa., describes the York Haven Power Plant, as follows:

The York Haven Water and Power Company's plant is located at the foot of the Conewago Falls on the Susquehanna River, ten miles from York and sixteen miles below Harrisburg. The natural fall at this point is about 23 feet in about three-quarters of a mile. The method of utilizing this fall is by building a wing dam out into the river above the falls and turning the greater portion of the flow by means of this wing dam within a retaining wall 3,500 feet long, constructed of masonry. This wall is built along the river shore just above low water. The wall is 16 feet high at the upper end and 32 feet high at the lower end, it is 6 feet wide on top all the way, and is built vertical on the inside and with a batter on the outside toward the river. The width of the foundation increases with the height of the wall, so that at the lower end it is about 22 to 24 feet in width. It is built of rubble masonry laid in cement.

The power house begins at the lower end of this wall, and is about 50 feet wide and 480 feet long. It contains twenty full-sized chambers and one smaller chamber. The design is to install in each of these chambers two 600-horsepower water wheels, and to connect the shafts of these water wheels by means of beveled gears at their top with the shaft of a 750-kilowatt generator, which runs horizontally and which is intended to develop at least 1,000 horsepower. To

equip the plant will require forty 600-horsepower water wheels and twenty generators. In addition to this, in the smaller chamber there will be installed two 300-horsepower water wheels which drive two exciters, duplicates, either one of which is capable of exciting the whole plant. This building up to a height of 34 feet is of the same class of masonry as the retaining wall, and these chambers for water wheels are practically openings in an otherwise solid mass of masonry 480 feet long by 50 feet wide and 34 feet high. On top of this foundation is a brick building, one portion of which is two story and the remaining, one story. In the two-story part the switch boards and controlling devices are located. At the lower end of this building and at right angles to it another wall is constructed the same height as the high part of the retaining wall and about 170 feet long. This wall then extends in an irregular form around the buildings of the York Haven Paper Company's plant to the main land. On the angle of this wall is constructed a transformer house sufficient to receive the machinery for transforming all the current generated in the generating plant. The current is developed at 2,400 volts and stepped up to 24,000 volts in this transformer house and is transmitted at this voltage to points of consumption. The company has built a transmission line capable of transmitting 6,000 horsepower from York Haven to York, where another transformer house has been built capable of transforming 24,000 volt current down to 2,200 volts, at which voltage it will be delivered to customers. It is the purpose of the company to build a like transmission line to Harrisburg, with a like transformer house at that city, and, possibly, also to Lancaster, Pa., which is about 20 miles from the plant. The machinery installed and to be installed in this plant is capable of an overload of 25 per cent, thus increasing the capacity to 25,000 horsepower, and of course it could be more largely increased by raising the head.

Between York Haven and the mouth of the river there is a fall of about 270 feet. The mean annual discharge at York Haven from 1891 to 1904, inclusive, is about 40,000 second-feet. By applying the rule that 11 second-feet of water falling 1 foot equals a horsepower with 80 per cent efficiency it is seen that between York Haven and the outlet of the river there about one million horsepower running to waste, though several neighboring cities would afford an eager market for all that could be developed. There are, of course, several obstacles in the way of development, perhaps the most serious of which would be the occasional ice freshets and gorges, making substantial protective works necessary and reducing or obliterating the available head. Between the narrows above McCalls Ferry and Port Deposit, however, the ice passes down through either a deep or a broad channel, with no tendency to gorge and seldom doing damage. At present there are several individuals and companies who are promoting power schemes on the lower river, and a large plant at York Haven has recently been completed.

Mr. H. F. Labelle, who spent several years in the study of the power possibilities of the lower Susquehanna, states the following in regard to the power developments on the lower Susquehanna River:

The bed of the stream from Columbia to Port Deposit is for the most part very wide, varying from 3,500 feet to about $2\frac{1}{2}$ miles opposite Washingtonboro. There are, however, a few "narrows," as at Conowingo and McCalls Ferry. The stream being wide and rapid, it naturally follows that at low water it is very shallow and can be forded in many places. The water in the narrows is, how-

ever, very deep. At Conowingo Bridge, on the west side, there is a narrow channel over one-half mile long in which depths of 75 feet have been found. At McCalls Ferry, where the river narrows to about 300 feet, the depth is also considerable. These deep channels are also met here and there on the wider parts of the river—namely, between Turkey Hill and Star Rock station, on the east side, where depths of over 90 feet have been found.

The Susquehanna and Tide-water canal skirts the west side of the river from Wrightsville to Havre de Grace. Before the building of the Philadelphia, Baltimore and Washington Railroad and the Frederick Branch of the Pennsylvania Railroad this canal had a brisk carrying trade, chiefly in coal from the anthracite regions. The flood of June, 1889, wrecked the canal in many places. The cost of repairs was very high, and the canal continued in operation until May, 1894, when another flood caused considerable damage to the property. Since that time it has been practically out of operation. After changing hands several times, it was finally bought by the Susquehanna Electric Power Company, of Baltimore. This company is about to begin the construction of their first plant, below Peach Bottom. The Frederick Branch of the Pennsylvania Railroad runs on the west side of the river from Columbia to Perryville, where it connects with the main line of the Philadelphia, Baltimore and Washington Railroad.

The minimum discharge of the river at Shures Landing can be taken safely at 6,000 second-feet. This would give a minimum gross power to be developed from Columbia to tide water of 153,000 horsepower. The proposed plants, however, have been designed for a supply of 10,000 second-feet, which is available most of the time.

This would give a possible power of about 255,000 horsepower. This available power can almost be totally utilized, and the writer knows of projects on the river aggregating over 185,000 horsepower.

The power available on the Susquehanna has at its disposal a much better market than any other in the United States, not barring Niagara Falls. Baltimore is a little more than 40 miles from the half of the minimum power and Philadelphia is within 65 miles of the two lower plants, taking on the way Wilmington, with its heavy power consumption.

The upper plants are within easy reach of Lancaster, York, Harrisburg, Reading, and other manufacturing centers. Eastern Pennsylvania, with its great manufacturing activity, will surely avail itself of whatever amount of power can be developed on the river, and towns like Havre de Grace (10 miles below Shures Landing), located on two of the large trunk lines between the North and the South and also at the head of Chesapeake Bay, can be transformed by cheap power into manufacturing centers of no mean importance.

There is no doubt that with the help of steam plants—and there are many already established in the larger cities of the district—400,000 horsepower could be developed on the river below Columbia and find a ready and remunerative market.

Starting from tide water the principal plants projected are as follows: (1) Conowingo plant, 25,000 to 35,000 horsepower; (2) the Peach Bottom plant, 40,000 horsepower; (3) the Fites-Eddy plant, 40,000 horsepower; (4) the York Furnace, McCalls Ferry plant, 45,000 horsepower; (5) the Turkey Hill plant, 30,000 horsepower.

There is about 9 feet fall available below the Conowingo works, but it is believed that the conditions would not make it advisable to develop any power at that point.

At Conowingo the power house is located a short distance above Shures Landing. The building extends for a distance of about 500 feet, square across the stream from the west shore. The original development is to be of 25,000 horsepower, but provision is made in the power house for the development of 10,000 additional horsepower. From the river end of the power house the dam extends upstream


a distance of 1,200 feet, the crest being at an elevation of 50.5 feet. The dam then turns toward the foot of McDowells Island, 800 feet away; thence it follows the center of McDowells Island for 3,600 feet to its head, and thence it goes diagonally to the east shore, a distance of 2,600 feet. The last 7,000 feet have their crest at an elevation of 43 feet, except 200 feet close to the high part of the dam, where a spillway for ice has been located, its crest being at an elevation of 41 feet. A needle dam will close this spillway at ordinary stages. The river above McDowells Island is over 3,000 feet wide and the dam forms a pool over 4 miles long. It has a sufficient rollway to pass the highest known floods without endangering the riparian property above it. The high part of the dam and the McDowells Island section are 8 feet wide on the crest. The remainder of the dam has a crest 12 feet wide. The whole dam will be of rubble, with ashlar facing on the downstream side. Borings have shown that a continuous rock bottom will be obtained on McDowells Island at an average depth of 11 feet. The generating plant will probably be divided into 1,250 kilowatt units. The turbines will be vertical, with draft tube. One pair of turbines will serve each dynamo, the connection between turbines and horizontal shaft of dynamo being made by two crown wheels engaging bevel gears on this shaft.

The working head will be 34 feet at low water and 30 feet at ordinary stages.


The Turkey Hill plant is located between Turkey Hill and Safe Harbor, on the east side of the river. At Turkey Hill the river is about 1 mile wide, and a low diverting dam about 5 feet high will form a large pond above it. This pond extends to Columbia, a distance of 5 miles, and its width varies between 1 and $2\frac{1}{2}$ miles. The head and tail race canals are formed by an embankment paralleling the railroad track and forming a canal varying from 190 to 250 feet in width at the bottom. This embankment is about 3 miles long. It is composed of a river wall in cement battering $1\frac{1}{2}$ inch per foot on the river side and $2\frac{1}{2}$ inches on the back. Next to this is the loose rock embankment proper, 40 wide on top and sloping 1 to 1 on the power-canal side. This mode of construction will meet the impact of the ice and prevent it from overtopping the embankment. At the main dam, and close to the head works, there will be a raft chute and a raft channel leading from it and close to the embankment on the river side. The average working head will be 30 feet, and the power house will be located at Star Rock.

DURATION OF THE STAGES OF THE LOWER SUSQUEHANNA.

In order to show the mean conditions and the duration of flow which have existed on the lower Susquehanna River during the last twelve years—1891 to 1902, inclusive—the curves in Pl. XXVII have been constructed. The dotted-line curve is plotted with gage heights as ordinates, and with the number of days during the mean year on which the stage of the river was less than the given gage height as abscissæ. The full-line curve shows the number of days during the mean year when the discharge was below any given amount. In the preparation of these curves the Harrisburg gage heights for each year, as shown on pages 108 to 114, were tabulated according to magnitude. The number of days during the year when the water stood at each gage height were then tabulated, and from these the number of days during the year when the river was lower than the various gage heights was determined. The curves were constructed from the mean of these yearly tables, and in the case of the full-line curve the discharges as given in the rating table on page 115 were substituted for the gage heights.




SBURG FOR 1891-1902, INCLUSIVE.



VERTICAL VELOCITY CURVES OF SUSQUEHANNA RIVER AT HARRISBURG PA.

Note: Curves are referred to the vertical lines nearest their tops. Station numbers are at the foot of the curves. Horizontal lines at the foot of the curves are at the river bottom. The curves terminate at their tops with the surface of the water.



CURVES SHOWING MEAN DURATION OF THE VARIOUS STAGES AND DISCHARGES OF SUSQUEHANNA RIVER AT HARRISBURG FOR 1891-1902, INCLUSIVE.

To use the two curves in conjunction with each other, enter the diagram with a certain gage height, find where it intersects the gage-height curve, then follow the ordinate of this intersection until it cuts the discharge curve, and the discharge for that particular gage height is found on the right side of the diagram.

Assuming that the discharges at the various points in this portion of the river vary in proportion to the drainage area above, one can readily determine by the use of the curves the conditions which may reasonably be expected at any point below Harrisburg. For example, suppose one wishes to know how many days during the mean year the discharge will be less than 5,500 second-feet at the Pennsylvania-Maryland line, where the drainage area is 27,150 square miles, or 13 per cent more than at Harrisburg. As the drainage area at Harrisburg is 88.6 per cent of that at the State line, 5,500 second-feet would correspond to a discharge of 4,870 second-feet at Harrisburg. From the full-line curve on Pl. XXVII we find that for twenty days during the mean year the discharge is less than 4,870 second-feet at Harrisburg, or 5,500 second-feet at the Maryland-Pennsylvania line.

By applying the following simple rule for horsepower it is possible to determine the probable power which could be developed during a mean year at any point in the lower Susquehanna:

Rule: Horsepower on the turbine shaft equals the discharge in second-feet multiplied by the fall divided by 11. This is based upon an assumption of 80 per cent efficiency for the turbines.

Applying this to the above example, we find that for three hundred and forty-five days during the mean year 500 horsepower for 80 per cent efficiency can be developed for each foot fall at the Maryland-Pennsylvania line.

RULES FOR ESTIMATING DISCHARGE.

The approximate mean monthly discharge in second-feet for any stream in the Susquehanna drainage basin, may be determined in either of two ways—

First. Its drainage area in square miles can be taken from the table on page 15, or measured on a map, and multiplied by the monthly run-off in second-feet per square mile given in the tables of the nearest gaging station.

Second. The monthly rainfall in inches for the district, as determined from the tables on pages 161 to 171, can be multiplied by the per cent of run-off for that month at the nearest of the three gaging stations—Wilkesbarre, Williamsport, or Harrisburg—giving the total monthly run-off in inches. This result multiplied by one of the following coefficients gives the mean monthly run-off in second-feet per square mile:

| | |
|---------------------------|--------|
| For month of 28 days..... | 0.9603 |
| For month of 30 days..... | .8963 |
| For month of 31 days..... | .8674 |

The drainage area in square miles may be found as before, and if multiplied by the above product will give the mean discharge of the stream for that month in second-feet.

The horsepower may then be computed by the rule on page 203.

TABLES SHOWING DEVELOPED HORSEPOWER AND ELEVATIONS.

Horsepower developed in New York on Susquehanna River and tributaries.^a

| County. | Grist and flour mills. | | Sawmills. | | Miscellaneous. ^b | | Total horsepower in county. |
|----------------------|------------------------|--------------------|------------------|--------------------|-----------------------------|--------------------|-----------------------------|
| | Number of mills. | Total horse-power. | Number of mills. | Total horse-power. | Number of mills. | Total horse-power. | |
| Broome ----- | 13 | 840 | 9 | 291 | 3 | 33 | 1,164 |
| Chemung ----- | 9 | 426 | 0 | 0 | 0 | 0 | 426 |
| Chenango ----- | 20 | 963 | 23 | 759 | 6 | 163 | 1,885 |
| Cortland ----- | 12 | 668 | 11 | 463 | 4 | 77 | 1,208 |
| Delaware ----- | 9 | 314 | 10 | 276 | 0 | ----- | 590 |
| Madison ----- | 9 | 367 | 8 | 359 | 2 | 175 | 901 |
| Otsego ----- | 23 | 748 | 35 | 1,453 | 2 | 155 | 2,356 |
| Schoharie ----- | 0 | ----- | 2 | 45 | 0 | ----- | 45 |
| Steuben ----- | 23 | 1,155 | 3 | 121 | 6 | 27 | 1,303 |
| Tioga ----- | 12 | 402 | 1 | 55 | 1 | 40 | 497 |
| Total in State ----- | 130 | 5,883 | 102 | 3,822 | 24 | 670 | 10,375 |

^aFrom manuscript schedules of the Twelfth Census.

^bIncludes woolen mills, tanneries, printing, cordage, and carriage works.

Horsepower developed in Pennsylvania on Susquehanna River and tributaries.^a

| County. | Flour and grist mills. | | Sawmills. | | Creameries and paper mills. | | Electric power plants. | | Total horsepower in county. |
|----------------------|------------------------|--------------------|------------------|--------------------|-----------------------------|--------------------|------------------------|--------------------|-----------------------------|
| | Number of mills. | Total horse-power. | Number of mills. | Total horse-power. | Number of mills. | Total horse-power. | Number of mills. | Total horse-power. | |
| Adams | 24 | 734 | 5 | 90 | | | | | 824 |
| Bedford | 34 | 699 | 5 | 100 | | | | | 799 |
| Blair | 26 | 597 | 2 | 40 | 1 | 25 | | | 662 |
| Bradford | 29 | 1,175 | 5 | 186 | | | | | 1,361 |
| Cambria | 4 | 111 | 8 | 218 | | | | | 329 |
| Center | 26 | 1,022 | 7 | 125 | 1 | 10 | | | 1,157 |
| Clearfield | 11 | 350 | 7 | 210 | | | | | 560 |
| Clinton | 11 | 451 | 6 | 213 | 1 | 120 | | | 784 |
| Columbia | 35 | 1,217 | 9 | 166 | 2 | 270 | | | 1,653 |
| Cumberland | 40 | 1,179 | 1 | 20 | 2 | 355 | 1 | 121 | 1,675 |
| Dauphin | 39 | 1,004 | 4 | 63 | | | 2 | 360 | 1,427 |
| Elk | 1 | 13 | | | | | | | 13 |
| Franklin | 9 | 169 | 1 | 10 | | | | | 179 |
| Fulton | 2 | 51 | 2 | 27 | | | | | 78 |
| Huntingdon | 30 | 979 | 2 | 40 | | | | | 1,019 |
| Juniata | 20 | 487 | 2 | 50 | | | | | 537 |
| Lackawanna | 7 | 324 | 3 | 90 | | | | | 414 |
| Lancaster | 176 | 5,451 | 11 | 667 | 9 | 225 | 4 | 1,262 | 7,605 |
| Lebanon | 22 | 615 | 2 | 30 | | | | | 645 |
| Luzerne | 24 | 712 | 8 | 205 | 1 | 125 | 1 | 208 | 1,250 |
| Lycoming | 31 | 1,530 | 6 | 140 | | | | | 1,670 |
| Mifflin | 16 | 605 | | | | | | | 605 |
| Montour | 6 | 135 | | | | | | | 135 |
| Northumberland | 22 | 445 | | | | | | | 445 |
| Perry | 31 | 697 | 7 | 154 | | | | | 851 |
| Potter | 1 | 20 | | | | | | | 20 |
| Snyder | 21 | 488 | 6 | 176 | | | | | 664 |
| Schuylkill | 17 | 277 | 2 | 45 | | | | | 322 |
| Sullivan | 7 | 224 | 5 | 129 | | | 1 | 250 | 603 |
| Susquehanna | 29 | 965 | 17 | 619 | | | 1 | 275 | 1,859 |
| Tioga | 15 | 554 | 1 | 55 | | | | | 609 |
| Union | 18 | 632 | 2 | 32 | | | | | 664 |
| Wyoming | 23 | 835 | 5 | 194 | | | | | 1,029 |
| York | 145 | 3,596 | 8 | 94 | 3 | 2,175 | 1 | 500 | 6,365 |
| Total in State | 952 | 28,343 | 149 | 4,188 | 20 | 3,305 | 11 | 2,976 | 38,812 |

^aFrom manuscript schedules of the Twelfth Census.

Water power used for electric light and power development in Susquehanna drainage.^a

| Name of establishment. | County. | Post-office. | Power. | | | | | |
|--|-------------|--------------|---------------|--------|---------|--------|-----------|--------|
| | | | Water wheels. | | Steam. | | Electric. | |
| | | | Number. | Power. | Number. | Power. | Number. | Power. |
| West Earl Electric Light and Power Co. | Lancaster | Brownstown | 1 | 50 | — | — | 2 | 50 |
| Eagles Mere Light Co. | Sullivan | Eagles Mere | 1 | 250 | — | — | 1 | 100 |
| Harrisburg Light, Heat and Power Co. | Dauphin | Harrisburg | 4 | 300 | 10 | 2,980 | 38 | 3,936 |
| Lancaster Electric Light, Heat and Power Co. | Lancaster | Lancaster | 8 | 1,050 | 1 | 325 | 12 | 1,762 |
| Manheim Electric Light, Heat and Power Co. | do | Manheim | 2 | 100 | 1 | 150 | 1 | 100 |
| Millersburg Electric Light, Heat and Power Co. | Dauphin | Millersburg | 2 | 60 | 2 | 175 | 2 | 250 |
| Delta Electric Power Co. | York | Peach Bottom | 2 | 500 | — | — | 1 | 470 |
| John Hosfeld Co. | Cumberland | Shippensburg | 4 | 121 | 1 | 40 | 4 | 200 |
| Strasburg Electric Light Plant | Lancaster | Strasburg | 2 | 62 | — | — | 1 | 65 |
| Susquehanna Electric Light, Heat and Power Co. | Susquehanna | Susquehanna | 1 | 275 | 2 | 320 | 4 | 294 |
| White Haven Electric Illuminating Plant. | Luzerne | Whitehaven | 2 | 208 | — | — | 4 | 270 |
| Total | — | — | 29 | 2,976 | 17 | 3,990 | 70 | 7,497 |

^aFrom manuscript schedules of the Twelfth Census.

Approximate elevations and slope of Susquehanna River and North Branch.

| Locality. | Distance from mouth. | Elevation above tide. | Distance between points. | Fall between points. | |
|---------------------------|----------------------------|--------------------------|--------------------------------|----------------------|---------------------|
| | <i>Miles.</i> | <i>Feet.</i> | <i>Miles.</i> | <i>Feet.</i> | <i>Ft. permile.</i> |
| Mouth | 0 | 0 | ----- | ----- | ----- |
| Port Deposit | 5 | 2 | 5 | 2 | 0.4 |
| Stateline | 15 | 69 | 10 | 67 | 6.7 |
| Peach Bottom | 18 | 85 | 3 | 16 | 5.3 |
| Muddy Creek | 21 | 98 | 3 | 13 | 4.3 |
| McCalls Ferry | 26 | 115 | 5 | 17 | 5.4 |
| York Furnace | 30 | 140 | 4 | 25 | 6.2 |
| Safe Harbor | 34 | 168 | 4 | 28 | 7.0 |
| Turkey Hill | 39 | 210 | 5 | 42 | 8.4 |
| Columbia | 45 | 225 | 6 | 15 | 2.5 |
| Head Conewago Falls | 58 | 273 | 13 | 48 | 3.7 |
| Harrisburg | 73 | 290 | 15 | 17 | 1.1 |
| Mouth Juniata River | 88 | 336 | 15 | 46 | 3.1 |
| Liverpool | 107 | 379 | 19 | 43 | 2.3 |
| Selinsgrove | 126 | 422 | 19 | 43 | 2.3 |
| Below Sunbury dam | 131 | 423 | 5 | 1 | .2 |
| Below Nanticoke dam | 189 | 509 | 58 | 86 | 1.5 |
| Wilkesbarre | 197 | 525 | 8 | 16 | 2.0 |
| Pittston | 204 | 539 | 7 | 14 | 2.0 |
| Gardners Creek | 210 | 551 | 6 | 12 | 2.0 |
| Tunkhannock | 228 | 587 | 18 | 36 | 2.0 |
| Mehoopany Creek | 239 | 615 | 11 | 28 | 2.5 |
| Tuscarora Creek | 249 | 630 | 10 | 15 | 1.5 |
| Wyalusing | 261 | 656 | 12 | 26 | 2.2 |
| Rummerfield Creek | 270 | 678 | 9 | 22 | 2.4 |
| Big Wysox Creek | 276 | 694 | 6 | 16 | 2.7 |
| Towanda | 281 | 706 | 5 | 12 | 2.4 |
| Ulster Ferry | 289 | 727 | 8 | 21 | 2.6 |
| Mouth Chemung River | 294 | 742 | 5 | 15 | 3.0 |
| Athens | 297 | 752 | 3 | 10 | 3.3 |

Approximate elevations and slope of Juniata River.

| Locality. | Distance from mouth. | Elevation above tide. | Distance between points. | Fall between points. | |
|---|----------------------------|--------------------------|--------------------------------|----------------------|----------------------|
| | <i>Miles.</i> | <i>Feet.</i> | <i>Miles.</i> | <i>Feet.</i> | <i>Ft. per mile.</i> |
| Mouth | 0 | 336 | ----- | ----- | ----- |
| Millerstown dam, water below .. | 16 | 380 | 16 | 44 | 2.7 |
| Millerstown dam, crest | 16 | 388 | 0 | 8 | ----- |
| Mifflin | 34 | 417 | 18 | 29 | 1.6 |
| Lewistown dam, water below .. | 44 | 442 | 10 | 25 | 2.5 |
| Lewistown dam, crest | 44 | 450 | 0 | 8 | ----- |
| McVeytown | 61 | 476 | 17 | 26 | 1.5 |
| Newton Hamilton dam, water below | 68 | 512 | 7 | 36 | 5.1 |
| Newton Hamilton dam, crest .. | 68 | 520 | 0 | 8 | ----- |
| Huntingdon dam, water below .. | 90 | ±610 | 22 | 90 | 4.1 |
| Huntingdon dam, crest | 90 | ±622 | 0 | 12 | ----- |

Approximate elevations and slope of Raystown Branch of Juniata River.


| Locality. | Distance from mouth. | Elevation above tide. | Distance between points. | Fall between points. | |
|--------------------|----------------------------|--------------------------|--------------------------------|----------------------|---------------------|
| | <i>Miles.</i> | <i>Feet.</i> | <i>Miles.</i> | <i>Feet.</i> | <i>Ft. per mile</i> |
| Mouth | 0 | 595 | ----- | ----- | ----- |
| Near Saxton | 40 | 837 | 40 | 242 | 6.0 |
| Pipers Run | 53 | 891 | 13 | 54 | 4.2 |
| Mount Dallas | 79 | 1,016 | 26 | 125 | 4.8 |

Approximate elevations and slope of Frankstown Branch of Juniata River.


| Locality. | Distance from Hunt- ingdon. | Elevation above tide. | Distance between points. | Fall between points. | |
|--|-----------------------------------|--------------------------|--------------------------------|----------------------|---------------|
| | Miles. | Feet. | Miles. | Feet. | Ft. per mile. |
| Huntingdon dam, crest..... | 0.0 | 622 | ----- | ----- | ----- |
| Piper's dam, water below..... | 2.5 | 628 | 2.5 | 6.0 | 2.4 |
| Piper's dam, crest..... | 2.5 | 636 | 0 | 8.0 | ----- |
| Petersburg dam, water below..... | 4.1 | 641 | 1.6 | 5.0 | 2.1 |
| Petersburg dam, crest..... | 4.1 | 648 | 0 | 6.5 | ----- |
| Big Water Street dam, water below..... | 10.0 | 693 | 5.9 | 45.0 | 7.6 |
| Big Water Street dam, crest..... | 10.0 | 712 | 0 | 19.3 | ----- |
| Little Water Street dam, water below..... | 12.4 | 714 | 2.4 | 2.0 | .8 |
| Little Water Street dam, crest..... | 12.4 | 726 | 0 | 12.0 | ----- |
| Willow dam, water below..... | 14.4 | 728 | 2.0 | 2.0 | 1.0 |
| Willow dam, crest..... | 14.4 | 741 | 0 | 13.0 | ----- |
| Donnelly's dam, water below..... | 17.0 | 770 | 2.6 | 29.0 | 11.2 |
| Donnelly's dam, crest..... | 17.0 | 784 | 0 | 14.0 | ----- |
| Smoker's dam, water below..... | 18.7 | 787 | 1.7 | 3.0 | 1.7 |
| Smoker's dam, crest..... | 18.7 | 799 | 0 | 12.0 | ----- |
| Mud dam, water below..... | 20.1 | 800 | 1.4 | 1.0 | .7 |
| Mud dam, crest..... | 20.1 | 808 | 0 | 7.5 | ----- |
| Williamsburg dam, water be- low..... | 23.0 | 831 | 2.9 | 23.0 | 7.9 |
| Williamsburg dam, crest..... | 23.0 | 839 | 0 | 10.0 | ----- |
| Threemile dam, water below..... | 24.1 | 839 | 1.1 | 0 | 0 |
| Threemile dam, crest..... | 24.1 | 856 | 0 | 17.5 | ----- |
| Crooked dam, water below..... | 27.2 | 856 | 3.1 | 0 | 0 |
| Crooked dam, crest..... | 27.2 | 866 | 0 | 10.0 | ----- |
| Frankstown dam, water be- low..... | 33.5 | 895 | 6.3 | 29.0 | 4.6 |
| Frankstown dam, crest..... | 33.5 | 899 | 0 | 3.5 | ----- |
| Hollidaysburg dam, water be- low..... | 36.4 | 923 | 2.9 | 24.0 | 8.3 |
| Hollidaysburg dam, crest..... | 36.4 | 927 | 0 | 4.5 | ----- |


Elevation and slope of West Branch of Susquehanna River.

| Locality. | Distance from mouth. | Elevation above tide. | Distance between points. | Fall between points. | |
|-------------------------------------|----------------------------|--------------------------|--------------------------------|----------------------|---------------------|
| | <i>Miles.</i> | <i>Feet.</i> | <i>Miles.</i> | <i>Feet.</i> | <i>Ft. permile.</i> |
| Mouth | 0 | 429 | ----- | ----- | ----- |
| Lewisburg dam, water below .. | 7 | 431 | 7 | 2 | 0.3 |
| Lewisburg dam, crest | 7 | 434 | 0 | 3 | ----- |
| Muncy dam, water below | 23 | 462 | 16 | 28 | 1.8 |
| Muncy dam, crest | 23 | 469 | 0 | 7 | ----- |
| Williamsport dam, water below | 39 | 498 | 16 | 29 | 1.8 |
| Williamsport dam, crest | 39 | 508 | 0 | 10 | ----- |
| Lock Haven dam, water below .. | 65 | 539 | 26 | 31 | 1.2 |
| Lock Haven dam, crest | 65 | 550 | 0 | 11 | ----- |
| Queen's Run dam, water below .. | 69 | 551 | 4 | 1 | 0.2 |
| Queen's Run dam, crest | 69 | 557 | 0 | 6 | ----- |
| Keating | 105 | 695 | 36 | 138 | 3.8 |
| Curwinsville | 160 | 1,117 | 55 | 422 | 7.7 |



SUSQUEHANNA





PROFILE OF SUSQUEHANNA RIVER FROM MOUTH TO ATHENS PA.



PROFILES OF SOME OF THE TRIBUTARIES OF SUSQUEHANNA RIVER.

INDEX.

| | Page. | | Page. |
|--|---------------|--|---------------|
| Accuracy of stream measurements..... | 182-183 | Cayuta Creek— | |
| Acknowledgments | 9-10 | at Waverly, N. Y.: | |
| Addison, N. Y., rainfall data..... | 160, 164 | description | 146-147 |
| Allenwood, Pa. | | discharge, 1903..... | 147 |
| West Branch Susquehanna River at: | | gage heights, 1898-1902..... | 148-150 |
| description | 84 | drainage areas..... | 147 |
| discharge, 1899-1902..... | 85 | Cayuta Lake, N. Y. | |
| discharge, daily, 1899-1902..... | 89-90 | description | 147 |
| discharge, low-water..... | 181 | Centerhall, Pa., rainfall data..... | 160, 169 |
| discharge, monthly, 1899-1902..... | 91-92 | Charlesville, Pa., rainfall data..... | 172 |
| gage heights, 1899-1902..... | 86-87 | Chemung, N. Y. | |
| rating curve..... | 88 | Chemung River at. <i>See</i> Chemung River | |
| rating table, 1900-1902..... | 88 | at Chemung. | |
| Altoona, Pa., rainfall data..... | 161, 170 | Chemung Forks, N. Y. | |
| Angelica, N. Y., rainfall data..... | 160, 164 | Toughnioga River at: | |
| Army engineers, acknowledgments to | 10 | description | 145-146 |
| Athens, Pa. | | discharge, 1903..... | 146 |
| profile of Susquehanna River from | | gage heights, 1903..... | 146 |
| mouth to..... | 210 | Chemung River— | |
| rainfall data..... | 160, 165 | at Chemung, N. Y.: | |
| Atlanta, N. Y., rainfall data..... | 160, 164 | description | 140 |
| Binghamton, N. Y. | | discharge, 1903-1904..... | 141 |
| Chenango River at: | | discharge, daily, 1903-1904..... | 144 |
| contour of bottom of..... | 189 | discharge, monthly, 1903-1904..... | 145 |
| description | 34 | gage heights, 1903-1904..... | 142 |
| discharge, 1901-1904..... | 35 | rating table, 1903-1904..... | 143 |
| discharge, daily, 1901-1904..... | 40-41 | drainage areas..... | 141 |
| discharge monthly, 1901-1904..... | 42-43 | tributaries of..... | 13 |
| gage heights, 1901-1904..... | 37-38 | Chenango River— | |
| rating curve..... | 36 | at Binghamton, N. Y.: | |
| rating table, 1901-1904..... | 39 | contour of bed of..... | 189 |
| vertical velocity curves (mean).... | 192 | description | 34 |
| vertical velocity measurements.... | 189, | discharge, 1901-1904..... | 35 |
| | 191, 194, 196 | discharge, daily, 1901-1904..... | 40-41 |
| rainfall data..... | 160, 163 | discharge, monthly, 1901-1904..... | 42-43 |
| Susquehanna River at: | | gage heights, 1901-1904..... | 37-38 |
| contour of bed of..... | 190 | rating curve..... | 36 |
| description | 25-27 | rating table, 1901-1904..... | 39 |
| discharge, 1901-1904..... | 27 | vertical velocity curves (mean).... | 192 |
| discharge, daily, 1901-1904..... | 30-32 | vertical velocity measurements.... | 189, |
| discharge, monthly, 1901-1904..... | 32-33 | | 191, 194, 196 |
| gage heights, 1901-1904..... | 28-29 | at Oxford, N. Y.: | |
| rating curve..... | 26 | description | 150 |
| rating table, 1901-1904..... | 30 | at South Oxford, N. Y.: | |
| vertical velocity curves (mean).... | 193 | gage heights, 1903..... | 151 |
| Bouckville, N. Y., rainfall data..... | 160, 161 | tributaries of | 13 |
| Brundage, F. H., acknowledgments to..... | 10 | Chenango River basin: | |
| Catawissa, Pa. | | diversions from..... | 154 |
| Susquehanna River near: | | Cooperstown, N. Y., rainfall data..... | 160, 161 |
| view on..... | 18 | Cortland, N. Y., rainfall data..... | 160, 163 |

| | Page. | | Page. |
|--|---------------|---|---------------|
| Coudersport, Pa., rainfall data..... | 172 | Gaging stations: | |
| Dager, J. H., on navigation along the Sus- | | list of..... | 25 |
| quehanna | 24 | map showing location of..... | 11 |
| on Susquehanna River above West | | Girardville, Pa., rainfall data | 160, 168 |
| Branch | 21-22 | Grampian, Pa., rainfall data..... | 161, 169, 172 |
| Danville, Pa. | | Harrisburg, Pa. | |
| Susquehanna River at: | | rainfall data..... | 161, 170 |
| description | 56 | Susquehanna River at: | |
| discharge, 1899-1903 | 57 | curve of mean velocity..... | 172 |
| discharge, daily, 1899-1903..... | 62-64 | curves showing duration of stages | |
| discharge, low-water | 181 | of, from 1891-1902..... | 202 |
| discharge, monthly, 1899-1903 | 64-66 | description | 104-106 |
| gage heights, 1899-1904 | 58-60 | discharge, 1897-1904 | 106-107 |
| rating curve | 60 | discharge, daily, 1891-1904..... | 116-122 |
| rating table, 1899-1904 | 61 | discharge, flood..... | 173, 176 |
| Deruyter, N. Y., rainfall data | 145 | discharge, low-water | 181 |
| Discharge measurements..... | 25-153 | discharge, maximum, minimum, | |
| accuracy of..... | 182-183 | and mean, 1891-1904 | 178 |
| of rivers. See River names. | | discharge, monthly, 1891-1904 | 123-129 |
| rules for estimating | 203-204 | discharge, monthly, compared with | |
| Diverted water, Chenango River basin..... | 154 | monthly discharge at McCalls | |
| Drainage areas: | | Ferry | 183 |
| Cayuta Creek, N. Y | 147 | gage heights, 1891-1904..... | 108-115 |
| Chemung River | 141 | rating curve | 114 |
| map showing..... | 11 | rating table, 1891-1904 | 115 |
| Susquehanna River and tributaries, ta- | | vertical velocity curves..... | 198 |
| ble..... | 15-18 | vertical velocity measurements .. | 197, 198 |
| Duncans Run section. See Susquehanna | | Susquehanna River basin above: | |
| River at McCalls Ferry, Pa. | | rainfall and run-off relation..... | 156-157 |
| Dushore, Pa., rainfall data | 160, 166 | rainfall stations in, list of..... | 155 |
| Eaton Brook, Madison County, N. Y.: | | Holidaysburg, Pa., rainfall data..... | 172 |
| description | 151 | Horsepower, developed, tables showing.. | 204-206 |
| discharge, monthly, 1835..... | 152 | possible development of, rules for de- | |
| Ehle, Boyd, acknowledgments to | 130 | termining | 203 |
| Electric light and power development | | Horton, R. E., acknowledgments to..... | 9 |
| in Susquehanna basin, water | | Huntingdon, Pa., rainfall data..... | 161, 170, 172 |
| power used for, table..... | 206 | Hutchinson, Cary T., acknowledgments to. | 10 |
| Elevations and slope: | | Jervis, John B., on flow of Eaton and Madi- | |
| Junata River and tributaries..... | 208-209 | son brooks, N. Y | 151 |
| Susquehanna River | 207 | Johnstown flood. See Flood of 1889. | |
| West Branch Susquehanna..... | 210 | Junata River. | |
| See also Profiles. | | description | 20-21 |
| Elevations of flood, March, 1904..... | 175 | elevations and slope..... | 208 |
| Elmira, N. Y., rainfall data..... | 160, 165 | near Newport, Pa.: | |
| Emporium, Pa., rainfall data..... | 160, 168, 172 | description | 93 |
| Flood discharges and values of "N" by | | discharge, 1899-1904..... | 94 |
| Kutter's formula | 178-180 | discharge, daily, 1899-1904..... | 99-101 |
| Flood of 1865, data regarding..... | 172 | discharge, flood | 176 |
| Flood of 1875, at Wilkesbarre, Pa., view | | discharge, low-water | 181 |
| showing | 174 | discharge, monthly, 1899-1904 | 102-104 |
| Flood of 1889, data concerning | 172-173 | gage heights, 1899-1904..... | 95-97 |
| rainfall of, duration and extent of..... | 172 | rating curve | 98 |
| Flood of 1904, damage due to..... | 176 | rating table, 1899-1904 | 98 |
| description of | 173-177 | profile of | 210 |
| heights of, above low water, table..... | 176 | tributaries of | 12 |
| view of, at McCalls Ferry, Pa..... | 176 | Kutter's formula, flood discharges and | |
| at Middletown, Pa..... | 178 | values of "N" by..... | 178-180 |
| at York Haven, Pa..... | 174 | map showing sections used in..... | 180 |
| Floods in Susquehanna basin, history of .. | 172-178 | Labelle, H. F., quoted on power develop- | |
| Flow measurements..... | 25-153 | ments of lower Susquehanna..... | 200-202 |
| accuracy of..... | 182-183 | Lawrenceville, Pa., rainfall data | 160, 165 |
| of rivers. See River names. | | Lebanon, Pa., rainfall data | 161, 171 |
| rules for computing..... | 203-204 | Leroy, Pa., rainfall data..... | 160, 166 |
| Frankstown Branch of Juniata River: | | Lewisburg, Pa., rainfall data..... | 160, 168 |
| elevations and slope..... | 209 | Life, loss of, by Susquehanna floods..... | 173 |
| tributaries of | 12 | Lockhaven, Pa., rainfall data | 160, 168 |

| | Page. | | Page. |
|---|---------------|--|---------------|
| Low-water conditions in Susquehanna basin, description of..... | 180-182 | Profiles: | |
| McCalls Ferry, Pa. | | Juniata River (Pl. 29) | 210 |
| Susquehanna River at: | | Raystown Branch of Juniata River (Pl. 29) | 210 |
| curve of mean velocity..... | 172, 182 | Susquehanna River from mouth to Athens, Pa. (Pl. 28) | 210 |
| description | 130-131 | West Branch of Susquehanna River (Pl. 29) | 210 |
| discharge, 1902-1904 | 132-133 | Rainfall and run-off relation, tables..... | 156-159 |
| discharge, daily, 1902-1904 | 137-138 | Rainfall data: | |
| discharge, flood | 173, 176, 177 | Addison, N. Y. | 160, 164 |
| discharge, low-water..... | 182 | Altoona, Pa. | 161, 170 |
| discharge, monthly, 1902-1904.... | 138-139 | Angelica, N. Y. | 160, 164 |
| discharge, monthly, compared with monthly discharge at Harrisburg..... | 183 | Athens, Pa. | 160, 165 |
| flood of 1904 on, view showing | 176 | Atlanta, N. Y. | 160, 164 |
| gage heights, 1902-1904 | 134-135 | Binghamton, N. Y. | 160, 163 |
| gaging car at, views of | 132 | Bouckville, N. Y. | 160, 161 |
| gaging stations, views of | 18, 130 | Centerhall, Pa. | 160, 169 |
| map showing sections used in Kutter's formula determinations.... | 180 | Charlesville, Pa. | 172 |
| rating curve..... | 136 | Coopertown, N. Y. | 160, 161 |
| rating table, 1902-1903 | 136 | Cortland, N. Y. | 160, 163 |
| vertical velocity curves | 198 | Coudersport, Pa. | 172 |
| vertical velocity measurements.... | 184, 185-188 | Dernyter, N. Y. | 145 |
| Madison Brook, Madison County, N. Y.: | | during flood of 1889..... | 172 |
| description | 151 | Dushore, Pa. | 160, 166 |
| discharge, monthly, 1835..... | 153 | Elmira, N. Y. | 160, 165 |
| Mather, E., acknowledgments to..... | 105 | Emporium, Pa. | 160, 168 |
| Middletown, Pa., view of, during flood of 1904..... | 178 | Girardville, Pa. | 160, 168 |
| Muncy, Pa., rainfall data..... | 162 | Grampian, Pa. | 161, 169, 172 |
| N, values of, by Kutter's formula..... | 178-180 | Harrisburg, Pa. | 161, 170 |
| Navigation along Susquehanna River..... | 24-25 | Hollidaysburg, Pa. | 172 |
| Newell, F. H., letter of transmittal by..... | 7 | Huntingdon, Pa. | 161, 170, 172 |
| New Lisbon, N. Y., rainfall data..... | 160, 162 | Lawrenceville, Pa. | 160, 165 |
| Newport, Pa. | | Lebanon, Pa. | 161, 171 |
| Juniata River at: | | Leroy, Pa. | 160, 166 |
| description | 93 | Lewisburg, Pa. | 160, 168 |
| discharge, 1899-1904..... | 94 | Lockhaven, Pa. | 160, 168 |
| discharge, daily, 1899-1904..... | 99-101 | Muncy, Pa. | 172 |
| discharge, flood | 176 | New Lisbon, N. Y. | 162 |
| discharge, low-water..... | 181 | Oneonta, N. Y. | 160, 162 |
| discharge, monthly, 1899-1904.... | 102-104 | Oxford, N. Y. | 150, 160, 162 |
| gage heights, 1899-1904..... | 95-97 | Perry City, N. Y. | 160, 163 |
| rating curve..... | 98 | Philipsburg, Pa. | 172 |
| rating table, 1899-1904..... | 98 | Ralston, Pa. | 172 |
| New York: | | Richmondville, N. Y. | 161 |
| counties in, drained by Susquehanna and tributaries | 11 | Selinsgrove, Pa. | 160, 169, 172 |
| horsepower developed on Susquehanna River and tributaries in, table showing | 204 | Siglerville, Pa. | 172 |
| rainfall stations in, list of..... | 155, 157, 160 | South Canisteo, N. Y. | 160, 164 |
| Oneonta, N. Y., rainfall data..... | 160, 162 | South Eaton, Pa. | 160, 167 |
| Oxford, N. Y., rainfall data..... | 150, 160, 162 | South Kortright, N. Y. | 160, 162 |
| Paul, E. G., acknowledgments to..... | 9 | State College, Pa. | 161, 169, 172 |
| Pennsylvania: | | Towanda, Pa. | 160, 166 |
| counties in, drained by Susquehanna and tributaries | 11 | Waverly, N. Y. | 160, 165 |
| horsepower developed on Susquehanna River and tributaries in, table.... | 205 | Wedgwood, N. Y. | 160, 163 |
| rainfall stations in, list of. 155, 157, 158, 160-161 | | Wellsboro, Pa. | 160, 166 |
| Perry City, N. Y., rainfall data..... | 160, 163 | West Branch watershed | 172 |
| Philipsburg, Pa., rainfall data..... | 172 | Wilkesbarre, Pa. | 160, 167 |
| Precipitation. <i>See</i> Rainfall. | | Williamsport, Pa. | 160, 167, 172 |
| | | York, Pa. | 161, 171 |
| | | Rainfall stations: | |
| | | map showing location of | 11 |
| | | Ralston, Pa., rainfall data..... | 172 |
| | | Raystown Branch of Juniata River: | |
| | | elevations and slope of | 208 |
| | | profile of | 210 |
| | | tributaries of | 12 |

| | Page. | | Page. |
|--|---------------|--|---------------|
| Richmondville, N. Y., rainfall data..... | 160, 161 | Susquehanna River—Continued. | |
| Rogers, H. D.: | | at Harrisburg, Pa.—Continued. | |
| acknowledgments to..... | 10 | discharge, low-water..... | 181 |
| quoted on Juniata River..... | 20-21 | discharge, maximum, minimum, | |
| quoted on Susquehanna River above | | and mean, 1891-1904..... | 178 |
| West Branch..... | 22 | discharge, monthly, 1891-1904.... | 123-129 |
| quoted on Susquehanna River below | | discharge, monthly, compared with | |
| West Branch..... | 19-20 | monthly discharge at McCall's | |
| quoted on West Branch of Susquehanna | | Ferry..... | 183 |
| River..... | 23-24 | gage heights, 1891-1904..... | 108-115 |
| Run-off and rainfall relation. See Rainfall | | rating curve..... | 114 |
| and run-off. | | rating table, 1891-1904..... | 115 |
| Saunders, H. J., acknowledgments to..... | 10 | vertical velocity curves..... | 198 |
| Scranton, Pa., rainfall data..... | 160, 167 | vertical velocity measurements.. | 197, 198 |
| Selinsgrove, Pa., rainfall data..... | 160, 169, 172 | at McCall's Ferry, Pa.: | |
| Shures Landing, Pa. | | cable station, view of..... | 18 |
| Susquehanna River at: | | curve of mean velocity..... | 172, 182 |
| discharge, minimum..... | 201 | description..... | 130-131 |
| Siglerville, Pa., rainfall data..... | 172 | discharge, 1902-1904..... | 132-133 |
| Slopes. See Elevations and slopes; Profiles. | | discharge, daily, 1902-1904..... | 137-138 |
| South Canisteo, N. Y., rainfall data..... | 160, 164 | discharge, flood..... | 173, 176, 177 |
| South Eaton, Pa., rainfall data..... | 160, 167 | discharge, low-water..... | 182 |
| South Kortright, N. Y., rainfall data..... | 160, 162 | discharge, monthly, 1902-1904.... | 138-139 |
| South Oxford, N. Y., | | discharge, monthly, compared with | |
| Chenango River at: | | monthly discharge at Harris- | |
| gage heights..... | 151 | burg, Pa..... | 183 |
| State College, Pa., rainfall data..... | 161, 169, 172 | flood of 1904 at, views showing.... | 176 |
| Stewart, W. F. Bay, quoted on the York | | gage heights, 1902-1904..... | 134-135 |
| Haven Power Plant..... | 199-200 | gaging car at, views of..... | 132 |
| Stockman, L. R., acknowledgments to..... | 10 | gaging stations, views of..... | 130 |
| Stream measurements, accuracy of..... | 182-183 | map showing sections used in Kut- | |
| Susquehanna River— | | ter's formula determinations... .. | 180 |
| above West Branch: | | rating curve..... | 136 |
| description of..... | 21-22 | rating table, 1902-1903..... | 136 |
| tributaries of..... | 13-14 | vertical velocity curves near..... | 198 |
| at Binghamton, N. Y.: | | vertical velocity measurements.... | 184, |
| contour of bed of..... | 190 | | 185-188 |
| description..... | 25-27 | at Shures Landing, Pa.: | |
| discharge, 1901-1904..... | 27 | discharge, minimum..... | 201 |
| discharge, daily, 1901-1904..... | 30-32 | at Wilkesbarre, Pa.: | |
| discharge, monthly, 1901-1904..... | 32-33 | description..... | 43-44 |
| gage heights, 1901-1904..... | 28-29 | discharge, 1899-1904..... | 45 |
| rating curve..... | 26 | discharge, daily, 1899-1904..... | 50-52 |
| rating table, 1901-1904..... | 20 | discharge, flood..... | 176 |
| vertical velocity curves (mean).... | 193 | discharge, monthly, 1899-1904.... | 53-55 |
| vertical velocity measurements.... | 189, | rating curve..... | 48 |
| | 191, 195, 196 | rating table, 1899-1904..... | 49 |
| at Catawissa, Pa.: view on..... | 18 | gage heights, 1899-1904..... | 46-48 |
| at Danville, Pa.: | | at York Haven, Pa.: | |
| description..... | 56 | discharge, mean annual..... | 200 |
| discharge, 1899-1903..... | 57 | below West Branch: | |
| discharge, daily, 1899-1903..... | 62-64 | description of..... | 19-21 |
| discharge, low-water..... | 181 | tributaries of..... | 12-13 |
| discharge, monthly, 1899-1903..... | 64-66 | elevations and slope, table..... | 207 |
| gage heights, 1899-1904..... | 58-60 | flood discharge of: | |
| rating curve..... | 60 | computed by Kutter's formula..... | 180 |
| rating table, 1899-1904..... | 61 | flood of 1865 on, data concerning.... | 172 |
| at Harrisburg, Pa.: | | flood of 1889 on, data concerning.... | 172-173 |
| curve of mean velocity..... | 172 | flood of 1904 on, data regarding.... | 173-177 |
| curves showing duration of stages | | profile of, from mouth to Athens, Pa... .. | 210 |
| of, 1891-1902..... | 202 | Susquehanna River and tributaries: | |
| description..... | 104-106 | drainage areas of..... | 15-18 |
| discharge, 1897-1904..... | 106-107 | horsepower developed on, in New York, | |
| discharge, daily, 1891-1904..... | 116-122 | table..... | 204 |
| discharge, flood..... | 173, 176 | in Pennsylvania, table..... | 205 |

| | Page. | | Page. |
|--------------------------------------|-------------------|--|----------|
| Susquehanna River basin— | | Turkey Hill, Pa., ice gorge at, during flood | |
| above Harrisburg, Pa.: | | of 1904 | 174 |
| rainfall stations in, list of | 155 | Vertical velocity measurements | 184-198 |
| rainfall and run-off relation | 156-157 | Water powers, discussion and tables | 199-210 |
| above Wilkesbarre, Pa.: | | Waverly, N. Y. | |
| rainfall and run-off relation, ta- | | Cayuta Creek at: | |
| bles | 158 | description | 146-147 |
| rainfall stations, list of | 157 | discharge, 1903 | 147 |
| above Williamsport, Pa.: | | gage heights, 1898-1902 | 148-150 |
| rainfall and run-off relation | 159 | rainfall data | 160, 165 |
| floods in: | | Wedgwood, N. Y., rainfall data | 160, 163 |
| history of | 172-178 | Wellsboro, Pa., rainfall data | 160, 166 |
| general features, of | 10 | West Branch of Susquehanna. <i>See</i> Susque- | |
| low-water conditions in | 180-182 | hanna River, West Branch. | |
| map showing drainage areas, gaging, | | Wilkesbarre, Pa.: | |
| and rainfall stations | 11 | rainfall data | 160, 167 |
| rainfall stations in, list | 155, 157, 160-161 | Susquehanna River at: | |
| water powers in, discussion and ta- | | description | 43-44 |
| bles | 199-210 | discharge, 1899-1904 | 45 |
| Susquehanna River, West Branch of: | | discharge, daily, 1899-1904 | 50-52 |
| description | 23-24 | discharge, flood | 176 |
| discharge, flood | 172 | discharge, monthly, 1899-1904 | 53-55 |
| elevations and slope | 210 | flood of 1875 on | 174 |
| near Allenwood, Pa.: | | gage heights, 1899-1904 | 46-48 |
| description | 84 | rating curve | 48 |
| discharge, 1899-1902 | 85 | rating table, 1899-1904 | 49 |
| discharge, daily, 1899-1902 | 89-90 | Susquehanna River basin above: | |
| discharge, low-water | 181 | rainfall and run-off relation, tables | 158 |
| discharge, monthly, 1899-1902 | 91-92 | rainfall stations in, list of | 157 |
| gage heights, 1899-1902 | 86-87 | Williamsport, Pa.: | |
| rating curve | 88 | rainfall data | 160, 167 |
| rating table, 1900-1902 | 88 | Susquehanna River basin above: | |
| near Williamsport, Pa.: | | rainfall and run-off relation | 159 |
| description | 67 | rainfall stations, list of | 158 |
| discharge, 1901-1904 | 67 | West Branch of Susquehanna River at: | |
| discharge, daily, 1895-1904 | 74-78 | description | 67 |
| discharge, flood | 176 | discharge, 1901-1904 | 67 |
| discharge, monthly, 1895-1904 | 79-83 | discharge, daily, 1895-1904 | 74-78 |
| gage heights, 1895-1904 | 68-72 | discharge, flood | 176 |
| rating curve | 72 | discharge, monthly, 1895-1904 | 79-83 |
| rating table, 1895-1904 | 73 | gage heights, 1895-1904 | 68-72 |
| profile of | 210 | rating curve | 72 |
| rainfall data of drainage area | 172 | rating table, 1895-1904 | 73 |
| tributaries of | 14 | York, Pa., rainfall data | 161, 171 |
| Tioughnioga River— | | York Haven, Pa. | |
| at Chemung Forks, N. Y.: | | Susquehanna River at: | |
| description | 145-146 | discharge, mean annual | 200 |
| discharge, 1903 | 146 | flood of 1904 at, view showing | 174 |
| gage heights, 1903 | 146 | York Haven Power Plant, description of | 199-200 |
| Towanda, Pa., rainfall data | 160, 166 | | |

LIBRARY CATALOGUE SLIPS.

[Mount each slip upon a separate card, placing the subject at the top of the second slip. The name of the series should not be repeated on the series card, but the additional numbers should be added, as received, to the first entry.]

Hoyt, John C[layton], 1874—

Author.

. . . Hydrography of the Susquehanna River drainage basin, by John C. Hoyt and Robert H. Anderson. Washington, Gov't print. off., 1905.

215 p., 1 l. illus., XXIX pl. (incl. map) diags. 23^{cm}. (U. S. Geological survey. Water-supply and irrigation paper no. 109)

Subject series: 'M, General Hydrographic investigations, 13; N, Water power, 9.

1. Water-supply—Pennsylvania. 2. Water-supply—New York (State)
3. Susquehanna River. I. Anderson, Robert H. joint author.

Hoyt, John C[layton], 1874—

Subject.

. . . Hydrography of the Susquehanna River drainage basin, by John C. Hoyt and Robert H. Anderson. Washington, Gov't print. off., 1905.

215 p., 1 l. illus., XXIX pl. (incl. map) diags. 23^{cm}. (U. S. Geological survey. Water-supply and irrigation paper no. 109)

Subject series: M, General hydrographic investigations, 13; N. Water power, 9.

1. Water-supply—Pennsylvania. 2. Water-supply—New York (State)
3. Susquehanna River. I. Anderson, Robert H. joint author.

U. S. Geological survey.

Water-supply and irrigation papers.

Series.

no. 109. Hoyt, J. C. Hydrography of the Susquehanna River drainage basin, by J. C. Hoyt and R. H. Anderson. 1905.

Reference.

U. S. Dept. of the Interior.

see also

U. S. Geological survey.

SERIES K—PUMPING WATER.

- WS 1. Pumping water for irrigation, by H. M. Wilson. 1896. 57 pp., 9 pls.
- WS 8. Windmills for irrigation, by E. C. Murphy. 1897. 49 pp., 8 pls.
- WS 14. Tests of pumps and water lifts used in irrigation, by O. P. Hood. 1898. 91 pp., 1 pl.
- WS 20. Experiments with windmills, by T. O. Perry. 1899. 97 pp., 12 pls.
- WS 29. Wells and windmills in Nebraska, by E. H. Barbour. 1899. 85 pp., 27 pls.
- WS 41. The windmill; its efficiency and economic use, Pt. I, by E. C. Murphy. 1901. 72 pp., 14 pls.
- WS 42. The windmill, Pt. II (continuation of No. 41). 1901. 73-147 pp., 15-16 pls.
- WS 91. Natural features and economic development of Sandusky, Maumee, Muskingum, and Miami drainage areas in Ohio, by B. H. Flynn and M. S. Flynn. 1904. 130 pp.

SERIES L—QUALITY OF WATER.

- WS 3. Sewage irrigation, by G. W. Rafter. 1897. 100 pp., 4 pls.
- WS 22. Sewage irrigation, Pt. II, by G. W. Rafter. 1899. 100 pp., 7 pls.
- WS 72. Sewage pollution in the metropolitan area near New York City and its effects on inland water resources, by M. O. Leighton. 1902. 75 pp., 8 pls.
- WS 76. Observations on the flow of rivers in the vicinity of New York City, by H. A. Pressey. 1903. 108 pp., 13 pls.
- WS 79. Normal and polluted waters in northeastern United States, by M. O. Leighton. 1903. 192 pp.
- WS 103. Review of the laws forbidding pollution of inland waters in the United States, by E. B. Goodell. 1904. 120 pp.
- WS 108. Quality of water in the Susquehanna River drainage basin, by M. O. Leighton, with an introductory chapter on physiographic features by G. B. Hollister. 1904. 76 pp., 4 pls.

SERIES M—GENERAL HYDROGRAPHIC INVESTIGATIONS.

- WS 56. Methods of stream measurement. 1901. 51 pp., 12 pls.
- WS 64. Accuracy of stream measurements, by E. C. Murphy. 1902. 99 pp., 4 pls.
- WS 76. Observations on the flow of rivers in the vicinity of New York City, by H. A. Pressey. 1903. 108 pp., 13 pls.
- WS 80. The relation of rainfall to run-off, by G. W. Rafter. 1903. 104 pp.
- WS 81. California hydrography, by J. B. Lippincott. 1903. 488 pp., 1 pl.
- WS 88. The Passaic flood of 1902, by G. B. Hollister and M. O. Leighton. 1903. 56 pp., 15 pls.
- WS 91. Natural features and economic development of Sandusky, Maumee, Muskingum, and Miami drainage areas in Ohio, by B. H. Flynn and M. S. Flynn. 1904. 130 pp.
- WS 92. The Passaic flood of 1903, by M. O. Leighton. 1904. 48 pp., 7 pls.
- WS 94. Hydrographic manual of the United States Geological Survey, prepared by E. C. Murphy, J. C. Hoyt, and G. B. Hollister. 1904. 76 pp., 3 pls.
- WS 95. Accuracy of stream measurements (second edition), by E. C. Murphy. 1904. 169 pp., 6 pls.
- WS 96. Destructive floods in the United States in 1903, by E. C. Murphy. 1904. 81 pp., 13 pls.
- WS 106. Water resources of the Philadelphia district, by Florence Bascom. 1904. 75 pp., 4 pls.
- WS 109. Hydrography of the Susquehanna River drainage basin, by J. C. Hoyt and R. H. Anderson. 1904. — pp., 23 pls.

SERIES N—WATER POWER.

- WS 24. Water resources of the State of New York, Pt. I, by G. W. Rafter. 1899. 92 pp., 13 pls.
- WS 25. Water resources of the State of New York, Pt. II, by G. W. Rafter. 100-200 pp., 12 pls.
- WS 44. Profiles of rivers, by Henry Gannett. 1901. 100 pp., 11 pls.
- WS 62. Hydrography of the Southern Appalachian Mountain region, Pt. I, by H. A. Pressey. 1902. 95 pp., 25 pls.
- WS 63. Hydrography of the Southern Appalachian Mountain region, Pt. II, by H. A. Pressey. 1902. 96-190 pp., 26-44 pls.
- WS 69. Water powers of the State of Maine, by H. A. Pressey. 1902. 124 pp., 14 pls.
- WS 105. Water powers of Texas, by T. N. Taylor. 1904. 116 pp., 17 pls.
- WS 107. Water powers of Alabama and water supply of rivers in Mississippi, by B. M. Hall. 1904. 253 pp., 9 pls.
- WS 109. Hydrography of the Susquehanna River drainage basin, by J. C. Hoyt and R. H. Anderson. 1904. — pp., 23 pls.

[Continued on fourth page of cover.]

SERIES O—UNDERGROUND WATERS.

- WS 4. A reconnaissance in southeastern Washington, by I. C. Russell. 1897. 96 pp., 7 pls.
- WS 6. Underground waters of southwestern Kansas, by Erasmus Haworth. 1897. 65 pp., 12 pls.
- WS 7. Seepage waters of northern Utah, by Samuel Fortier. 1897. 50 pp., 3 pls.
- WS 12. Underground waters of southeastern Nebraska, by N. H. Darton. 1898. 56 pp., 21 pls.
- WS 21. Wells of northern Indiana, by Frank Leverett. 1899. 82 pp., 2 pls.
- WS 26. Wells of southern Indiana (continuation of No. 21), by Frank Leverett. 1899. 64 pp.
- WS 30. Water resources of the Lower Peninsula of Michigan, by A. C. Lane. 1899. 97 pp., 7 pls.
- WS 31. Lower Michigan mineral waters, by A. C. Lane. 1899. 97 pp., 4 pls.
- WS 34. Geology and water resources of a portion of southeastern South Dakota, by J. E. Todd, 1900. 34 pp., 19 pls.
- WS 53. Geology and water resources of Nez Perces County, Idaho, Pt. I, by I. C. Russell. 1901. 86 pp., 10 pls.
- WS 54. Geology and water resources of Nez Perces County, Idaho, Pt. II, by I. C. Russell. 1901. 87-141 pp.
- WS 55. Geology and water resources of a portion of Yakima County, Wash., by G. O. Smith. 1901. 68 pp., 7 pls.
- WS 57. Preliminary list of deep borings in the United States, Pt. I, by N. H. Darton. 1902. 60 pp.
- WS 59. Development and application of water in southern California, Pt. I, by J. B. Lippincott. 1902. 95 pp., 11 pls.
- WS 60. Development and application of water in southern California, Pt. II, by J. B. Lippincott. 1902. 96-140 pp.
- WS 61. Preliminary list of deep borings in the United States, Pt. II, by N. H. Darton. 1902. 67 pp.
- WS 67. The motions of underground waters, by C. S. Slichter. 1902. 106 pp., 8 pls.
- B 199. Geology and water resources of the Snake River Plains of Idaho, by I. C. Russell. 1902. 192 pp., 25 pls.
- WS 77. Water resources of Molokai, Hawaiian Islands, by Waldemar Lindgren. 1903. 62 pp., 4 pls.
- WS 78. Preliminary report on artesian basins in southwestern Idaho and southeastern Oregon, by I. C. Russell. 1903. 52 pp., 2 pls.
- PP 17. Preliminary report on the geology and water resources of Nebraska, west of the one hundred and third meridian, by N. H. Darton. 1903. 4°. 69 pp., 43 pls.
- WS 90. Geology and water resources of part of the lower James River Valley, South Dakota, by J. E. Todd and C. M. Hall. 1903. 47 pp., 23 pls.
- WS 101. Underground waters of southern Louisiana, by G. D. Harris, with discussions of their uses for water supplies and for rice irrigation, by M. L. Fuller, 1904, 98 pp., 11 pls.
- WS 102. Contributions to the hydrology of eastern United States, 1903; M. L. Fuller, geologist in charge. 1904. 522 pp.
- WS 104. The underground waters of Gila Valley, Arizona, by W. T. Lee. 1904. 71 pp., 5 pls.

The following papers also relate to this subject: Underground waters of Arkansas Valley in eastern Colorado, by G. K. Gilbert, in Seventeenth Annual, Pt. II; Preliminary report on artesian waters of a portion of the Dakotas, by N. H. Darton, in Seventeenth Annual, Pt. II; Water resources of Illinois, by Frank Leverett, in Seventeenth Annual, Pt. II; Water resources of Indiana and Ohio, by Frank Leverett, in Eighteenth Annual, Pt. IV; New developments in well boring and irrigation in eastern South Dakota, by N. H. Darton, in Eighteenth Annual, Pt. IV; Rock waters of Ohio, by Edward Orton, in Nineteenth Annual, Pt. IV; Artesian well prospects in the Atlantic Coastal Plain region, by N. H. Darton, Bulletin No. 138.

SERIES P—HYDROGRAPHIC PROGRESS REPORTS.

Progress reports may be found in the following publications: For 1888-89, Tenth Annual, Pt. II; for 1889-90, Eleventh Annual, Pt. II; for 1890-91, Twelfth Annual, Pt. II; for 1891-92, Thirteenth Annual, Pt. III; for 1893-94, Bulletin No. 131; for 1895, Bulletin No. 140; for 1896, Eighteenth Annual, Pt. IV, WS 11; for 1897, Nineteenth Annual, Pt. IV, WS 15, 16; for 1898, Twentieth Annual, Pt. IV, WS 27, 28; for 1899, Twenty-first Annual, Pt. IV, WS 35-39; for 1900, Twenty-second Annual, Pt. IV, WS 47-52; for 1901, WS 65, 66, 75; for 1902, WS 82-85; for 1903, WS 97-100.

Correspondence should be addressed to

The DIRECTOR,

UNITED STATES GEOLOGICAL SURVEY,

WASHINGTON, D. C.

LIBRARY OF CONGRESS



0 019 953 666 7